



Emerald Gazette


# Icy Wilderness

31000–30901 BCE

Issue 011 of 340



Compiled & Edited by Gerard J. Hannan BA MBS MA




Emerald Gazette

**Icy Wilderness**

31000–30901 BCE

Issue 011 of 340

Compiled & Edited by Gerard J. Hannan BA MBS MA



**Emerald Gazette  
Icy Wilderness  
31000–30901 BCE  
Issue 011 of 340**

**Compiled & Edited by Gerard J. Hannan BA MBS MA**

Gerard J. Hannan BA MBS MA

**Copyright © Gerard J. Hannan. All rights reserved.**

First Edition

Published 2026

Emerald Gazette

Sources and references for the articles in this issue are available through Emerald Archives.

Historical interpretation may vary as new evidence emerges and scholarship develops. Emerald Gazette presents historical material in good faith, based on the sources and research available at the time of publication.

No part of this publication may be reproduced, stored in a retrieval system, or transmitted in any form or by any means without prior permission, except for brief quotations used for review, research, scholarship or citation.

# Contents

|                 |      |                 |      |
|-----------------|------|-----------------|------|
| 31000 BCE ..... | 4240 | 30961 BCE ..... | 4395 |
| 30999 BCE ..... | 4244 | 30960 BCE ..... | 4398 |
| 30998 BCE ..... | 4248 | 30959 BCE ..... | 4402 |
| 30997 BCE ..... | 4252 | 30958 BCE ..... | 4406 |
| 30996 BCE ..... | 4256 | 30957 BCE ..... | 4410 |
| 30995 BCE ..... | 4260 | 30956 BCE ..... | 4414 |
| 30994 BCE ..... | 4264 | 30955 BCE ..... | 4418 |
| 30993 BCE ..... | 4268 | 30954 BCE ..... | 4422 |
| 30992 BCE ..... | 4272 | 30953 BCE ..... | 4426 |
| 30991 BCE ..... | 4276 | 30952 BCE ..... | 4430 |
| 30990 BCE ..... | 4280 | 30951 BCE ..... | 4434 |
| 30989 BCE ..... | 4284 | 30950 BCE ..... | 4438 |
| 30988 BCE ..... | 4288 | 30949 BCE ..... | 4442 |
| 30987 BCE ..... | 4292 | 30948 BCE ..... | 4446 |
| 30986 BCE ..... | 4296 | 30947 BCE ..... | 4450 |
| 30985 BCE ..... | 4300 | 30946 BCE ..... | 4454 |
| 30984 BCE ..... | 4304 | 30945 BCE ..... | 4458 |
| 30983 BCE ..... | 4308 | 30944 BCE ..... | 4462 |
| 30982 BCE ..... | 4312 | 30943 BCE ..... | 4466 |
| 30981 BCE ..... | 4316 | 30942 BCE ..... | 4470 |
| 30980 BCE ..... | 4320 | 30941 BCE ..... | 4474 |
| 30979 BCE ..... | 4324 | 30940 BCE ..... | 4478 |
| 30978 BCE ..... | 4328 | 30939 BCE ..... | 4482 |
| 30977 BCE ..... | 4332 | 30938 BCE ..... | 4486 |
| 30976 BCE ..... | 4336 | 30937 BCE ..... | 4490 |
| 30975 BCE ..... | 4340 | 30936 BCE ..... | 4494 |
| 30974 BCE ..... | 4344 | 30935 BCE ..... | 4498 |
| 30973 BCE ..... | 4348 | 30934 BCE ..... | 4501 |
| 30972 BCE ..... | 4352 | 30933 BCE ..... | 4505 |
| 30971 BCE ..... | 4356 | 30932 BCE ..... | 4509 |
| 30970 BCE ..... | 4360 | 30931 BCE ..... | 4513 |
| 30969 BCE ..... | 4364 | 30930 BCE ..... | 4517 |
| 30968 BCE ..... | 4368 | 30929 BCE ..... | 4521 |
| 30967 BCE ..... | 4372 | 30928 BCE ..... | 4525 |
| 30966 BCE ..... | 4376 | 30927 BCE ..... | 4529 |
| 30965 BCE ..... | 4380 | 30926 BCE ..... | 4533 |
| 30964 BCE ..... | 4383 | 30925 BCE ..... | 4537 |
| 30963 BCE ..... | 4387 | 30924 BCE ..... | 4541 |
| 30962 BCE ..... | 4391 | 30923 BCE ..... | 4545 |



|                 |      |
|-----------------|------|
| 30922 BCE ..... | 4549 |
| 30921 BCE ..... | 4553 |
| 30920 BCE ..... | 4557 |
| 30919 BCE ..... | 4561 |
| 30918 BCE ..... | 4565 |
| 30917 BCE ..... | 4569 |
| 30916 BCE ..... | 4573 |
| 30915 BCE ..... | 4577 |
| 30914 BCE ..... | 4581 |
| 30913 BCE ..... | 4585 |
| 30912 BCE ..... | 4589 |
| 30911 BCE ..... | 4593 |
| 30910 BCE ..... | 4596 |
| 30909 BCE ..... | 4600 |
| 30908 BCE ..... | 4604 |
| 30907 BCE ..... | 4608 |
| 30906 BCE ..... | 4612 |
| 30905 BCE ..... | 4616 |
| 30904 BCE ..... | 4620 |
| 30903 BCE ..... | 4623 |
| 30902 BCE ..... | 4627 |
| 30901 BCE ..... | 4631 |

# Introduction

Ireland's history is a long and layered story shaped by people, place, belief, conflict, migration, creativity and change. Across thousands of years, successive generations have left their mark upon the island, creating a historical landscape in which ancient traditions coexist with moments of dramatic transformation. Emerald Gazette was created to explore that story in an accessible, engaging and carefully structured form, allowing readers to move through Ireland's past one period at a time while retaining a sense of the much larger historical journey.

Each issue forms part of a continuing chronological series designed to bring together significant events, personalities, communities and developments from across Irish history. Political change and military conflict are important parts of that story, but they are only part of it. Ireland's history can also be discovered through the lives of ordinary people, the growth of towns and settlements, religious belief, agriculture, trade, education, language, literature, music, folklore, industry, migration and the countless social changes that shaped everyday experience.

The purpose of Emerald Gazette is therefore not simply to present a sequence of dates or isolated historical events. It is to provide context. Events rarely occur independently of what came before them, and their consequences frequently continue long after the people directly involved have disappeared from the historical record. By following the series chronologically, readers can observe how circumstances developed over time, how ideas and institutions evolved, and how decisions made during one generation influenced those that followed.

The material presented throughout the series draws upon the wider research and historical collections of Emerald Archives. Wherever possible, individual articles place events within their broader Irish and international setting while remaining readable for both the general reader and those already familiar with Irish history. References and source information associated with the articles are available through the Emerald Archives website, enabling readers who wish to investigate particular subjects in greater depth to continue their research beyond the pages of each issue.

History is rarely a simple account of agreement and certainty. Surviving evidence may be incomplete, interpretations may change, and different historians may place differing emphasis upon the same events. Emerald Gazette recognises this complexity while seeking to present the available historical record clearly and responsibly. The objective is not to reduce Ireland's past to a single narrative, but to provide readers with a gateway into the people, events and experiences that contributed to its development.

Every issue should therefore be understood both as an individual publication and as another chapter in a much larger project. Read separately, each volume offers a portrait of a particular historical period. Read together, the complete collection becomes an extended chronological journey through the story of Ireland.


We invite you to explore that journey, discover unfamiliar stories, revisit familiar events from new perspectives, and continue through the pages of Emerald Gazette as the remarkable history of Ireland unfolds.



# Chapter 001 of 100

## 31000 BCE

### Castlepook's Uncertain Cut<sup>[1]</sup>



**“31,000 BCE” is a useful modern label, not a date at which an Irish event can be placed. No contemporary calendar, writing or year-by-year record existed, and archaeological dating at this depth works in ranges rather than anniversaries. In the convention of years before AD 1950, the label falls roughly 33,000 years before present. It belongs broadly to the later part of Marine Isotope Stage 3, during the long approach to the Last Glacial Maximum. The closest Irish evidence is uneven: a buried freshwater deposit at Derryvree near Maguiresbridge in County Fermanagh, and an exceptionally important but complicated cave-fossil archive at Castlepook, near Doneraile in north County Cork. Neither permits a narrative of a particular day, season or individual.**

## Dating a Changing Ireland

The distinction between radiocarbon years and calendar years matters especially here. A radiocarbon result measures the remaining carbon-14 in a sample and must be calibrated against changing atmospheric carbon levels before it can be expressed as a calendar range. Beyond about 30,000 years ago, the resulting ranges are often broad and are regularly refined as methods and calibration curves improve. A numbered BCE year should therefore not be treated as a point on which a cave bone, pollen grain or ice advance can be pinned.

The Derryvree freshwater silts and fine sands produced a radiocarbon determination of 30,500 BP, with an uncertainty of more than a millennium. The deposit lies between two thick tills within a drumlin, showing that it represents an interval between episodes of glaciation rather than a familiar, stable landscape. It has conventionally been assigned to the Middle Midlandian, within the wider cold-stage sequence preceding the full Last Glacial Maximum. Its age is close enough to illuminate the world denoted by 31,000 BCE, but it is not evidence for a precisely dated ‘year 31,000 BCE’ in Fermanagh.

At the scale of the island, the strongest modern reconstructions describe the British–Irish Ice Sheet as building from about 31,000 years ago, expanding markedly across the following millennia and reaching its greatest overall volume much later, around 23,000 years ago. That does not mean every part of Ireland was already buried beneath a uniform blanket of ice in 31,000 BCE. Ice margins, uplands, lowlands and coasts changed at different rates. The responsible picture is one of a cold, unstable northern landscape in which habitable ground, ice and meltwater environments shifted over time.

## **Derryvree's Open Wetland**

Derryvree provides the clearest local environmental evidence. Its plant remains, pollen and small animal evidence point to an open tundra or steppe-tundra setting under periglacial conditions: ground strongly affected by freezing and thawing, rather than a forested Ireland. The assemblage included mosses and sedges, along with fossil evidence for bogbean, alternate water-milfoil and mountain avens. These are not merely botanical curiosities. Together they indicate freshwater, wet ground and low vegetation adapted to a short growing season and cold climate.

The site should not be imagined as a continuous carpet of snow or lifeless gravel. Freshwater silts preserve a more varied scene: shallow water and muddy margins, moss-rich wetland, sedge beds and patches of herbaceous tundra. Some ground may have been sparsely vegetated, while sheltered or waterlogged places retained plants. Yet the same record rules out projecting later Irish scenery backwards. There were no oak woods, hazel scrub, enclosed fields or peatlands of the modern sort. The productive months would have been brief, and winter conditions severe.

This is environmental evidence, not evidence of a settlement at Maguiresbridge. No dwelling, hearth, tool scatter, grave or food-processing site of this age has been recovered there. The Derryvree deposit can demonstrate that northern Ireland contained freshwater habitats and cold-adapted plant communities during this part of the glacial cycle. It cannot demonstrate who visited them, how many people lived in Ireland, or whether people were present at all.

## **Castlepook and the Reindeer Question**

Castlepook Cave, sometimes called Mammoth Cave, is the other indispensable Irish archive. Antiquarian excavation there produced a remarkable mixture of Late Pleistocene animal remains. Reindeer, giant deer, mammoth, wolf, brown bear, Arctic fox, hares, lemmings and spotted hyena are among the species recorded from the cave complex. These animals did not all necessarily live together at one moment; deposits accumulated, were disturbed by carnivores and water, and were excavated long before modern field standards. New radiocarbon work has also shown that some older determinations from Irish caves were substantially too young, underlining why individual dates require reassessment.

Nevertheless, the Castlepook fauna is compelling evidence that southern Ireland supported, or was reached by, large mammals and their predators during portions of the pre-maximum glacial period. Reindeer are particularly informative. They are animals of open northern environments, and their presence accords with the cold, treeless settings indicated at Derryvree. Mammoth, giant deer and hyena add to the sense of a more diverse Pleistocene fauna than survived into later Irish history. A cave assemblage, however, records animals carried into, dying near or entering a cave; it cannot map their exact ranges or calculate their population sizes.



A reindeer femur from Castlepook has been publicised as bearing a deep mark interpreted as a fresh-bone cut or chop made by a sharp stone tool, and has been associated broadly with about 31,000 BCE. If the interpretation is upheld through further microscopic study, secure dating and contextual investigation, it could indicate that a person processed a reindeer in Ireland far earlier than the better-attested terminal-Pleistocene evidence. It would be an extraordinary find.

But the conclusion must remain deliberately narrow. The bone comes from an old cave collection rather than a newly excavated occupation surface with associated tools, hearths and food refuse. A date on a bone dates the animal's death within a range; it does not automatically date a surface mark or establish the identity of its maker. No securely associated stone toolkit, habitation floor, human remains or repeated hunting camp of comparable age has yet been found at Castlepook. The femur is therefore proposed evidence for a brief human encounter with an animal, not proof of permanent settlement, continuous occupation or an Irish population in 31,000 BCE.

## People Beyond the Evidence

Should people have reached Ireland during this period, they would have belonged to Upper Palaeolithic hunter-gatherer worlds known elsewhere in north-west Europe. Their lives would have depended on mobility, intimate ecological knowledge, stone tools, clothing and shelter suited to cold conditions, and decisions shaped by animal movements and seasonal resources. Yet these general comparisons cannot be converted into facts about an Irish band, family or camp. There is no basis for assigning language, ethnicity, population numbers, kinship system or migration route to Ireland at this date.

Low global sea levels exposed much more of the continental shelf than exists today. Ireland was not necessarily separated from Britain by the sea barrier familiar in the modern map; later evidence suggests insular separation was established only much later in the glacial cycle. But exposed ground was not automatically an easy corridor. Ice, meltwater, marshes, river systems, bare terrain and severe weather could all obstruct movement. Whether an early visitor crossed connected land, coastal waters, seasonal ice or a mixture of routes remains unknown.

There is similarly no evidence for political affairs, diplomacy or organised warfare in Ireland at this time. No chiefs, territories, alliances or named communities can responsibly be inferred. A possible hunting episode need not imply conflict, trade or control of a region. Trade in the later prehistoric sense is untraceable: there are no demonstrated Irish exchange networks, imported artefacts or quarries linked to people of this age. Nor is there evidence for farming, livestock, ceramics, metalworking, monuments or permanent villages. Those belong to much later chapters of Irish prehistory.

## Culture Without Written Memory

Religion, art and learning are also beyond direct recovery in Ireland around this date. Upper Palaeolithic communities elsewhere in Europe created sophisticated tools, ornaments and images, and may have held complex beliefs. Ireland has not yielded securely dated material of that sort for this period. It would be misleading to transfer continental cave art, ritual or social institutions to Castlepook merely because the island lay at the far western edge of the same broad climatic world.

The culture that can be described with confidence is the culture of evidence itself: cave bones studied in museum collections; collagen extracted for accelerator radiocarbon dating; marks assessed through zooarchaeology; pollen, seeds and mosses read from sediments; and glacial landforms reconstructed

through mapping and exposure dating. These methods have replaced an older image of Ireland as an empty, simple Ice Age margin with a more nuanced one. The island's environments could be locally varied, rich in animals and repeatedly transformed by climate. Whether people made use of those openings remains one of the most important unanswered questions in Irish archaeology.

## **An Iceward Threshold**


The principal development around 31,000 BCE was thus environmental rather than political: Ireland was moving towards the most extensive glaciation of the last ice age. Derrynree preserves a cold freshwater tundra landscape before later ice sealed it beneath till. Castlepook preserves animals that inhabited or passed through southern Ireland during changing pre-maximum conditions. The marked reindeer femur offers a tantalising possibility of human action, but not a settled history.

For Ireland at this depth in time, restraint is not a failure of imagination. It is the historical achievement. We can responsibly see wet tundra, frost-affected ground, freshwater plants, grazing animals and carnivores, with ice expanding in the wider landscape. We can recognise a possible human trace at Castlepook. We cannot yet name a people, reconstruct a society or narrate an event for this particular calendar year. The evidence preserves a threshold: a landscape on the edge of a great ice advance, and perhaps on the edge of the human story of Ireland.

# Chapter 002 of 100

## 30999 BCE

### Derryvree's Sedgewater Interval<sup>[2]</sup>



**There is no event that can responsibly be assigned to Ireland in the single modern calendar year 30,999 BCE. Nobody on the island kept a calendar of that kind, and the archaeological and geological evidence cannot resolve a particular season, much less a named year, so far back in time. The date is best treated as a point within the later Ice Age: roughly 32,948 calendar years before AD 1950, the conventional radiocarbon “present”. It falls within Marine Isotope Stage 3, a long, unstable cold phase before the Last Glacial Maximum. For Ireland, the evidence is sparse, local and sometimes difficult to date; its value lies in showing changing environments rather than supplying an annual chronicle.**

## **A Date Within Broad Ranges**

The most useful chronological language is therefore calibrated range rather than apparent precision. A freshwater organic deposit at Derryvree, near Maguiresbridge in County Fermanagh, produced a conventional radiocarbon age of about  $30,500 \pm 1,100$  radiocarbon years BP. Calibration converts such a measurement into a broad calendar-age span, commonly given at approximately 36,900–31,700 calibrated years BP. In BCE terms, that is roughly 34,950–29,750 BCE. The notional year 30,999 BCE sits within that large interval, but it was not dated itself. The deposit records an episode in a changing landscape, not a moment frozen in an Irish historical diary.

This distinction matters because radiocarbon years are not calendar years. Atmospheric carbon concentrations have varied greatly through time, while old samples have measurement uncertainties and deposits may accumulate over generations or centuries. Nor should a date on a bone automatically be treated as a date for a cave layer, an animal population, or human activity. Recent reassessment of older

Irish radiocarbon determinations, using improved collagen-extraction methods, has shown how necessary that caution is. Deep-time Ireland is reconstructed by bringing together stratigraphy, pollen, plant macrofossils, insects, bones, landforms and carefully calibrated scientific dates.

## Fresh Water Between Ice Deposits

Derryvree is especially important because roadworks exposed fine sand and organic freshwater sediment enclosed between two layers of glacial till. Till is debris deposited by ice. The sequence therefore supplies a robust relative order: glacier ice affected the locality; an ice-free interval allowed water and organic sediment to accumulate; later ice overrode or sealed the site beneath a further till. It is a powerful, if local, record of environmental change in northern Ireland.

The organic bed preserves a surprisingly detailed ecological assemblage. Pollen, mosses, plant fragments, seeds and insect evidence indicate open, cold, periglacial country rather than forest. Sedges, grasses, hardy herbs and mosses grew around wet ground and shallow water. Finds associated with bogbean (*Menyanthes trifoliata*) and mountain avens (*Dryas octopetala*) show that aquatic or waterlogged niches and cold-tolerant vegetation existed together. Such evidence supports a mosaic of pools, marshy margins, frost-affected ground and more exposed mineral surfaces. It does not justify imagining a uniform landscape across all Ireland, nor a permanently snow-covered wasteland.

Seasonality must have been severe. A short growing season could nevertheless have produced a burst of plant growth around water and sheltered hollows, supporting invertebrates and grazing animals. Winter freezing, wind exposure, sparse soils and poor drainage would have sharply constrained productivity. The familiar wooded Ireland of later prehistory was still far in the future. At Derryvree, the most secure picture is of a treeless, biologically active wetland embedded in an austere cold-climate landscape.

## An Island Landscape in Transition

Ireland at this time lay within the wider climatic system that governed Britain, the Atlantic shelf and north-west Europe. The British–Irish Ice Sheet was not a static object: its growth, changing margins and later retreat took place over millennia, with different sectors behaving differently. The Last Glacial Maximum, when ice reached its greatest late-glacial extent, came later than the Derryvree interval. Around 30,999 BCE, parts of Ireland may have been ice-free while other districts retained ice or were influenced by advancing glaciers. Existing evidence does not permit a reliable map of the ice edge for this exact year.

Lower sea levels altered coastlines and shelf landscapes, but they do not prove a simple, continuously usable land route for people or animals. The Irish Sea region was shaped by changing ice, water, terrain and climate. The presence of animals in Ireland demonstrates that movements into and within the island were possible during particular periods; it does not identify a route, establish a permanent connection, or show that every species arrived at the same time. Regional change was fundamental, but its detail remains unevenly known.

## Caves, Mammals and Uncertain Associations

In southern Ireland, Castlepook Cave near Doneraile in County Cork is the principal faunal archive relevant to this broad period. Antiquarian excavations recovered a rich and complex collection including remains attributed to reindeer, giant deer, woolly mammoth, brown bear, wolf, Arctic fox, lemmings and

spotted hyaena. Together, these animals point towards episodes when cold-adapted and open-country fauna inhabited or reached Irish landscapes. A mammoth bone from disturbed cave sediment received an early radiocarbon determination of  $33,500 \pm 1,200$  BP, while modern dating work has demonstrated that some Castlepook specimens are substantially older than dates obtained by methods used in the 1990s.

The cave is not a straightforward snapshot of one living community. Carnivores could carry bones in; animals might die in fissures or use shelter; water, sediment movement, excavation and collecting could mix materials of different ages. Cave deposits can therefore reveal which species occurred in Ireland during broad phases, yet still leave uncertainty about whether particular animals encountered one another, or exactly when they occupied the cave. The evidence supports an Irish Ice Age fauna, not a neat scene of mammoths, hyaenas and reindeer assembled on one day.

## **The Human Question**

The question of people is more difficult still. A reindeer femur from Castlepook has been presented in County Cork heritage material as around 33,000 years old and as bearing a deep mark consistent with cutting by a stone tool. If that interpretation is confirmed by further taphonomic study, secure dating and contextual evidence, it could indicate the processing of a reindeer by a small Upper Palaeolithic party during the wider MIS 3 period. It would be an important discovery, because it would extend evidence for human activity in Ireland far beyond the better documented terminal-Pleistocene and Mesolithic record.

But it cannot establish a settled population in 30,999 BCE. No securely associated hearth, stone-tool assemblage, dwelling, burial, food-processing floor or repeatedly occupied campsite of that age has been recovered from Castlepook. The National Museum of Ireland continues to state that clear evidence for human presence in Ireland during the Palaeolithic has not emerged. The responsible conclusion is consequently limited: the marked bone is a significant and potentially consequential item, while its human interpretation and wider implications require continued testing. It is evidence to investigate, not proof of an Irish hunting settlement.

## **What Cannot Be Recovered**

There is no basis for describing political authorities, diplomacy, warfare, named groups, religious ceremonies, learning, art or trade in Ireland at this date. There are no known houses, graves, monuments, workshops or artefact assemblages from which to reconstruct social organisation. Even if occasional hunter-gatherers reached the island, their language, identities, kinship, beliefs and movements remain unknown. Comparisons with Upper Palaeolithic communities elsewhere in Europe can suggest that mobile groups often relied on detailed environmental knowledge and made sophisticated stone, bone and antler equipment; they cannot fill Ireland's evidential silence with invented local customs.

Similarly, reindeer and other large mammals make seasonal hunting conceivable, but they do not demonstrate an Irish economy. A single possible cut mark cannot reveal whether a carcass was hunted, found, scavenged, killed elsewhere or processed by one person rather than several. It cannot show whether meat, fat, hide, sinew or antler was used, although each was valuable to Ice Age hunters elsewhere. The strongest historical subject for this date is not a kingdom or a battle, but a changing ecological threshold: ice, freshwater, cold-adapted plants and animals, and perhaps a fleeting human trace.

## **A Landscape Rather Than a Chronicle**

Ireland around 30,999 BCE is therefore illuminated by the Derryvree freshwater bed and the Castlepook faunal record, not by year-specific events. Derryvree proves that a cold, open and locally ice-free wetland environment existed during a broad Middle Midlandian interval. Castlepook shows that remarkable Ice Age mammals formed part of Ireland's longer Pleistocene story, while its marked reindeer bone poses an important but unresolved question about people. Future excavation, direct dating and microscopic analysis may alter the balance of evidence. For now, the honest account is of a harsh but living landscape whose sediments and bones preserve fragments of a past far older than Ireland's historical memory.

# Chapter 003 of 100

## 30998 BCE

### Derryvree's Frostwater Basin<sup>[3]</sup>



**“30,998 BCE” is a useful modern filing point, not a date at which Ireland can be described year by year. No calendar, written record, settlement sequence or dated human episode gives that precision. In archaeological terms, the year falls roughly 32,947 years before the conventional radiocarbon ‘present’ of 1950, within the later part of Marine Isotope Stage 3, a climatically unstable portion of the last Ice Age. The responsible history of Ireland at this depth of time is therefore a history of ranges, deposits and probabilities. It concerns the evidence that overlaps this point in time, rather than an invented event on a particular day.**

## **A Date Inside a Long Range**

The clearest Irish environmental archive relevant to this date lies at Derryvree, near Maguiresbridge in County Fermanagh. Roadworks in 1969 cut through a drumlin and exposed freshwater silts, fine sands and organic deposits trapped between two thick layers of glacial till. Till is debris laid down by ice; its position above and below the organic bed establishes an important sequence. Ice had affected the locality, then an ice-free freshwater environment formed there, and a later advance buried that landscape. This is not a diary of continuous conditions, but it is unusually eloquent evidence for a habitable patch of cold-country Ireland.

Material from the Derryvree bed returned a conventional radiocarbon age of 30,500 +1,170/–1,030 radiocarbon years BP, known as BIRM-166. Radiocarbon years are not calendar years, especially so far back in time, because atmospheric carbon levels have varied. Calibration produces a broad calendar range, commonly expressed at approximately 36,900–31,700 calibrated years BP, or roughly 34,950–29,750

BCE. The modern notional year 30,998 BCE falls within that interval, but does not identify the moment at which any particular seed fell, insect lived or pool filled with silt. The date is best treated as a point within Derryvree's long environmental window.

Older regional terminology calls this the Middle Midlandian, while wider Quaternary scholarship places it in MIS 3. Neither label means that Ireland was environmentally uniform. North Atlantic climates changed abruptly between relatively milder interstadials and harsher stadials. Ice margins, snow cover, watercourses and vegetation could alter markedly over periods far longer than a human lifetime, yet short in geological terms. Modern ice-sheet reconstructions likewise show that the growth of the British–Irish Ice Sheet was uneven and uncertain in detail around 31,000 years ago. It would be wrong either to picture the whole island under a single unbroken ice cap or to imagine an entirely open land awaiting settlement.

## Water Between the Tills

Derryvree's fossils make the local setting more tangible. Pollen, plant macrofossils, mosses and insect remains indicate an open, largely treeless, periglacial landscape. Sedges, grasses and herbaceous plants grew around wet ground; the assemblage includes cold-adapted species such as mountain-avens, dwarf willow and arctic-alpine clubmoss. Bogbean and water-milfoil are particularly valuable because they point to standing or slow-moving fresh water. Mosses and insect evidence suggest a wet, peat-forming terrain with shallow pools and plant-rich margins, often described as muskeg-like.

That word should not summon an imaginary uniform tundra. The evidence instead suggests a mosaic: open water, saturated mossy ground, sedge-fringed hollows, patches of sparse dry-land vegetation and frost-disturbed mineral soils. Long winters and severe freezes would have restricted plant growth; seasonal thaw nevertheless allowed freshwater habitats to persist. A basin capable of preserving organic mud was therefore not an empty white desert. It supported a small but resilient community of plants and invertebrates, while offering drinking water and forage to animals moving through the wider landscape.

The direct evidence applies first to Derryvree itself. A pollen grain or seed does not provide a complete map of the island, and a few grains from trees do not prove local woodland: pollen can travel considerable distances. Nor does the buried wetland establish that every part of modern Ireland was ice-free at the same time. Its great value lies in being specific. It demonstrates that, during part of the broad range encompassing 30,998 BCE, an exposed Fermanagh hollow held freshwater, organic sediment and cold-adapted life between phases of glaciation.

## Castlepook and the Animal World

In north County Cork, Castlepook Cave near Doneraile supplies a different, though equally difficult, archive. Its nineteenth- and early twentieth-century excavations recovered a large collection of Late Pleistocene animal bones. Later reassessment and improved radiocarbon pretreatment have shown that some earlier determinations were too young, a warning against treating old cave dates as final. Even so, the cave establishes that Ireland formed part of a wider north-west European faunal world before the Last Glacial Maximum. Its assemblage has included woolly mammoth, giant deer, reindeer, brown bear and spotted hyaena.

These finds require careful reading. A cave bone does not necessarily mean that its animal lived, died and was eaten at the point where excavators found it. Carnivores can drag remains into caves; water, sediment movement and older excavation methods can disturb their position. Castlepook is particularly associated with hyaena activity, and the cave probably acted at times as a carnivore den or scavenging



place. The fauna nevertheless shows that large mammals reached at least parts of Ireland during this long pre-maximum interval. Their presence implies productive open-country habitats somewhere in the landscape, but not a stable population size, a mapped migration route or a single shared date for every species.

Reindeer are the most relevant animal for thinking about possible human subsistence, because throughout Upper Palaeolithic Europe they were often a major resource for highly mobile groups. Yet continental analogy is not Irish proof. At Castlepook, a reindeer femur has been reported as bearing a deep mark interpreted by some investigators as having been made by a sharp stone tool on fresh bone. County Cork heritage interpretation has presented the bone as possible evidence of butchery around 31,000 BCE. If confirmed, it would be extraordinarily early evidence of a person handling a reindeer in Ireland.

For now, however, the interpretation must remain qualified. No securely associated hearth, stone-tool assemblage, dwelling floor, burial, repeatedly used camp or stratified food-processing area of comparable age has been published from Ireland. The marked femur cannot tell us whether one traveller, a small hunting party or no people at all were present in the island at the exact time represented by this article. It is evidence worth investigating, not a licence to populate Ice Age Ireland with organised reindeer-hunting communities.

## **No Politics, No Recorded Conflict**

Accordingly, there is no evidence for political affairs, rulers, diplomacy, tribes or warfare in Ireland in 30,998 BCE. There are no known houses, villages, farms, monuments, graves, artworks or writing from this horizon. There is likewise no direct basis for reconstructing language, kinship, religious practice, social rank or gender roles. The absence of such evidence does not prove that people could not have made a brief visit; it means that neither permanent settlement nor a particular society can responsibly be described.

The same restraint applies to economy and trade. Derryvree records natural freshwater productivity, not fishing, cultivation or exchange. Castlepook's fauna records animal presence and cave processes, not a market in hides, ivory or meat. Lower global sea levels altered the surrounding continental shelves and the geography of western Europe, but it is unsafe to turn this into a simple land-bridge story. The relationship between Ireland, Britain, sea and ice changed through time, and the practical routes available to people or animals remain uncertain. Movement was possible only through landscapes shaped by ice margins, exposed shelves, waterways and changing coastlines; no route can be assigned to an individual or community.

## **An Island Becoming Iceward**

The major development relevant to this date was environmental change. Derryvree's organic layer was ultimately sealed by renewed glaciation. The larger British–Irish Ice Sheet expanded towards its Last Glacial Maximum in the millennia after this interval, profoundly reshaping Irish terrain. Drumlins, scoured rock basins, glacial deposits and meltwater systems visible in Ireland today are much later legacies of repeated ice movement, but they also conceal or erase many earlier surfaces. This helps explain why evidence for any fleeting human activity is so sparse.

Later Irish prehistory should not be projected backwards. Firm evidence for substantial, sustained settlement belongs to the Mesolithic, beginning around 8000 BCE. A butchered bear bone from Alice and Gwendoline Cave in County Clare provides published evidence for a much later Late Upper Palaeolithic


human presence, around 10,800–10,500 BCE. Those discoveries show both the promise and the limits of cave archaeology: rare bones can transform a chronology, but they cannot fill a gap of tens of millennia with invented continuity.

Around 30,998 BCE, then, Ireland's best-supported story is one of frostwater rather than folklore. At Derryvree, freshwater accumulated among sedges, mosses and cold-adapted plants in an exposed basin between episodes of ice. At Castlepook, an assemblage of large mammals demonstrates a wider Ice Age ecosystem and preserves a provocative, but not yet decisive, clue to human action. These scattered records do not yield a political narrative. They reveal something more fundamental: an Irish landscape that was changing rapidly, locally alive, and poised within the long approach to greater glaciation.

# Chapter 004 of 100

## 30997 BCE

### Derryvree's Buried Bogbean<sup>[4]</sup>



**“30,997 BCE” is a modern chronological label, not a year that can be recovered from Ireland’s archaeological record. It corresponds roughly to 32,946 years before AD 1950, the conventional ‘present’ used in radiocarbon dating, but neither people nor events in Ice Age Ireland can be assigned to that calendar year. The responsible frame is the later part of Marine Isotope Stage 3, about 33,000 calendar years ago, when climates, ice margins and animal ranges could change substantially over centuries or millennia. The evidence is therefore environmental and palaeontological rather than historical: layers of mud, pollen, seeds, insect fragments, bones, cave sediments and the changing footprint of ice.**

This was not an Ireland of kingdoms, named communities or recorded beliefs. There is no basis for describing politics, diplomacy, warfare, religion, language, art, trade or settlement in the usual historical sense. At most, the period offers a difficult question about whether people ever made very brief visits to the island. The central fact is not a human event but a changing northern landscape, caught between open cold-country habitats and the growth of the British–Irish Ice Sheet.

## **A Date Without Annual Precision**

The difference between calendar years, radiocarbon years and calibrated dates matters especially here. Radiocarbon ages are measured against AD 1950 and must be calibrated because atmospheric carbon-14 has varied through time. At around 30,000 radiocarbon years ago, calibration uncertainties and the shape of the calibration curve make any conversion broad rather than exact. A literal BCE number should consequently be treated as a navigational aid, not as a claim that an Irish deposit formed in one particular winter or summer.

The closest particularly informative Irish environmental record is not exactly contemporary with 30,997 BCE. It comes from Derryvree, near Maguiresbridge in County Fermanagh, where a road cutting through a drumlin exposed organic freshwater silts and fine sands between two thick tills. The conventional radiocarbon determination, BIRM-166, was 30,500 with an uncertainty of about 1,100 radiocarbon years before present. In calendar terms it belongs broadly in the mid-30,000s years ago. That makes it evidence for the general world surrounding this date, rather than a diary entry for the numbered year.

## The Wetland Below the Drumlin

Derryvree is valuable because the buried organic layer preserves a small living landscape. Its plant and animal remains indicated open tundra and a periglacial climate: ground shaped by repeated freezing and thawing, with a short growing season and no closed forest. Mosses, sedges, aquatic plants and cold-adapted herbs grew around freshwater. Among the most memorable finds was a seed of bogbean, *Menyanthes trifoliata*, a plant of shallow wetlands and marshy margins. Mountain-avens, *Dryas octopetala*, is also represented by macrofossil evidence. Such remains make the scene more precise than the generic phrase ‘Ice Age’ suggests: not an unbroken white desert, but a treeless mosaic of wet hollows, pools, damp sedge ground, exposed mineral soil and sparse tundra vegetation.

That local precision has limits. Derryvree was a freshwater basin in what is now Fermanagh, not a complete map of the island. Pollen and plant macrofossils show which organisms reached, grew beside or were washed into that basin; they cannot provide a national census of vegetation. Nor does an organic layer trapped between tills prove that every district was ice-free at the same time. Its strongest conclusion is nevertheless important: before later ice overran the area, part of northern Ireland supported a functioning cold-climate wetland ecosystem.

## Ice in Motion

Ireland’s ice history at this depth of time is actively researched and remains unevenly dated. Modern reconstructions reject the old picture of a single, static ice sheet simply advancing to one all-island maximum. The British–Irish Ice Sheet grew and retreated asynchronously, with different sectors responding differently to climate, topography and the sea. Around 31,000 years ago, a major synthesis models advancing ice across northern and central Ireland, while acknowledging that direct chronological constraints on much of that advance are sparse. The same work shows that the ice sheet’s maximum extent was not reached everywhere at once; offshore sectors to the north and west behaved differently from those in the Irish Sea.

For the period represented by 30,997 BCE, the safest interpretation is a volatile regional frontier. Ice had existed in the wider Irish–Scottish region earlier in Marine Isotope Stage 3, and substantial ice expansion followed. Yet ice-free refuges or intervals existed in Ireland, as Derryvree’s sediments demonstrate for their own broad date range. A person standing at one site could have encountered frozen ground, meltwater, wind-blown sediment and an open horizon; another site, perhaps not far away in geological terms, could later be buried beneath moving ice. The landforms now familiar as drumlins, till sheets and glacially reshaped valleys were partly products of these repeated advances and reworkings.

## **Animals of Open Country**

Caves in southern Ireland provide a second, complementary archive. Castlepook Cave, also called Mammoth Cave, near Doneraile in north County Cork, has yielded remains belonging to a varied Ice Age fauna. Re-dating of material from Castlepook and other southern caves has shown that some previously accepted dates were too young, placing parts of the fauna much more securely in Marine Isotope Stage 3. Reindeer, woolly mammoth, giant deer, brown bear, wolf, fox, hare, lemmings and spotted hyaena belong to the wider picture assembled from cave deposits and collections.

These animals do not all prove that they lived together in one valley on one day. Cave deposits often accumulate through many episodes: carnivores carry in prey; animals die in caves; water moves bones; excavators working before modern recording standards may mix contexts. Even so, the fauna strongly supports the interpretation of open, cold and ecologically varied country. Reindeer are especially well suited to such terrain. Mammoths and giant deer suggest corridors of grass-rich or herb-rich habitat, while hyaenas indicate large predators and scavengers capable of exploiting the same animal populations. Ireland was not biologically empty, even if human presence remains uncertain.

## **The Castlepook Human Question**

A reindeer femur from Castlepook has been presented as carrying a deep mark consistent with cutting or chopping by a sharp stone tool. Its reported age, around 33,000 years, has made it potentially transformative: if the mark is human-made and contemporary with the fresh bone, it could be evidence that Upper Palaeolithic people processed a reindeer in Ireland far earlier than the long-established post-glacial settlement record.

The claim must be handled carefully. A cut-marked bone would record an action on one carcass, not a village, a permanent population or an Irish cultural tradition. The date of bone collagen establishes when the animal died, not automatically when a surface mark was made. Castlepook's early excavations also did not recover a securely associated hearth, stone-tool assemblage, dwelling surface, burial or concentration of butchered remains of comparable age. Ireland's National Museum accordingly continues to state that clear evidence for Palaeolithic human presence has not yet emerged. The careful historical position is that Castlepook offers a serious and intriguing possible trace of human butchery, but not proof of continuous occupation.

## **Society, Exchange and Belief: What Cannot Be Claimed**

If people did reach Ireland at this time, they left no demonstrable settlement plan, named territory, burial rite, symbolic object, artwork or exchange network. No political authority can be inferred. No conflict between human groups is evidenced, and the pursuit or scavenging of animals must not be recast as warfare. Likewise, no evidence supports claims about religion, seasonal ceremonies, kinship systems or learning. The presence of a possible butchered bone could be compatible with a small mobile party using a coastal crossing and exploiting a carcass; it cannot tell us where those people came from, how long they stayed or whether they returned.

Economy, in the human sense, is therefore unknown. Ecology supplies the only secure 'economy' visible in the record: plants capturing a short season's growth; herbivores moving through suitable open habitats; predators and scavengers using carcasses; freshwater organisms inhabiting cold pools. Ice, sea level and the availability of crossing routes shaped the possibilities for all of them. Even with lower global

sea levels, Ireland's separation from Britain remained a major practical boundary for people, while animals could arrive through a mixture of swimming, drifting ice, short sea crossings and changing coastal geography.

## **An Island of Evidence, Not Certainty**

For this point in deep time, Derryvree's bogbean seed is more historically useful than an invented story of chiefs or hunters. It records life at the edge of severe cold: a wetland plant growing in an open tundra basin before later glaciation sealed the deposit beneath a drumlin. Castlepook's bones show that large mammals and carnivores used southern Irish landscapes during the wider Marine Isotope Stage 3 interval. The disputed reindeer femur keeps open the possibility of a fleeting human encounter.

Together, these records reveal an Ireland undergoing regional environmental change on a scale beyond any annual chronicle. Around the modern label 30,997 BCE, the island was a fragmented Ice Age world of tundra wetlands, animal movement, advancing ice and sparse surviving evidence. Its most important history is the making, burial and later rediscovery of that landscape.

# Chapter 005 of 100

## 30996 BCE

### Derryvree's Water-Milfoil <sup>[5]</sup>



**The modern label 30,996 BCE cannot identify a particular Irish event, season or generation. Nobody in Ireland kept a calendar at this depth of time, and neither archaeological nor environmental dating can responsibly resolve a single year so far back. In calendar terms this point falls roughly 32,900–33,000 years before AD 1950, within the Late Pleistocene and broadly Marine Isotope Stage 3. The appropriate evidence is therefore regional and range-based: deposits, fossils and radiocarbon determinations with substantial uncertainties, rather than a narrative of named people or dated events.**

The closest Irish environmental archive is at Derryvree near Maguiresbridge, County Fermanagh. There, a road cutting in 1969 exposed freshwater silts, fine sands and organic material sealed between two layers of glacial till within a drumlin. A radiocarbon measurement from the deposit,  $30,500 \pm c.1,100$  radiocarbon years BP, has been calibrated in later discussion to a broad calendar range that overlaps the notional date considered here. It records an interval when this part of Fermanagh was not beneath glacier ice, before a subsequent ice advance covered and preserved the wetland sediments. It does not record the whole island at one instant, but it gives an unusually vivid local view of Ireland during a severe phase of the last Ice Age.

## A Wetland Between Glaciers

Derryvree overturns the easy image of an Ireland continuously smothered beneath unbroken ice. The lower till proves an earlier glacier had crossed the area. Above it, freshwater deposits accumulated in a hollow or shallow basin. The upper till demonstrates that ice later returned. Between those episodes lay a

cold but living landscape: water, sediment, plants, insects and mosses survived long enough to leave an archive. This sequence is often assigned to the Derryvree Cold Phase, part of the regional Midlandian glacial succession.

The plant evidence indicates open, treeless tundra or tundra-like wetland, not the wooded island familiar from later prehistory. Herb pollen is plentiful, although often poorly preserved. Macrofossils and moss remains provide more specific testimony. Sedges and grasses grew around wet ground; water-milfoil indicates shallow freshwater; bogbean, mountain-avens, dwarf willow and clubmoss point towards cold, exposed conditions. The combined evidence has been described as muskeg-like: waterlogged, uneven ground with pools, saturated vegetation and low growth rather than a modern blanket bog. Seasonal freezing, short summers and strong winds would have shaped the terrain.

This was not a landscape without productivity. During the brief growing season, wet hollows could support aquatic plants, mosses and sedges, while drier patches carried sparse herbs and dwarf shrubs. Yet the scale of that productivity should not be romanticised. There is no indication of forest, arable ground, livestock or permanent village life. The plants reveal an ecosystem adapted to cold and disturbance, not a comfortable refuge. Their survival also shows why a local site matters: even in a glacial climate, a basin with fresh water could sustain a distinctive community of organisms.

## Climate, Ice and Changing Geography

The date belongs to a climatically unstable interval before the Last Glacial Maximum, when the British–Irish Ice Sheet reached its greatest known extent around 25,000–23,000 years ago. Around 33,000 calendar years BP, ice was expanding and shifting across the wider region, but its limits were neither static nor uniform. Derryvree itself preserves an ice-free interval; it cannot be used to claim that all of Ireland was open country at precisely the same time. Conversely, later evidence for extensive ice does not mean that every Irish valley was permanently frozen at this earlier point.

Sea level was lower than today because enormous quantities of water were held in continental ice sheets. Ireland was consequently part of a broader north-west European geographical system with altered coastlines and exposed shelf landscapes. Precisely where dry land, tidal channels and water barriers lay changed through time, and researchers continue to refine those reconstructions. It is reasonable to infer that animals could reach Ireland during suitable phases, because the fossil record shows repeated colonisation. It is not responsible, however, to draw a simple, permanent ‘land bridge’ on a map or to assume that people and animals crossed the same route at the same date.

Regional change was thus the major historical force. Glacier growth could erase soils, reroute drainage and compress habitable terrain into local ice-free zones. Frost shattered exposed rock and repeatedly disturbed surface deposits. Later ice and meltwater removed much evidence that might once have existed. The scarcity of sites from this period is therefore not proof of an empty island; neither is it proof of a sizeable human population. It is a condition of the surviving record.

## Animals in an Open Country

Southern Irish caves, especially Castlepook Cave or Mammoth Cave near Doneraile in north County Cork, supply a complementary faunal record. Their deposits have produced bones of woolly mammoth, reindeer, giant deer, brown bear, wolf, fox, mountain hare, lemmings and spotted hyaena. These are not a single herd or a single moment preserved together. Cave deposits accumulated across long periods, were



affected by carnivores, water movement, excavation history and later reassessment. Improved radiocarbon pretreatment has shown that several older determinations from Castlepook need caution and that parts of the fauna are older than formerly supposed.

Nevertheless, the assemblage establishes an important point: Ireland intermittently supported large herbivores and their predators during Marine Isotope Stage 3. Reindeer and mammoth evoke open feeding grounds; hyaenas, wolves and bears show that carcasses and caves were part of a wider predator–scavenger landscape. A cave is not a neutral census of all animals nearby. Hyaenas may have dragged bones in, animals may have died naturally, and deposits may mix material from separate episodes. The evidence supports a changing cold-country fauna, not a precise reconstruction of what stood beside the Derryvree pool in 30,996 BCE.

For people, the most intriguing but least settled evidence is a reindeer femur from Castlepook reported to have a deep mark consistent with cutting by a stone tool. It has been publicly associated with an age of about 33,000 radiocarbon years BP; that is a radiocarbon age, not the same as 33,000 calibrated calendar years BP, and it may pre-date the Derryvree interval by several millennia. The bone raises the possibility that a human visitor butchered a reindeer in Ice Age Ireland. It does not demonstrate a settlement, a hunting camp, a family group or continuous occupation.

## **The Limits of Human History**

No securely associated hearth, stone-tool assemblage, house floor, human burial, food store or occupation surface of this age has been excavated in Ireland. Accordingly, there is no evidence for political authority, diplomacy, organised warfare, territorial boundaries or named communities. There is equally no basis for describing a local religion, language, artistic tradition or system of learning. Such absences are historically meaningful: the sources available are geological and palaeontological, not documentary or social.

If the marked Castlepook bone ultimately proves human modification, it would be evidence for a brief act of carcass processing, perhaps by highly mobile Upper Palaeolithic hunter-gatherers familiar with the wider European world. A cut mark could imply the recovery of meat, marrow, hide or sinew; it cannot reveal who performed the act, whether they travelled alone or in a group, or whether they returned. The careful interpretation is therefore one of possible contact rather than colonisation. Ireland's first firmly evidenced human presence remains much later, after the last major glaciation.

There can be no demonstrated economy or trade network for Ireland at this date. The closest defensible economic picture is ecological: wild animals moved through environments whose usable resources changed with weather, ice and season. If people reached the island, their subsistence would have depended on mobility and knowledge of animals, freshwater and sheltered ground. But that is an inference from comparable Upper Palaeolithic lifeways elsewhere, not direct Irish proof. It must remain clearly separate from the Derryvree fossils and Castlepook bones themselves.

## **What This Date Can Mean**

For Ireland around this notional year, the central development was neither a battle nor a dynasty but an unstable environmental interval. At Derryvree, cold freshwater wetland formed between glacial advances. Mosses, sedges, bogbean and water-milfoil documented a living Arctic-alpine landscape in


what is now County Fermanagh. Elsewhere, cave remains attest that large mammals and predators entered an Irish landscape connected ecologically, if not always physically, to north-western Europe. The possible reindeer cut mark offers an arresting human question, but not a settled answer.

That restraint is not a failure of history. It is the proper achievement of Ice Age research: to distinguish a dated deposit from a calendar year, an animal bone from a community, and a suggestive mark from proof of settlement. Around 30,996 BCE, Ireland can be seen only in fragments. Yet those fragments preserve a remarkable country of frost-affected ground, shallow pools, low vegetation, roaming fauna and approaching ice—an Ireland whose deep past is written not in chronicles, but in silt between tills.

# Chapter 006 of 100

## 30995 BCE

### Mosses Beneath Fermanagh<sup>[6]</sup>



The label 30,995 BCE gives an apparent precision that the evidence cannot sustain. No written calendar, named individual, settlement horizon or event can be assigned to that year in Ireland. In calibrated archaeological terms, it falls roughly 32,944 years before AD 1950, within the Late Pleistocene, Marine Isotope Stage 3 (MIS 3), and the Irish regional sequence often called the Middle Midlandian. The responsible history of this point is therefore not a chronicle of a single year, but an account of a changing Ice Age landscape, reconstructed from buried sediments, animal bones, plant remains and the geometry of later glaciers.

The most closely relevant evidence comes from Derryvree, near Maguiresbridge in County Fermanagh. There, a road cutting made in 1969 exposed freshwater silts and fine sands enclosed between two layers of glacial till beneath a drumlin. The lower till shows that ice had previously crossed the ground; the organic sediments record a period in which open water and wet ground existed locally; the upper till demonstrates that ice later returned. Organic material from the freshwater bed produced a conventional radiocarbon determination of 30,500 +1,170/-1,030 BP. Calibrated with modern curves, the broad uncertainty range is approximately 36,900-31,700 cal BP, or about 34,950-29,750 BCE. The date under consideration lies within that span, but not at a point that can be isolated in the deposit.

## A Landscape Between Ice Advances

Derryvree matters because it preserves a rare Irish record from a time when later glaciation destroyed or buried much of the evidence. Its sequence does not prove that all Ireland was ice-free at once. It establishes something more limited, but still important: during part of this wide interval, south Fermanagh contained a freshwater environment not occupied by glacier ice. The site was part of a landscape

repeatedly altered by cold-climate processes. Freeze-thaw fractured ground; thin soils were vulnerable to wind and runoff; and seasonal meltwater redistributed silt and sand. A drumlin now conceals the former wetland, a striking reminder that the visible Irish landscape is often younger than the deposits below it.

The wider picture is one of instability rather than a simple march towards an Ice Age maximum. Research on the British–Irish Ice Sheet indicates growth, retreat and renewed advances during the last cold stage. The great maximum came later: the ice sheet reached its largest known extent in the Irish sector principally around 25,000–23,000 BP, while advances and maxima varied markedly between regions. Southern Irish deposits show that some raised beaches and shallow-marine sediments formed during MIS 4–3, before glacial deposits dating to after about 24,000 cal BP. At around the notional date considered here, Ireland stood in a long transition towards more severe and extensive glaciation, not yet in the fully developed Last Glacial Maximum familiar from maps of an ice-covered island.

That distinction is essential. It would be misleading to picture a uniform white expanse, but equally misleading to imagine a temperate, wooded Ireland. Local circumstances differed between coasts, lowlands and uplands, and the ice margin itself moved over long timescales. Lower global sea level altered coastlines and exposed parts of the continental shelves. Yet there is no basis for drawing a precise shoreline for 30,995 BCE, or for assuming an easy land route by which every animal or person could have travelled. Connections between Ireland, Britain and continental Europe changed with sea level, ice and the availability of habitable terrain.

## The Derryvree Wetland

The fossils in the Derryvree freshwater bed offer the clearest view of everyday life in this Irish environment—not human everyday life, but that of plants and waters. The deposits contained poorly preserved pollen, mosses and plant macrofossils. Together they indicate open, tundra-like vegetation and a periglacial climate. The record includes plants associated with damp ground and pools, among them bogbean (*Menyanthes trifoliata*) and alternate water-milfoil (*Myriophyllum alterniflorum*), as well as dwarf willow (*Salix herbacea*) and mountain avens (*Dryas octopetala*). Such finds show that a cold freshwater mosaic could support aquatic plants, mossy margins and low-growing vegetation even in a largely treeless setting.

Evidence is strongest at the scale of habitat. It can support an interpretation of shallow water, wet sediment and sparse open ground, rather than a detailed map of every plant community. A pollen grain may have travelled; macrofossils generally speak more closely to their source, but a single basin never represents an entire island. Nor do these fossils establish the precise season in which a plant flowered, the duration of the pond, or the temperature of a particular winter. Their value lies in demonstrating that a small but biologically varied refuge existed between episodes of ice cover.

This was not the later Ireland of dense oak woodland, peat bogs, enclosed fields or familiar lakeside farms. Trees, if present locally at all, were not the defining feature of the Derryvree landscape. The resources available to animals would have been seasonal and patchy: herbaceous plants on exposed ground, browse from low willow, and water-associated vegetation around pools and drainage lines. The phrase ‘tundra’ should not conjure an empty wasteland. It denotes an open cold-climate ecosystem, capable of sustaining distinctive plant communities and, elsewhere in Ireland, substantial mammals.

## Caves, Animals and a Human Question

County Cork's Castlepook Cave, near Doneraile, provides the principal southern counterpart to Derryvree. It is Ireland's richest known site for vertebrate remains from the middle and later part of the Ice Age before the Last Glacial Maximum. More than 2,000 bones recovered from its deposits have yielded dates spanning roughly 45,700–19,950 BP. The assemblage includes woolly mammoth, giant deer, reindeer, brown bear and spotted hyaena; later material includes lemmings, Arctic fox and wolf. These remains show that Ireland supported, at different times, a much richer large-mammal fauna than the island of later millennia.

But a cave bone assemblage is not a census taken in one season. Castlepook's deposits accumulated across many thousands of years, and water disturbance has affected parts of the site. Some carcasses may have been brought in by hyaenas, scavengers or natural processes. Modern redating has also demonstrated that older radiocarbon results from Irish caves can require substantial revision. Consequently, the assemblage is strong evidence for the presence of Ice Age animals in southern Ireland during MIS 3; it is not proof that mammoths, giant deer, hyaenas and reindeer all stood together outside the cave in 30,995 BCE.

The possibility of people in Ireland at this deep date must be handled with equal care. A reindeer bone from Castlepook has been directly dated to about 33,000 years ago and carries a mark that has been discussed as potentially human-made. If that interpretation is confirmed, it would radically extend the known human story of Ireland. Yet there is no securely excavated Upper Palaeolithic hearth, tool assemblage, dwelling surface or cemetery from this time on the island. The National Museum of Ireland therefore continues to state that no clear evidence demonstrates human presence in Palaeolithic Ireland. For now, the bone is an important research question, not a foundation for a confident narrative of resident hunters.

## Society Without a Social Record

There is no evidence from which to identify a polity, chiefdom, territory, alliance, conflict or diplomatic exchange in Ireland at this date. There are no inscriptions, monuments, weapons, houses or burials attributable to a human community around 30,995 BCE. It is equally impossible to demonstrate trade, sea crossings, religious practice, language, teaching or artistic traditions. These absences are not minor gaps: they define the limits of what can responsibly be said.

If people did occasionally reach Ireland during MIS 3, they would have needed practical knowledge of weather, animal movement, stone and organic materials, route-finding and food preservation. That is a reasonable general inference from Upper Palaeolithic lifeways elsewhere in north-west Europe, not direct evidence for Irish society. No Irish find presently permits us to say whether such visitors camped, hunted, crossed from Britain, returned elsewhere, or formed a continuing population. The strongest established story remains environmental: plants persisted in cold wet ground, animals moved through changing habitats, and glaciers were preparing to erase or bury much of the evidence.

## What Survives of This Moment

For Ireland, the importance of this notional year lies in the tension between survival and loss. Derryvree's mosses, sedges and aquatic plants record a locally ice-free freshwater world in the broad interval that includes it. Castlepook records animal communities able to reach and inhabit parts of the


island before the climatic maximum. The subsequent expansion of ice transformed those landscapes, reworked deposits and sharply reduced the chance that traces of people would endure.

Thus 30,995 BCE is best understood neither as the beginning of Irish settlement nor as a year of known action. It represents a narrow calendar label placed upon a long, uncertain interval. Beneath a Fermanagh drumlin, the silts preserve the most intimate evidence available: the remains of plants that grew beside cold water while Ireland's Ice Age geography was still in motion.

## Chapter 007 of 100

30994 BCE

Derryvree's Cold Fen<sup>[7]</sup>



**The label 30,994 BCE is a modern chronological convenience, not a year that anyone in Ireland could have named or recorded. There were no written calendars, states, rulers or dated events on the island from which a single twelve-month history can be recovered. Expressed in the archaeological convention of years before AD 1950, it lies roughly 32,943 years before present. That conversion is useful for orientation only: evidence from this depth of time is dated in calibrated ranges, often spanning centuries or millennia. The most responsible subject is therefore Ireland during the later part of the Last Ice Age, in Marine Isotope Stage 3 (MIS 3), rather than an invented event in one exact year.**

For this broad horizon, the most informative Irish evidence is neither a settlement nor a grave. It is a combination of organic mud trapped beneath later glacial deposits in County Fermanagh, bones from limestone caves in the south, cave mineral deposits, and the larger reconstruction of the British–Irish Ice Sheet. Together they show an island region of sharp climatic instability: locally ice-free ground, freshwater hollows and open cold-country vegetation existed during parts of MIS 3, while expanding ice was already altering the prospects for animals and any people who might have reached Ireland.

### **A Date Range, Not a Dateline**

The closest dated environmental archive is at Derryvree near Maguiresbridge, County Fermanagh. Road works in 1969 cut through a drumlin and revealed organic-rich silts and fine sands between two tills: layers of sediment laid down directly by ice. The buried freshwater deposit returned a radiocarbon result of 30,500 BP, with a substantial uncertainty. Later assessment places its calibrated age broadly between about 31,700 and 36,900 calendar years before present. The modern year-label in this article falls within that wide interval, but the deposit does not identify conditions on a particular day, season or year.

This distinction matters. A radiocarbon date is an estimate based on the remaining radioactive carbon in once-living material; calibration translates that measurement through an independently constructed record of changing atmospheric carbon. At around 33,000 calendar years ago, the resulting ranges are necessarily broad. Nor is one Fermanagh basin a miniature map of the whole island. It records a local environment at a particular stage in a complicated sequence of deposition, erosion, freezing and renewed glaciation. It can illuminate the kind of country that existed in part of Ireland, not provide a uniform national weather report.

## The Derryvree Landscape

The Derryvree silts preserve freshwater mosses, sedges and other plant remains, alongside pollen and insects associated with cold northern conditions. Their combined message is of open, largely treeless ground rather than woodland. Small pools, wet sedge beds and mossy ground lay within a frost-affected landscape. Earlier writers used the term *muskeg* for this mosaic of wetland, shallow water and saturated vegetation. That is an interpretative comparison, not proof that every feature looked like a modern northern peatland.

Open country need not have been lifeless. Low vegetation could sustain grazing and browsing animals, while wetlands would have offered sheltered, seasonally productive patches. Yet the conditions were severe by later Irish standards. Trees were scarce or absent locally, winters were harsh, and exposed ground was vulnerable to frost action, wind and seasonal thaw. The plants and invertebrates recorded at Derryvree are especially valuable because later ice sealed the deposit under till. Without that accident of preservation, this brief glimpse of Irish MIS 3 ecology would have disappeared.

Elsewhere in Fermanagh, deposits at Hollymount and Greenagho also demonstrate that intervals of non-glacial conditions occurred between ice advances. Cave calcite at Crag Cave in County Kerry adds a different kind of evidence. Speleothems grow only when water can circulate through the rock and cave temperatures permit deposition, so their episodic growth records milder pulses amid the wider glacial climate. Such evidence does not mean that Ireland was continuously temperate. Rather, it confirms that the Late Pleistocene Atlantic margin changed abruptly and repeatedly, with consequences for vegetation, animals and ice.

## Animals in Southern Caves

County Cork and Waterford caves provide the principal evidence for animals living in, moving through, or being transported into southern Ireland before the Last Glacial Maximum. Castlepook Cave, near Doneraile in north Cork, is the best known. Its historic collections include remains attributed to woolly mammoth, reindeer, giant deer, brown bear, wolf, hare, Arctic fox, lemmings and spotted hyaena. These species should not be imagined as a single herd or a single scene. Cave deposits may contain material accumulated over many thousands of years, and some bones were redeposited by water, carnivores or later disturbance.

Nevertheless, the cave fauna establishes an important point: parts of Ireland could support a varied cold-stage mammal community during MIS 3. Reindeer and mammoth indicate extensive open habitats; lemmings and Arctic fox point to cold conditions; hyaenas and wolves remind us that large herbivores were part of a predator–scavenger food web. Giant deer, despite the popular name “Irish elk”, was a widespread Eurasian animal, not an animal unique to Ireland. Its presence in Irish cave collections belongs to a long and changing Pleistocene history rather than to any national origin story.



The collections also require caution because many were excavated in the late nineteenth and early twentieth centuries, before modern standards of stratigraphic recording and sample treatment. The Irish Quaternary Fauna Project demonstrated both the value and the difficulty of this material: accelerator radiocarbon dating established that a range of mammals reached Ireland between at least about 45,000 and 20,000 radiocarbon years ago, but it also showed that bone position in an old cave excavation could not automatically be treated as a secure age. More recent ultrafiltration dating has revised some earlier results. The lesson is methodological as well as historical: each bone, date and claimed association must be tested anew.

## **The Castlepook Human Question**

A reindeer femur from Castlepook is directly relevant to this period because it has been publicly presented as about 33,000 years old and as bearing a deep mark interpreted by zooarchaeologist Ruth Carden as a stone-tool cut or chop made while a carcass was processed. If both the dating and the interpretation are confirmed through full specialist publication and contextual study, it would be evidence that one or more Upper Palaeolithic people handled a reindeer in Ireland at roughly this time.

That is an important possibility, but it is not the same as proof of a settled population. No securely associated Irish hearth, dwelling, stone-tool assemblage, human burial, art panel or living surface has been established for around 30,994 BCE. A mark on one animal bone could represent a brief visit, a hunting episode, or carcass processing elsewhere before scavengers carried remains into the cave. It cannot identify a named people, a language, a route of arrival, continuity of occupation, or descent from later inhabitants. Natural damage, carnivore activity and old excavation handling must also be distinguished carefully from human modification.

The strongest published evidence for human activity in Ireland remains much later: a cut-marked brown-bear kneecap from Alice and Gwendoline Cave, County Clare, independently dated to 12,810–12,590 and 12,810–12,685 calibrated years before present. The difference between this securely published terminal-Pleistocene evidence and the earlier Castlepook claim should be kept clear. Castlepook expands the research question; it does not yet provide a conventional archaeological settlement record.

## **Society Beyond Recovery**

Because human presence is unproven at settlement scale, political affairs, diplomacy, organised conflict, religion, artistic traditions, teaching and trade cannot responsibly be described for Ireland in this year. There is no evidence for chiefs, territories, ritual sites, exchange networks or permanent communities. Even if the Castlepook mark proves anthropogenic, it would indicate an encounter with an animal carcass, not a polity or a society in the later historical sense.

What can be said is more modest. Any people present would have depended on detailed practical knowledge: reading animal movement, finding shelter, maintaining warmth, navigating a cold and rapidly changing coastal world, and obtaining food where vegetation and large mammals permitted. These are reasonable inferences from Upper Palaeolithic lifeways elsewhere in north-west Europe, but they are comparative context, not directly excavated Irish biography. No Irish tool kit of this age allows the attribution of a particular cultural tradition.

## Ice, Coasts and Lost Ground

The broader regional change was the growth of the British–Irish Ice Sheet. Its eventual maximum lay ahead, but ice was already advancing and reorganising landscapes during the period around this date. Modern reconstruction shows that different sectors reached their maxima at different times, rather than behaving as one simple frozen blanket. Later ice eroded, buried and redeposited earlier surfaces, helping to explain why an open-air camp from MIS 3 would be exceptionally difficult to find.

Sea level was lower than today because immense volumes of water were held in ice sheets. Coastlines and shallow seas therefore differed greatly from the familiar outline of Ireland, but the exact accessibility of routes into Ireland at any one time remains uncertain. It is unsafe to assert a simple land bridge or a particular migration corridor from the available Irish evidence. The cave fauna shows that animals reached suitable habitats; it does not by itself reveal how, how often, or whether people travelled with them.

Thus the history of Ireland around 30,994 BCE is not one of kingdoms or monuments but of precarious environments and fragmentary traces. Derryvree preserves cold freshwater life between ice advances. Castlepook preserves evidence for a varied Ice Age fauna and a consequential, unresolved possibility of human activity. The approaching ice sheet would later erase much of this world. What survives is enough to show that Ireland was neither timelessly empty nor reliably hospitable: it was a shifting northern landscape whose history must be told in ranges, deposits and probabilities.

## Chapter 008 of 100

30993 BCE

Castlepook's Mammoth-Steppe Archive<sup>[8]</sup>



**“30,993 BCE” is a modern chronological label, not a recoverable Irish year. No calendar, written record, named community or datable event allows historians to describe this point in time with annual precision. The responsible approach is to place it within a broad archaeological horizon: the later part of Marine Isotope Stage 3, an unstable phase of the Last Glacial Period before the greatest expansion of the last British–Irish Ice Sheet. Around this notional date, Ireland’s history is recorded not in chronicles but in buried silts, pollen, plant fragments, insects, animal bones and the scars left by later ice.**

The closest useful chronological anchor is Derryvree, near Maguiresbridge in County Fermanagh. There, a road cutting through a drumlin exposed freshwater silts and fine sands trapped between two thick sheets of glacial till. A conventional radiocarbon determination of  $30,500 \pm 1,170$  radiocarbon years BP was obtained from the organic deposits. Calibration converts this into a broad calendar range, commonly placed at roughly 36,900–31,700 calibrated years BP, or approximately 34,950–29,750 BCE. That range encompasses 30,993 BCE, but it is a span of millennia, not a date for a single season or generation.

### A Wetland Between Glaciations

Derryvree is therefore the strongest direct guide to conditions in at least one Irish locality around this remote point in time. Its sediments accumulated during an interval when the site was ice-free, after one advance of ice had laid down till and before a later advance sealed the wetland beneath another. This does not prove that all Ireland was free of ice at once. It proves something more precise and more valuable: in the Fermanagh locality, shallow freshwater, sediment, plants and small animals existed long enough to form a preserved organic record.

The environmental evidence indicates a cold, open and largely treeless landscape. Mosses, sedges, grasses, herbs and dwarf shrubs were important components of the vegetation. Finds associated with the deposit include aquatic and wet-ground plants such as bogbean and alternate water-milfoil, while dwarf willow, mountain-avens and lesser clubmoss indicate conditions familiar from Arctic or alpine environments. Insects and plant remains point to a muskeg-like mosaic: waterlogged ground, mossy margins, pools and patches of tundra vegetation rather than a uniform frozen desert.

This was not the wooded Ireland later generations would know. Trees, if present anywhere nearby, were not forming a closed forest around Derryvree. Winters were severe, the growing season short, and frost processes would have shaped exposed soils. Yet the organic bed is an important corrective to an image of an entirely lifeless island. Freshwater habitats could support plants, insects and other small organisms even in a harsh climate, while the surrounding open country provided forage for cold-adapted herbivores.

## **Ice, Water and Regional Uncertainty**

At 30,993 BCE the last glaciation was intensifying, but the ice sheet had not yet reached its fullest known extent. Research on the British–Irish Ice Sheet shows that its growth, advance and retreat were regionally variable. Offshore records suggest smaller or fragmented ice masses in parts of the Irish–Scottish region during Marine Isotope Stage 3, while later advances transformed the landscape much more drastically. The maximum phase is generally placed considerably later, around 24,000–20,000 calibrated years BP in Ireland and adjacent seas.

The distinction matters because Ireland should not be imagined either as wholly ice-covered or as a stable, hospitable peninsula. Its geography, coastlines and routes of movement differed greatly from those of today because sea level was lower, but ice, cold seas, shifting river systems and seasonal conditions were formidable constraints. The Derryvree record captures only one local window. Elsewhere, glaciers, bare ground, permafrost-like conditions, river valleys, caves and patches of grassland may have produced very different landscapes over relatively short distances.

## **The Animals of Southern Caves**

County Cork's Castlepook Cave, near Doneraile, supplies another major body of evidence for this wider period. The cave has yielded remains attributed to mammoth, reindeer, giant deer, brown bear, wolf, fox, Arctic fox, hare, lemmings and spotted hyaena. Modern re-dating has shown that parts of the southern Irish cave fauna are substantially older than earlier radiocarbon programmes suggested. In particular, the Castlepook evidence demonstrates that, before the Last Glacial Maximum, Ireland could at times support a much richer cold-stage mammal community than its modern fauna implies.

These remains should nevertheless be read carefully. A cave bone assemblage is not a census of creatures living together on one day. It may combine animals deposited over long periods, bones moved by water or sediment, material accumulated by carnivores, and remains disturbed by old excavations. At Castlepook, spotted hyaenas are especially significant because hyena activity can bring, break and modify bones in caves. Mammoth, reindeer and giant deer bones establish the presence of large herbivores in the wider regional environment; they do not automatically describe a single herd, hunting ground or seasonal migration route.

Even so, the faunal evidence supports an interpretation of open, productive grazing country in suitable phases. Reindeer and mammoth depended on substantial plant resources, while predators and scavengers could exploit herbivores and carrion. The combination of large grazers, carnivores, freshwater wetlands and exposed ground evokes a variable north-western extension of the wider Ice Age ‘mammoth-steppe’ world. It was an ecosystem of mobility and seasonality, not a settled agricultural landscape.

## **The Reindeer Femur Question**

Castlepook also raises the most intriguing, and most limited, question of human history at this depth in time. A reindeer femur from the cave collection has been reported as bearing a deep linear mark interpreted by palaeozoologist Ruth Carden as a cut or chopping trace made with a sharp stone implement while the bone was fresh. The specimen has been publicly associated with an age of about 33,000 years. If microscopic study and contextual reassessment ultimately sustain the interpretation, it would show that one or more people handled a reindeer in Ireland during the Upper Palaeolithic, far earlier than the island’s formerly accepted human record.

That possibility must not be inflated into a story of a settled population. A radiocarbon date on bone dates the animal’s death within a range; it does not independently date the making of a surface mark. Nor does one modified bone identify the people involved, their language, sex, age, homeland, technology beyond the proposed sharp tool, or the duration of their stay. Castlepook has produced no securely associated hearth, stone-tool assemblage, dwelling floor, burial, artwork or repeated occupation surface from this horizon. The evidence can support a hypothesis of brief human activity; it cannot support a village, tribe, permanent colony or line of descent to later Irish populations.

## **Society Without Institutions**

Accordingly, there is no evidence for political affairs, diplomacy, territorial rule or organised conflict in Ireland around 30,993 BCE. There were no known Irish kingdoms, chiefs, monuments or institutions. Nor can archaeologists responsibly identify a local ethnic group or attach later Gaelic, Celtic or national identities to this period. If people did reach the island, they may have travelled in small, highly mobile Upper Palaeolithic groups, as hunter-gatherers elsewhere in north-west Europe did. But that is a comparative possibility, not a demonstrated social history of Ireland.

The same caution applies to everyday life and economy. There is no evidence here for cultivation, livestock, pottery, metalworking, houses, long-distance trade networks or established exchange centres. A humanly made mark on a reindeer femur, if confirmed, would suggest the practical use of animal resources: meat, marrow, sinew, hide or bone may all be considered possibilities. The surviving evidence cannot choose among them. It does, however, show why large herbivores would have been economically significant to any visitors capable of exploiting them.

## **Belief, Culture and Learning**

No Irish evidence from this period demonstrates religion, ritual, burial practice, symbolic art or formal learning. It would be wrong to infer a belief system from an animal bone or to project the celebrated cave art of France and Iberia onto Ireland. People elsewhere in Europe had developed


sophisticated artistic and technological traditions by this broad stage of the Upper Palaeolithic, but an Irish connection remains unproven. Absence of evidence does not prove that no symbolic activity occurred; it means that none has survived in a context where it can be securely recognised.

The principal story of Ireland around 30,993 BCE is therefore environmental change. Derrynvree preserves an ice-free freshwater wetland within a cold, treeless landscape. Castlepook preserves evidence of a striking Ice Age fauna and a serious but unresolved question about human intervention. Later glacial advances destroyed, buried and reworked much of the island's earlier surface archaeology. The result is a fragmentary archive, yet it is enough to replace the old image of a simple, empty prehistory with a more compelling one: an Ireland of tundra pools, mossy ground, large mammals, shifting ice margins and perhaps fleeting human contact at the Atlantic edge of Upper Palaeolithic Europe.

# Chapter 009 of 100

## 30992 BCE

### BIRM-166 and the Fermanagh Thaw<sup>[9]</sup>



**“30,992 BCE” is a modern calendar label, not a year that can be recovered from Irish evidence. No written record, annual chronology or event horizon permits precision on that scale. The date falls within the later Pleistocene, broadly Marine Isotope Stage 3 (MIS 3), a climatically unstable part of the last Ice Age. The responsible approach is therefore to ask what dated deposits, animal remains and glacial landforms can reveal about Ireland within a wide interval around this notional year, while distinguishing observation from interpretation.**

The strongest chronological bridge is a buried freshwater deposit at Derryvree, near Maguiresbridge in County Fermanagh. Its conventional radiocarbon determination, BIRM-166, was 30,500 +1,170/–1,030 radiocarbon years before present. Calibration converts this into a broad range of roughly 36,900–31,700 calibrated years before present, rather than a single calendar year. In the convention where “present” is AD 1950, 30,992 BCE lies within that wide range. That does *not* mean the Derryvree mud was laid down in that year, only that it is the best Irish environmental archive relevant to this stretch of deep time.

## A Wetland Between Glaciers

Derryvree was exposed during road works in 1969, when a cut through a drumlin revealed organic-rich freshwater silts and fine sands enclosed between two thick tills. Tills are sediments deposited directly by ice. Their sequence is decisive: an earlier glacier crossed the locality; an interval then allowed freshwater sediment, plants and small animals to accumulate; a later advance buried the deposit beneath new glacial debris. The evidence establishes locally ice-free conditions in this part of Fermanagh during the interval represented by the organic bed. It cannot demonstrate that every region of Ireland was free of ice at the same moment.

The deposit gives an unusually intimate, though still partial, view of an Irish cold-stage landscape. Pollen, plant macrofossils, mosses and insects indicate open, treeless terrain rather than woodland. Grasses and sedges were important, with juniper and herb pollen also recorded. Mosses flourished around waterlogged ground, while a fossil seed of bogbean (*Menyanthes trifoliata*) confirms shallow freshwater conditions. The insect fauna has a cold, northern character. Together these observations support an interpretation of muskeg-like wetland: mossy, sedge-rich ground interspersed with pools and saturated channels, set within sparse tundra vegetation.

This was not a timeless white wilderness. Summer growth, standing water and plant litter sustained small wetland ecosystems, even though winters were severe and the ground was shaped by frost. Nor should modern bogs be projected backwards unchanged. The landscape was periglacial: intensely seasonal, largely treeless and vulnerable to freezing, thawing, erosion and changing drainage. Derryvree's plants reveal what could grow in one protected basin; they do not provide a complete map of the island.

## Ice Sheet in the Making

At this date Ireland stood before, rather than at, the fullest extent of the Last Glacial Maximum. Later, between roughly 26,500 and 19,000 calibrated years before present, ice covered much or probably all of the island and heavily eroded its earlier surface deposits. Research on the British–Irish Ice Sheet shows that its growth was regionally uneven. Some northern and marine sectors advanced early, while the evidence from Derryvree and other Fermanagh sites records exposed ground in north-central Ireland before the major expansion of the last Irish ice sheet.

That regional variation matters. “Ireland” was not a uniform environmental unit: ice margins, uplands, river basins, caves and coastal lowlands responded differently to climatic shifts. Lower sea levels also made the surrounding geography very different from that of the modern island, although the exact routes available to animals or people at any particular moment remain uncertain. Crag Cave in County Kerry preserves another kind of evidence. Episodes of stalagmite growth there during MIS 3 indicate periods when liquid water could penetrate cave systems, signalling climatic amelioration on a broader south-western Irish scale. Such records reinforce the picture of fluctuation, not a simple march towards ever colder conditions.

These geological changes had a lasting historical consequence. Later ice scoured and rearranged much of the land surface, destroyed many potential campsites and mixed sediments. The scarcity of very early archaeological sites in Ireland is therefore partly a preservation problem. Yet erosion is not a complete explanation: it cannot turn isolated environmental indications into proof of settlement. The record has to be read for what it retains, and for what it has lost.

## Animals of the Open Country

Caves in the south, especially Castlepook Cave near Doneraile in County Cork, preserve the principal Irish faunal evidence for MIS 3. Re-dating of bones held by the National Museum of Ireland has shown that older radiocarbon methods often made specimens appear too young. Improved pretreatment placed several Castlepook animals much further back in the glacial period. The assemblage includes reindeer, Arctic fox, wolf, brown bear, giant deer, woolly mammoth, spotted hyaena and lemmings.

It would be mistaken, however, to picture all of these animals meeting on one day in a single Cork valley. Cave deposits accumulated over long periods through carnivore activity, natural deaths, water movement and earlier excavation. Individual dates vary widely. The secure conclusion is that cold-stage



animal communities reached Ireland during MIS 3, and that the island could support sizeable herbivores and predators before the glacial maximum. Reindeer and Arctic fox fit open, cold habitats; mammoth, giant deer and hyaena point to a richer and more varied large-mammal history than Ireland possesses today.

For everyday ecology, the Fermanagh wetland and the Cork cave complement one another. Derryvree shows plants, water and small invertebrates in a northern basin. Castlepook shows the wider animal world, but not a precisely contemporary food chain. Both are archives of intervals, not snapshots.

## The Human Question

The possibility of people in Ireland at this depth of time remains exceptionally important and exceptionally narrow. A reindeer femur from Castlepook, in the National Museum of Ireland collection, has been publicised as approximately 30,000 years old and as bearing a sharp mark interpreted as possible stone-tool butchery. If that interpretation is confirmed, it would show that a person handled a reindeer in Ireland during the Upper Palaeolithic, dramatically earlier than the well-established post-glacial settlement record.

But the limits are as important as the possibility. A date on bone establishes the age of the animal's death within an uncertainty range; it does not automatically date a surface mark or establish how the bone reached the cave. Castlepook was excavated in the early twentieth century, its deposits were disturbed, and its fauna accumulated through several processes. No securely associated hearth, stone-tool assemblage, dwelling floor, burial, repeated campsite or butchered-bone concentration has been published for this horizon. A single potentially modified bone cannot tell us population size, season of visit, language, kinship or whether any visitors returned.

If people did enter Ireland around this broad period, they were most plausibly small, mobile hunter-gatherer parties exploiting a changing cold-country landscape, not founders of a documented permanent population. That is an interpretation drawn from the ecological setting and wider European Upper Palaeolithic comparisons, not an established Irish settlement narrative.

## What Cannot Be Written

There were no recoverable Irish states, rulers, borders, diplomacy or wars in 30,992 BCE. No evidence identifies a political community, a treaty, a raid or a territory. Nor is there Irish evidence from this horizon for farming, villages, trade networks, monuments, formal religion, art, schools or writing. The named galleries of Castlepook—such as Elephant Hall and Hyaena Hall—are modern excavation labels, not ancient places of assembly or ritual.

Absence of evidence does not prove that people could never have crossed or briefly used the land. It does mean that the historian must resist filling the silence with imagined chiefs, camps or ceremonies. The most meaningful development is environmental: local ice retreat or absence allowed Fermanagh wetland life to persist; colder phases and advancing ice later sealed that evidence; and animal remains in southern caves survived to demonstrate an unexpectedly complex Ice Age fauna.

For Ireland around this notional year, BIRM-166 is therefore more valuable than a fabricated event. Its moss-rich mud records open pools, sedges, bogbean and cold-adapted life in a temporary ice-free landscape. Castlepook records animals moving through another Irish region across the long span of MIS

3. Together they show an Ireland that was neither empty in every biological sense nor securely inhabited in the historical sense: a shifting, severe and regionally varied land whose evidence must be measured in calibrated ranges, deposits and probabilities.

## Chapter 010 of 100

30991 BCE

Cork's MIS 3 Fauna<sup>[10]</sup>



**The label 30,991 BCE is a modern chronological convenience, not a year that can be recovered from Ireland's deep past. No contemporary calendar, written record, named people or datable event exists. At this depth of time, archaeologists work with radiocarbon determinations, calibrated probability ranges, stratigraphy and environmental proxies. The safest setting is the later part of Marine Isotope Stage 3, roughly 33,000 calendar years before present, well before the fullest expansion of the Last Glacial Maximum. It was an Ice Age world, but not necessarily one in which every part of Ireland lay continuously beneath ice.**

The most significant Irish evidence relevant to this broad interval comes from Castlepook Cave, near Doneraile in north County Cork. Its deposits and museum collections preserve a remarkable, though complicated, record of Pleistocene animals. A reindeer femur from the cave has been presented by County Cork heritage authorities as dating to about 31,000 BCE and as bearing a deep mark interpreted by zooarchaeologist Ruth Carden as the work of a sharp stone tool. If that interpretation is sustained, it may be Ireland's earliest known indication that people processed an animal. It does not establish that a particular hunting party was present in this numbered year.

### **A Date of Ranges, Not an Occasion**

Radiocarbon measurements do not provide the precision implied by a BCE year. They estimate the age of organic material by measuring surviving radioactive carbon, then require calibration against changing atmospheric carbon levels. For dates approaching the practical limits of radiocarbon dating, calibrated ranges can span centuries or more. A measurement on a reindeer bone primarily dates the animal's death; it cannot, by itself, identify the exact moment when a surface mark was made, the place where the carcass was cut, or the identity of the person who may have handled it.

The period is therefore better understood as a broad horizon around the thirty-third millennium before present. It belongs to the Late Pleistocene, when climatic conditions across north-west Europe shifted repeatedly between colder and somewhat milder phases. Ireland's record is unusually fragmentary because later ice movement eroded, reworked and buried many older surfaces. Caves, protected sediment pockets, marine records and deposits sealed beneath glacial material have consequently become disproportionately important archives.

Modern re-dating has changed the picture. The Irish Quaternary Fauna Project first brought together evidence from cave collections, but later accelerator mass spectrometry and improved ultrafiltration of bone collagen showed that several earlier dates were too young. Re-dating at Castlepook produced ages thousands of radiocarbon years older than previous determinations for some specimens. That revision gives the cave genuine importance for pre-Last Glacial Maximum Ireland, while also demonstrating why older collections and inherited chronologies must be treated cautiously.

## **Castlepook's Uneven Archive**

Castlepook is sometimes called Mammoth Cave, an apt reminder of the large mammals represented there. Its wider Pleistocene assemblage has included woolly mammoth, reindeer, giant deer, brown bear, wolf, Arctic fox, mountain hare, lemmings and spotted hyaena. These remains demonstrate that cold-stage animal communities reached Ireland during Marine Isotope Stage 3. They do not demonstrate that all these species lived together in one valley, one season or one generation. Individual bones may belong to separate climatic episodes spread across many millennia.

Nor was the cave a simple snapshot of the landscape outside its entrance. Carnivores could drag carcass parts into a den; water could move sediments and bones; roof collapse could disturb deposits; and antiquarian excavations between 1904 and 1913 removed much material before the routine use of modern recording, sieving and geoarchaeological sampling. Castlepook is valuable precisely because it has retained evidence despite these processes. Yet its complexity prevents the cave from being described responsibly as a securely excavated hunting camp.

The marked reindeer femur must be read in that light. A sharp incision on fresh bone can be consistent with stone-tool butchery, but specialists must distinguish such marks from carnivore damage, trampling, sediment abrasion, breakage, weathering and damage caused during recovery. The specimen is therefore important proposed evidence for human activity, not proof of a permanent population. No securely associated hearth, lithic assemblage, dwelling floor, human burial or concentration of butchered animal remains of comparable age has yet been recovered in Ireland.

## **Open Country and Mobile Animals**

The animal evidence nevertheless permits a restrained reconstruction of the setting. Reindeer, lemmings, Arctic fox and mountain hare point to cold, open habitats rather than the dense woodland familiar from later Holocene Ireland. Grassland, herb-rich steppe-tundra, dwarf-shrub vegetation and wet ground probably formed a changing mosaic, governed by local relief, drainage, soils, exposure and the proximity of ice. Mammoth and giant deer show that, at intervals, the landscape could support large herbivores; wolves and spotted hyaenas indicate predators and scavengers within that wider ecosystem.

This was not a timeless frozen waste. Even a generally cold phase contained seasonal and regional contrasts. Low vegetation may have supported grazing and browsing animals in favourable places, while valleys and limestone country offered shelter, water and routes through the terrain. Derryvree near

Maguiresbridge in County Fermanagh, although not securely tied to this exact date, preserves intertill organic deposits that show how freshwater pools, sedges, mosses and cold-adapted plants could survive within unstable glacial landscapes. Such evidence helps illuminate Irish environments broadly comparable to this phase, rather than describing north Cork on a particular day.

Sea level was lower than today, exposing more of the continental shelf and altering coastlines beyond recognition. However, the exact accessibility of Ireland from Britain and continental Europe at this moment remains uncertain. Changing sea levels, ice margins, tidal waters and exposed plains make simplistic claims about a continuous land bridge unsafe. If people did reach Ireland, they may have travelled through a shifting north-west European landscape that combined broad lowlands, water crossings and glacial barriers. The Irish evidence cannot yet determine their route.

## **People: A Possibility, Not a Population**

The Castlepook femur opens a major question about the earliest human presence in Ireland. A stone-tool mark, if confirmed, would fit a world in which Upper Palaeolithic groups elsewhere in north-west Europe moved across large territories, using lithic tools and exploiting seasonally available animal resources. Reindeer could provide meat, fat, hide, sinew, antler and bone. Yet none of those uses, apart from the possible processing represented by the single mark, can be demonstrated at Castlepook itself.

It would be unjustified to turn that possibility into a story of an Irish tribe, settlement or migration. There is no evidence for a village, a named group, a social hierarchy, an established territory or continuous occupation. At most, the bone may record a brief incursion by a very small and highly mobile party, perhaps one that encountered, hunted or scavenged a reindeer. It cannot show whether visitors stayed for hours, days or a season; whether they returned; or whether they crossed from Britain, travelled along an exposed shelf, or came by another route.

The distinction matters because the better-attested record of human activity in Ireland is vastly later. At Alice and Gwendoline Cave in County Clare, a butchered brown-bear patella has calibrated dates around 12,890–12,678 cal BP, although its cave context has also prompted debate. Early Holocene settlement evidence, including Mount Sandel in County Londonderry, is later again. Castlepook would therefore push the possible human story back by many millennia, but its claim rests on a far narrower evidential base than those later horizons.

## **No Politics, Diplomacy or Ritual Record**

Political affairs cannot responsibly be reconstructed for Ireland at this time. There are no known rulers, communities, boundaries, alliances, battles or diplomatic contacts. Nor is there evidence for religion, formal burial, art, language, teaching institutions or ritual practice in Ireland around this horizon. Absence of evidence is not proof that people lacked beliefs, speech, knowledge or social relationships; it means that Irish archaeology has not recovered material capable of describing them.

Likewise, there is no demonstrable trade network. The possible use of a stone tool would imply practical knowledge of cutting technology, but no associated tool survives at Castlepook and no source of stone can be linked to the femur. There is no basis for claims about exchange, craft specialisation or organised hunting. The only defensible economic description is ecological: large herbivores, predators and small cold-adapted mammals moved through an environment in which any human visitors, if present, would have depended on mobility and immediate local resources.

## Ice Ahead


Whatever short-lived opportunities existed in this broad period, they were followed by increasingly severe glacial conditions. Research on the British–Irish Ice Sheet indicates extensive advance across Ireland and its offshore shelves later in the Last Glacial Maximum, especially after about 26,000 cal BP. Ice erosion and deposition transformed the terrain, helping to explain the scarcity of surviving open-air Palaeolithic evidence. Much of the physical Ireland visible today—its tills, drumlins, sands and gravels—was shaped or inherited from those later ice-sheet processes.

For 30,991 BCE, then, the responsible historical picture is not a dated event but a fragile window. Castlepook’s fauna proves that Ice Age animals inhabited or reached Ireland during the wider period. Its marked reindeer femur may preserve an exceptionally early human trace. Between those two statements lies the necessary discipline of deep-time history: evidence can enlarge Ireland’s past, but it cannot yet supply the people, places and episodes that later centuries record.

# Chapter 011 of 100

## 30990 BCE

### Doneraile's Reindeer and Reedbeds<sup>[11]</sup>



The label 30,990 BCE gives a useful position in a modern chronological sequence, but it cannot identify an event that happened in one Irish calendar year. No written record, settlement sequence or dated human life allows that degree of precision. Expressed in the convention used by Quaternary scientists, the point is roughly 32,939 years before AD 1950; radiocarbon and environmental evidence must be read as calibrated ranges, often spanning centuries or millennia. The responsible picture is therefore of Ireland during the cold, changeable Marine Isotope Stage 3, shortly before the great expansion of the last Irish Ice Sheet, rather than of a named people or a particular happening.

## A Date Within Broad Ranges

The nearest important environmental archive is Derryvree near Maguiresbridge in County Fermanagh. There, road works exposed organic freshwater silts and sands sealed between two layers of glacial till. The classic radiocarbon determination from this deposit, Birm-166, was  $30,500 \pm 1,200$  radiocarbon years BP. Modern calibration has been published as a broad interval of about 36,900–31,700 calibrated years BP. Thus 30,990 BCE falls near the younger end of a range represented by the Derryvree sediments, but not at a point which can be isolated within them.

That distinction matters. The organic layer demonstrates that its locality was ice-free while a cold freshwater environment existed; it does not provide a nationwide weather report, a precise annual chronology, or a continuous record of every intervening year. Nor does a radiocarbon date tell us that every plant or animal found in a different Irish deposit lived at the same moment. Ireland's surviving evidence from this period is fragmentary because later glaciers eroded, buried and rearranged much of the earlier landscape.

## An Open, Cold Landscape

The Derryvree plant remains point to a treeless, tundra-like wetland or muskeg landscape, not to the familiar wooded and rain-rich Ireland of later millennia. Sedges, mosses, dwarf shrubs and cold-tolerant herbs could grow around shallow water, saturated ground and seasonal pools. Bogbean and water-milfoil are among the fossils used to reconstruct freshwater conditions. Their presence is evidence for particular local habitats, while the wider interpretation—an open, strongly seasonal and cold environment—is supported by the associated plant assemblage and by comparison with other north-west European records.

In such a country, summer growth could be concentrated into a short season, while winter brought hard frosts, snow cover and frozen ground. Wind would have mattered greatly on exposed uplands and plains. Watercourses and wet hollows nevertheless created sheltered pockets of vegetation. The landscape was not a single blank of snow or an unbroken glacier. At this time, evidence from Fermanagh, western offshore areas and southern Ireland indicates that substantial ground remained ice-free in some regions, even though ice was building elsewhere and climatic conditions were deteriorating.

Sea level was far lower than it is today because vast volumes of water were held in northern ice sheets. Coastlines consequently lay beyond their modern positions, and the Irish Sea basin had a different geography. Yet lower sea level should not be turned automatically into a simple land bridge from Ireland to Britain or continental Europe. Routes across the wider north-west European landscape depended on changing shorelines, rivers, marshes, channels and ice margins. For animals and any people, movement was possible only through particular corridors at particular times.

## Castlepook's Animal Archive

The strongest Irish faunal evidence relevant to this broad period comes from Castlepook Cave, also called Mammoth Cave or Doneraile Cave, in north County Cork. Excavations undertaken largely in the early twentieth century by the naturalist Richard J. Ussher produced a remarkable but imperfectly recorded collection. Geological Survey Ireland regards the cave as Ireland's richest vertebrate site for the period leading towards the Last Glacial Maximum. Its remains include woolly mammoth, reindeer, giant deer, brown bear, wolf, Arctic fox, mountain hare, lemmings and spotted hyaena.

This list should not be imagined as a single herd and its predators gathered outside the cave on one day. Cave bone assemblages accumulate over long periods, and at Castlepook water disturbance, carnivore activity and early excavation have mixed the evidence. A hyaena could drag in prey or scavenge a carcass; an animal could die near an entrance; water could move bones from their original resting place. The fauna nevertheless establishes something significant: pre-maximum Ireland could support, or intermittently receive, a richer cold-stage mammal community than the later island's fauna might suggest.

Reindeer are especially evocative because they indicate open grazing country and potentially seasonal movement. Mammoth and giant deer required substantial feeding grounds, while hyaenas, wolves and bears occupied different ecological roles as predators or omnivores. Lemmings and Arctic fox reinforce the cold character of the wider habitat. These animals do not prove that every valley in Ireland looked alike, but they rule out any picture of a uniformly forested, isolated island. Ireland was connected ecologically to a larger north-west European world, even if its exact routes of recolonisation and local extinctions remain debated.



## The Human Question

One Castlepook find gives this date unusual importance: a reindeer femur bearing a deep surface incision that zooarchaeologist Ruth Carden has interpreted as consistent with stone-tool butchery. Public reports described the bone as about 33,000 years old, and its possible modification has been presented as evidence that people processed a reindeer in Ireland far earlier than the previously accepted archaeological record allowed. If that interpretation is sustained, it would show a human visit during the later Palaeolithic, broadly within the cold-stage world discussed here.

But the finding must be described carefully. The bone came from an old cave collection rather than a modern, intact occupation layer. Dating establishes the age of the animal bone, not automatically the exact moment when an incision was made. No securely associated hearth, stone-tool assemblage, dwelling floor, burial or repeated occupation horizon has yet been recovered at Castlepook for this period. Recent work has identified surviving Pleistocene, faunal-bearing deposits with considerable potential, but potential is not the same as proof of a camp or settled population.

Accordingly, the most cautious conclusion is that Ireland may have been visited by hunter-gatherers who exploited a reindeer carcass, perhaps while following animal movements through a wider landscape. It cannot support a claim that the island had a permanent human population at 30,990 BCE. Nor can it identify whether the visitors were few or many, how long they remained, which route they travelled, or whether they returned. The absence of evidence is partly a consequence of preservation, but it remains an absence.

## Life Without Recorded Communities

There is no basis for political history at this date. No kingdom, chieftdom, border, diplomatic relationship, war, treaty or named community can be reconstructed. Later identities—Irish, Gaelic and Celtic—belong to vastly later historical and linguistic contexts and must not be projected back into the Pleistocene. If people were present, their social arrangements, languages and kinship systems are unknown.

The same restraint applies to religion, culture and learning. There are no Irish cave paintings, portable artworks, graves or ceremonial places securely assignable to around 30,990 BCE. A possible butchery mark can illuminate a practical action: the use of a sharp implement to dismember or process an animal. It cannot reveal myths, rituals, artistic traditions or systems of teaching. The wider European Upper Palaeolithic shows that *Homo sapiens* elsewhere possessed sophisticated technologies and symbolic cultures, but Irish evidence cannot yet demonstrate which, if any, of those practices reached this island.

Economy and trade must also be framed as possibilities rather than institutions. If hunters reached Ireland, subsistence would probably have depended on mobile foraging, the opportunistic use of animal carcasses and knowledge of seasonal terrain. Reindeer meat, fat, hides, sinew and bone were valuable resources to Palaeolithic peoples elsewhere, but no Irish assemblage of this age documents their full use. There is no evidence for exchange networks, managed herds, farming, pottery, metalworking or permanent markets. The only securely visible economy is the natural one: plants feeding herbivores, herbivores sustaining carnivores, and freshwater wetlands offering local ecological resources.

## **Towards the Ice Maximum**


The long-term development deserves greater emphasis than any hypothetical human episode. Within several millennia, the last British-Irish Ice Sheet expanded dramatically. Reconstructions place its maximum extent much later, broadly between about 26,500 and 19,000 years ago, with regional advances and retreats that did not occur everywhere simultaneously. By then, ice had transformed much of Ireland and removed or concealed earlier deposits. The Derryvree organic bed is precious precisely because later till sealed a small record of a living cold landscape beneath the advancing glacial history.

Around 30,990 BCE, then, Ireland was neither the familiar green island nor simply an ice-covered void. It was a climatically unstable northern landscape of open vegetation, reed-fringed and mossy water, grazing mammals and formidable predators, with glaciers increasingly important in its future. Castlepook and Derryvree provide different kinds of testimony: one a cave archive of animals, the other a buried wetland archive of plants and sediment. Together they reveal a world that can be reconstructed in broad outline, while reminding us that its people—if present at all—remain almost invisible.

# Chapter 012 of 100

## 30989 BCE

### Awbeg Valley Reindeer Country<sup>[12]</sup>



30,989 BCE is not a date at which Irish history can be written year by year. It is a modern calendar label projected far beyond the reach of written records, annual chronologies or securely dated events. In archaeological terms it falls at about 32,900 calibrated years before present (cal BP, where “present” is 1950), within Marine Isotope Stage 3 of the Late Pleistocene. Dates from this depth of time carry substantial uncertainty: radiocarbon ages must be calibrated, deposits may represent long episodes rather than a single moment, and older excavations rarely recorded layers to modern standards. The responsible question is therefore not what happened in Ireland in one exact year, but what evidence illuminates the island during the broad interval around it.

## A Cold, Changing Island

Ireland at this time belonged to the last Ice Age, but it was not yet simply the wholly ice-covered country familiar from images of the Last Glacial Maximum. The climatic sequence was unstable. Colder and somewhat milder phases altered the reach of ice, the extent of open ground, vegetation and animal movement. The later maximum expansion of the British–Irish Ice Sheet lay ahead, principally after about 27,000 cal BP, although ice was already an important and growing force in northern and upland parts of the region. One should not imagine a fixed national landscape: conditions varied sharply between sheltered lowlands, mountain margins, caves, wetlands and areas nearer advancing ice.

Sea levels were much lower than today because large quantities of water were held in continental ice sheets. Ireland’s coastlines and surrounding seas consequently differed radically from modern ones. Yet low sea level does not by itself demonstrate a dry land bridge usable by people or animals at every point. The Irish Sea basin, local ice masses, changing shorelines and routes across exposed or shallow terrain

make the geography of movement difficult to reconstruct. Faunal evidence shows that large mammals did reach Ireland intermittently during the Late Pleistocene; the precise paths, timing and conditions of each arrival remain matters for investigation.

## **Derryvree's Periglacial Wetland**

The clearest environmental evidence relevant to this broad horizon comes from Derryvree near Maguiresbridge, County Fermanagh. Road cutting through a drumlin exposed freshwater silts and fine sands sealed between two tills: a rare survival of an organic landscape episode between glacial advances. The deposit produced a conventional radiocarbon age of 30,500  $\pm$  1,170/–1,030 BP. That is not an exact equivalent of 30,989 BCE, and its calibrated age is a range rather than a point. It nevertheless places the deposit in the Middle Midlandian, or MIS 3, world broadly relevant to this article.

Its pollen, plant macrofossils, mosses and insects indicate an open, treeless tundra or muskeg environment: wet ground with shallow pools, sedges, mosses and herb-rich vegetation, affected by severe frost and short summers. Finds included plants adapted to cold, exposed conditions, among them dwarf willow, mountain avens, sedges, clubmosses and the aquatic bogbean. Such remains are evidence, not illustration. They establish that at least one part of Fermanagh supported freshwater habitats and sparse tundra vegetation during a cold interval. They do not allow us to map every hill, valley or coastline across Ireland in a single season.

Derryvree also cautions against treating Ice Age Ireland as lifeless. It was austere, but ecologically varied. Pools and wet hollows could sustain aquatic plants; mossy, waterlogged ground trapped pollen and insect remains; drier patches carried scattered herbs and grasses. The seasonal rhythm was probably exacting: long cold winters, frost-disturbed soils, limited woody cover and a brief growing period. There is no evidence here for farming, managed pasture or deliberate landscape clearance. This was a world shaped by climate, water, animals and ice rather than by settled human land use.

## **Castlepook's Animal Archive**

In the south, Castlepook Cave near Doneraile in County Cork is the key faunal archive. Also called Mammoth Cave, it lies in the Awbeg Valley beneath the Ballyhoura Hills. Excavations undertaken between 1904 and 1913 recovered a remarkable assemblage, but their early date matters: bones came from complex cave passages, sands, fissures and deposits disturbed over long periods by water, collapse, carnivores and excavation itself. Castlepook is therefore not a neatly sealed campsite or a single contemporaneous animal bone-bed.

Even with that warning, the cave demonstrates that Ireland was repeatedly part of a wider north-west European animal world before the Last Glacial Maximum. Its recorded cold-stage fauna includes woolly mammoth, reindeer, giant deer, brown bear, wolf, Arctic fox, mountain hare, stoat, collared and Norwegian lemmings, and spotted hyaena. Improved radiocarbon methods have revised some older measurements substantially, underlining why individual dates from historical collections must be treated carefully. The strongest conclusion is that the cave accumulated evidence from more than one Late Pleistocene episode, not that every species stood together in the Awbeg Valley in 30,989 BCE.

For the broad period around 32,900 cal BP, reindeer are particularly evocative but should not be romanticised. Their presence indicates open-country grazing opportunities and ecological connection with Britain and continental Europe. Mammoth and giant deer point to a large-herbivore fauna capable of exploiting cold landscapes, while lemmings and Arctic fox reinforce the northern character of parts of the

environment. Spotted hyaenas are especially significant. Their bones, teeth and coprolites, together with gnawed material, suggest that caves could function as carnivore dens or scavenging places. A bone in Castlepook need not record where an animal died, nor even where it was first consumed.

## **The Marked Reindeer Femur**

A reindeer femur from the Castlepook collection has transformed discussion of this period. It carries a deep linear modification interpreted by zooarchaeologist Ruth Carden as a cut or chopping mark made with a sharp stone implement on fresh bone. Public heritage material assigns the specimen broadly to about 31,000 BC, while news reporting has described it as approximately 33,000 years old. These are useful broad guides, not an annual date or a published stratigraphic horizon that can be equated precisely with 30,989 BCE.

If the mark is confirmed as humanly made and contemporary with the animal's death, it is important evidence for Upper Palaeolithic processing of a reindeer in Ireland. It would imply at least a brief human incursion into the island during the last Ice Age, vastly earlier than the secure record of post-glacial settlement. It might represent hunters using a stone edge to dismember a carcass, perhaps somewhere outside the cave before a scavenger carried part of it inside. That is a reasonable interpretation of a modified animal bone; it is not evidence for a permanent village, a large population or a named people.

Equally important is what has not yet been found for this horizon. There is no securely associated hearth, stone-tool assemblage, dwelling floor, burial, art panel or repeatedly occupied camp published from Castlepook. There are no human bones. Recent excavation has sought intact deposits and further evidence, but the old collection cannot by itself resolve every question. The femur is best understood as a potentially momentous, tightly limited clue: it may record an action by one or more people, rather than continuous habitation.

## **Society Without States**

Political affairs, diplomacy and warfare cannot responsibly be reconstructed for Ireland at this date. There were no known states, kingdoms, chiefs, boundaries or written agreements, and no evidence from Ireland for a local community with institutions that can be described in those terms. Nor is there evidence for religious monuments, formal burials, ritual practice, language, storytelling or teaching. Silence in the archaeological record is not proof that people lacked social lives or beliefs; it means that no specifically Irish evidence survives that can identify them.

If the Castlepook bone represents human activity, the most that can be inferred is a small, mobile group capable of using a stone cutting tool and exploiting a large animal. Comparable Upper Palaeolithic communities elsewhere in Europe possessed sophisticated knowledge of animal behaviour, weather, materials and seasonal movement. They made tools, clothing and shelters, and maintained social connections across considerable distances. Such wider European evidence provides context, but it must not be converted into an invented Irish camp, trade network, ritual system or artistic tradition. No Irish artefact of this age has yet established such particulars.

## **Movement, Not Trade**

The relevant economy was ecological rather than commercial. Reindeer, mammoth, giant deer and smaller mammals moved through shifting habitats; carnivores followed prey and scavenging opportunities; any human visitors would have depended upon mobility, knowledge and portable technology. “Trade” is too strong a word for the evidence. There are no identified imports, exchange goods, quarries, workshops or routes in Ireland from around this date. What can be said is that animal dispersal and any possible human movement connected Ireland intermittently to the wider north-west European world before ice and changing seas later made those connections more difficult.

The chief development around 30,989 BCE was thus environmental precariousness. Ireland was an Ice Age landscape of open tundra, cold wetlands, caves, large herbivores and formidable predators, moving towards more extensive glaciation. Derrynvree preserves a northern wetland snapshot; Castlepook preserves a southern faunal archive and perhaps a trace of human butchery. Together they offer a richer picture than an empty frozen island, while firmly limiting what can be claimed about people. This is not yet the history of an Irish society in the later sense. It is the deep prehistory of a changing island at the north-western edge of Eurasia.

# Chapter 013 of 100

## 30988 BCE

### Hyaena Hall and Derryvree<sup>[13]</sup>



**30,988 BCE is not a year that can be recovered from an Irish annal, settlement sequence or historical calendar. It is a modern retrospective label, roughly 32,937 years before AD 1950, imposed upon a much less precise prehistoric record. No evidence can identify an event, individual, community or seasonal occurrence in Ireland in this particular numbered year. The responsible subject is instead a broad interval of the Late Pleistocene, within Marine Isotope Stage 3, when climates fluctuated sharply, glaciers advanced and retreated, and the landscapes available to animals – and perhaps occasionally to people – changed dramatically.**

Radiocarbon dates provide ranges rather than historical timestamps, and their conversion into calendar ages depends on calibration curves. This is particularly important beyond 30,000 years ago, when the relationship between radiocarbon years and calendar years is neither simple nor exact. Ireland around this point is therefore illuminated by deposits and bones dated across centuries or millennia. The evidence is geographically patchy: an exceptional freshwater deposit at Derryvree, near Maguiresbridge in County Fermanagh, and a complex animal-bone archive at Castlepook Cave near Doneraile in north County Cork are especially significant. Neither should be mistaken for a record of the whole island on one day.

## **A Cold-Stage Ireland**

The period belonged to the Midlandian, Ireland's last major glacial cycle. It preceded the fullest expansion of the Last Glacial Maximum, when the British–Irish Ice Sheet reached its greatest known extent around 23,000 years ago. That later maximum should not be projected uncritically backwards. Evidence now suggests a more dynamic history: ice existed and grew during earlier cold phases, but its

precise limits during Marine Isotope Stage 3 remain debated. At approximately 31,000 BCE, some regions may have been ice-covered or affected by nearby ice margins while others retained exposed ground, wetlands and animal habitat.

Such regional variation is crucial. Ireland was not uniformly a featureless white wilderness, nor can it be reconstructed as a continuously habitable open plain. The ice sheet, sea level, permafrost-like ground conditions, snow cover and vegetation changed over long intervals. Later glaciers also eroded or buried much of the evidence. The apparent scarcity of archaeological sites may therefore reflect a genuine scarcity of people, but it also reflects the destructive power of ice, water and time. What survives is a selective archive rather than a complete census of life.

## **Derryvree's Freshwater Window**

At Derryvree, roadworks in 1969 cut through a drumlin and exposed freshwater silts and fine sands sealed between two distinct tills, the unsorted deposits left by glacial ice. The organic layer produced the conventional radiocarbon determination BIRM-166, 30,500  $\pm$  1,170/–1,030 radiocarbon years BP. That determination has a substantial uncertainty and requires calibration; it cannot responsibly be equated with 30,988 BCE. Yet it provides a rare, nearby environmental window onto the severe conditions of the wider period.

The fossil record at Derryvree indicates a cold, predominantly treeless tundra or muskeg environment. Pollen was poorly preserved, but herbaceous taxa, sedges and mosses were important. Plant macrofossils included bogbean and mountain-avens, while the wider assemblage also contained cold-adapted plants such as dwarf willow, rosy saxifrage and alpine clubmoss. These remains show that the ground was not simply sterile: summer thaw and shallow water supported specialised vegetation. At the same time, the assemblage offers no basis for imagining woodland, farming country or a settled human landscape.

“Tundra” is useful shorthand but can conceal variety. Derryvree is better envisaged as a mosaic of wet sedge margins, mossy ground, shallow pools, slow-moving freshwater, sparsely vegetated mineral surfaces and patches of drier exposed terrain. Insects and plants point to harsh periglacial conditions, with a short growing season and long, severe winters. The organic bed establishes that south Fermanagh was ice-free at some point within its dated interval; it does not prove that every Irish region was simultaneously free of glacier ice, nor that the wetland persisted unchanged for millennia.

## **Ice, Water and Changing Ground**

The two tills enclosing the Derryvree deposit make the wider story especially vivid. Before the freshwater sediments accumulated, ice had crossed the district. After vegetation and wetland conditions developed, ice returned and buried the landscape beneath further glacial sediment. This sequence demonstrates environmental change rather than a stable Ice Age equilibrium. In practical terms, a pool, animal corridor or plant community could be created, altered or erased as climate changed and ice margins shifted. The rolling drumlin landscapes familiar in parts of modern Ireland are later expressions of this powerful glacial remodelling.

For animals, accessible land and reliable water mattered more than any modern county boundary. The position of coastlines was also different because global sea level was lower during the cold stage, although the exact availability of routes between Ireland, Britain and continental Europe changed through



time. The Irish evidence does not permit a map of a particular migration route in 30,988 BCE. It does show, however, that Ireland participated intermittently in the wider north-west European world of cold-adapted mammals and predators.

## Castlepook's Animal Archive

Castlepook Cave, also called Mammoth Cave, is the richest Irish site for vertebrate remains from the period leading towards the Last Glacial Maximum. Excavations begun in the early twentieth century recovered more than 2,000 bones from a cave system whose evocative chambers include Hyaena Hall and Elephant Hall. Its fauna includes woolly mammoth, giant deer, reindeer, brown bear and spotted hyaena; later cold-stage deposits also produced lemmings, Arctic fox and wolf. A spotted-hyaena skull from the cave is held by the National Museum of Ireland.

These animals do not necessarily represent a single local herd, one season or even one climate phase. Castlepook was a repository into which bones could arrive through carnivore activity, natural deaths, flowing water and disturbance over a long span. Modern redating has also shown that older radiocarbon determinations from Irish caves can require substantial revision when improved pretreatment methods are used. The cave's value lies precisely in its long, complicated archive; its limitation is that it cannot be read as a neatly stratified hunting camp.

Nevertheless, the fauna firmly supports the existence of open-country habitats capable of sustaining large herbivores and their predators during parts of the period. Reindeer are especially suggestive of cold, seasonal landscapes, while mammoth and giant deer indicate substantial grazing resources somewhere within the wider region. Spotted hyaena adds an important corrective to romantic visions of an empty wilderness: large carnivores were active agents, transporting carcass parts and shaping what entered caves. Hyaena Hall was not a human monument; it was part of an ecological landscape in which predators, scavengers and water all affected the fossil record.

## The Reindeer Femur Question

A reindeer femur from Castlepook has made this period unusually important for Irish prehistory. It has been reported as carrying a deep linear mark interpreted as a cut or chopping trace made by a sharp stone tool while the bone was fresh. County Cork's heritage publication assigns the object broadly to about 31,000 BCE. If the interpretation of the mark is sustained, it would be striking evidence that a person handled and butchered a reindeer in Ireland far earlier than the traditionally accepted terminal-Pleistocene human evidence.

That conclusion must remain conditional. The date of a bone establishes when the animal died within a probability range; it does not automatically prove the exact moment when a surface modification was made. Nor does one marked bone establish a settlement, a population, a hunting territory or a repeated route. No securely associated hearth, stone-tool assemblage, dwelling floor, burial or excavated camp of comparable age has yet been published from Ireland. The most responsible reading is that Castlepook presents an important claim for early human activity, not proof of a resident Upper Palaeolithic society.

## Society Without a Chronicle

Accordingly, political affairs, diplomacy, warfare, named leaders and institutions cannot be reconstructed for Ireland at this date. There are no texts, monuments or securely recognised settlements from which to infer a polity. It would be equally unsafe to assign language, ethnicity, religion or ancestry to any possible visitors. If people did reach the island, they may have travelled in small, mobile groups equipped to exploit a demanding seasonal environment; but this is an inference from broader Upper Palaeolithic patterns in Europe, not a demonstrated fact about an Irish community.

The same caution governs everyday life and economy. Hunting, scavenging and the use of animal resources are plausible activities in a landscape containing reindeer and other large mammals, and the proposed femur mark is relevant to carcass processing. Yet Ireland has yielded no securely dated toolkit, camp refuse, food store, shelter or clothing evidence from around this time. There is no evidence for agriculture, livestock, craft production, market exchange or long-distance trade networks based in Ireland. Mobility, rather than permanent settlement, is the only possibility suggested by the limited record, and even that cannot be quantified.

Religion, art and formal learning likewise leave no identifiable Irish trace from this horizon. The survival knowledge required in cold conditions – reading animal movement, weather, snow, water and fuel – would have been considerable if people were present, but it cannot be recovered as a documented tradition. Ireland's cultural history at this date is therefore chiefly a history of landscapes and evidence: the ability of pollen, seeds, mosses, bones, cave sediments and radiocarbon samples to preserve fragments of a vanished world.

## What Can Be Said Responsibly


Ireland around 30,988 BCE was part of a changing cold-stage environment, not a country with an annual political history. Derryvree shows that freshwater wetlands and treeless, cold-adapted vegetation could exist in Fermanagh between glacial episodes. Castlepook demonstrates that an imposing Ice Age fauna, including mammoth, reindeer and hyaena, occurred in Cork across a long and complex span. A cut-marked reindeer femur may point to an exceptionally early human encounter, but it cannot yet bear the weight of a story about settlement or society.

The most important development was environmental instability: ground became available, wetlands formed, animals moved through open habitats, and advancing ice later transformed the evidence. Continued excavation at Castlepook, improved radiocarbon pretreatment, new palaeoenvironmental studies and reassessment of museum collections may refine this picture. For now, the soundest history of this deep past remains deliberately modest – a cold, living Ireland known through a Fermanagh wetland, a Cork cave and the uncertainties that make their evidence valuable.

# Chapter 014 of 100

## 30987 BCE

### Castlepook's Mammoth Bones<sup>[14]</sup>



**“30,987 BCE” is a modern chronological label, not a year in which an Irish event can be narrated. No calendar, written record, named people or datable political episode survives from this depth of time. In relation to the archaeological convention of “before present”, fixed at AD 1950, the label lies about 32,936 years ago. It belongs to the Late Pleistocene, within Marine Isotope Stage 3, a climatically unstable part of the last Ice Age. Modern calendar-year precision is unavailable: radiocarbon determinations must be calibrated, have uncertainties, and date particular organic remains rather than an entire landscape. The responsible subject is therefore Ireland in a broad interval around 33,000 calibrated years before present, not an invented occurrence on a particular day.**

## **A Landscape Before Maximum Ice**

This was not yet the fullest extent of the Last Glacial Maximum. The British–Irish Ice Sheet grew markedly after this period and reached its broad maximum later, roughly between 26,500 and 19,000 years ago, although timings differed between regions and ice lobes. Around the date represented by 30,987 BCE, parts of Ireland were ice-free, while others were affected by advancing ice, intense frost action and changing drainage. It would be misleading to picture the whole island either as a single ice cap or as a hospitable, continuous grassland. Conditions changed sharply through time and varied with altitude, latitude, proximity to ice and local topography.

The most useful Irish evidence close to this broad horizon comes from deposits which escaped later destruction only by unusual good fortune. At Derryvree, near Maguiresbridge in County Fermanagh, road works exposed freshwater silts and fine sands trapped between two layers of glacial till. The lower till records an earlier advance of ice; the organic sediments record an ice-free interval with standing or slow-

moving water; the upper till shows that a later glacier again overran the district. That sequence is a powerful record of environmental change, but it is not a diary. Its radiocarbon age of  $30,500 \pm 1,100$  radiocarbon years BP has been calibrated broadly to about 36,900–31,700 cal BP. The latter range overlaps the notional year, but cannot place a particular plant, animal or person in 30,987 BCE itself.

## Derryvree's Cold Wetland

Derryvree supplies an unusually detailed image of an Irish environment during this pre-maximum cold phase. Fossil pollen, plant macrofossils and insects indicate open, treeless ground and a wet, moss-rich landscape often described as muskeg or tundra wetland. Sedges and grasses grew beside pools and waterlogged ground. Finds include mountain avens, dwarf willow or willow-type vegetation, juniper, clubmosses and the aquatic plant bogbean. Such a community was not a modern Irish bog transplanted into the past. It belonged to a cold, periglacial world, with long severe winters, short growing seasons and ground repeatedly affected by freezing and thawing.

Its significance lies partly in correcting an easy misconception. Ice-Age Ireland was not always featureless ice. In suitable ice-free intervals, freshwater habitats could sustain a varied small-scale ecology: aquatic plants in pools, mosses and sedges around their margins, insects feeding or breeding among decaying vegetation, and hardy herbs on better-drained ground. The evidence does not establish a uniform island-wide climate on a single date. It does demonstrate that northern Ireland contained, at some point within the Derryvree interval, a cold but biologically active wetland between glacial advances.

There was no humanly managed countryside. There were no fields, livestock, houses, roads or permanent settlements known from Ireland at this age. The familiar wooded appearance of later prehistoric and historic Ireland had not developed. Indeed, the Derryvree evidence is valuable precisely because later ice, erosion and sea-level change eliminated so much of the older record. The present terrain—its drumlins, soils, river courses and shorelines—cannot simply be projected backwards. A large part of the physical stage on which later Irish history unfolded was still being remade.

## Castlepook's Animal Record

Far to the south, Castlepook Cave, also called Mammoth Cave, near Doneraile in County Cork, preserves Ireland's most important collection of pre-Last Glacial Maximum vertebrate remains. Excavations undertaken mainly between 1904 and 1908, followed by later investigation and dating, recovered a striking range of animals. The assemblage includes woolly mammoth, reindeer, giant deer, brown bear, wolf, Arctic fox, mountain hare, lemmings and spotted hyaena. Individual bones and deposits have different histories and dates; they do not represent a single herd, season or perfectly preserved ecosystem. Nonetheless, collectively they establish that Ireland was connected to wider north-west European faunal worlds during favourable phases of the Late Pleistocene.

Reindeer, lemmings and Arctic fox are strong indicators of open, cold habitats. Mammoth and giant deer show that substantial herbivores reached the island, while wolves and hyaenas reveal a food web with large predators and scavengers. Castlepook should not be imagined as a calm procession of animals through a cave. Hyaenas may have carried bones into its passages, gnawed them or disturbed them; water, sediment movement and later excavation also altered the deposits. A cave bone demonstrates that an animal, or material containing it, reached that location. It does not by itself reveal whether the species was abundant throughout Ireland, whether it was present in the same generation as another species, or how long it persisted.

Recent sedimentary ancient-DNA work at Castlepook has added genetic evidence for several taxa, including woolly mammoth and cave hyaena, and suggests links with wider Eurasian populations before the Last Glacial Maximum. This is an important developing line of research, though the 2026 study remains a preprint rather than a final peer-reviewed publication. Its main value for this date is cautious: it strengthens the case for repeated faunal connectivity, not a claim that a particular migration route or an exact animal population can be mapped in 30,987 BCE.

## The Human Question

The greatest uncertainty concerns people. A reindeer femur from Castlepook has been reported as approximately 33,000 years old and as carrying a deep mark interpreted by zooarchaeologist Ruth Carden as damage made to fresh bone with a sharp stone implement. If that interpretation survives further study, it may be evidence that Upper Palaeolithic people butchered or otherwise processed reindeer in Ireland during a broadly comparable interval. It would be a major revision to the traditional chronology, which long placed the first direct evidence for people in Ireland much later, near the end of the Pleistocene.

Yet this is not proof of an established Irish population. The specimen originated in an old cave collection, excavated before modern stratigraphic methods and without a securely associated hearth, stone-tool assemblage, dwelling floor, burial or occupation surface. Radiocarbon dating establishes the age of the animal bone, not automatically the date or agent of every surface modification. Nor can one potentially cut-marked bone decide whether visitors stayed briefly, returned seasonally, travelled in a small party, or left descendants. Continuing work at the cave is searching for undisturbed deposits and directly associated evidence. Until such evidence is found, the most defensible conclusion is that an early human visit is possible and consequential, but unconfirmed as a settled community.

For that reason, political affairs, diplomacy and organised warfare cannot responsibly be described. There are no rulers, tribes, languages, territories or alliances known for Ireland at this date. Terms such as Gaelic, Celtic and Irish belong to immensely later contexts and should not be projected backwards. Equally, there is no direct Irish evidence for religion, ritual, art, formal learning or social rank. The absence of evidence does not mean Ice-Age people elsewhere lacked stories, beliefs, skills or complex relationships; it means that no surviving Irish material permits these to be specified here.

## Mobility Without a Recorded Society

If people did reach Ireland in this era, their survival would have depended on mobility, close knowledge of seasonal animal movements, fire, clothing, shelters and tools, as among Upper Palaeolithic communities elsewhere in Europe. But this is an inference from neighbouring regions, not an excavated Irish way of life. No Irish flint-working site, camp refuse, hearth or built shelter currently demonstrates such activity around 33,000 cal BP. Economy and exchange therefore cannot be reconstructed as local institutions. The animal evidence does, however, show that the island formed part of a changing ecological zone in which large mammals could disperse when coastlines, sea levels, ice barriers and terrain allowed.

Lower global sea levels altered the geography of the Irish Sea region, but a simple, permanent “land bridge” is not an adequate explanation. Routes between Ireland, Britain and continental Europe shifted as sea level fell, ice margins advanced or retreated, and water or ice blocked different corridors. The exact route used by mammoths, hyaenas, reindeer—or any people—is unknown for this particular interval.

Ireland's prehistory at 30,987 BCE is thus not the beginning of a continuous national story. It is a brief window on a cold, dynamic frontier, preserved in Fermanagh wetland sediments and Cork cave bones, and framed by large uncertainties that are themselves central to the history.

# Chapter 015 of 100

## 30986 BCE

### Ireland's MIS Three Tundra<sup>[15]</sup>



**“30,986 BCE” is a modern, retrospective label, not a date that anyone living in Ice Age Ireland could have recognised. At this depth of time, modern calendar-year precision is unavailable. The label corresponds broadly to about 32,935 calendar years before present, where “present” conventionally means 1950. The responsible way to approach it is through radiocarbon ranges, calibrated calendar ranges and geological sequences. The strongest Irish evidence places this notional year within the later part of Marine Isotope Stage 3, a cold and highly variable interval before the Last Glacial Maximum. It does not permit a diary-like account of one year, a named community or a political event.**

## **A Date Within a Broad Window**

The closest securely relevant environmental sequence is at Derryvree near Maguiresbridge, County Fermanagh. There, roadworks exposed organic silts and fine sands trapped between two layers of glacial till in a drumlin. The order of deposits is crucial. Ice had laid down the lower till; open water, plants and sediment later accumulated without local glacier cover; then a further ice advance sealed the freshwater deposits beneath the upper till. Organic material from this interval produced a conventional radiocarbon determination of 30,500 radiocarbon years before present, with a substantial uncertainty. Calibration gives a broad range of roughly 36,900–31,700 calendar years before present, or approximately 34,950–29,750 BCE.

Thus 30,986 BCE falls within the broad calibrated span associated with the Derryvree deposits, though not at a point that can be isolated within them. The date is best understood as an informed environmental horizon rather than an anniversary. Radiocarbon years are not identical to calendar years

because atmospheric carbon-14 levels have varied; calibration is especially important, and uncertainty necessarily widens, so far back in time. Nor can one Fermanagh exposure be treated as a weather station for every valley, coast and upland across the island.

## **The Derryvree Landscape**

Derryvree offers an unusually intimate glimpse of Irish conditions before the later ice sheet remade much of the landscape. Fossil pollen, plant remains, mosses and insects indicate open, treeless ground rather than woodland. Grasses, sedges, herbs, juniper and cold-adapted wetland plants occurred around shallow freshwater pools and saturated ground. Researchers have described the setting as tundra or muskeg: a waterlogged mosaic of sedge-rich vegetation, mossy surfaces, plant litter and patches of open water, shaped by severe cold and periglacial processes.

This was not a featureless white desert. During the short growing season, low vegetation could flourish in sheltered, wet places, while winter frost, snow cover, frozen ground and strong seasonality imposed severe limits. The evidence supports a cold, open landscape with freshwater habitats; it does not establish exact temperatures, annual snowfall or a uniform island-wide biome. The term “tundra” is a useful ecological shorthand, but the ancient environment was a changing local mosaic rather than a modern Arctic landscape transplanted wholesale to Ireland.

At this time the last British–Irish Ice Sheet was building towards a much larger expansion, but it had not yet erased every ice-free refuge or wetland record. Derryvree and other pre-maximum deposits demonstrate that parts of north-central Ireland were free of local ice during portions of the preceding interval. Greenagho, also in Fermanagh, preserves another organic deposit beneath till. Together such sites show alternating conditions of ice occupation and ice-free sediment accumulation. They do not prove that the whole of Ireland was simultaneously clear of ice, nor that all regions experienced precisely the same sequence.

## **Caves, Carrion and Large Mammals**

In north County Cork, Castlepook Cave near Doneraile provides the principal Irish animal archive relevant to this deep period. Its old collections contain remains attributed to reindeer, woolly mammoth, spotted hyaena, brown bear, Arctic fox, hare, wolf and small cold-country mammals. Such animals evoke an open, productive but demanding landscape in which grazing herds, predators and scavengers could move through the wider region. Reindeer are especially consistent with sparse, open vegetation; mammoth and hyaena reveal that Ireland’s Ice Age fauna was once much richer than its later historical fauna.

Yet cave bones are not a straightforward census of an outdoor community. Castlepook was used and altered by carnivores, water movement and later human excavation. Carnivores could have dragged carcass parts into galleries; bones may have accumulated across many generations; and early twentieth-century collecting did not preserve the fine stratigraphic detail expected in modern excavation. The cave therefore demonstrates the presence of animals in the wider region over extended periods, not a single simultaneous herd gathered at one spot in 30,986 BCE.

Dating adds another necessary caution. Early radiocarbon determinations from Castlepook helped associate mammoth and hyaena with the cold phase represented by Derryvree, but later scholarship has reassessed the reliability and limits of some old bone dates. The broad conclusion remains robust: a distinctive pre-Last Glacial Maximum fauna occupied southern Ireland during Marine Isotope Stage 3.



The precise ages, overlap and duration of individual species are less secure than popular summaries sometimes imply. Evidence must be allowed to be uneven without turning uncertainty into a more dramatic story.

## The Human Question

The most consequential possibility is a reindeer femur from Castlepook reported to bear a deep incision interpreted as a stone-tool butchery mark. Its public presentation has linked it to approximately 31,000 BCE and suggested that people may have handled a reindeer in Ireland far earlier than the formerly accepted Late Upper Palaeolithic evidence. If that interpretation is sustained, it would indicate only a small episode of carcass processing: perhaps hunters, perhaps people exploiting an animal already dead, and perhaps activity undertaken away from the cave before part of the carcass reached it.

It would not demonstrate a settled population, a village, a seasonal camp, a named culture or continuous occupation. No securely associated stone-tool assemblage, hearth, dwelling floor, burial or art of this age has yet been recovered in Ireland. The National Museum of Ireland's cautious framing of the Palaeolithic record remains important: unequivocal evidence for sustained human presence is extraordinarily scarce. The better-established butchered brown-bear bone from Alice and Gwendoline Cave, County Clare, is far later, dating to about 12,800–12,600 calibrated years before present.

For 30,986 BCE, therefore, human presence is a research question rather than a settled chapter of national history. Continental north-west Europe and parts of Britain were inhabited by Upper Palaeolithic hunter-gatherers during Marine Isotope Stage 3. That wider context makes short visits or movement into Ireland conceivable, but possibility is not proof. Lower sea levels changed coastlines and exposed land now underwater, while ice, sea, rivers and local topography created shifting barriers. A lowered sea alone does not demonstrate an easy land bridge, much less a documented route into Ireland.

## Society Without a Settlement Record

Because the material record contains no known settlement of this age, political affairs, diplomacy and organised conflict cannot responsibly be reconstructed. There are no Irish chiefs, territories, alliances, weapons caches or fortifications to describe. Nor is there evidence for farming, animal husbandry, trade networks, pottery, metalworking or long-distance exchange. Even if people did visit the island, the most restrained interpretation is of small, mobile foraging parties whose material traces have either not survived, lie beneath later deposits or remain undiscovered.

The same restraint applies to religion, culture and learning. Human communities elsewhere in Upper Palaeolithic Europe made tools, ornaments, images and musical objects, but none can be assigned to Ireland at this date. It would be misleading to project continental cave art, ritual or social arrangements across the Irish Sea merely because they were broadly contemporary. Ireland's record instead preserves environmental knowledge: pollen grains, seeds, insect fragments, cave bones, sediment layers and the glacial deposits that enclosed them.

Everyday life can be described more confidently for the animals than for people. Reindeer and other herbivores would have followed forage across open ground; carnivores and scavengers exploited them; pools and wet mosslands supported specialised plants and insects. The economy visible here is ecological, not human: seasonal primary production, grazing, predation, scavenging and decomposition. In a cold, unstable climate, access to sheltered ground, unfrozen water and patches of edible vegetation would have mattered as much as any broad regional pattern.

## Approaching the Ice Maximum


The long-term direction was towards greater glaciation. Within several millennia, the Last Glacial Maximum brought the Irish Ice Sheet to far greater extent, burying and reshaping large areas and helping to remove or conceal earlier evidence. Drumlins, tills and glacially scoured rock are the surviving consequences, but they also explain the archival gaps. The prehistoric Ireland of 30,986 BCE is therefore known chiefly through rare deposits that escaped complete destruction and through cave collections assembled before modern archaeological methods.

This makes the period important precisely because it resists easy narrative. Around this notional year, Ireland was neither the familiar green island of later farming communities nor simply an empty white ice field. The best evidence points to cold, open and locally wet terrain, with freshwater pools in Fermanagh and a striking large-mammal fauna in Cork. Whether humans briefly entered that world remains a significant but unresolved question. The honest history of 30,986 BCE is one of tundra, animals, advancing ice and carefully bounded inference.

# Chapter 016 of 100

## 30985 BCE

### Ussher's Reindeer Femur<sup>[16]</sup>



## A Year Beyond the Calendar

**30,985 BCE cannot be treated as a year in the ordinary historical sense. No written records, named individuals, political events or securely dated occupations allow an annal for this point in Ireland's past. Modern calendar precision is unavailable. The date is best understood as a convenient position within the Late Pleistocene, during Marine Isotope Stage 3 (MIS 3), a long and climatically unstable phase of the last Ice Age.**

In calendar terms, 30,985 BCE lies about 32,934 years before AD 1950, the conventional "present" used in radiocarbon reporting. Yet a radiocarbon determination does not translate into a single historical date. Carbon-14 levels in the atmosphere changed through time, samples may carry their own uncertainties, and calibration produces ranges rather than exact points. The responsible history of Ireland at this notional date is therefore an account of landscapes, animals, sediments and the extremely limited possibility of human activity, not a claim that a particular event occurred in this particular year.

The strongest Irish environmental evidence close to this horizon comes from Derryvree, near Maguiresbridge in County Fermanagh. There, roadworks exposed a remarkable deposit sealed inside a drumlin: freshwater silts, sands and organic material lay between two tills, the unsorted debris left by separate glacier advances. The sequence shows that ice had occupied the district, then withdrew or ceased to cover the immediate site long enough for water, sediment and plants to accumulate, before a later ice advance buried the deposit.

Organic material from Derryvree produced the radiocarbon determination BIRM-166, conventionally dated to about 30,500 radiocarbon years before present, with a substantial uncertainty. Later discussion places the deposit broadly around 36,900–31,700 calibrated years before present, approximately 34,950–

29,750 BCE. This is a wide span, not a timestamp for a pond, a plant or an animal. It nevertheless makes Derryvree one of the best windows onto the kind of Irish environment that may have existed around 30,985 BCE.

## Fresh Water Between Ice Advances

Derryvree was not a green, wooded Ireland. Pollen, plant macrofossils and insect evidence from the inter-till deposits indicate a treeless, cold environment, with open vegetation and wet ground. Mosses, sedges, dwarf shrubs and hardy arctic-alpine plants could survive around shallow pools, marshes and sluggish watercourses. Bogbean, water-milfoil and other aquatic or waterside plants show that fresh water was present; mountain-avens, dwarf willow and clubmoss point towards exposed, tundra-like ground nearby.

This should not be imagined as a uniform white wilderness. Even in severe climates, sheltered hollows, streams, thawed margins and wet basins could sustain different plant communities from the surrounding drier ground. The word “tundra” is useful only if it conveys this patchiness. Derryvree records a cold, open wetland mosaic, not an exact photograph of all Ireland. Conditions varied with altitude, distance from ice, drainage and the changing North Atlantic climate.

The two tills are equally important. They demonstrate that this landscape was precarious in geological time. An ice-free or lightly glaciated interval could be replaced by renewed ice cover, grinding, transporting and sealing sediments beneath fresh debris. Around this date the British–Irish Ice Sheet had not yet reached its later maximum extent, generally placed between roughly 26,000 and 20,000 years ago, but ice-sheet growth and regional glacier activity were already transforming the island and its surrounding seas. Ireland’s surface was a shifting frontier between ice, periglacial ground and locally habitable open country.

## Animals of an Open Landscape

Southern Irish cave deposits provide a complementary, if less neatly stratified, record. Castlepook Cave, also known as Mammoth Cave, near Doneraile in north County Cork, produced bones recovered during excavations led by Richard J. Ussher in the early twentieth century. The collections include remains associated with a markedly different Ice Age fauna: reindeer, woolly mammoth, giant deer, brown bear, wolf and spotted hyaena are among the animals discussed in research on Ireland’s MIS 3 caves.

Such animals were not all necessarily present together on one day, in one valley, or even in the same climatic phase. Cave deposits are often accumulations made over long periods, disturbed by burrowing, water, collapse, scavengers and earlier excavation. Re-dating work has also shown why old bone dates must be revisited as laboratory methods improve. Castlepook therefore offers a regional faunal archive, not a census for 30,985 BCE.

Even so, its evidence makes the Derryvree landscape more intelligible. Reindeer are well suited to open, cold country and could have exploited seasonal vegetation over wide ranges. Mammoths and giant deer needed substantial forage, though their exact habitat preferences and movements differed. Carnivores and scavengers, including hyaenas, were part of the same food web. Their presence cautions against sentimental visions of an empty Ice Age. Ireland contained dangerous competitors as well as potential prey, and caves may often have been carnivore shelters or bone accumulators rather than human dwellings.

Sea level was lower globally than it is now because great volumes of water were stored in ice sheets. The outlines of Ireland, Britain and the Irish Sea were consequently unlike those of the modern map. But lowered sea level did not automatically create an easy, continuous walking route from continental Europe to Ireland. The channels, shelves, glaciers and shorelines of the western archipelago changed repeatedly. Any movement of animals or people must be considered in that dynamic geographical setting rather than assumed from a modern atlas.

## **The Castlepook Human Question**

The closest possible evidence for people in Ireland at this depth of time is also the most controversial in historical terms: a reindeer femur from Castlepook reported to bear a deep mark interpreted as a stone-tool cut made during butchery. Public presentations describe the bone as Palaeolithic and approximately 31,000 BCE. If the mark is securely anthropogenic, it would indicate that somebody used a sharp tool on a reindeer in Ireland during the later Ice Age, thousands of years before the better-established Late Upper Palaeolithic evidence from a butchered brown-bear bone at Alice and Gwendoline Cave in County Clare.

That possibility deserves attention, but not exaggeration. The Castlepook femur is not accompanied by a securely associated hearth, stone-tool assemblage, house floor, burial, food store or occupation surface of comparable age. Nor does one modified bone identify its maker as a Neanderthal or a modern human, establish a permanent population, or prove repeated settlement. It may represent a brief visit by a small mobile group, the processing of a carcass elsewhere, and later transport of bone into the cave by carnivores. It remains possible evidence of human action, rather than proof of an Irish community.

This distinction matters especially for society and everyday life. If people reached Ireland during MIS 3, the most cautious inference is that they would have been highly mobile hunter-gatherers, dependent on sophisticated knowledge of animal behaviour, weather, terrain and stone tools. Such a party could have hunted, scavenged or butchered an animal and departed without leaving the kinds of remains archaeologists usually recognise as a settlement. But inference must not replace evidence. We cannot responsibly describe their language, kinship, clothing, leadership, beliefs or route to Ireland.

## **No Politics, No Proven Ritual**

There were no known Irish states, kings, tribes, treaties or diplomatic relations at this date. There is likewise no evidence for warfare, territorial boundaries, formal religion, shrines, burial practice, art, writing or teaching institutions in Ireland around 30,985 BCE. The silence is not evidence that people lacked beliefs, social bonds or customs; all human societies have them. It means that Irish archaeology currently cannot recover them for this period.

Nor is there evidence for farming, herding, metallurgy, pottery, long-distance trade or settled village life. The economy visible in the record is ecological rather than commercial: plants growing in cold wet ground; herbivores grazing and moving across open country; carnivores hunting or scavenging; glaciers advancing, melting and reshaping drainage. If people were present, they would have entered this animal world as occasional foragers, not as farmers transforming it.

Learning, in the literal sense, can only be inferred as practical skill: recognising safe crossings, finding stone suitable for cutting edges, reading tracks, anticipating seasonal change and surviving exposure in a harsh climate. Yet no Irish artefact from this exact horizon demonstrates those skills directly. The potential cut-marked bone is significant precisely because it may preserve a tiny trace of such knowledge, but it cannot carry the weight of an entire lost culture.

## **An Archive, Not an Annal**

The most meaningful development around 30,985 BCE was not a dated human event but a changing environment. Derryvree records freshwater life and open vegetation in an interval between glacial episodes. Castlepook preserves evidence that large mammals ranged through parts of southern Ireland during MIS 3, while its reindeer femur raises an unresolved question about early human presence. Together they show that Ireland was neither simply an ice-covered blank nor a settled prehistoric homeland. It was a climatically severe, ecologically varied and repeatedly disrupted land.

That is the proper scale for this year. Modern historical chronology asks what happened next; Pleistocene evidence asks what survived to be found. At Derryvree, sediment, pollen and plant remains survived beneath a drumlin. At Castlepook, animal bones survived in a cave archive shaped by scavengers, water and antiquarian excavation. They offer no annual narrative, but they illuminate the deep conditions from which Ireland's much later human history eventually emerged.

# Chapter 017 of 100

## 30984 BCE

### Maguirebridge's Tundra Reedbed<sup>[17]</sup>



**“30,984 BCE” is a useful modern label, but it cannot describe a dated Irish event in the way that a later historical year can. No written record, settlement sequence or scientific chronology can resolve one particular calendar year at this depth of time. In calendar terms it falls roughly 32,900 years before AD 1950, within the later part of Marine Isotope Stage 3 (MIS 3), a long and climatically unstable phase of the last Ice Age. The responsible approach is therefore to examine dated ranges and stratified evidence that illuminate Ireland around this broad interval, rather than inventing a happening for the numbered year.**

## **A Landscape Without Annals**

Ireland at this time had no known kingdoms, borders, leaders, diplomacy or historical communities in the usual sense. There was no agriculture, metalwork, pottery, monument building or writing. There is also no securely identified house, hearth, burial ground or tool-making floor in Ireland that can be assigned to 30,984 BCE. Political history is consequently silent, not because prehistoric people necessarily lacked social relationships, but because the surviving evidence does not reveal institutions or named groups.

What survives instead is a difficult archive of cave bone, freshwater silt, fossil plants, insects, glacial sediment and landforms. Each preserves a different part of the past. A bone may demonstrate that an animal lived in Ireland, but not that every species found in the same cave lived together. A bed of silt can record shallow water and vegetation near one former pool, but not the weather of the whole island. Ice-scoured hills and offshore moraines show that ice moved across large regions, but their dates commonly constrain intervals rather than a single season or generation. Around 30,984 BCE, this distinction between evidence and interpretation is fundamental.

## The Derryvree Evidence

The most informative Irish environmental record for the broader period lies at Derryvree, near Maguiresbridge in County Fermanagh. Road works there exposed organic silts and fine sands trapped between two thick sheets of till within a drumlin. This sequence matters because it records a non-glacial interval: after one episode of ice deposition and before another advance sealed the deposits beneath fresh till, open water and wet ground existed at the site.

The original radiocarbon determination from the Derryvree organic beds was 30,500 radiocarbon years before present, with a substantial uncertainty of +1,170 and –1,030 years. That is not the same thing as a precise calendar age, and it cannot identify 30,984 BCE itself. Radiocarbon ages of this antiquity need calibration and carry broad ranges. Yet the stratigraphy securely establishes the important point: at some stage during the Middle Midlandian, broadly within MIS 3, part of Fermanagh was ice-free long enough for freshwater sediment and organic matter to accumulate, before later ice overrode it.

The fossil assemblage gives that interval its character. Mosses, sedges and other wetland plants, alongside bogbean, water-milfoil, dwarf willow and mountain-avens, indicate shallow water, saturated ground and open, largely treeless vegetation. Insects and plant remains point to a cold periglacial regime rather than woodland or temperate pasture. The best picture is not of a uniformly blank, snow-covered island, but of a local mosaic: pools, marshy margins, sedge-rich ground and low tundra-like vegetation exposed to severe winters and short growing seasons.

Derryvree should not be made to stand for all Ireland. It is a small, local archive in northern Ireland, and its preservation between tills tells a story of changing ice margins rather than long-term stability. Still, it is one of the clearest demonstrations that late Pleistocene Ireland contained ecologically productive refuges or intervals of open ground amid a broader world becoming increasingly glacial.

## Fauna at the Atlantic Edge

Irish cave deposits show that large mammals and carnivores reached the island during MIS 3, although the dates and associations of older collections must be handled carefully. Castlepook Cave near Doneraile in north Cork is especially important. Excavated largely in the late nineteenth and early twentieth centuries, it produced an exceptional collection of bones attributed to animals including reindeer, wolf, fox, hare, spotted hyaena, mammoth and giant deer. The cave was used and disturbed over long periods; many specimens lack the fine stratigraphic context expected of modern excavation.

Recent reappraisal has sharpened this warning. Improved pretreatment and radiocarbon methods have shown that some older determinations for southern Irish MIS 3 fauna are unreliable or require revision. The result is not that the animals vanish from the record, but that apparent single “assemblages” cannot automatically be treated as one living community. Mammoth, hyaena, reindeer and giant deer remains may represent different episodes, conditions and routes into Ireland. The presence of carnivore bones can reflect denning, scavenging or the transport of prey into caves, rather than an ordinary view of the open landscape.

There are, however, securely dated indications of large deer in Ireland close to the broad time under discussion. A study of Irish red deer remains identified two pre-Last Glacial Maximum samples from County Waterford caves calibrated to 32,930–31,280 and 30,297–29,594 calendar years before present. These ranges are much more useful than a nominal year: they demonstrate that deer occurred in south-eastern Ireland during late MIS 3, while also making clear that the precise relationship of any one animal to Derryvree, Castlepook or 30,984 BCE cannot be known.



Reindeer are particularly compatible with the open-country setting suggested by Derryvree. They were adapted to cold, sparsely wooded environments and could have ranged across broad tracts of grass-, herb- and shrub-rich terrain. Their fossil presence does not prove regular migration routes through every Irish region, but it confirms that Ireland was connected, at least intermittently, to the wider animal world of north-west Europe. Lower sea levels altered coastlines and passages, while advancing and retreating ice repeatedly changed accessible terrain. It would be unsafe, however, to claim a known land bridge or a specific crossing route for this date.

## The Human Question

The possibility of people in Ireland during this period rests chiefly on a much-debated reindeer bone from Castlepook. A modified reindeer femur has been reported to carry marks consistent with butchery by a stone tool and to date to roughly 33,000 years ago. If the marks are demonstrably human-made and contemporary with the animal's death, the specimen would push evidence for human activity in Ireland far earlier than the long-accepted post-glacial record.

That conditional language matters. One marked bone, recovered from an old cave collection without a modern excavation context, is not evidence for a settled population, a camp, a family group or a continuous Irish Palaeolithic tradition. No associated hearth, lithic assemblage, dwelling surface, human bone or burial currently supplies that missing context. Nor can this evidence identify the language, identity, beliefs or social organisation of any visitors. It supports, at most, a cautious possibility that people handled and butchered a reindeer in Ireland during a late MIS 3 episode.

If humans were present, comparison with Upper Palaeolithic groups elsewhere in north-west Europe suggests highly mobile hunter-gatherers able to exploit animal carcasses, hides, marrow and sinew, and to move through seasonally demanding landscapes. This is an informed analogy, not direct Irish proof. It cannot establish whether people hunted the animal, found it dead, arrived by boat, crossed temporary terrestrial connections, or stayed for days rather than years. For this period, "economy" means animal and plant resources visible in the environmental record, not a demonstrable Irish trading system or settled livelihood.

## Ice Sheet Build-Up

By the time represented by the modern year 30,984 BCE, Ireland was moving towards the major glacial conditions of the Last Glacial Maximum. The British–Irish Ice Sheet did not expand everywhere at once, and later ice margins were highly asynchronous. Modern reconstructions show major Irish and British ice growth during the interval after about 31,000 years ago, with maximum Irish extent achieved much later, around 27,000–26,000 years ago in several western and south-western sectors. Ice subsequently reached the continental shelf edge west of Ireland, while fast-flowing outlet systems developed in places.

Those later reconstructions should not be projected too mechanically backwards. They do show why Derryvree's position between two tills is so valuable: its wetland was part of a changing glacial landscape, not an isolated curiosity. Farther west, mountain evidence and offshore sediment cores reveal the scale eventually reached by Irish ice. Yet the precise extent of ice on any particular Irish coast or upland at 30,984 BCE remains unresolved. Regional variation was considerable, and dated evidence is much denser for the maximum and retreat than for the preceding build-up.

## What Cannot Be Recovered

Religion, art, language and learning leave no secure Irish trace for this moment. A living human group may have carried stories, technical knowledge and ritual practices, but neither Derryvree's plants nor Castlepook's bones can recover them. Equally, there is no basis for imagining tribal territories, conflict, diplomacy or trade networks. The absence of evidence is especially acute because later glaciation eroded landscapes, buried deposits and repeatedly reshaped coasts.

The enduring historical significance of this period is therefore environmental and evidential. Around 30,984 BCE, Ireland was not an empty stage awaiting recognisable history. It was a cold, dynamic Atlantic landscape inhabited by plants and animals whose remains survive in rare pockets, while ice expanded and the routes through north-west Europe changed. The Derryvree freshwater beds demonstrate local wetland life; cave fauna demonstrate shifting ecological links; the Castlepook bone poses an important but still limited human question. Together, they permit a disciplined reconstruction of possibility, while refusing the false certainty of a year-by-year event narrative.

# Chapter 018 of 100

## 30983 BCE

### The Doneraile Femur Debate<sup>[18]</sup>



**30,983 BCE is not a recoverable year in Ireland's human story. It is a modern calendar label for a point roughly 32,900 years before AD 1950, during the Late Pleistocene and broadly within Marine Isotope Stage 3 (MIS 3). No Irish calendar, settlement sequence or historical record can distinguish this particular year from those around it. Radiocarbon measurements at this depth have substantial uncertainties and must be calibrated; they cannot be translated into an exact modern BCE anniversary. The responsible subject is therefore Ireland during a broad late-MIS-3 interval: a climatically unstable, increasingly glacial landscape represented by exceptionally fragmentary environmental and faunal evidence.**

The most important conclusion is also the most limiting. Ireland was not an arena of known kingdoms, tribes, diplomacy or warfare in 30,983 BCE. There are no named communities, human burials, houses, hearths, unequivocal stone-tool scatters, fields or monuments securely dated to this horizon. There is, however, compelling evidence that parts of Ireland sustained cold-stage life before the Last Glacial Maximum, and one remarkable reindeer bone from County Cork that may preserve evidence of human butchery. Its significance is considerable; its limitations are equally important.

## Dating a Changing Island

MIS 3, conventionally dated to about 57,000–29,000 years ago, was not one unbroken deep freeze. It contained abrupt swings between colder stadials and relatively milder interstadials. In Ireland, ice margins, sea level, vegetation and animal ranges responded to these changes on scales far beyond a single year or generation. The date in question falls late in that sequence, as the British–Irish Ice Sheet was

expanding towards its eventual maximum. Recent ice-sheet reconstructions show that growth and maximum extent were not simultaneous everywhere: sectors advanced and retreated differently, and the available evidence cannot draw a precise island-wide ice boundary for 30,983 BCE.

Low global sea levels exposed much more of the continental shelf than exists today. Yet it is misleading to picture a simple, reliable land bridge connecting Ireland to Britain or mainland Europe. The geography of the Irish Sea was changing, while ice and cold seas presented formidable barriers. Animals demonstrably reached Ireland during parts of the Pleistocene, but the routes, frequency and seasonality of those movements remain uncertain. What can be said is that Ireland belonged to a wider north-west European ecological zone, not to an isolated world untouched by continental climatic and biological change.

## **Derryvree's Buried Wetland**

The clearest local environmental window relevant to this era comes from Derryvree near Maguiresbridge, County Fermanagh. There, road works exposed organic freshwater sediments lying between two tills: deposits of mud and plant material formed during an ice-free interval, then sealed beneath later glacial deposits. The original study obtained a radiocarbon determination of 30,500  $\pm$  1,170/–1,030 radiocarbon years BP. That is not a date for 30,983 BCE, and calibration does not transform it into a precise historical timestamp. It nevertheless places the deposit broadly within late MIS 3 and demonstrates that open, biologically active ground existed in this part of Ireland before renewed ice cover.

Derryvree's contents are unusually informative. Pollen, plant macrofossils, mosses and insects record grasses, sedges, herbs, juniper and cold-adapted plants, including bogbean, mountain avens and lesser clubmoss. The assemblage supports an interpretation of open, treeless tundra or muskeg-like terrain, with wet mossy ground, plant-rich margins and shallow pools. Inference must be separated from observation: the fossils directly show organisms that lived in or near the basin; the broader image of a periglacial mosaic is a reconstruction based on their combined ecological requirements and regional comparison.

This was not necessarily a featureless desert of snow. During favourable seasons, wet hollows could support aquatic plants and invertebrates, while sedges, grasses and herbs created patches of grazing. Elsewhere, thin soils, frost disturbance, exposed gravel and strong winds probably restricted vegetation. The Derryvree record cannot show that all Ireland looked the same, nor does it tell us which animals stood beside its pools in a particular season. It does establish a landscape in which freshwater life persisted under harsh conditions, and it demonstrates why the later Irish Ice Sheet did not erase every trace of the preceding world.

## **Castlepook's Animal World**

For large animals, Castlepook Cave near Doneraile in north County Cork is the crucial Irish archive. Also known as Mammoth Cave, it was excavated principally in the early twentieth century, long before modern standards of stratigraphic recording. Its collections contain remains attributed to woolly mammoth, giant deer, reindeer, brown bear, wolf, Arctic fox, lemmings and spotted hyaena. The cave is Ireland's richest known source for Pleistocene vertebrate remains, while later radiocarbon reassessment has shown that elements of its fauna belong to MIS 3.

The collection should not be mistaken for a snapshot of one day, one habitat or one food chain. Cave hyaenas and other carnivores could carry carcass parts underground; scavenging, gnawing, water movement, sediment collapse and early excavation could mix remains from different episodes. A mammoth bone demonstrates that a mammoth, or part of one, reached the cave; it does not prove a resident herd immediately outside its entrance. Similarly, the occurrence of predators does not reveal their numbers, social organisation or precise prey choices in Ireland.

Even with those cautions, the fauna is powerful evidence. Reindeer, lemmings and Arctic fox are consistent with severe, open-country conditions. Mammoth and giant deer indicate that, at intervals, enough forage existed to sustain very large herbivores. Wolves and spotted hyaenas show that carcasses were contested resources and that Ireland's Pleistocene ecosystems included formidable carnivores. This was an ecological setting radically unlike the wooded post-glacial island familiar from later prehistory. It was dynamic, seasonal and vulnerable to rapid climatic deterioration.

## **A Mark on a Reindeer Bone**

Castlepook's most consequential object is a fragment of reindeer femur reported to carry a deep linear mark interpreted by zooarchaeologist Ruth Carden as a cut or chop made with a sharp stone implement while the bone was fresh. The animal bone has been presented publicly as approximately 33,000 years old. In scientific terms, its age must be expressed through its laboratory result and a calibrated range, not treated as proof that butchery occurred in the calendar year 30,983 BCE. Nor does an age for the animal automatically date the mark or identify its maker.

If the modification is confirmed as a stone-tool mark, it would be the earliest known indication of human activity in Ireland by a very large margin. It would suggest that one or more people handled a reindeer carcass during MIS 3, perhaps on a brief hunting or scavenging visit at Europe's north-western edge. It would not demonstrate a permanent population. There is no securely associated lithic assemblage, hearth, dwelling surface, human bone, repeated processing area or cemetery from Castlepook of comparable antiquity. The specimen derives from an old, complex cave collection, precisely the sort of context in which taphonomic alternatives must be rigorously tested.

The distinction matters. A cut-marked bone can transform the chronology of human presence while still revealing almost nothing about settlement duration, group size or movement. It is possible that people reached Ireland sporadically and left little trace; it is also possible that the mark will require further qualification. Subsequent glaciation scoured much of the landscape and makes the survival of open-air sites unlikely, but destruction alone cannot be used as proof for a population for which direct archaeological evidence has not yet been found.

## **Society Beyond Recovery**

Political affairs, conflict and diplomacy cannot responsibly be written for Ireland at this date. There were no documented polities, boundaries, leaders or treaties, and even continuous human occupation remains unproven. Later ethnic labels, Gaelic language, Celtic identity and Irish origin traditions belong to vastly later periods and have no evidential place in this Pleistocene setting. Farming, settled villages, trade in the later prehistoric sense and formal institutions are likewise unsupported.

The same restraint applies to religion, culture and learning. No securely dated Irish cave art, portable art, grave, shrine or ceremonial feature belongs to this horizon. Upper Palaeolithic groups elsewhere in Europe possessed sophisticated technical knowledge, social networks and, in some regions, rich symbolic

traditions. Those comparisons show what people who might have visited Ireland were capable of; they do not establish that such objects or practices existed here. Should a small group have processed the Castlepook reindeer, its everyday economy would have involved immediate decisions about meat, marrow, hide, sinew and safe movement through a dangerous landscape. But the Irish evidence cannot tell which resources were taken, whether the animal was hunted, or how knowledge was shared.

## **What This Date Can Mean**

Ireland around 30,983 BCE is therefore best understood as a time of cold, unstable environmental change rather than a year of recorded human events. Derrynree preserves a local wetland world of sedges, mosses, herbs and shallow freshwater; Castlepook preserves a broader, time-averaged animal record of reindeer, mammoth and predators. Together they refute any idea of a uniformly lifeless island before the Last Glacial Maximum. The Doneraile reindeer femur adds a potentially momentous human question, but not a settled Palaeolithic Ireland. Its mark asks for more excavation, dating and microscopic analysis—not for an invented hunting story. In this deepest period of Irish history, caution is not a lack of narrative: it is the evidence-based achievement.

# Chapter 019 of 100

## 30982 BCE

### Fermanagh's Glacial Reedlands<sup>[19]</sup>



The modern label 30,982 BCE should not be mistaken for a date at which Ireland's past can be recovered year by year. No written record, settlement sequence or archaeological layer can identify an event in that particular calendar year. In radiocarbon terms it falls roughly 32,931 years before the conventional present of 1950, within the later part of the Late Pleistocene and broadly Marine Isotope Stage 3 (MIS 3). At this depth of time, even apparently precise scientific dates are ranges with uncertainties, not historical anniversaries. What can responsibly be described is an Ireland moving towards the greatest cold of the last glacial cycle, with habitats, ice margins and routes of animal movement changing over centuries and millennia.

## A Landscape Approaching Major Change

Ireland at this time was not the familiar green, wooded island of later prehistory. It lay in a cold-stage north-west European world in which sea level was far lower than today, expanding the lands around Ireland and narrowing or altering marine crossings. Yet Ireland was not necessarily an unbroken sheet of ice in every district at every moment. The growth of the British–Irish Ice Sheet was regionally complex. Recent reconstructions are designed to resolve broad thousand-year phases between about 31,000 and 15,000 years ago, rather than to tell us the weather, coastline or ice limit in one named year. They nevertheless show why 30,982 BCE belongs to a threshold period: conditions were deteriorating, ice was becoming a decisive force in the making and destruction of habitats, and later glaciation would erase or bury much of the evidence.

For Ireland, environment is not merely the backdrop to human history in this era; it is the principal history that survives. Glaciers scoured bedrock, redistributed sediment and reshaped valleys. Meltwater, frost action and seasonal thaw altered slopes and river courses. Permafrost or deeply seasonally frozen

ground probably affected many exposed areas. These processes made life difficult for plants and animals, but also created local mosaics: shallow pools, marshy hollows, gravelly ground, river margins and patches of vegetation capable of sustaining cold-adapted species.

## The Derryvree Record

The clearest Irish environmental archive relevant to this broad period comes from Derryvree, near Maguiresbridge in County Fermanagh. Road works there in 1969 cut through a drumlin and exposed organic silts and fine sands trapped between two thick tills. This was an extraordinary find because the sediments preserved a freshwater episode between glacial advances. The original radiocarbon determination, BIRM-166, was 30,500 radiocarbon years BP, with a substantial uncertainty of +1,170 and -1,030 years. A later calibration cited in glacial research places it around  $35.9 \pm 1.1$  thousand calibrated years BP.

That is older than the modern calendar point of 30,982 BCE and must not be used as proof of conditions in Ireland on that exact date. It is, however, the best direct demonstration that northern Ireland had experienced an ice-free, cold terrestrial interval within the wider MIS 3 world preceding the later major glacial expansion. The Derryvree deposit provides actual biological evidence rather than an imagined Ice Age scene: pollen, plant macrofossils, mosses and small animal remains point to open tundra vegetation and a periglacial freshwater setting.

The plant evidence is particularly valuable. Sedges and aquatic plants indicate wet ground and standing or slow-moving fresh water. Bogbean, water-milfoil, dwarf willow, mountain-avens and arctic-alpine mosses show that the margins of the water were not barren. They suggest a treeless landscape with low vegetation, moisture-loving communities and patches of plants adapted to severe cold, short growing seasons and exposed ground. The sensible picture is not of a single uniform “tundra”, but of a local wetland set within an open, climatically harsh landscape.

## Animals, Caves and Uncertain Associations

Southern Irish caves provide another window, though a more difficult one. Castlepook Cave near Doneraile in County Cork is Ireland’s richest known archive for vertebrate life in the period before the Last Glacial Maximum. Its faunal collections include woolly mammoth, reindeer, giant deer, brown bear and spotted hyaena, alongside wolf, Arctic fox, mountain hare and lemmings. Such animals establish that, during parts of MIS 3, Ireland could be connected ecologically to the wider cold-stage faunas of north-western Europe.

The cave should not be read as a census for 30,982 BCE. Its bones accumulated through different episodes; carnivores carried material into caves; water moved sediments; burrowing animals disturbed deposits; and much of the early excavation took place before modern recording standards. Improved radiocarbon pretreatment has also shown that some earlier measurements were too young. A reassessment of Castlepook and other southern Irish caves concluded that important elements of the fauna belonged much earlier in MIS 3, and that giant deer and spotted hyaena may have disappeared locally before about 40,000 calibrated years BP. Therefore neither species can safely be placed in every later MIS 3 landscape, including this calendar-labelled point.

Reindeer are especially important because a Castlepook femur has been interpreted as bearing a fresh-bone incision made by a sharp stone implement. The bone has been publicly associated with an age of roughly 33,000 years ago. If the mark is confirmed as butchery, it would indicate that people handled a



reindeer in Ireland vastly earlier than the formerly accepted evidence for human activity. But it is one potentially transformative trace, not a securely excavated camp. No associated stone-tool assemblage, hearth, dwelling, burial, repeated occupation surface or stratified living floor of comparable age has yet been demonstrated in Ireland. The responsible conclusion is that an early human visit is possible and important, while permanent settlement remains unproven.

## People Beyond the Evidence

There is no basis for describing an Irish polity, leader, tribe, diplomatic relationship or war in 30,982 BCE. There were no known states, boundaries, monuments or named communities here. Nor can archaeology presently identify a religion, language, artistic tradition or system of learning for Ireland at this point. To supply any of these would turn a sparse and contested record into fiction.

If people did reach Ireland during this interval, they would have arrived as highly mobile Upper Palaeolithic hunter-gatherers from a wider European world in which human groups already possessed sophisticated stone technologies, clothing and social knowledge. That wider comparison helps explain what an expedition might have required: fire, shelter, navigation, shared practical skills and intimate knowledge of animal behaviour. It does not prove that any particular technology, rite or social custom was practised in Ireland. The sea and land routes available then differed from those of today, but the precise journey, frequency of crossings and duration of any stay are all unknown.

Likewise, “economy” can only be discussed at the most basic ecological level. Wild animals, plants, freshwater and perhaps coastal resources were the potential basis of subsistence, not evidence for agriculture, herding, markets or regular trade. Reindeer, where present, could have offered meat, fat, hide, sinew, antler and bone; large mammals and predators also structured risk and opportunity. Yet the Castlepook evidence cannot show which resources people took, whether hunters killed an animal or scavenged one, or whether a single marked bone represents a brief stop rather than recurrent activity.

## An Island of Refuges and Gaps

The most important development around this point was climatic and geographical, not political. Ireland’s habitable ground was becoming less secure as the last ice sheet built towards its eventual maximum. Open wetland and grass-herb communities could support animals in favourable seasons, while exposure, winter cold and advancing ice narrowed the places in which they could persist. Faunal movements were likely intermittent, responding to vegetation, snow cover, water, predators and shifting routes across the broader Irish Sea region.

Regional contrasts mattered. The Fermanagh deposit records a freshwater landscape in the north during an earlier cold interval. The Cork caves preserve evidence of a rich, but time-averaged, southern fauna. Neither can be expanded into a detailed all-Ireland map, still less into a scene fixed to one calendar year. Their very survival is exceptional: later ice and erosion removed countless comparable deposits. Absence of evidence in other counties may reflect destruction and non-discovery as much as true absence of life.


Thus 30,982 BCE is best understood as a point within a long, unstable Late Pleistocene transition. Ireland was a place of exposed ground, wet hollows, cold-adapted vegetation and mobile animal populations, increasingly constrained by the growth of ice. Derryvree gives firm evidence for the kind of cold freshwater ecology that had existed in the wider period; Castlepook demonstrates the former presence of a remarkable Ice Age fauna and raises a serious, unresolved question about early human

contact. The archaeological task is not to make this evidence tell a dramatic annual story. It is to preserve the distinction between what bones and sediments directly establish, what calibrated ranges allow, and what remains an informed but still provisional interpretation.

## Chapter 020 of 100

30981 BCE

### Ballyhoura's Mammoth-Steppe Passage <sup>[20]</sup>



The label 30,981 BCE is useful for organising a modern chronology, but it cannot identify an event in Ireland on a particular day, season or year. No calendar, writing, named community or securely dated settlement survives from this depth of time. The responsible subject is instead an interval within Marine Isotope Stage 3 (MIS 3), a climatically unstable part of the Late Pleistocene before the Last Glacial Maximum. Around this notional year, the strongest Irish evidence concerns cold-environment landscapes, animal communities and a small but potentially momentous clue to human activity in north Cork.

Calendar-year precision is not available. Radiocarbon results have measurement uncertainties, must be calibrated against changing atmospheric carbon, and date a specimen rather than an entire landscape. The nearest major environmental sequence, at Derryvree near Maguiresbridge in County Fermanagh, produced a conventional radiocarbon determination of 30,500 +1,170/-1,030 radiocarbon years BP. Its calibrated range has been discussed as roughly 36,900–31,700 calendar years BP, or approximately 34,950–29,750 BCE. Thus 30,981 BCE falls within a broad archaeological and palaeoenvironmental horizon, not within an observable annual record.

## Before the Great Ice Advance

Ireland was not yet at the fullest extent of the last ice age. The Last Glacial Maximum developed later, broadly during the period after about 27,000 years ago, although the precise growth, thickness and margins of the Irish sector of the British–Irish Ice Sheet remain subjects of active research. Ice did not behave as a single, unchanging blanket: advances and retreats differed between regions, and evidence for its exact position at any one pre-maximum moment is limited. It would therefore be misleading to colour all of Ireland as either certainly frozen or certainly open country in 30,981 BCE.

What can be said is that portions of the island supported environments hostile to woodland but capable of sustaining specialised plants and animals. Derryvree is especially valuable because roadworks exposed organic silts and fine sands between two substantial tills in a Fermanagh drumlin. The lower and upper tills record glacial action; the enclosed freshwater deposits record an interval when water, sediment, plants and small animals accumulated locally before renewed ice overran the site. This is direct evidence for a cold, periglacial wetland at Derryvree, not proof that every Irish valley had the same ecology at precisely the same time.

## **A Treeless Wetland in Fermanagh**

The Derryvree assemblage points to open tundra vegetation. Mosses, sedges, dwarf willow, mountain avens, clubmoss, bogbean and aquatic plants indicate a mosaic rather than an empty snowfield: shallow freshwater, marshy edges, exposed mineral ground and low-growing vegetation. The biological evidence supports severe conditions with short growing seasons and prolonged frost, yet also reveals ecological productivity where meltwater and shelter allowed plants to establish. In such a setting, ground conditions may have changed rapidly between frozen winter surfaces, spring thaw, standing water and drier summer margins.

This is the closest evidence for ordinary life on the land, though it is plant and invertebrate life rather than human life. There were no fields, livestock, villages, tracks, farms or managed woods. The landscape had not acquired political boundaries, kingdoms, diplomatic ties or institutions. Indeed, such categories cannot responsibly be projected back onto Ireland at this date. Its history is environmental and archaeological: sediments reveal processes, fossils reveal organisms, and neither by itself can disclose languages, identities or social arrangements.

## **Animals of the Open Country**

Caves in the south, particularly Castlepook Cave near Doneraile in the Awbeg Valley beneath the Ballyhoura Hills, preserve the more dramatic side of this world. Re-dating has shown that important elements of its fauna belong to MIS 3, much older than several earlier radiocarbon determinations suggested. The wider Castlepook assemblage includes evidence for reindeer, woolly mammoth, giant deer, brown bear, wolf, Arctic fox, mountain hare, lemmings and spotted hyaena. The mix is consistent with open, cold-country habitats and shows that Ireland could support or receive a far richer Pleistocene fauna than the island's later, historically familiar animal communities.

These bones do not amount to a census. Caves are selective archives: carnivores can carry carcass parts inside, water can move material, bone preservation is uneven, and antiquarian excavation often disturbed deposits before modern recording standards existed. Some animals may have ranged locally; others may be represented by occasional visits, scavenged remains or carcasses accumulated over long periods. Yet the faunal record is powerful evidence that north Cork was connected ecologically to the wider north-west European world during favourable phases of the Ice Age.

Reindeer are particularly important. Their presence implies forage and movement through open terrain, while mammoth and giant deer demonstrate that very large herbivores also reached Ireland. Predators and scavengers followed the same food web. The cave should not be imagined as a scene continually occupied by all these animals together. Rather, its deposits are a time-compressed record of many episodes: deaths on the landscape, carnivore activity, transport into cavities and later burial within cave sediments.

## The Castlepook Bone Question

A reindeer femur from Castlepook has made this interval unusually significant for Irish prehistory. Zooarchaeologist Ruth Carden identified a deep surface mark interpreted as having been made by a sharp stone tool during the processing of fresh bone. Public heritage accounts have associated the specimen with about 31,000 BCE. If the mark is confirmed as an anthropogenic cut or chop mark contemporary with the animal's death, it would indicate that people reached Ireland far earlier than the formerly accepted terminal-Pleistocene evidence.

The distinction between evidence and interpretation matters. The bone itself is evidence for reindeer in Ireland during the relevant cold-stage world. The mark is physical evidence requiring taphonomic assessment. Its identification as a tool mark is an expert interpretation, strengthened or weakened by microscopic study, comparison with carnivore damage, trampling, sediment abrasion and experimental butchery traces. Moreover, the specimen came from an old cave collection rather than a newly excavated, intact camp floor. Castlepook has yielded no securely associated hearth, lithic assemblage, dwelling, human remains or animal-processing area of equivalent age.

Accordingly, it is not yet possible to write of a settled Irish population in 30,981 BCE. The most that can presently be argued is both more modest and more remarkable: a person or small group may have encountered and butchered a reindeer in Ireland during MIS 3. The carcass need not have been processed in the cave; carnivores may have transported a discarded limb there afterwards. Nor can one marked bone demonstrate continuous occupation, migration routes, family structure, hunting territories or a local tradition of stone-tool manufacture.

## Possible Visitors, Not a Documented Society

If people did reach the island, their way of life was almost certainly mobile and reliant on detailed knowledge of season, animals, terrain and weather, as among Upper Palaeolithic hunter-gatherers elsewhere in Europe. But this is comparative inference, not an Irish excavation result. There is no basis for assigning these possible visitors an ethnic name, a language, a religion or a political allegiance. No Irish ritual site, grave, art panel, ornament or house can be securely placed in this horizon.

There is likewise no evidence for trade in the later sense of regular exchange between identifiable communities. Movement of people and animals depended on changing sea levels, coasts, ice and possible routes through Britain or across exposed shelf landscapes. Low global sea levels altered north-west European geography, but the exact accessibility of Ireland during MIS 3 remains more complex than a simple land-bridge narrative. The animal record demonstrates arrival; it does not reveal the route, frequency or seasonality of crossings.

## What This Year Can Mean


The great development represented by 30,981 BCE is therefore not a battle, reign or foundation, but the survival of evidence. Derryvree preserves a local cold wetland later sealed beneath ice. Castlepook preserves a fragmented record of an open-country fauna, and a reindeer bone that may carry Ireland's earliest sign of human action. Together they replace the old image of an utterly lifeless, unknowable Ice Age island with a more precise one: a changing northern landscape where freshwater habitats, tundra plants and large mammals persisted, and where human presence is possible but not yet securely demonstrated as settlement.

Future controlled excavations, direct dating, biomolecular work and microscopic analysis may alter that picture. For now, the appropriate history of Ireland at this date is a disciplined one: an island on the edge of Ice Age Europe, environmentally varied, intermittently accessible, and known chiefly through mud, bone and the questions they still pose.

# Chapter 021 of 100

## 30980 BCE

### The Maguiresbridge Drumlin Archive <sup>[21]</sup>



30,980 BCE is not a date to which Irish prehistory can be pinned with calendar-year certainty. No community in Ireland named or recorded such a year, and the surviving evidence cannot isolate a particular season, journey or event within it. In modern chronological terms, it falls about 32,929 years before AD 1950, the conventional radiocarbon baseline. The responsible subject is therefore a broad later-Pleistocene interval, within Marine Isotope Stage 3 (MIS 3), rather than an annual chronicle. Calibrated ranges, sediment sequences and animal remains offer a compelling but deliberately incomplete picture.

## A Date Inside a Wide Range

The closest major Irish chronological anchor is Derryvree townland, near Maguiresbridge in County Fermanagh. Road construction in 1969 cut through a drumlin and exposed a remarkable sequence: freshwater silts and fine sands, including organic-rich layers, lay between two thick sheets of till. Till is the unsorted mixture of clay, stones and other debris laid down by glacier ice. The order of deposits establishes an environmental sequence of real importance. Ice had covered the locality; an interval then followed in which standing or slowly moving freshwater and plants accumulated sediment; later ice advanced again and sealed the archive beneath further till.

Organic material from the freshwater series, sample BIRM-166, produced a conventional radiocarbon result of 30,500 years BP, with a substantial uncertainty of +1,170 and -1,030 years. Calibration is essential because atmospheric carbon-14 has fluctuated through time. Published discussion places the deposit broadly at about 36,900–31,700 calibrated years BP. The modern label 30,980 BCE falls within that large span, but it does not date a particular plant, pool or animal in the deposit. It is better understood as one point within a cold phase lasting millennia.

This limitation is not a defect in the evidence; it is its proper scale. Derryvree demonstrates that this part of Fermanagh was locally ice-free when freshwater sediment accumulated. It does not demonstrate that every district of Ireland shared the same conditions at the same moment. Nor can it resolve whether the requested year belonged to an earlier or later part of the deposit. The island's glacial history was regionally varied, and later ice repeatedly eroded, mixed, buried or removed older landscapes.

## Wet Ground in a Treeless Land

The Derryvree flora and fauna indicate open tundra vegetation and a periglacial regime: a landscape shaped by severe cold, repeated freezing and thawing, and a short growing season. This was not the wooded, rain-softened Ireland familiar from later millennia. The organic deposits, pollen, plant macrofossils and insect evidence instead point to wet ground with open pools, moss-rich vegetation, sedges and low-growing Arctic-alpine plants. Fossil records include mountain avens and bogbean, plants compatible with cold, open and waterlogged conditions. The older term *muskeg* usefully conveys the mixture of saturated ground, plant matter and shallow water, though it should not suggest an unchanging uniform bog.

Such a setting could be biologically productive in summer. Water margins concentrate vegetation, insects and grazing opportunities; mosses and sedges bind wet sediment; pools can preserve plant remains exceptionally well. Yet winter conditions were plainly formidable. Frozen ground and exposed terrain limited tree growth and changed the movement of water across the land. The rhythm of life was seasonal, but the evidence cannot recover a seasonal calendar for any one year. It can only show that Ireland contained living cold-climate ecosystems during part of this wider interval, rather than being permanently sealed beneath an ice sheet.

Crag Cave in County Kerry provides a separate, though less directly local, climate archive. Its broken and reworked speleothems show that liquid water entered the cave episodically during MIS 3. Since calcite growth requires conditions above freezing in the cave system, the record supports a wider picture of climatic instability: colder phases alternated with intervals in which moisture and temperatures permitted cave deposits to form. Ireland around this time was not environmentally static. Advances and retreats of ice, altered drainage and rapid North Atlantic climatic shifts repeatedly changed the possibilities for plants and animals.

## Animals Before the Great Ice Expansion

Irish caves, especially Castlepook Cave near Doneraile in north County Cork, illuminate the animal world more vividly than they illuminate people. Castlepook was excavated principally in the early twentieth century and became known as Mammoth Cave because of its striking Ice Age fauna. Reassessment using improved radiocarbon methods has shown that some bones from the cave are considerably older than earlier measurements indicated, placing elements of its assemblage in MIS 3. Reindeer, woolly mammoth, giant deer, brown bear, wolf, fox and spotted hyaena are among animals represented in the broader pre-Last Glacial Maximum record.

That list should not be turned into a wildlife census for 30,980 BCE. Cave deposits accumulated over long periods and through several processes. Carnivores dragged in carcass parts; animals died naturally; water shifted sediments; collapses and early excavation disturbed the original relationships between



bones. A mammoth bone or hyaena remain proves that the species reached Ireland during the relevant broad period, not that it stood beside a particular Derryvree pool in the notional year under discussion. Nor do all species necessarily belong to the same season, generation or climate phase.

Nonetheless, the fauna matters. Large herbivores and predators indicate that, in at least some ice-free landscapes and milder windows, Ireland was connected ecologically to the wider north-west European world. Low sea levels exposed more of the surrounding continental shelves than exist today, although coastlines, sea passages, ice margins and viable routes changed substantially. The fossils demonstrate animal dispersal; they do not reveal precisely how, when or along which route each population arrived. The subsequent growth of the last Irish Ice Sheet was to destroy habitats and obscure much of this earlier record.

## **The Reindeer Femur Question**

The most consequential possible human trace is a reindeer femur from Castlepook Cave. Public heritage interpretation has associated it broadly with about 31,000 BCE and zooarchaeologist Ruth Carden has identified a deep linear modification as a possible cut or chop made with a sharp stone tool while the bone was fresh. If that interpretation is confirmed, it would indicate that a person processed a reindeer in Ireland during the Upper Palaeolithic, far earlier than the traditionally accepted post-glacial record of human activity.

It would not, however, prove an Irish settlement, a village, an annual migration route or a resident population. The bone comes from an old cave collection rather than a modern excavation of a sealed occupation floor. Its radiocarbon age dates the animal's death, not automatically the marking of the bone, the location of killing, or the length of any human visit. No securely associated hearth, stone-tool assemblage, dwelling, burial or repeated food-processing area of comparable age has yet been recovered at Castlepook. Recent excavations have demonstrated the continuing archaeological potential of the cave but have not supplied such corroborating evidence.

The distinction between evidence and interpretation is therefore decisive. The femur is a serious and potentially transformative indication of human butchery; it is not yet a secure foundation for detailed claims about society. Upper Palaeolithic groups elsewhere in Europe made sophisticated stone tools, travelled across large territories and maintained social networks, but those wider comparisons cannot be projected wholesale onto Ireland. At most, if people reached Ireland during this phase, they may have been highly mobile visitors exploiting animal resources during a temporary environmental opportunity.

## **No Politics, No Proven Diplomacy**

There is no evidence from Ireland around 30,980 BCE for political institutions, named peoples, chiefs, territorial boundaries, warfare, diplomacy, formal religion, monuments, writing or organised trade. There are no known Irish structures, graves, artworks or ritual deposits that can responsibly be assigned to this narrow point in MIS 3. Silence on these subjects is not an omission from the history: it is the correct historical conclusion.

Everyday life is similarly beyond direct recovery. If the Castlepook mark is human-made, it concerns carcass processing and therefore food, tools and practical knowledge. It cannot tell us the size of a group, whether people sheltered in the cave, what language they spoke, how they understood the landscape or

whether they returned. The principal history of this time is environmental: freshwater gathering beneath a future drumlin, tundra vegetation persisting through harsh seasons, animals moving through a changing western edge of Europe, and glacier ice preparing to transform the evidence they left behind.

## **Approaching a Different Ireland**


The wider trajectory gives Derryvree its significance. Research on the last Irish and British-Irish ice sheets indicates that substantial expansion followed this locally ice-free MIS 3 interval, with maximum ice extent reached many thousands of years later during the Last Glacial Maximum. The chronology and precise extent of early ice build-up remain debated because pre-existing deposits are scarce and many older radiocarbon determinations require cautious treatment. Yet the stratigraphy at Derryvree preserves the essential fact: Ireland's last Ice Age was a sequence of advances, withdrawals and ecological rearrangements, not a single uninterrupted freeze.

For 30,980 BCE, then, the Maguiresbridge drumlin offers the most responsible focal point. Beneath later glacial debris survived the remains of a cold wetland, preserving evidence that an open, treeless Irish landscape could support plants and animals during a volatile climate phase. Castlepook adds a richer but more complicated faunal archive and a tantalising human question. Together they reveal a country without recorded history, but not without a past: a changing Pleistocene Ireland whose deepest witnesses are silt, bone, water and ice.

## Chapter 022 of 100

### 30979 BCE

#### Castlepook Reindeer Mark<sup>[22]</sup>



Modern calendar-year precision is not available for Ireland in 30,979 BCE. No one on the island used a calendar, wrote a record or left an event that can be assigned to that numbered year. The date is best treated as a modern point within a much broader Late Pleistocene interval: roughly 32,900 years before the radiocarbon reference year of AD 1950, during Marine Isotope Stage 3 (MIS 3), a climatically volatile phase of the last Ice Age. What can responsibly be said comes from calibrated ranges, cave-bone collections, buried freshwater sediments and the changing evidence for glacier ice—not from a year-specific narrative.

### An Island in a Cold Interval

Ireland at this remote point was not the green, wooded island familiar from later prehistory. It lay in the northern Atlantic zone of the last glacial cycle, where climate swung sharply between colder stadials and comparatively milder interstadials over centuries and millennia. The later Last Glacial Maximum, when the British–Irish Ice Sheet reached its greatest overall extent, still lay ahead. Yet this does not mean that 30,979 BCE belonged to a uniformly ice-free Ireland. The timing, thickness and reach of ice varied substantially by region, and the evidence for the pre-maximum ice sheet remains incomplete.

The most relevant environmental evidence comes from Derryvree, near Maguiresbridge in County Fermanagh. Roadworks exposed organic freshwater silts and sands sealed between two tills: deposits left by separate glacial advances. The sequence establishes an order rather than a precise historical moment. An earlier ice mass had deposited the lower till; an interval of open water, wet ground and plant growth followed; then a later glacier buried that landscape beneath fresh till. Organic material from the intervening deposits produced a conventional radiocarbon determination of about 30,500 BP, with a large

uncertainty. Modern calibration places the deposit broadly at about 36,900–31,700 calibrated years BP. The nominal year 30,979 BCE falls within that wide range, but cannot be tied to a particular pool, season, plant or occupation.

Derryvree matters because it rules out a simple picture of uninterrupted, island-wide ice cover. Its freshwater sediments and plant remains indicate that at least one northern locality supported water, wetland and cold-climate vegetation during part of MIS 3. Comparable stratigraphic sequences at Aghnadarragh near Lough Neagh show how varied the Irish record can be: tills, organic deposits, shallow-water sediments and fossil remains survive as fragments of changing glacial and non-glacial conditions. They are local archives, however, not maps of the entire island. It would be unsafe to project a Fermanagh wetland directly onto Munster, Connacht or the coast.

## **Cold Landscapes, Not Empty Landscapes**

The available evidence points towards open, strongly seasonal environments where low shrubs, herbs, sedges, mosses and wet-ground plants could occupy suitable ground. Such terrain was very different from later oak- and hazel-rich woodland. Permafrost processes, bare mineral ground, meltwater channels and pools would have shaped many landscapes, while glacier margins and snow cover shifted over long spans. Plant and insect remains from Irish inter-till deposits are especially valuable because they demonstrate ecological opportunity in places that later ice overran and sealed.

Animal fossils show that Ice Age Ireland could support an impressive, if changing, mammal community. Castlepook Cave—also known as Mammoth Cave—near Doneraile in north County Cork is the key site. Its collections include remains attributed to reindeer, woolly mammoth, giant deer, brown bear, wolf, Arctic fox, mountain hare, lemmings and spotted hyaena. These finds do not describe a single living landscape or one contemporaneous animal population. The cave accumulated material over a long period, and bones could have been brought in by carnivores, moved by water or sediment, disturbed by later animals, and affected by early excavation methods.

That qualification is essential. The Irish Quaternary Fauna Project established that mammals reached Ireland during a broad interval between at least about 45,000 and 20,000 years ago. Subsequent redating using improved pretreatment methods showed that some Castlepook results obtained in the 1990s were thousands of radiocarbon years too young. In particular, the revised work indicates an older MIS 3 history for parts of the southern Irish fauna and suggests that some species, including giant deer and spotted hyaena, may have disappeared locally before the Last Glacial Maximum. A mammoth, hyaena and reindeer should therefore not be imagined automatically standing together beside Castlepook in 30,979 BCE. Their bones establish an extended ecological record, not a single scene.

## **A Reindeer Bone and a Human Question**

One Castlepook specimen gives this period unusual historical importance. A reindeer femur has been reported by palaeozoologist Ruth Carden and County Cork heritage material as carrying a deep mark made by a sharp stone tool during carcass processing. The bone has been presented as dating broadly to around 30,000 BC. If the mark is confirmed as anthropogenic, it would be potentially the earliest known evidence that a person handled an animal in Ireland, vastly earlier than the island's better-established post-glacial archaeology.

Its implications must remain proportionate to the evidence. The reported date concerns the age of the animal bone, not a known day on which the incision was made. The old cave collection is not a modernly excavated, sealed occupation floor. No securely associated hearth, stone-tool assemblage, dwelling, human burial, food store or repeated concentration of butchered animals has yet been recovered from Castlepook for this period. Nor does a cut-marked bone prove that the reindeer was killed at the cave: a carcass part could have been processed elsewhere and later carried, dragged or washed into it.

The most responsible conclusion is therefore modest but important. Around the broad time represented by the bone, a person or small group may have entered Ireland and processed reindeer with a stone-edged implement. That is evidence for an action, if the cut-mark interpretation is sustained; it is not evidence for a settled population, continuous occupation or an established Irish hunting culture. Excavations at Castlepook in 2022 sought surviving undisturbed deposits precisely because new stratigraphy, lithics, charcoal, modified bones or dating could test these possibilities more firmly.

## **Movement Across a Changing Seaway**

Large mammals plainly reached Ireland during parts of the Late Pleistocene, and any human visitors indicated by the Castlepook bone must also have arrived from beyond the island. The geography of that movement remains uncertain. Global sea level was lower than today because vast quantities of water were held in ice sheets, but lower sea level did not necessarily create a simple, continuous land bridge from Ireland to Britain. Ice margins, relative sea-level change, deep basins and shifting coastlines made the Irish Sea region complex. Possible routes across exposed coastal plains, short water crossings, seasonally altered shores or combinations of these have not been demonstrated for this specific time.

In wider north-west Europe, *Homo sapiens* groups were present and developed Upper Palaeolithic stone technologies. It is reasonable to see the Castlepook claim in that continental context, but no Irish stone-tool industry of this age has been recovered. Terms such as Aurignacian or Gravettian should not be assigned to Ireland on the basis of one marked bone. If people did visit, their practical economy would have depended on mobility, hunting, gathering and knowledge carried from elsewhere, rather than on farming, permanent villages or local manufacture evidenced archaeologically on the island.

## **What Cannot Be Recovered**

There is no evidence from 30,979 BCE for political authorities, territories, diplomacy, warfare, formal trade networks, religious monuments, named communities or systems of learning in Ireland. Absence of evidence is not proof that visiting people had no social relationships, beliefs or traditions; all hunter-gatherers possessed social and cultural lives. But Ireland's surviving record cannot identify them here. The same restraint applies to everyday life. We cannot say how many people travelled, whether they came as a family party or hunting task group, what language they spoke, how long they remained, or whether they ever returned.

Nor should later Irish identities be projected backwards into this period. The familiar cultural landscapes of prehistoric Ireland—Mesolithic camps, Neolithic farms and tombs, Bronze Age fields, Iron Age polities—belonged to a far future. The National Museum of Ireland still describes clear, substantial evidence for human settlement as post-glacial, while the terminal Pleistocene bear bone from Alice and Gwendoline Cave in County Clare, dated around 12,800–12,600 calibrated years BP, provides much later and more securely contextualised evidence of butchery.

The true subject of this approximate year is therefore a threshold: a cold and regionally variable island, a fauna capable of reaching it, and a single provocative reindeer bone from a difficult cave archive. Later ice sheets eroded, buried and rearranged much of the older landscape, helping to explain why campsites and coastlines have proved so elusive. That possibility must not be used to invent lost settlements. At 30,979 BCE, Ireland can be seen only in fragments—freshwater mud beneath a drumlin, bones in a Cork cave, and traces of a changing ice sheet—but those fragments show that the island's deep past was environmentally dynamic and perhaps, fleetingly, touched by people.

# Chapter 023 of 100

## 30978 BCE

### Derryvree's Sedge Pools<sup>[23]</sup>



**30,978 BCE is not a date at which Irish prehistory can be resolved to a single year. It is a modern calendar label, approximately 32,927 years before AD 1950, the conventional reference point for “before present” dating. No written calendar, annual sediment sequence or excavated occupation surface allows us to identify an event, a person or even a particular season in Ireland at this point. The responsible approach is therefore to place the date within a broader archaeological and environmental horizon: the later part of the Middle Midlandian, Ireland’s regional term for part of the last glacial cycle, within Marine Isotope Stage 3.**

The most relevant evidence is not a settlement or monument but an exceptional buried wetland deposit at Derryvree near Maguiresbridge, County Fermanagh. Its conventional radiocarbon determination of 30,500 +1,170/–1,030 BP requires calibration and carries a substantial uncertainty; scholarship has accordingly treated it as belonging broadly to a late MIS 3 interval rather than to an exact calendar year. Calibrated ranges depend on the curve and statistical treatment used, but a range of roughly 36,900–31,700 cal BP has been associated with the deposit. The requested year falls within that broad window, not at a demonstrable moment within it.

## **A Wetland Between Ice Advances**

Derryvree was exposed in 1969 when road works cut through a drumlin, one of the streamlined hills that now characterise much of Fermanagh. The section revealed a striking sequence: glacial till below, organic-rich freshwater sediments and fine sands in the middle, and another till above. This order is fundamental. It demonstrates that glacier ice had occupied the locality, that an ice-free interval then permitted water, plants and animals to leave traces there, and that later ice again overran and buried the landscape.

Such a sequence does not prove that all Ireland was ice-free at once. It records conditions at one locality, and glaciers, lakes, exposed ground and frozen soils could have formed a complicated regional mosaic. But it firmly rules out a simple picture of an island continuously smothered by ice throughout the whole period. Around the broad horizon represented by 30,978 BCE, at least parts of northern Ireland could sustain freshwater habitats between episodes of glaciation.

The wider climatic setting was unstable. Marine Isotope Stage 3, generally placed between about 57,000 and 29,000 years ago, contained repeated large shifts between relatively milder interstadial conditions and severe stadials. The eventual Last Glacial Maximum lay ahead rather than already at its height: major reconstructions place the fullest development of the British–Irish Ice Sheet principally after about 27,000 years ago. That later expansion would profoundly rework the land and erase or conceal many earlier traces. Derryvree is valuable precisely because its sediments survived beneath later glacial deposits.

## **Sedges, Mosses and Cold Water**

The Derryvree organic beds preserve a cold freshwater and wet-ground environment. Pollen, plant macrofossils, mosses and insect evidence point towards open, treeless vegetation with wet hollows, shallow pools and mossy ground. Grasses and sedges were important elements; finds also include plants associated with cold northern or Arctic-alpine settings, including mountain avens, dwarf willow and bogbean. A fossil bogbean seed is especially evocative, because it indicates standing or slow-moving freshwater with vegetated margins rather than a wholly dry, windswept plain.

Yet the scene should not be turned into a postcard. The evidence can support an open, periglacial wetland mosaic, but not a map of every slope, stream or plant community in Fermanagh in one particular year. Periglacial means shaped by intense cold and seasonal freezing and thawing near an ice-sheet environment; it does not mean that the deposit itself lay beneath glacier ice. Nor should sparse tree pollen automatically be read as proof of nearby woodland. Pollen can travel far, be redeposited, or represent vegetation beyond the immediate catchment. The strongest conclusion is a cold, largely open landscape with freshwater refuges.

For animals, such terrain offered both opportunity and constraint. Pools, sedge beds and herb-rich ground could sustain invertebrates and grazing or browsing mammals in favourable seasons, while long winters, snow cover, frost-shattered ground and abrupt climatic reversals limited what could persist. The relationship was ecological, not economic: there is no evidence that people in Ireland were managing herds, planting crops, storing grain or marking controlled pastures. The important history here is one of shifting habitats, animal movement and increasing glacial pressure.

## **Castlepook and the Southern Fauna**

County Cork supplies a different, complementary record. Castlepook Cave, also known as Mammoth Cave, near Doneraile has produced Ireland's most important assemblage of mammals from the last cold stage. Its collections include remains attributed to mammoth, reindeer, giant deer, brown bear, wolf, foxes, hare, lemmings and spotted hyaena. A spotted-hyaena skull and many other specimens are held by the National Museum of Ireland. Together they show that, during suitable pre-Last Glacial Maximum phases, Ireland formed part of a much wider north-west European zone in which cold-adapted mammals could reach and use the land.



The cave is not, however, a snapshot of one living community. Its deposits accumulated through several processes and probably across more than one episode. Carnivores could have dragged prey or scavenged bones into passages; animals may have died naturally; water could move sediments; and excavations in the early twentieth century removed much contextual information that modern field methods would preserve. Improved radiocarbon pretreatment has also shown that some older determinations from southern Irish caves were too young. Recent reassessment places important Castlepook material securely within MIS 3 and suggests that some species, including spotted hyaena and giant deer, disappeared locally before the Last Glacial Maximum.

That warning matters at 30,978 BCE. Castlepook establishes that these animals belonged to Ireland's broader Ice Age fauna, but it cannot demonstrate that a mammoth, hyaena or reindeer stood at the cave entrance in this exact year. Nor can a cave-bone list be assumed to represent one simultaneous food web. What it does reveal is a fluctuating faunal frontier: a country capable, at intervals, of supporting animals now absent from Ireland and, in some cases, from Europe altogether.

## The Human Question

The most consequential possible human evidence is a reindeer femur from Castlepook reported as carrying a deep mark interpreted as having been made by a sharp stone tool during carcass processing. If the mark is confirmed as anthropogenic and securely tied to the bone's Late Pleistocene age, it would indicate a remarkably early Upper Palaeolithic human visit to Ireland, far earlier than the island's formerly accepted post-glacial record.

It must remain a possibility, not a reconstructed society. A bone date establishes when the animal died, not necessarily the instant at which a surface mark was made. Identifying a mark as a cut made with a stone implement requires separate taphonomic analysis, distinguishing it from damage caused by carnivore teeth, trampling, sediment movement, excavation tools or later handling. Even a confirmed butchery mark would show the processing of one carcass, not the size of a group, the duration of a visit, the existence of a camp or a settled population.

There is no securely dated house, hearth, stone-tool assemblage, human burial, occupation floor or artistic object from Ireland at this horizon. Later evidence from Alice and Gwendoline Cave in County Clare demonstrates Upper Palaeolithic activity near the close of the Ice Age, but it cannot fill this much older gap. The approximately twenty-millennia distance between the two records is itself a warning against assuming continuity.

## No Kingdoms, No Settlements

Political affairs, diplomacy and warfare cannot responsibly be described for Ireland around 30,978 BCE. There are no named communities, leaders, languages, territories or institutions. "Ireland", "Fermanagh" and "Cork" are modern geographical conveniences, not evidence of identities existing then. Likewise, there is no basis for describing religion, formal learning, ceremonial practice, social hierarchy, marriage rules or exchange systems.

If people did reach the island during this interval, they were most plausibly mobile foragers operating at the far north-west edge of the inhabited European world. That is an interpretation based on the wider Upper Palaeolithic context, not a fact established by an Irish camp. A crossing or overland route cannot be specified from the present evidence. Lower sea levels changed coastlines, but the exact arrangement of

water, ice, exposed shelves and viable travel corridors was variable and requires local reconstruction. Claims of a permanent population, regular trade, organised hunting territories or a “first settlement” would go beyond the evidence.

## Approaching the Great Ice


The decisive development was environmental. Derryvree records a brief geological opening: cold freshwater, sedges, mosses and low vegetation occupying a place that had been glaciated and would be glaciated again. Castlepook records a wider world of mobile large mammals and predators. Both archives indicate that Ireland was neither an unchanging wilderness nor a documented human homeland. It was a climatically volatile edge-land whose habitable patches expanded and contracted over thousands of years.

Later ice-sheet growth would close many of those opportunities. Reconstructions based on landforms, marine cores and numerical modelling show the British–Irish Ice Sheet enlarging after this period and reaching much greater extent during the Last Glacial Maximum. Its advance transformed drainage, coastlines and terrain, while erosion and burial made the earlier record exceptionally fragmentary. For that reason, the sedge pools sealed beneath Derryvree’s drumlin are more than local curiosities: they are one of the clearest surviving witnesses to an Ireland that briefly held cold wetlands, wandering animals and perhaps the faintest trace of human action before the great ice reshaped the island.

## Chapter 024 of 100

30977 BCE

Dwarf Willow Below Maguiresbridge<sup>[24]</sup>



The label *30,977 BCE* is a modern filing device, not a date that anyone in prehistoric Ireland could have known or recorded. At this depth of time, calendar-year precision is impossible. Radiocarbon results carry statistical uncertainties, older determinations require careful calibration, and deposits may represent episodes lasting generations or centuries rather than a single year. The responsible subject is therefore Ireland in the later part of Marine Isotope Stage 3, roughly 33,000 years ago: a cold, changing Pleistocene world on the threshold of major ice-sheet growth, known from a very small and difficult body of environmental and faunal evidence.

### Evidence Rather Than Annals

There are no Irish annals, settlements, monuments, artefacts in secure context or named communities for this period. There can be no account of a king, battle, alliance, migration fleet or religious ceremony in the normal historical sense. Nor is it responsible to convert a single animal bone or a patch of buried mud into a story of a settled population. What survives instead is a scattered archive: sediments sealed beneath later glacier deposits, pollen and plant macrofossils, insect remains, cave bones, landforms and radiocarbon measurements. These materials reveal environmental conditions and the presence of particular animals; they only sometimes allow cautious inferences about human activity.

The period belongs to the Middle Midlandian cold stage in older Irish terminology and to MIS 3 in the wider international framework. It preceded the full Last Glacial Maximum, when ice covered Ireland and its continental shelf most extensively, conventionally placed at about 27,000–23,000 calibrated years before present in Irish syntheses. Newer British–Irish Ice Sheet reconstructions stress that ice growth, maximum extent and retreat differed greatly from one sector to another. They begin their island-wide

reconstruction at 31,000 years before present because earlier constraints are sparse, then depict ice building across Ireland and Britain between 31,000 and 26,000 years ago. That uncertainty is especially important for a modern date-label such as 30,977 BCE.

## **A Wet, Treeless Fermanagh**

The closest Irish environmental witness is Derryvree, near Maguiresbridge in County Fermanagh. Roadworks exposed freshwater silts and fine sands trapped between two layers of glacial till. The organic bed produced a conventional radiocarbon age of 30,500  $\pm$  1,170–1,030 radiocarbon years BP. That is not a precise equivalent of 30,977 BCE: calibration converts it into an older and wider calendar range. Yet it securely places the deposit in the late Pleistocene interval relevant to this article and demonstrates that this part of Ireland was not continuously buried beneath ice during the entire cold stage.

Its fossils indicate an open, largely treeless and waterlogged landscape, often described by researchers as tundra-like muskeg. Grasses, sedges, herbs, juniper and a rich moss flora grew around shallow freshwater. Plant remains include bogbean and dwarf willow, while mountain-avens and lesser clubmoss point towards cold, exposed conditions. Water-milfoil indicates open water. This was not the green, wooded Ireland familiar from later prehistory or the present day. Growing seasons were short, frost was a persistent force, and the ground probably alternated between saturated hollows, pools, sedge margins and drier patches of sparse vegetation.

Derryvree must not, however, be mistaken for a complete map of the island. Pollen can travel, sediments can be reworked, and a road-cut deposit records conditions in one locality over an interval of deposition. It does establish a powerful minimum: a freshwater ecosystem existed in Fermanagh during a severe cold phase. It makes a simple image of an Ireland already smothered entirely by permanent ice untenable. At the same time, it does not prove that every coast, upland or lowland was similarly open, nor that the wetland was occupied by people.

## **Castlepook's Animal World**

For large mammals, Castlepook Cave—also called Mammoth Cave—near Doneraile in north County Cork is the crucial site. Excavations in the early twentieth century and later work recovered remains of woolly mammoth, reindeer, giant deer, brown bear, wolf, Arctic fox, hare, lemmings and spotted hyaena. The National Museum of Ireland describes Castlepook as the country's most important site for mammal remains from the last cold stage. Its fauna shows that Ireland could support, or at least receive, a striking assemblage of large herbivores and predators during parts of the late Pleistocene.

The cave record must be read with care. A cave is not a census of a living landscape: animals can die there, be dragged in by predators, be scavenged, or be redistributed by water, sediment movement and nineteenth- or twentieth-century excavation. Direct dates from Castlepook span a very long period, and recent work has reconsidered older radiocarbon determinations using improved methods of bone pretreatment. The assemblage therefore illuminates the broader MIS 3 and pre-maximum cold world, not one synchronised herd crossing Cork in a single year.

Nevertheless, the animals make ecological sense alongside the Fermanagh evidence. Reindeer, mammoth and giant deer suggest extensive open country rather than closed forest. Arctic foxes and lemmings reinforce the evidence for a cold climate, while spotted hyaenas and wolves remind us that predators were part of the same landscape. Ireland's position was also different from today's in a world of



lower sea levels and repeatedly changing ice margins. Animals had evidently reached the island from Britain or the wider north-west European landmass during favourable phases, although the precise routes and shoreline configurations at every date remain uncertain.

## **The Human Question**

The most arresting, but also most limited, possible evidence for people is a reindeer femur from Castlepook reported in 2021 as bearing a deep mark made while fresh and consistent with stone-tool butchery. The bone was publicised as approximately 33,000 years old, a result that, if its interpretation and context are sustained, would place a human action in Ireland far earlier than the traditionally recognised terminal-Pleistocene evidence. It would not establish a village, an enduring population, a named culture or even a repeated seasonal camp. At most, it would indicate that one or more people reached the island and processed an animal.

That distinction matters. No hearth, stone-tool assemblage, dwelling floor, burial or securely associated collection of butchered animals has been published from Castlepook for this age. The National Museum of Ireland's general prehistoric guidance still states that no clear Palaeolithic evidence has emerged for humankind in Ireland, reflecting the caution appropriate to such an exceptional claim. Cut-mark identification requires close taphonomic study because carnivore activity, sediment abrasion, trampling, excavation damage and later handling can also alter bone surfaces. The reindeer femur is therefore an important research problem, not a licence to write a settled Palaeolithic history of Ireland.

## **Society Without States**

Political affairs, diplomacy and organised warfare cannot be recovered here. If people did reach Ireland, the evidence is compatible only with small, mobile Upper Palaeolithic foraging parties, not states or tribes known by name. Any crossing would have required knowledge of landscapes, weather, animal movements and routes, but the means of travel cannot be specified. No material supports claims about language, kinship, leadership, trade networks or relations between separate groups. It is equally unwarranted to assume permanent isolation: the animal record proves that the island was connected ecologically to wider north-west Europe at least intermittently, but animals and people need not have moved under the same conditions.

Everyday life, if human activity occurred, would have been structured by cold, mobility and the risks of meeting large carnivores. Reindeer could theoretically offer meat, fat, hide, sinew, antler and bone; this is a general inference from hunter-gatherer practice, not something demonstrated at Castlepook. There is no Irish evidence from this horizon for houses, clothing, fires, art, burial, ritual, teaching or exchange. Culture and learning were doubtless essential to any people who survived in Ice Age Europe, yet their local Irish expression remains archaeologically invisible.

## **Approaching the Ice Maximum**

The great development of the age was environmental, not political: the build-up of the British-Irish Ice Sheet. Later ice would reshape much of Ireland, eroding bedrock, depositing till and helping to create the drumlins, moraines and other landforms that dominate many modern landscapes. Around the period represented by this article, that outcome was not yet uniform across the island. Derryvree preserves an


ice-free wetland interval; the broader reconstruction shows ice accumulating and expanding over subsequent millennia. The future maximum should not be projected backwards as though it had already happened everywhere.

For Ireland at 30,977 BCE, then, the strongest historical conclusion is also the most restrained. This was a cold, open and regionally varied Pleistocene landscape, inhabited by distinctive mammals and increasingly affected by advancing ice. A Fermanagh wetland preserves dwarf willow, sedges and aquatic plants beneath later glacial deposits; a Cork cave preserves the bones of reindeer, mammoth and hyaena. A possible cut-marked reindeer bone raises the prospect of a fleeting human presence, but does not yet provide a human society. The archive is thin, but it is enough to replace blankness with a real, changing Ice Age Ireland.

# Chapter 025 of 100

## 30976 BCE

### Derryvree's Muskeg Witness<sup>[25]</sup>



**The label 30,976 BCE is a modern chronological convenience, not a recoverable Irish year. Nobody in Ireland recorded it, and neither archaeology nor environmental science can isolate a particular season, journey, hunt or death at such depth in time. Expressed against the conventional radiocarbon baseline of AD 1950, it is roughly 32,925 calendar years before present. The responsible setting is therefore a broad part of the Late Pleistocene, within Marine Isotope Stage 3 (MIS 3), rather than an annual chronicle.**

The evidence is sparse, local and uneven. It consists chiefly of sediments, fossil plants and insects sealed beneath later ice, cave-bone collections whose formation histories are complicated, and reconstructions of glaciers and ancient coastlines. These sources reveal much more about climates, habitats and animals than they do about people. They provide no basis for naming an Irish community, leader, political territory, religion or language at this date.

## **A Date Within a Wide Range**

The closest Irish chronological anchor is Derryvree, near Maguiresbridge in County Fermanagh. Road-cutting in 1969 exposed a remarkable sequence inside a drumlin: a lower glacial till, organic-rich freshwater silts and fine sands, and a second, later till above. The order of the deposits is the crucial evidence. Ice had covered the locality, then retreated or ceased to occupy it long enough for standing or slow-moving freshwater, plants and sediment to accumulate; later glacier ice buried the whole wetland archive.

Organic material from the Derryvree deposit produced a radiocarbon determination of 30,500 radiocarbon years BP, with a large uncertainty. Calibration is essential because radiocarbon years are not identical to calendar years: atmospheric carbon-14 has varied through time. Published discussion places

the result broadly at about 36,900–31,700 calibrated years BP, approximately 34,950–29,750 BCE. The notional year 30,976 BCE falls within that broad range. It does not, however, identify a specific layer, living plant or event within it. The range itself, and the distinction between a measurement and its calendar-age interpretation, are more historically meaningful than any artificial single-year precision.

Derryvree is not a weather station for all Ireland. It records one Fermanagh locality during one ice-free interval, and its conditions cannot automatically be projected to Cork, Kerry, the western seaboard or the Irish Sea basin. Yet it is exceptionally valuable because later glaciers eroded, mixed or sealed so much of Ireland's older landscape. It demonstrates that parts of Ireland could contain terrestrial and freshwater habitat during the unstable middle part of the last cold stage, before the greatest expansion of the last British–Irish Ice Sheet.

## **Wet Tundra Under a Changing Sky**

The Derryvree fossils indicate an open, treeless and waterlogged environment often described as tundra or muskeg: moss-rich wet ground with shallow pools, sedges and low herbaceous vegetation. Plant evidence includes grasses, sedges, juniper, bogbean, water-milfoil, dwarf willow, mountain-avens and arctic-alpine mosses. Insects add detail, pointing to open wetland conditions, exposed ground and a severe periglacial regime. This was not an evergreen forest nor an empty white waste, but a patchwork whose appearance altered with drainage, season and climate.

That reconstruction is evidence-based, but it must be kept at the right scale. Fossil plant remains show that suitable habitats existed near the Derryvree pool; they do not supply a complete map of Irish vegetation in 30,976 BCE. Likewise, the word “tundra” is a useful ecological comparison, not a claim that every part of the island resembled modern Arctic terrain. Ireland lay at the Atlantic edge of north-west Europe, where oceanic influences, relief and the proximity of ice could create strong regional contrasts.

Climate in MIS 3 was not stable. Greenland ice-core records reveal abrupt warmer interstadials and colder stadials across the North Atlantic world. Irish cave flowstones and intertill organic deposits independently show that cold-stage conditions included intervals when liquid water moved through caves and wetlands developed. Around the date in question, the best interpretation is of a harsh but changing environment, with cold winters, short growing seasons and recurring shifts in the extent of snow, frozen ground, vegetation and local ice. It was not yet the full Last Glacial Maximum: large-scale reconstructions indicate that the British–Irish Ice Sheet grew substantially from about 31,000 to 26,000 years BP, before reaching its greatest volume later, around 23,000 years BP.

## **Castlepook and the Animal Record**

County Cork's Castlepook Cave, also called Mammoth Cave, provides the other major Irish window onto this broad period. Excavated mainly between 1904 and 1918, it yielded more than 2,000 animal bones and remains of woolly mammoth, reindeer, giant deer, brown bear and spotted hyaena, alongside smaller cold-adapted animals in other parts of the sequence. Geological Survey Ireland describes it as Ireland's richest vertebrate-fauna site for the period leading towards the Last Glacial Maximum.

The cave's importance should not turn its collection into a single imagined scene. Bones accumulated over a long interval, water disturbance affected deposits, and early excavation methods removed much of the original context. Modern re-dating has shown that several old radiocarbon results underestimated the age of bones by thousands of years. The revised evidence places some Castlepook fauna firmly in MIS 3; for spotted hyaena and giant deer, the research suggests local disappearance before the Last Glacial

Maximum. A mammoth, a hyaena and a reindeer bone from the site are direct evidence that such animals reached Ireland at different points in this extended cold-stage world. They are not proof that all stood together beside one Fermanagh pool in 30,976 BCE.

Nevertheless, the combined Derrynvree and Castlepook record gives Ireland an unexpectedly varied ecological history. Large herbivores would have depended on open vegetation, while predators and scavengers used the same wider landscapes in different ways. Reindeer are especially associated with open cold country; woolly mammoth evokes steppe-tundra grazing; spotted hyaena demonstrates that Pleistocene Ireland included carnivores wholly absent from its later fauna. Cave bones reveal presence and, sometimes, the action of predators or water. They do not reveal herd sizes, migration routes or a balanced food web with certainty.

## **People: A Possibility, Not a Population**

A reindeer femur from Castlepook has made this period especially important for the history of human presence in Ireland. The bone has been presented in Cork heritage material as dating to about 31,000 BC and as bearing a deep mark interpreted as having been made on fresh bone by a sharp stone tool during butchery. If that interpretation is sustained, it would be a striking indication that a person handled a reindeer in Ireland far earlier than the well-established evidence for terminal Pleistocene activity.

Its implications must be expressed conditionally. The date concerns the death of the animal, not a calendar date for the incision. A single marked bone does not establish a camp, a resident population, a family group, a crossing route or recurring occupation. No securely associated hearth, stone-tool assemblage, dwelling surface, burial, food store or concentration of butchered animals has been published for Castlepook at this age. The cave's complex history makes context especially important. At most, the evidence presently permits the possibility of brief, mobile human activity in Ireland during MIS 3.

This restraint matters because the usual historical categories do not yet apply. There is no evidence for government, diplomacy, territorial rule, warfare or organised trade. Nor can archaeology recover named kin groups, language, religious observance, stories, art or systems of learning for Ireland at this date. Small hunter-gatherer parties elsewhere in Upper Palaeolithic Europe certainly possessed rich social and cultural lives, but that wider knowledge cannot be converted into a description of a documented Irish society. Absence of evidence is not proof that no person ever arrived; it is, however, decisive against inventing an Irish people or culture from one disputed trace.

## **Land, Sea and Access**

Lower global sea level exposed more of the continental shelf than exists today, changing coastlines and the extent of lowland terrain. But "lower sea level" should not be simplified into a guaranteed land bridge or an easy route. Ice margins, proglacial water, changing drainage, sea ice, exposed shelf surfaces and the Irish Sea basin all affected access differently over time. Ireland's physical relationship with Britain and continental Europe was dynamic, and the precise route available at one moment cannot be read from a cave bone or wetland silt.

For animals, the practical economy was ecological rather than commercial: survival depended on seasonal forage, freshwater, shelter and movement through habitats that could vanish as ice advanced. If people did visit, they would have lived by mobile foraging, hunting and the careful use of animal and

plant resources, not by farming, permanent villages or exchange networks known from later prehistory. That is an inference from the environmental setting and comparable Upper Palaeolithic lifeways, not direct evidence from an Irish settlement.

## **Approaching the Ice Maximum**


The major development around 30,976 BCE was therefore environmental change, not a datable public event. Derryvree preserves a rare moment when wet tundra and freshwater life existed between separate episodes of glaciation. Castlepook preserves a longer, difficult animal archive from a land intermittently used by mammals ranging from reindeer to hyaena. Together they show that Ireland before the Last Glacial Maximum was neither permanently ice-covered nor simply hospitable. It was a changing northern landscape in which habitable pockets could emerge, contract and disappear.

Within a few millennia, expanding ice would transform the island and destroy or conceal many traces of this earlier world. The surviving sediments and bones are consequently not marginal curiosities: they are the principal witnesses. They support a history of cold wetlands, open ground, remarkable fauna and possible fleeting human contact, while firmly withholding the political and cultural narrative that later Irish history makes familiar.

# Chapter 026 of 100

## 30975 BCE

### Lesser Clubmoss at Derryvree<sup>[26]</sup>



30,975 BCE is a modern chronological label, not a year that anyone in Ireland recorded or recognised. At this depth in time, modern calendar-year precision is unavailable. The label falls roughly 32,924 years before AD 1950, the conventional reference point for radiocarbon chronology, but that arithmetic conversion must not be mistaken for an archaeological date. The responsible setting is a broad Late Pleistocene interval within Marine Isotope Stage 3 (MIS 3), the fluctuating cold phase before the Last Glacial Maximum. Ireland can be illuminated here by calibrated ranges, buried sediments, fossils and landforms—not by a year-specific event, named person or political narrative.

## A Wetland Between Glaciers

The most informative Irish evidence close to this notional date comes from Derryvree near Maguiresbridge, County Fermanagh. Roadworks in 1969 cut through a drumlin and revealed freshwater silts, fine sands and organic deposits sealed between two distinct layers of till: unsorted sediment left by glacier ice. The stratigraphy gives a secure relative sequence. Ice had deposited the lower till; later, the locality supported open water and wet ground long enough for sediments, plants and animals to accumulate; then another advance of ice buried the deposit beneath upper till. This is exceptionally valuable evidence, because later glaciation removed or obscured many older Irish landscapes.

Organic material from the Derryvree freshwater series produced a radiocarbon determination of about  $30,500 \pm 1,170$  radiocarbon years BP. On modern calibration, its wide probability range has been placed broadly around 36,900–31,700 calibrated years BP, approximately 34,950–29,750 BCE. The requested date lies within that long interval, but it cannot be tied to a particular sediment layer, season or generation.

Nor does one Fermanagh wetland prove that all of Ireland shared the same conditions at precisely the same time. It does, however, demonstrate that an inland locality was not continuously overridden by ice during this part of the last cold stage.

## Cold Water, Open Ground

Derryvree's pollen, plant macrofossils, mosses, insects and small-animal remains point to treeless, cold-stage country. Sedges, grasses, mosses and herbs grew around shallow or slow-moving freshwater. Arctic-alpine plants, including lesser clubmoss, indicate short growing seasons and severe winter conditions. The older term *muskeg* has been used for the deposit's wet, organic-rich character, but it should not suggest a modern peat bog transplanted intact into the Ice Age. The evidence supports a mosaic of pools, silty margins, marshy ground and more exposed mineral surfaces, shaped by frost, thaw and seasonal runoff.

This was not necessarily a lifeless white expanse. Summer thaw permitted plant growth and made wetlands locally productive, while winter frost, low light and wind imposed extreme limits. A few grains of tree pollen in such deposits cannot establish nearby woodland: pollen can travel very long distances, and the wider Derryvree assemblage is overwhelmingly consistent with open vegetation. The strongest factual claim is therefore local: a cold freshwater environment existed at Derryvree during an interval between ice advances. Reconstructing a wider tundra-like landscape is a cautious interpretation, well supported by the fossils and regional climatic evidence but still broader than the deposit itself.

## Castlepook's Animal Archive

In the south, Castlepook Cave near Doneraile in County Cork provides the principal Irish animal archive for the period leading towards the Last Glacial Maximum. The cave's early excavations recovered more than 2,000 bones. Subsequent radiocarbon work and reassessment have shown that its fauna accumulated over a long and complicated span, rather than during one occupation or one ecological moment. Finds include woolly mammoth, reindeer, giant deer, brown bear, wolf, Arctic fox, hare, lemmings and spotted hyaena. Their presence demonstrates that cold-adapted and open-country mammals reached Ireland in several Late Pleistocene phases.

Caves are not neutral stores of evidence. Carnivores could drag carcass parts underground; animals could die naturally in or near entrances; water could move bones; and early twentieth-century excavation disturbed original relationships between deposits. Castlepook therefore cannot be read as a tidy inventory of animals that stood together outside the cave on a single day. Yet the cumulative faunal evidence is important. It indicates an Ireland connected, at least intermittently, to the wider north-west European world of grazing herds, predators and scavengers. Lower sea levels exposed far more land on the continental shelves than exists today, although the exact routes, timings and ease of animal crossings remain matters of research rather than certainty.

## The Reindeer Femur Question

Castlepook is also central to a major, unresolved question in Irish prehistory. A reindeer femur from the cave, re-examined by Ruth Carden, bears a deep mark interpreted as compatible with butchery using a stone tool. The animal bone has been publicised as approximately 33,000 years old, making the find



potentially relevant to the broad period represented by this article. If the modification is securely anthropogenic, it would be the earliest currently claimed indication that people handled an animal in Ireland, far earlier than the long-established record of post-glacial settlement.

Its importance should not be exaggerated. A marked bone would document an action, not a settled community. The age of the bone is not an exact date for the mark, and the find lacks a securely associated hearth, stone-tool assemblage, occupation floor, dwelling, burial or repeated concentration of butchered remains. There is no basis for naming the people involved, assigning them an ethnic identity or reconstructing their language. It is possible that a small group briefly reached Ireland, killed or processed an animal, and left little else that survived later glaciation. It is equally essential to acknowledge that the interpretation requires continued scrutiny and publication of the cave's stratified deposits.

## **No Politics, No Proven Trade**

Political affairs, diplomacy and warfare cannot responsibly be supplied for Ireland at this point. There are no written records, settlements, weapons assemblages, boundaries, graves or monuments from which to infer leaders, alliances or territorial communities. The evidence does not support claims for tribes, kingdoms or an organised Irish population. The possible Castlepook intervention, if confirmed, belongs to a much smaller scale: a transient encounter between people, an animal and a demanding landscape.

Likewise, there is no evidence for agriculture, herding, permanent villages, pottery, long-distance commerce or formal trade in Ireland around this date. The economic framework visible in the fossils is ecological rather than institutional. Reindeer and other herbivores would have converted sparse vegetation into mobile food resources for predators, scavengers and, perhaps, passing hunters. Any human group present would have depended on close knowledge of animal movements, weather, shelter and the seasonal availability of fuel and water. That is a reasonable inference from Late Upper Palaeolithic lifeways elsewhere in north-west Europe, but it is not direct evidence for an Irish camp.

## **Culture Beyond Recovery**

Religion, art, storytelling, kinship and learning surely mattered to any humans who may have entered this landscape, but none is recoverable from the Irish evidence of this age. No figurative art, engraved object, musical instrument, ritual deposit or human burial can be assigned securely to Ireland around 30,975 BCE. Silence in the record is not proof that people had no culture; it is a limit imposed by preservation and discovery. The later ice sheet was an especially destructive historical force, eroding ground surfaces and redepositing sediments across much of the island.

For the same reason, absence of an excavated camp should not be equated mechanically with absence of every person. The archaeological claim must remain proportionate: there is no confirmed occupation site of this age in Ireland. Castlepook offers a potentially transformative but isolated trace; Derryvree offers a rich environmental sequence rather than a human one. Together they make a historical landscape visible without allowing it to be overpopulated with imagined scenes.

## **Ice Was Building**

The fuller expansion of the last British–Irish Ice Sheet lay ahead, though ice growth was already reshaping the wider archipelago. A widely used chronological model places major British–Irish Ice Sheet build-up after about 35–32 thousand years ago, with maximum extent broadly around 27–21 thousand


years ago; other reconstructions stress strong regional variation in the timing and thickness of ice. Ireland was thus entering a period in which local ice margins, sea level, drainage and habitable ground could change greatly over millennia. Derryvree's upper till is physical testimony that conditions there did not remain benign.

The most meaningful development around this notional year was therefore environmental instability. In Fermanagh, freshwater life occupied a cold interlude between glacier advances. In Cork, cave deposits preserve the remains of a varied Ice Age fauna, together with the contested possibility of human butchery. These are not fragments of an annual chronicle; they are the surviving evidence of a changing Pleistocene Ireland. They show an island—or, more accurately, a changing north-western peninsula and shelf-edge landscape—whose ecological opportunities were real but narrow, and whose human history remains tantalisingly difficult to prove.

# Chapter 027 of 100

## 30974 BCE

### Derryvree's Sealed Waterline<sup>[27]</sup>



**“30,974 BCE” is a modern chronological label, not a year that can be recovered from an Irish calendar, a written record or a dated human event. In archaeological terms it is approximately 32,923 years before AD 1950, the conventional “before present” reference point. That numerical conversion is useful only for orientation. At such depth in time, radiocarbon measurements require calibration and normally yield broad probability ranges rather than annual precision. The most responsible account of Ireland at this point therefore concerns a late-Pleistocene interval whose surviving deposits overlap the date, not a supposed episode that happened within one particular year.**

## **A Cold-Phase Ireland**

The relevant setting is Marine Isotope Stage 3, part of the last glacial cycle and, in Irish terminology, the Midlandian. This was not the Last Glacial Maximum itself. The greatest expansion of the British–Irish Ice Sheet came later, although its timing and extent varied greatly between regions. Around the notional date in question, Ireland was subject to pronounced climatic instability: colder stadial conditions alternated with comparatively milder interstadial episodes across the North Atlantic world. The island’s terrain, coastlines, drainage and ice margins did not necessarily resemble their modern forms, and no single reconstruction can safely stand for every valley or county.

The best Irish environmental evidence close to this horizon comes from Derryvree, near Maguiresbridge in County Fermanagh. Roadworks in 1969 cut through a drumlin and exposed silts, fine sand and organic material lying between two thick tills: unsorted sediments deposited by glacier ice. The sequence is especially valuable because it establishes relative order. A phase of glaciation produced the

lower till; an interval in which freshwater sediment accumulated followed; and a later ice advance buried the deposit beneath upper till. Derryvree is not a settlement site, but it preserves an unusually local record of a living landscape that later ice sealed from view.

## The Limits of the Date

Organic material from the Derryvree freshwater series produced a conventional radiocarbon determination of 30,500 years BP, with substantial laboratory uncertainty. Published calibration has placed the deposit broadly at about 36,900–31,700 calibrated years BP, approximately 34,950–29,750 BCE. The requested date lies within that long interval. It does *not* follow that any one seed, insect, moss stem or silt layer can be assigned to 30,974 BCE, still less that conditions observed at Derryvree prevailed throughout Ireland in that year. Calibration curves, including IntCal20, are essential because atmospheric radiocarbon concentrations have changed through time; they improve chronology but cannot turn an Ice Age deposit into an annual diary.

Older descriptions sometimes called Derryvree an interstadial deposit, suggesting a notably milder break within glacial conditions. The fossils themselves require a more restrained formulation. They indicate that ice was not overriding that particular Fermanagh locality while the freshwater bed formed, and that plants and small animals occupied a cold, open environment. They do not demonstrate a warm, wooded Ireland, a nationwide thaw, or a stable climate lasting for a known number of generations. The later till above the organic bed is a powerful reminder that the apparent environmental opportunity was eventually ended or transformed by renewed glaciation.

## Wetland on Open Tundra

Derryvree's pollen, plant macrofossils, mosses and insect remains indicate tundra-like, periglacial surroundings. The evidence includes sedges, mosses and plants associated with shallow water and wet ground, alongside arctic-alpine species such as mountain-avens and dwarf willow. Bogbean and alternate water-milfoil are particularly revealing: they point to freshwater and damp margins rather than an entirely dry, barren plain. In combination, the material suggests a mosaic of pools, silty shallows, saturated ground and open herb-rich vegetation, with little or no tree cover in the immediate area.

This was a demanding but not lifeless landscape. Seasonal freezing and thawing, short growing seasons, exposed ground and changing water levels would have shaped every habitat. Yet the freshwater record demonstrates that plants, invertebrates and other small organisms found viable niches. It is better imagined as patchy cold-country wetland than as a uniform sheet of snow. Equally, it should not be romanticised as a modern nature reserve transported into the past. The assemblage survives from one basin under exceptional geological circumstances; it offers a close view of its locality, not a complete inventory of Irish life.

## Animals and the Cave Record

Far to the south, Castlepook Cave near Doneraile in north County Cork provides a different kind of evidence. Reassessment and improved radiocarbon dating of cave fauna have shown that several Irish animal remains once thought much younger belong in Marine Isotope Stage 3. The cave's wider Pleistocene assemblage includes reindeer, woolly mammoth, giant deer, brown bear, wolf, fox, hare,

lemmings and spotted hyaena. These species were not necessarily all present together, nor should every bone be treated as evidence for the precise year under discussion. Cave deposits can combine material accumulated across long periods and altered by carnivores, water, collapse, frost and early excavation.

Even so, Castlepook confirms that Ireland was ecologically connected to the wider cold-stage world of north-west Europe. Reindeer and lemmings indicate severe, open-country conditions; mammoth and giant deer evoke the large herbivores capable of ranging through suitable grass-, herb- and shrub-rich terrain; hyaena, wolf and bear show that predators and scavengers were part of the food web. A cave is not a transparent sample of the surrounding countryside. Carnivores may have carried carcass parts into it, and bones may have been reworked. Its principal value is to show the possible breadth of fauna, while Derryvree supplies the sharper environmental picture.

## **A Possible Human Trace**

Castlepook also holds the most consequential, but still limited, evidence relevant to people. A reindeer femur from the cave has been publicly dated to roughly 31,000 BCE and bears a deep mark interpreted by palaeozoologist Ruth Carden as damage made by a sharp stone tool during butchery. If that interpretation is sustained, it would indicate that Upper Palaeolithic people processed a reindeer in Ireland during this broad pre-maximum glacial period. It would substantially extend the island's known human story beyond the better-established terminal-Pleistocene and Mesolithic records.

The qualification matters. The bone came from an old cave collection, not from a modern excavation of an intact occupation floor. No securely associated hearth, lithic assemblage, dwelling, burial, repeated camp surface or food store has yet established a permanent human community in Ireland at this age. A date on the animal bone is not automatically a date for the incision, although analysis of fresh-bone modification is central to the interpretation. The responsible conclusion is that brief human visitation or carcass processing is plausible and important, but that settlement, population size, routes of arrival and continuity of occupation remain unknown.

## **No Politics, No Proven Trade**

There is therefore no evidence from Ireland around this horizon for political institutions, named groups, diplomacy, territorial rule, warfare, formal religion, monuments, writing or organised learning. Nor can trade be demonstrated. A mobile hunter-gatherer party, if people were indeed present, might have depended on skills familiar elsewhere in Upper Palaeolithic Europe—stone-tool use, clothing, shared knowledge of animals and seasonal movement—but those are continental comparisons, not Irish facts. Ireland has not yielded the tools, ornaments, structures or art needed to show that such practices occurred here at this date.

Everyday life must be approached through the same distinction. The fauna and wetland flora establish available environments and potential resources, not meals, households or social identities. Reindeer, other large mammals, freshwater settings and plant-rich ground may have offered opportunities for mobile foragers, but archaeology has not yet demonstrated a local economy. The most important historical development is consequently environmental: some places supported cold-adapted ecosystems before later ice rearranged the land and obscured much of the evidence.


## **A Landscape, Not a Nation**

Ireland at this remote point was neither an empty abstraction nor a known human society awaiting a national history. It was a changing Pleistocene landscape of wetlands, open tundra vegetation, mobile animals and encroaching or retreating ice. Derryvree's buried freshwater sediments establish that cold ecological communities could persist locally between glacial episodes. Castlepook suggests that a surprisingly diverse fauna ranged in the south and preserves a provocative possible sign of human action. Together, the sites demand both imagination and restraint: they illuminate an Ice Age Ireland, but they do not permit a year-by-year narrative, a map of peoples or a story of permanent settlement for 30,974 BCE.

# Chapter 028 of 100

## 30973 BCE

### Hyenahall's Reindeer Femur<sup>[28]</sup>



**30,973 BCE is not a year for which Ireland has an annal, a named people or an identifiable event. It is a modern calendar label projected deep into the Late Pleistocene. No calendar was used in Ireland, and archaeological dating at this depth of time cannot isolate a particular season, generation or year. In the archaeological convention of years before AD 1950, the label falls at roughly 32,900 years before present. The responsible subject is therefore Ireland during the later part of Marine Isotope Stage 3 (MIS 3), a long and climatically unstable stretch of the last Ice Age, rather than an invented episode in a single year.**

The evidence is fragmentary but important. It comes chiefly from buried freshwater sediments at Derrynree near Maguiresbridge in County Fermanagh, and from the rich animal-bone assemblage of Castlepook Cave, also called Mammoth Cave, near Doneraile in north County Cork. Together they show that parts of Ireland supported cold-adapted plants and animals before the Last Glacial Maximum. One marked reindeer femur from Castlepook also raises the possibility of a far earlier human presence than was once accepted. Yet possibility must not be mistaken for proof of settlement.

## **A Date Range, Not a Dated Event**

The closest dated environmental sequence is Derrynree. Roadworks in 1969 exposed fine sands, freshwater silts and organic material lying between two thick sheets of till, the unsorted debris deposited by glacier ice. The sequence records a clear order of events: ice affected the locality; an ice-free freshwater environment later developed; and a renewed advance of glacier ice buried the deposit. It does not provide a diary of a single year, but it is powerful evidence that this part of Fermanagh was not continuously overridden by ice throughout the later Pleistocene.

The organic bed produced a conventional radiocarbon determination of 30,500  $\pm$  1,170/–1,030 radiocarbon years BP. Radiocarbon years are not calendar years, particularly so far back in time, because atmospheric carbon-14 levels changed. Calibration using modern northern-hemisphere curves gives a broad calendar range, commonly expressed at approximately 36,900–31,700 calibrated years BP. The nominal year 30,973 BCE falls within that span, but the overlap is broad: it cannot tell us what happened at Derryvree in that particular year, or even prove that all districts of Ireland shared its conditions simultaneously.

This distinction is fundamental. Derryvree is a local archive sealed beneath later ice deposits, not a weather station for the whole island. The age range nevertheless places its freshwater ecosystem in the same wider late-MIS 3 world as the year under consideration: a cold, variable Ireland in which ice margins, wetlands, open ground and animal ranges changed over centuries and millennia.

## Derryvree's Cold Wetland

The Derryvree fossils replace the misleading image of an Ice Age Ireland as either uniformly ice-covered or lifeless. Pollen, plant macrofossils, mosses and insects indicate open, treeless terrain with wet ground, shallow pools and freshwater channels. Sedges and grasses grew with herbs and low shrubs. Finds reported from the deposit include bogbean, alternate water-milfoil, dwarf willow and mountain-avens: plants consistent with cold, damp, periglacial conditions but also with standing or slow-moving water and a short productive season.

The older term *muskeg*, used by researchers for this sort of moss-rich wetland, is useful if it is not allowed to suggest a modern landscape reproduced exactly in the past. Derryvree was probably a shifting mosaic. Frost, seasonal freezing and sparse tree cover shaped exposed ground; pools and saturated margins gave shelter to aquatic plants and insects; nearby drier patches could support herbs and grazing. The evidence directly establishes species and depositional conditions near one body of water. Reconstructing its wider appearance as a tundra-like landscape is a reasonable interpretation, but one that should retain that local limit.

Climate was harsh. Earlier analysis of the plant and insect evidence inferred severe winters and relatively cool summers. Yet harsh did not mean permanently frozen. Freshwater sediment accumulated, plants flowered and mosses spread. Such habitats mattered because they offered water, forage and cover within an exposed northern environment. They also show why the history of glaciation cannot be reduced to a simple story of an ice sheet arriving once and covering every part of Ireland continuously until its final retreat.

## Castlepook's Animal World

In County Cork, Castlepook Cave preserves Ireland's most substantial assemblage of vertebrate remains from the period before the Last Glacial Maximum. Excavations undertaken mainly between 1904 and 1913 recovered more than 2,000 bones from galleries given evocative names including Hyenahall and Elephant Hall. The cave's fauna includes woolly mammoth, reindeer, giant deer, brown bear, wolf, foxes, hare, stoat, lemmings and spotted hyaena. It is evidence that Ireland was connected ecologically to the wider north-west European cold-stage world, even though the precise routes, timings and durations of individual animal movements remain difficult to reconstruct.



The animal list should not be read as a photograph of one living herd gathered outside the cave. Castlepook was a cave repository used and disturbed over a long period. Carnivores could carry in bones; water could move sediments and remains; collapse, frost and early excavation could disturb their original relationships. Modern re-dating has also shown that some older radiocarbon determinations from Irish caves were too young, because improved pretreatment removes contaminants from ancient bone collagen more effectively. Individual Castlepook remains now demonstrate a long chronological spread rather than a single occupation horizon.

Even so, the fauna supports an image of open country able to sustain large grazers and browsers, alongside formidable predators and scavengers. Reindeer fit cold, open landscapes and may have ranged seasonally; mammoth and giant deer attest to an ecological richness now wholly absent from Ireland. Spotted hyaena is particularly significant. Castlepook is its only known Irish site, and hyaenas may themselves explain part of the bone accumulation. A cave full of bones is therefore not automatically a human hunting camp.

## **The Mark on One Bone**

The most consequential possible human evidence is a fragment of reindeer femur from Castlepook. Public heritage material places it broadly around 31,000 BC and identifies a deep linear mark which zooarchaeologist Ruth Carden has interpreted as damage made by a sharp stone implement while fresh bone was being processed. If that interpretation is sustained, it would indicate that a person used a cutting edge on a reindeer carcass in Ireland during the Upper Palaeolithic, vastly earlier than the formerly accepted evidence for human activity after the final glacial retreat.

That is a major claim, but it is a narrow one. The bone does not come from a modern, sealed excavation trench containing associated flint tools, hearths, dwelling traces, human remains and a complete butchered assemblage. Its radiocarbon age dates the animal's death within a scientific range; it does not automatically identify the maker of the mark, establish where the carcass was processed or demonstrate that hunters killed the reindeer at the cave. County Cork heritage interpretation reasonably suggests that a carnivore may have transported discarded limb material into a den after people had processed the animal elsewhere.

No securely contemporary stone-tool assemblage, camp floor, burial, shelter, art or repeated food-processing area has yet been identified in Ireland. The careful conclusion is therefore that the Castlepook femur may record a human encounter with a reindeer, not that Ireland had a permanent or numerous population. It may represent a short visit by a small mobile group, one episode within a longer pattern of visits, or an activity whose original location has been lost. Further work on intact deposits, microscopic surface analysis and securely recorded finds is needed before stronger claims can be made.

## **People Without a Recorded Society**

If people were present, their likely technology was perishable or portable: sharp stone edges, wooden shafts and clothing or bindings made from hide, sinew and plant fibres are plausible within the wider Upper Palaeolithic world. But none can presently be demonstrated from Ireland at this date. It would be unjustified to assign them a language, ethnic name, artistic tradition, social hierarchy or ancestry among later Irish populations. There is no basis for identifying a polity, chiefdom, territory or diplomatic relationship.

The same restraint applies to conflict and religion. Reindeer, wolves and hyaenas shared a dangerous landscape, and a hunting group would have needed knowledge, co-operation and mobility; those are general inferences from survival in cold environments, not discoveries about a named Irish community. There is no Irish evidence of weapons, organised violence, shrines, graves, ritual deposits or symbolic art from around this time. Silence in the evidence is not proof that such practices did not exist, but it prevents responsible description of them.

## **Movement, Exchange and Loss**

Lower global sea levels altered the geography of north-west Europe, exposing areas now submerged around Ireland and Britain. But no surviving Irish evidence can show exactly how any human visitors reached the island, whether they travelled over connected lowlands, crossed water, followed animal movements or arrived during a particular climatic interval. Nor is there evidence for trade: no imported tools, shells, pigments or other exchange goods can be securely assigned to Ireland around 30,973 BCE.


What can be said is that animal populations repeatedly reached Ireland during MIS 3, while later ice advances transformed or destroyed much of the contemporary landscape. This helps explain the archaeological imbalance. A mobile party may have left little behind; subsequent glaciation, erosion, rising seas and the patchy survival of caves reduced the chance that traces endured. Castlepook and Derryvree are exceptional precisely because they preserve indirect evidence where most open-air ground surfaces have vanished.

Ireland around this notional date was thus neither a blank frozen void nor a settled prehistoric country. It was a changing cold-stage landscape of wetlands, open ground and large mammals, subject to the advance and retreat of ice. Derryvree provides firm environmental evidence for an ice-free freshwater interval in Fermanagh; Castlepook documents a diverse southern fauna and preserves a provocative reindeer bone. The marked femur may be the earliest sign that people entered this landscape. For now, however, it remains a singular clue rather than the foundation for a full human history.

# Chapter 029 of 100

## 30972 BCE

### Derryvree's Buried Tundra Pool <sup>[29]</sup>



## A Modern Year in Deep Time

**“30,972 BCE” is a modern chronological label, not a year that anyone in prehistoric Ireland could have named, recorded or remembered. At this depth of time, calendar-year precision is not available. The label falls in the Late Pleistocene, within Marine Isotope Stage 3, during the Midlandian phase of the last Ice Age. Arithmetically, it stands about 32,921 years before AD 1950, the conventional reference point for “before present”; that arithmetic must not be mistaken for an exact archaeological date. Ireland has no securely dated settlement, burial, hearth, tool assemblage or written source that can be assigned to this particular year.**

The responsible history of Ireland at this point is therefore an environmental reconstruction, built from layers of sediment, fossil plants and insects, animal bones, cave deposits and the landforms left by moving ice. These records have different strengths. Some show that water, vegetation or animals were present in a locality. Others establish only that ice advanced before or after an interval. Still others raise possibilities—notably of fleeting human activity—which remain far short of evidence for a resident population. Rather than an annual chronicle, this is a view into a long, cold and changeable episode of Irish prehistory.

## Silt Between Two Ice Advances

The closest unusually informative Irish archive is at Derryvree, near Maguiresbridge in County Fermanagh. Road works in 1969 cut through a drumlin and exposed a remarkable sequence: a lower glacial till, then freshwater sands, silts and organic layers, followed by a second, thick till. Till is the

mixed debris laid down directly by glacier ice. The order of the deposits demonstrates a clear sequence of events. Ice had affected the site; later, an ice-free locality supported standing or slow-moving freshwater and enough plant growth for organic sediment to build up; eventually a renewed ice advance sealed that evidence beneath fresh glacial debris.

Organic material from the Derryvree deposit produced the conventional radiocarbon determination BIRM-166: 30,500 years BP, with a large quoted uncertainty. Radiocarbon years are not calendar years. They must be calibrated against changing atmospheric carbon-14 levels, and calibration at this antiquity gives broad probability ranges rather than a date to a season, generation or numbered year. A range commonly used for the Derryvree horizon is about 36,900–31,700 calibrated years BP, approximately 34,950–29,750 BCE. The requested modern label lies within that wide span. It cannot, however, locate a particular pond, animal track or human action within the deposit.

## **A Cold Wetland, Not a White Void**

Derryvree's fossils provide direct evidence for a cold, open environment. The plant and insect assemblages include freshwater mosses and sedges, while plants such as bogbean and water-milfoil indicate wet ground and open water. Other pollen and macrofossil evidence points to treeless or very sparsely wooded country, with grasses, herbs, dwarf shrubs and tundra-like vegetation better suited to exposure and short growing seasons than closed forest. Cold-adapted insect evidence reinforces that reading. These remains do not allow a detailed map of all Ireland, but they make the local picture much richer than the familiar shorthand of an island simply "under ice".

The landscape around the Derryvree waterbody was probably a mosaic. Shallow pools, marshy margins and sedge beds could have been productive during the growing season; better-drained ground would have carried open herb-rich vegetation. Frost action, seasonal meltwater and strong winds shaped soils and drainage. Winter was severe, but a cold-stage wetland was not necessarily lifeless or permanently snow-covered. The evidence supports ecological patchiness—water, plants, insects and exposed ground—not a settled countryside of fields and woods. It also records a place that later glacier ice overran, eroded and buried.

## **Animals in a Changing Island**

County Cork's Castlepook Cave, near Doneraile, gives a complementary but different record. It is Ireland's richest known repository of pre-Last Glacial Maximum vertebrate remains. More than two thousand bones recovered from its passages include woolly mammoth, reindeer, giant deer, brown bear and spotted hyaena; later cold-stage deposits also contain animals such as Arctic fox, wolf and lemmings. These finds establish that, over a long period, Ireland was connected to wider north-west European animal worlds and could support large herbivores and formidable predators.

Yet Castlepook must not be treated as a photograph of one year. The cave accumulated bones over many millennia, and water movement, old excavation methods and the activities of carnivores mixed the material. A dated bone shows when an animal died, not automatically when every other creature in the cave was present. Nor does the presence of hyaena prove that it hunted every animal represented there. The secure conclusion is regional and long-term: parts of Ireland before the full growth of the last ice sheet contained open-country habitats used by varied cold-stage fauna.

## The Human Question

A reindeer femur from the old Castlepook collections has become important because a deep mark on it has been interpreted as a possible fresh-bone cut or chop made with a sharp stone implement. The animal has been reported as dating to roughly 33,000 years ago, broadly close to the period considered here. If the mark is confirmed as human-made, it would show that people handled a reindeer carcass in Ireland during the Upper Palaeolithic, dramatically earlier than the well-established post-glacial settlement record.

That conditional matters. The bone does not establish a camp, a family group, an occupation lasting years or a settled Irish population. It was recovered from an old, disturbed cave collection, not from a modern excavation in a securely stratified domestic floor. There is no associated hearth, stone-tool assemblage, dwelling, grave or art from Ireland that can securely describe people in 30,972 BCE. The most that can responsibly be inferred is the possibility of a brief visit by a small, mobile group equipped with a sharp stone edge and able to exploit animal resources. Even that remains dependent on continued scrutiny of the modification and context.

## No Kingdoms, No Trade Network

There is no evidence for political institutions, chiefs, diplomacy, organised warfare, religion or formal learning in Ireland at this date. There were no farms, domesticated livestock, pottery, metalworking, monuments or writing. Trade cannot be demonstrated: no securely dated imported tools or exchanged goods identify a network. If people did enter the island, their movements would have taken place within a wider Late Palaeolithic world of mobile foragers, but Ireland's evidence is too slight to reconstruct routes, languages, beliefs or social organisation. Carnivore activity and competition for carcasses belong to the ecological record, not to evidence of human conflict.

The economy visible here is therefore ecological rather than social: wetland plants and insects, grazing animals, predators and the shifting availability of freshwater, shelter and exposed ground. Any human subsistence strategy remains hypothetical. Reindeer and other large mammals could have offered meat, fat, hide, sinew and bone, but no Irish assemblage of this age demonstrates systematic hunting or processing. The distinction between what fossils prove and what a plausible human scenario might suggest is essential.

## Before the Ice Sheet's Maximum

This was not yet the Last Glacial Maximum, the later interval when the British–Irish Ice Sheet reached its greatest extent. Modern reconstructions show that ice growth and retreat across Ireland and its surrounding shelf were uneven, regionally varied and still debated in detail. Around this broad period, some areas could preserve ice-free cold landscapes while glaciers or ice caps occupied others. Derryvree's inter-till sequence is especially valuable because it preserves precisely such an interruption: evidence for local open freshwater conditions bracketed by glacial advances.


The eventual ice expansion transformed and often destroyed earlier landscapes. It scoured ground surfaces, reorganised rivers, deposited tills and helped create the drumlin landscapes now so characteristic of parts of Ireland. That destructive power explains the scarcity of archaeological traces from this era. For

30,972 BCE, the most meaningful Irish story is not of named people or events but of a vulnerable record beneath later ice: a Fermanagh wetland, cold-adapted life around it, animal communities known from caves, and the unresolved possibility that people briefly reached this changing Atlantic edge of Europe.

## Chapter 030 of 100

30971 BCE

### Castlepook's Contested Reindeer<sup>[30]</sup>



**30,971 BCE is a modern calendar label, not a date that can be recovered from Ireland's prehistoric record. It corresponds approximately to 32,920 years before AD 1950, conventionally expressed as c. 32.9 thousand calibrated years before present (cal BP). No Irish site supplies evidence precise enough to say what occurred in that individual year, name a community, or reconstruct an annual sequence of events. The responsible history of this point in time is therefore a history of landscape, climate, animal remains and the limits of archaeological interpretation.**

Ireland then belonged to the Late Pleistocene, within Marine Isotope Stage 3, a long and unstable phase of the last Ice Age. It stood before the fullest expansion of the British–Irish Ice Sheet during the Last Glacial Maximum, generally placed around 27,000–19,000 cal BP. Ice was advancing and retreating on a geological timescale, climates changed abruptly, and sea level was lower than today. Yet Ireland was not simply a featureless white wilderness. Evidence from buried sediments and cave deposits shows that, at different moments in this broader interval, open cold-country habitats supported a striking range of mammals.

## A Year Beyond Calendar Precision

The dating language needs care. Radiocarbon measurements are reported in radiocarbon years before present, with “present” fixed at AD 1950; they are not identical to calendar years. At this depth of time, atmospheric radiocarbon changed significantly, and calibration produces probability ranges rather than an annual answer. The modern IntCal20 calibration curve extends to 55,000 cal BP, but the uncertainties remain substantial. Thus 30,971 BCE should be treated as a convenient point within a broad environmental horizon, not as a date to which a bone, plant seed or human action can securely be pinned.

The Derryvree deposits near Maguiresbridge, County Fermanagh, are especially important for understanding Ireland's cold-stage environment. Roadworks exposed freshwater silts and fine sands lying between two tills: sediments left by ice at different stages. An organic deposit yielded a radiocarbon determination of 30,500  $\pm$  1,170/–1,030 BP. On modern calibration, that result belongs broadly within the mid-30th millennium cal BP, rather than to one exact year. It may therefore be older than the nominal date used here, but it remains one of the best Irish windows onto the kind of treeless, cold landscape that preceded the island's later, more extensive glaciation.

## **Derryvree's Cold Wetlands**

Derryvree does not reveal a settlement. It preserves a palaeoenvironment. Fossil pollen, plant macrofossils, mosses and insect remains indicate a wet, open terrain often described as tundra or muskeg: waterlogged ground with pools, sedges, grasses, mossy surfaces and low Arctic-alpine vegetation. Mountain avens, dwarf willow, juniper, clubmoss and bogbean are among the plants used to reconstruct these conditions. The combination suggests summer growth in exposed ground and shallow water, but harsh winters and an environment far too cold and unstable for woodland comparable with modern Ireland.

This was not a single uniform biome spread unchanged across the island. Local shelter, drainage, elevation and proximity to ice mattered. Fermanagh's drumlin country preserves a wetland sequence because sediment was trapped and later sealed beneath glacial deposits. Elsewhere, especially on exposed uplands and coastal lowlands, evidence has often been eroded, reworked by later ice, submerged offshore or never deposited in the first place. Derryvree should therefore illuminate ecological possibilities, not be mistaken for a complete map of Ireland in 30,971 BCE.

The environment was nevertheless productive enough to sustain insects, aquatic plants and grazing animals during favourable intervals. Open ground allowed grasses and herbs to flourish; pools and sedge beds provided moisture and plant matter; snow, frost and seasonal thaw shaped every surface. The familiar Irish pattern of enclosed fields, hedgerows, farms and oak woodland lay tens of millennia in the future. In its place stood a changing mosaic of wet hollows, sparse vegetation, exposed mineral ground and, in some districts, looming ice margins.

## **Castlepook and the Animal Record**

In north County Cork, Castlepook Cave near Doneraile—historically also called Mammoth Cave—provides the island's most celebrated cold-stage faunal archive. Early twentieth-century excavations recovered remains attributed to woolly mammoth, reindeer, giant deer, brown bear, wolf, red and Arctic foxes, mountain hare, lemmings and spotted hyena. The National Museum of Ireland regards it as the country's most important site for mammal remains of the last cold stage. The assemblage shows that Ireland had intermittent ecological connections with Britain and continental north-west Europe when geography and climate permitted animal movement.

It does not, however, demonstrate that all these species met one another in a single season, let alone in 30,971 BCE. Cave sediments accumulated over long periods; old excavations did not record every layer to modern standards; and fossils may have been disturbed by carnivores, water, collapse or later excavation. Modern redating has been particularly consequential. Improved pretreatment of bone samples showed that several Castlepook and southern Irish cave specimens were thousands of radiocarbon years



older than earlier results suggested. The work places important elements of the fauna firmly in MIS 3 and indicates that animals such as spotted hyena and giant deer may have disappeared locally before the Last Glacial Maximum, around 40,000 cal BP.

That conclusion makes Castlepook simultaneously invaluable and difficult. Its mammals supply a powerful picture of the wider Pleistocene world relevant to the date, but not a securely contemporaneous census. At c. 32.9 ka cal BP, Ireland was approaching a period of growing glaciation; some of the best-known Cork bones may already have belonged to earlier phases. The appropriate conclusion is that open, cold-adapted animal communities had reached Ireland during this broad age, while the exact composition and distribution of fauna in any nominated year remain unknown.

## **The Reindeer Femur Question**

One Castlepook reindeer femur has become central to the question of people in very early Ireland. Ruth Carden has identified a deep linear modification on the bone as a possible cut or chop made with a sharp stone tool during butchery. County Cork heritage publications have presented the specimen as dating to about 31,000 BC. If that interpretation is confirmed, it would be extraordinarily important: evidence that a person, or small group, handled a reindeer carcass in Ireland during the Upper Palaeolithic, far earlier than the island's better contextualised terminal-Pleistocene evidence.

But the claim must be stated as proposed evidence, not settled fact. The femur came from an old cave collection rather than a newly excavated occupation floor with an intact sequence of associated artefacts. A radiocarbon result dates the death of the animal within a range; it does not automatically date the surface mark, prove where the animal was killed, or identify the person who made it. Likewise, distinguishing a stone-tool cut from carnivore damage, breakage or other modification depends on detailed taphonomic assessment. No securely associated hearth, stone-tool assemblage, dwelling, human bone, ornament or burial of comparable antiquity has yet been recovered in Ireland.

If the mark is human-made, the most that can responsibly be inferred is brief, mobile exploitation of a large animal. People may have hunted the reindeer, found a carcass, stripped meat, removed hide or sinew, or broken the limb in another place before carnivores carried bone into the cave. It does not establish a permanent settlement, an Irish population, a named culture or continuous occupation. Even the route by which people might have reached the island cannot be reconstructed from the bone alone. Lower sea levels altered coasts and routes, but changing channels, ice and sea ice made access contingent rather than predictable.

## **Society Without a Social Record**

There is no evidence from Ireland at this date for political institutions, chiefs, warfare, diplomacy, law or territorial boundaries. Nor can historians responsibly describe religion, ceremony, language, music, art or formal learning. These subjects were certainly meaningful to any people who may have visited, but they leave no identified Irish trace around 32.9 ka cal BP. The absence is archaeological, not a judgement that Ice Age people elsewhere lacked complex social lives.

Economy and trade are equally elusive. There is no evidence for farming, livestock, pottery, metalworking, built houses or exchange networks in Ireland at this time. If the Castlepook modification was made by people, a stone cutting edge and animal processing are plausible elements of a short-term

foraging economy; beyond that lies speculation. The best documented relationships are ecological rather than political: herbivores feeding in open country, carnivores and scavengers using caves, and plants and insects responding to cold, wet ground.

## **Approaching the Ice Maximum**


Within several millennia, the Last Glacial Maximum would transform Ireland dramatically. The British–Irish Ice Sheet expanded across much of the island and its continental shelf, eroding landscapes and destroying or concealing many earlier deposits. That later ice helps explain the thinness of the surviving archive. Derryvree endured because a wetland layer was buried between tills; Castlepook endured because limestone caves protected bones, although not always their original contexts.

For 30,971 BCE, then, the central development is not a recorded event but a threshold. Ireland was a cold, environmentally variable place in which wetlands could briefly preserve delicate plants and insects, and where a wider Pleistocene fauna had left bones in Cork caves. A marked reindeer femur offers a tantalising possibility of human presence, but only further analysis and securely stratified discoveries can decide how far that possibility should carry the story of Ireland's first people.

# Chapter 031 of 100

## 30970 BCE

### Derryvree's Trifoliate Wetland<sup>[31]</sup>



## A Date Without a Diary

30,970 BCE is a modern calendar label imposed on a period that cannot be resolved in calendar years. No inscription, settlement layer or securely dated human object allows us to describe events in Ireland in that particular year. In archaeological terms, it falls about 32,900 calendar years before AD 1950, within the later part of the Late Pleistocene and broadly within Marine Isotope Stage 3, a climatically unstable phase of the last Ice Age. The responsible account is therefore one of dated ranges, deposits and cautious comparisons, not of named rulers, battles or annual happenings.

The most important Irish evidence near this point comes from an unlikely source: silts and organic sediment exposed during roadworks at Derryvree, near Maguiresbridge in County Fermanagh. The deposit is valuable because it records a brief environmental interval between episodes of glaciation. It does not demonstrate what happened across the whole island, and still less what occurred in one numbered year. Yet it offers a rare, direct glimpse of an Irish landscape that later ice partly buried and reshaped.

## Freshwater Between Two Ice Advances

In 1969, a road cutting passed through a drumlin at Derryvree, roughly two kilometres north-east of Maguiresbridge. Beneath and above the exposed freshwater sediments lay tills: unsorted mixtures of clay, stones and other debris deposited by glacial ice. The sequence is decisive in its basic meaning. Ice had

occupied the locality, then conditions permitted fine sands, silts and organic material to accumulate in freshwater or waterlogged ground, before a later advance deposited another till over them.

Organic material from the freshwater bed produced the conventional radiocarbon determination BIRM-166, 30,500 radiocarbon years before present, with a sizeable uncertainty of plus 1,170 and minus 1,030 years. Radiocarbon years are not identical to calendar years. Calibration against changing atmospheric carbon-14 levels produces a broad calendar range, commonly expressed at approximately 36,900–31,700 calibrated years before present. The label 30,970 BCE falls towards the young end of, and close to, that range. It is consequently reasonable to use Derryvree to illuminate conditions around this date, but not to assign every layer or organism there to 30,970 BCE itself.

The same caution applies to ice. Ireland was not simply either ‘frozen’ or ‘ice-free’. The British–Irish Ice Sheet changed in extent and form over long periods, while local topography, snow accumulation, meltwater and shifting margins produced different conditions in different regions. Derryvree shows that south Fermanagh experienced a non-glacial interval between ice advances. It cannot prove that all coasts, uplands and interior lowlands were simultaneously open country.

## **A Treeless, Waterlogged Country**

Derryvree’s biological remains point firmly towards cold, open conditions. Poorly preserved pollen was dominated by herbaceous plants rather than trees. Plant macrofossils included a remarkable assemblage of mosses, while other evidence indicates grasses, sedges, low herbs and juniper. Aquatic and wet-ground plants, including bogbean and water-milfoil, suggest shallow freshwater, saturated margins and pools amid sedge-rich vegetation. The excavators described a periglacial setting: a landscape shaped by intense frost, seasonal thaw and a short growing season beyond, or between, major ice-sheet advances.

This was not a wood-filled version of modern Fermanagh. Trees were absent or exceedingly scarce locally. The open vegetation has often been described as tundra, though the word should not conjure a uniform plain. The fossil record instead implies a patchwork of wet hollows, shallow water, mossy ground, sedges and drier, sparsely vegetated surfaces. Snow cover, frozen ground and meltwater would have changed seasonally. In such a landscape, a few sheltered spots could sustain richer plant communities than wind-exposed ridges or frost-heaved ground only a short distance away.

This wetland evidence is particularly important because the later Irish landscape has been so heavily modified by ice, sea-level change, peat formation, farming and settlement. Derryvree is not a picturesque reconstruction based on guesswork; it is a sealed sample of pollen, plant fragments, insects and sediment. Nevertheless, its significance is local and environmental. It preserves an ecosystem, not a complete map of Ireland.

## **Animals in the Irish Ice-Age Record**

Cave deposits, especially at Castlepook or Mammoth Cave near Doneraile in north Cork, show that Ireland supported a striking Late Pleistocene fauna during parts of the broader pre-Last Glacial Maximum interval. The Irish Quaternary Fauna Project identified evidence for animals including woolly mammoth, reindeer, giant deer, brown bear, wolf, fox, Arctic fox, spotted hyaena, mountain hare and both collared and Norwegian lemmings. These remains demonstrate that cold-adapted and open-country mammals reached Ireland during the last Ice Age.

Castlepook is highly informative, but its cave deposits also require restraint. Material was collected during early excavations from complex sediments, and bones may have accumulated through carnivore activity, natural deaths, movement by water and later disturbance. Individual radiocarbon measurements date parts of the faunal record rather than a single, neatly bounded animal community. It would therefore be unsafe to imagine every listed species standing together in Fermanagh in 30,970 BCE. The better conclusion is that Ireland, at different points in this long climatic interval, could sustain a cold-climate fauna consistent with extensive open vegetation.

A reindeer femur from Castlepook has recently been publicised as bearing a possible stone-tool cut or chop mark, and as evidence for human activity around 33,000 years ago. If that interpretation is confirmed through full contextual and taphonomic study, it would be of exceptional importance. For now it cannot support a story of established population, hunting territories or repeated occupation. A marked bone would show at most a human encounter with an animal, not a settlement, camp, kin group or cultural tradition.

## **People: What Cannot Yet Be Said**

There is no securely demonstrated human settlement in Ireland at this date. No excavated hearth, stone-tool assemblage, dwelling, burial, art site or human bone can be assigned to around 30,970 BCE. The National Museum of Ireland accordingly treats the Palaeolithic human record as unproven in the sense required for a settled archaeological sequence, while research on the butchered brown-bear bone from Alice and Gwendoline Cave in County Clare indicates a much later Late Upper Palaeolithic human presence, around 12,500 years ago.

This absence matters to every conventional category of a year-by-year history. There is no evidence for Irish political affairs, diplomacy, warfare, law, leadership, religion, language, artistic practice, formal learning, trade or household economy at this point. Nor is there evidence from which to infer seasonal camps, clothing, food-sharing or ritual. Humans lived elsewhere in north-west Europe during the Upper Palaeolithic, and Britain has a far richer record. But proximity is not proof of an Irish population. Lower sea levels altered coastlines and passages, yet Ireland's changing geography and climate made crossing, survival and archaeological preservation separate questions.

It is possible that brief human incursions occurred and left no surviving trace, especially given later glacial erosion. That is a research question, not a fact. The distinction is vital: the loss of evidence may explain silence, but it cannot be used to fill that silence with imagined communities.

## **Regional Change on an Iceward Threshold**

The wider climatic setting was volatile. Greenland ice-core records show abrupt shifts during Marine Isotope Stage 3, and the growth of the British–Irish Ice Sheet was not a smooth, island-wide advance. At Derryvree, the very existence of freshwater sediment between tills records environmental change on a substantial scale: conditions once allowed water, plants and small animals to establish, but later ice overrode or sealed the ground. By the Last Glacial Maximum, after roughly 29,000 years ago, ice cover became much more extensive across Ireland.

For Ireland around 30,970 BCE, then, the principal development was not human politics but environmental instability. Parts of the island could be open, cold and ecologically productive enough for tundra vegetation and large mammals; other districts may have lain closer to expanding ice or beneath it. The evidence preserves neither a stable homeland nor an empty white wilderness. It instead reveals a changing northern Atlantic borderland in which wetlands briefly flourished between glacial episodes.

## What Derryvree Leaves Us

Derryvree's freshwater bed is a small archive with large implications. Its pollen, mosses, plant remains and sediments establish that one part of Ireland supported treeless, wet tundra-like vegetation during a pre-maximum interval of the last Ice Age. Cave faunas show that cold-adapted mammals had entered the island during the wider period. Neither line of evidence establishes a society in Ireland in 30,970 BCE.

That limitation is not a failure of history. It is the history. At this depth of time, the most truthful annual overview follows the evidence at its own scale: a buried Fermanagh wetland, animals moving through open country, ice returning, and a calendar year that survives only as a modern label for a world no person recorded.

# Chapter 032 of 100

## 30969 BCE

### BIRM-166 Between Glaciers<sup>[32]</sup>



The label 30,969 BCE is a modern way of placing an extraordinarily remote point in time on a familiar calendar. It corresponds approximately to 32,918 years before AD 1950, the reference year used in archaeological “before present” dating. It cannot, however, identify an Irish event in a particular year. No written calendar, settlement sequence or securely dated human occupation in Ireland has the resolution to do that. The responsible history of this moment is therefore an account of a period: the later part of Marine Isotope Stage 3, within the last Ice Age, reconstructed from buried sediments, plant and insect remains, animal bones, cave deposits and the larger history of the British–Irish Ice Sheet.

## Dating a Calendarless Landscape

Calendar conversion can give a false impression of precision. Radiocarbon determinations measure the decay of carbon-14 and must be calibrated against independently dated records because atmospheric carbon-14 levels have changed through time. For ages this old, calibrated results can span centuries or millennia and may form more than one probability range. The notional year 30,969 BCE should thus be read as a point within a broad chronological horizon, not as the date of a hunt, migration or climatic turning point.

Ireland’s best evidence for this horizon is not a village or a grave but the Derryvree organic deposit near Maguiresbridge in County Fermanagh. Exposed in a road cutting, fine freshwater sediments and organic material lay between two tills: unsorted debris deposited by glacier ice. Their position establishes the essential sequence. Ice had crossed the locality; an ice-free interval then allowed water, mud, plants and animals to accumulate; later ice advanced over the ground and sealed the deposit below a further till.

A conventional radiocarbon measurement from the deposit, BIRM-166, was  $30,500 \pm 1,100$  radiocarbon years BP. Its calibrated implications are necessarily broad, but the date places the deposit within the unstable MIS 3 world relevant to this calendar label.

The surrounding North Atlantic climate was not steady. Greenland ice-core records show abrupt alternations between colder stadials and shorter, milder interstadials. Around 32.9 thousand calendar years ago, the wider region was in a cold phase following the brief Greenland Interstadial 5. That does not provide a thermometer reading for Fermanagh on one day or one year. It does, though, help explain why Irish environmental records preserve rapid shifts between ice activity, exposed ground, wetlands and renewed glaciation rather than a simple march from warm to cold.

## **A Wetland Under the Drumlins**

Derryvree offers the clearest local picture. Fossil pollen, plant macrofossils and insects point to open, treeless terrain rather than woodland. Sedges, grasses, herbs, juniper and an abundant moss flora grew around shallow freshwater. Finds including bogbean, water-milfoil, mountain-avens and lesser clubmoss indicate wet ground and pools within a cold, exposed setting. The older term “muskeg” is useful if used cautiously: not a modern blanket bog transplanted into the past, but a mosaic of saturated organic ground, sedge margins, shallow water and low vegetation in a periglacial landscape.

This was an environment of strong seasonality. Winter frost and repeated freezing and thawing would have disturbed soils and restricted tree growth. During the growing season, however, waterlogged hollows and stream margins could be highly productive. Mosses, sedges and flowering plants supported insects and provided fodder for herbivores. The evidence does not allow a reconstruction of a continuous lake, a single shoreline or a particular year’s weather. It supports something more durable: northern Ireland was not uniformly buried beneath ice while the Derryvree sediments formed. There were intervals in which living freshwater habitats existed between glacial episodes.

That conclusion matters because the familiar image of Ice-Age Ireland as a permanently blank white sheet is misleading for MIS 3. Ice was an active force in the landscape, but its margins and extent changed. The full Last Glacial Maximum came later. Reconstructions of the British–Irish Ice Sheet place its major maximum development broadly after this period, with important sector-by-sector variation; the Irish Sea Ice Stream reached a far southern extent around 27,000 years ago, while maximum global ice volume occurred later still. At 30,969 BCE, Ireland stood within an approaching glacial crisis, not at its final maximum.

## **Caves and Cold-Adapted Fauna**

In southern Ireland, Castlepook Cave near Doneraile, County Cork, supplies another kind of evidence. Old cave excavations recovered a rich but complicated collection of bones. Improved radiocarbon pretreatment has shown that several Castlepook specimens are far older than earlier results suggested, by roughly 5,000 to 12,000 radiocarbon years in the re-dating programme. The revision confirms that elements of the assemblage belong to MIS 3, well before the Last Glacial Maximum.

Reindeer are central to the Castlepook story. Their presence fits an open, cold landscape in which mobile grazers could exploit seasonal forage. Other southern Irish cave evidence includes large mammals and predators, notably giant deer and spotted hyaena, though it is essential not to compress every bone in a cave collection into one simultaneous community. Cave deposits may accumulate over long periods;



carnivores can transport carcass parts; water and sediment can move bones; and nineteenth- and early twentieth-century excavation methods rarely recorded contexts to modern standards. A cave fauna is evidence for animals in a region across a span of time, not a census taken in one season.

Even so, the combination is revealing. Reindeer, giant deer, carnivores and small cold-adapted species point to habitats unlike later forested Ireland: more open country, shorter growing seasons and large ranges in which animals could move between patches of food and shelter. Stable-isotope research on later Irish giant deer suggests seasonal movement between landscapes, a useful reminder that animals were not fixed inhabitants of a single valley. It cannot demonstrate the route of a particular MIS 3 herd, but it makes mobility a sensible ecological expectation.

## **The Castlepook Human Question**

A reindeer femur from Castlepook has given this period exceptional archaeological interest. It has been publicly interpreted by zooarchaeologist Ruth Carden as bearing a deep fresh-bone mark made by a sharp stone implement during butchery; the specimen has been presented as about 33,000 years old. If the mark is anthropogenic, it would be evidence that a person processed a reindeer in Ireland during the Upper Palaeolithic, vastly earlier than the island's better-established terminal-Pleistocene evidence.

But it must remain a carefully qualified possibility, not the foundation for an invented population. A radiocarbon result dates the animal bone, not necessarily the moment when a surface mark was made. The bone was recovered from an old cave collection, without a securely associated stone-tool assemblage, hearth, dwelling floor, human remains or repeated occupation deposit of comparable age. Carnivore damage, trampling, sediment movement, weathering and excavation damage must all be excluded when marks on bone are assessed. Renewed excavation at Castlepook is valuable precisely because it can test the older collection against intact sediments and modern methods.

Accordingly, no named hunting band, camp, leader or route across Ireland can responsibly be placed in 30,969 BCE. If people did visit, the most that can presently be proposed is a brief and probably mobile Upper Palaeolithic presence linked to the animal resources of north-west Europe. Whether Ireland was reached across exposed coastal lowlands, ice, water or a shifting combination of these remains a question of palaeogeography, not an established narrative of migration. Lower sea levels changed the map, but the existence, timing and usefulness of land connections between Ireland and Britain remain debated.

## **Society Beyond Recovery**

There is no evidence from this date for political institutions, diplomacy, territorial rule, organised warfare, formal religion, art, language, farming, trade networks or permanent Irish settlement. Their absence from the record is not proof that every form of social relationship was absent if people briefly entered the island; it is a limit on what the evidence can bear. A single possible butchered bone cannot reveal kinship, belief, exchange or authority. Nor should the later Mesolithic, Neolithic or early medieval past be projected backwards into this very different world.

The demonstrable "economy" was ecological rather than social: plants converting a short season's light into forage; grazing animals moving through open ground; predators and scavengers using carcasses and caves; freshwater pools sustaining specialised wetland life. The principal conflict was environmental. Ice, frost, changing drainage and shifting vegetation repeatedly remade the opportunities available to


every organism. Such changes also help explain the scarcity of evidence: later glacial erosion, sediment disturbance, rising seas and antiquarian excavation have all reduced the chance that fragile campsites survived.

For Ireland around this notional year, then, BIRM-166 is more informative than any imagined human story. The Fermanagh deposit records water, plants and organic life sheltered between advances of ice. Castlepook records a wider cold-country fauna and a tantalising, unconfirmed prospect of human butchery. Together they show an Ireland that was harsh but not empty: a changing northern landscape whose history must be read in silt, pollen, bone and ice, with uncertainty acknowledged as part of the evidence rather than a gap to be filled by invention.

# Chapter 033 of 100

## 30968 BCE

### The Derryvree Freshwater Bed<sup>[33]</sup>



**30,968 BCE is not a recoverable year in Irish history. No calendar, written record, named community or event can be assigned to it, and neither archaeology nor environmental science can distinguish one Irish year from the next at this distance in time. The date is best treated as a modern reference point within the Late Pleistocene, broadly Marine Isotope Stage 3 (MIS 3), a period of marked climatic instability during the last Ice Age. The evidence relevant to Ireland consists of radiocarbon ranges, layers of sediment, fossil plants, insects and animal bones. It can illuminate landscapes and ecological possibilities; it cannot yield a year-by-year political narrative.**

The closest especially informative record is the Derryvree freshwater deposit near Maguiresbridge in County Fermanagh. It was exposed during roadworks in 1969 in a section through a drumlin, one of the streamlined hills moulded by moving glacier ice. Fine sands, silts and organic material lay between two substantial layers of till, the unsorted sediment left by glaciers. This sequence securely establishes a local order: glacial conditions, an interval in which freshwater sediments and living organisms accumulated, then renewed glaciation. It does not establish what happened across every part of the island at the same moment.

## **A Date Within a Range**

Organic material from the Derryvree bed produced the radiocarbon determination BIRM-166: 30,500 radiocarbon years before present, with a large published uncertainty of +1,170 and -1,030 years. “Before present” conventionally means before AD 1950, not before the current year. Radiocarbon years are also not calendar years. Changes in atmospheric radiocarbon over time mean that measurements must be calibrated against independently constructed curves, and uncertainty widens considerably at this depth of time.

Published discussion therefore places Derryvree within a broad Middle Midlandian, or MIS 3, interval rather than at an exact date. Calibrated estimates extend across several millennia, approximately from the mid-thirty-fifth to around the thirtieth millennium BCE depending on the confidence range and calibration approach used. The requested year falls close enough to this window for Derryvree to be highly relevant, but it cannot responsibly be identified as the date of a particular pool, plant, animal or human action. The lesson is methodological as well as historical: a precise-looking BCE number must not be allowed to create false precision.

## **Cold Water Between Glaciers**

Derryvree offers an unusual glimpse of an Irish landscape that later ice buried. The deposit's pollen, plant macrofossils, mosses and small-animal remains indicate a cold, open, periglacial environment rather than a forested country. Periglacial means a landscape affected by severe freezing and thawing near an ice margin, whether or not ice lay directly on the ground at that locality. The evidence suggests wet ground, shallow or slow-moving freshwater, and sparse tundra-like vegetation under a treeless sky.

Among the plants identified are sedges, mosses and species with modern arctic-alpine associations. Fossil remains reported from the deposit include mountain avens, dwarf willow and bogbean, while water-milfoil pollen points to freshwater conditions. These finds matter because they show that life persisted locally in a rigorous climate: not an empty white desert, but a mosaic of wetland, exposed mineral ground and low-growing vegetation. Dry-land cover may often have been thin. Short growing seasons, hard winters, frost disturbance and shifts in water level would have governed the rhythm of the landscape.

This was not necessarily the condition of all Ireland. Derryvree is a local archive in present-day Fermanagh, not a national weather station. Yet its position between tills is powerful evidence that this district experienced an ice-free interval before a later advance. It also complicates any simple picture of Ireland as continuously smothered by ice throughout the last Ice Age. During MIS 3, the North Atlantic climate oscillated sharply between colder stadials and comparatively milder interstadials, sometimes on timescales far shorter than traditional historical periods. The island's habitats, ice margins, drainage and animal opportunities changed accordingly.

## **Animals in a Changing Country**

The best evidence for larger animals comes chiefly from caves and fossil deposits rather than open-air hunting sites. Castlepook Cave, also called Mammoth Cave or Doneraile Cave, near the Ballyhoura foothills in north County Cork is the outstanding Irish archive for pre-Last Glacial Maximum vertebrate fauna. Its deposits have yielded remains attributed to woolly mammoth, giant deer, reindeer, brown bear, wolf, Arctic fox, mountain hare, lemmings and spotted hyaena. The assemblage demonstrates that Ireland, or parts of the landscape now forming Ireland, could support a much richer cold-stage fauna than survives today.

It would nevertheless be wrong to turn this list into a single, perfectly observed herd crossing a single landscape in 30,968 BCE. Cave deposits accumulated through different processes and episodes: carnivores dragged in prey or scavenged carcasses; animals died naturally; water moved bones; and early excavations disturbed contexts that modern archaeologists would have recorded more fully. Radiocarbon redating has shown that some older determinations for southern Irish cave fauna were substantially too young. Castlepook is consequently an exceptional faunal archive, but not a neatly sealed snapshot.

Even so, its mammals help make sense of Derryvree's open vegetation. Reindeer, mammoth and giant deer were adapted in differing ways to expansive cold-country habitats; predators and scavengers formed part of the same broader food web. Their occurrence indicates ecological links with Britain and north-western Europe during portions of the Late Pleistocene. Lower sea levels altered coastlines and the shape of the Irish Sea basin, but the precise routes by which animals or people reached this western edge of Europe remain uncertain. Evidence does not justify a confident claim that a particular land bridge was available at this particular date.

## **The Human Question at Castlepook**

One object gives this period an exceptional, though unresolved, place in Irish human history: a reindeer femur from Castlepook Cave. The bone has been reported as approximately 33,000 radiocarbon years old and bears a deep linear modification interpreted by zooarchaeologist Ruth Carden as a cut or chopping mark made with a sharp stone implement while the bone was fresh. If that interpretation and its association with the animal's death are sustained, it may record Upper Palaeolithic people processing a reindeer in Ireland long before the later, better-attested settlement of the island.

That possibility must be expressed carefully. A radiocarbon result dates the animal's death, not automatically the making of a surface mark. Identifying a mark as human-made requires separate taphonomic judgement: researchers must distinguish tool damage from tooth scoring, trampling, sediment abrasion, breakage and other natural processes. Nor has Castlepook produced a securely contemporary hearth, stone-tool assemblage, dwelling floor, burial, human bone or repeated occupation sequence. The femur may represent a fleeting visit, a single episode of carcass processing, or a process not yet fully understood. It is not evidence for a settled Irish population.

Modern humans were present in western Europe during this broad period, so an occasional movement into Ireland is plausible. But plausibility is not proof. The later expansion of ice across Ireland, erosion, changing coasts, and the complex histories of cave deposits may have destroyed or concealed evidence. Equally, the striking scarcity of indisputable Upper Palaeolithic sites may reflect real limits on human use of the island. Responsible history leaves both possibilities open.

## **No Politics, No Trade Network**

There is no basis for describing political affairs, rulers, diplomacy, warfare, language, religion or formal learning in Ireland at this point. There are no identifiable communities from which kin groups, territories or beliefs can be reconstructed. Terms such as "Ireland", "Fermanagh" and "Cork" are modern geographical conveniences, not ancient identities. Nor is there evidence for agriculture, domestic animals, pottery, metalworking, monuments, permanent villages or trade in the sense documented in later prehistory.

If people did briefly enter the island, their economy would have depended on immediate knowledge of terrain, weather, animal movement, fuel and shelter. A modified reindeer bone could be consistent with obtaining meat, hide, sinew, marrow or bone from a carcass, but none of those actions can be individually demonstrated. It cannot prove hunting rather than scavenging, nor reveal how many people were present. The sharing of food, making of tools, stories, ritual practice and social negotiation are all imaginable human behaviours; none can be claimed for Ireland from this evidence alone.

## Approaching the Ice Maximum


Environmental change was the principal historical force. Derryvree records a life-supporting wetland during an interval when its locality was not overridden by glacier ice. In the millennia after the broad horizon represented by the deposit, the British–Irish Ice Sheet expanded towards its Last Glacial Maximum, which research generally places between about 27,000 and 21,000 years ago. Much of Ireland and its surrounding shelf was subsequently transformed by ice flow. Drumlins, tills and reshaped drainage patterns are among the physical consequences visible in the modern landscape.

For 30,968 BCE, therefore, the most defensible Irish story is neither one of recorded human society nor one of total lifelessness. It is a story of fragile freshwater habitats beneath cold skies; of low tundra plants and mobile mammals; of locally ice-free ground that would later be buried and remodelled; and of one debated reindeer bone that may preserve a brief human encounter. The surviving record is fragmentary, but it replaces a simplistic vision of an empty frozen island with a more compelling and more accurate one: a changing Late Pleistocene country, rich in environmental history and still uncertain at its human edge.

# Chapter 034 of 100

## 30967 BCE

### Mammoth Cave's Cold Fauna<sup>[34]</sup>



The label 30,967 BCE gives a useful place in a modern chronological sequence, but it cannot describe a recorded Irish year. No written dates, named people, political communities or events survive from this depth of time. Archaeologists instead work with deposits, animal bones, plant remains, landforms and laboratory dates, each carrying a margin of error. Arithmetically, 30,967 BCE falls about 32,916 years before AD 1950, the conventional starting point for “BP” dating. It belongs to the later part of Marine Isotope Stage 3 (MIS 3), a climatically volatile interval of the Last Glacial Period, shortly before the Last Glacial Maximum transformed Ireland beneath an extensive ice sheet.

The responsible history of Ireland at this point is therefore not a year-by-year narrative but a carefully bounded reconstruction of a cold, changing environment. Two very different archives are particularly important. At Derryvree near Maguiresbridge in County Fermanagh, sediments trapped between glacial tills preserve a freshwater and wetland world. At Castlepook Cave, near Doneraile in north County Cork, bones accumulated in a limestone cave record animals adapted to open, cold country. A single reindeer bone from Castlepook has also been interpreted as possible evidence of human butchery. It is potentially momentous, but it remains far too slight to prove a settled population.

## Dating a Calendarless Landscape

Modern calendar precision should not be projected back into the Pleistocene. A radiocarbon age is not automatically a calendar age: the quantity of radioactive carbon in the atmosphere varied through time, so results must be calibrated against independently constructed curves. At such antiquity, both the original measurement and the calibration carry substantial uncertainty. The Derryvree organic deposit produced a

conventional radiocarbon result of about 30,500 radiocarbon years BP, with an uncertainty of roughly a thousand years. One later synthesis expresses its calibrated position broadly in the mid-30,000s calendar years BP, approximately 34.8–37.0 thousand years before 1950.

That range is older than the notional year used here, rather than an exact match for it. Yet it remains one of the nearest securely relevant Irish environmental records for this broad phase of the Ice Age. Castlepook's faunal sequence is likewise a long-lived archive, not a sealed deposit from one season or one generation. Re-dating has shown that some older cave dates required revision and that several animals formerly thought later were present much earlier in MIS 3. The lesson is fundamental: a precise-looking BCE year is a filing device, whereas the evidence speaks in overlapping ranges, deposits and phases.

## **Wet Ground Beneath Fermanagh**

Derryvree was exposed during road works in a drumlin landscape. Beneath later glacial sediments lay beds of sand, silt and organic mud, evidence that water had stood or moved slowly across the site before advancing ice buried it. Plant macrofossils, mosses, pollen and small animal remains make this deposit unusually valuable. Much of the Irish Pleistocene landscape was later scoured, redeposited or sealed by ice; a protected organic layer can therefore preserve a local ecological record that has vanished almost everywhere else.

The assemblage indicates a treeless, cold landscape, but not a uniform desert of snow and bare rock. Wet hollows supported sedges, mosses and aquatic plants, while low-growing Arctic and alpine vegetation occupied the surrounding ground. Bogbean, water-milfoil, dwarf willow, mountain avens, clubmosses and other cold-tolerant plants have all featured in interpretations of the Derryvree evidence. This was a mosaic: shallow freshwater, marshy margins, exposed mineral soils and periglacial ground, responding sharply to changes in temperature, moisture and the position of ice.

Such evidence illuminates environment and regional change, not human settlement. There are no houses, fields, hearths, cultivated plants, pottery or tools at Derryvree. Nor can the deposit identify an Irish "people" with a language, religion or political order. Its importance lies in demonstrating that parts of the island could, during a cold non-forest phase, sustain freshwater habitats and a varied tundra-like flora before later glaciation overwhelmed or reshaped large areas.

## **The Cave at Doneraile**

Castlepook Cave, historically called Mammoth Cave, provides the richer animal archive. Its deposits yielded remains of woolly mammoth, reindeer, giant deer, brown bear, wolf, foxes, mountain hare, lemmings and spotted hyaena. This combination conveys an open, cold-steppe or tundra environment with large grazing animals, predators and scavengers. It does not mean that every species lived together at the cave on the same day. Cave deposits commonly mix material introduced over long periods by carnivores, water, roof collapse and human excavation. Still, the fauna confirms that Ice-Age Ireland supported animals now absent from the island and, in some cases, from north-west Europe.

Spotted hyaena is especially revealing. Castlepook was not simply a human shelter waiting to be discovered; it was also a place to which carnivores could drag carcass parts, feed, den or leave bones. Tooth damage, breakage and the distribution of skeletal elements are therefore as important as species names. The cave was explored in the early twentieth century, before the refined recording standards now



expected in excavations. Its old collections remain scientifically valuable, but the original positions and associations of many bones cannot always be reconstructed. Recent fieldwork has sought undisturbed deposits that may clarify this complex history.

The broader landscape beyond the cave was unlikely to resemble modern wooded Cork. Trees were scarce or absent in the coldest exposed settings, and the terrain offered seasonal grazing, sheltering hollows, rock outcrops and frozen or waterlogged ground. The exact coastline, sea level and travel routes were very different from today. Lower global sea levels altered the Irish Sea region, but the physical accessibility of Ireland varied with time, local ice and changing marine barriers. The evidence does not justify a simple claim that people walked easily from continental Europe to Cork.

## **A Reindeer Bone and a Large Question**

The most arresting object associated with this horizon is a reindeer femur from Castlepook. County Cork heritage material assigns it broadly to about 31,000 BCE and records a deep incision which zooarchaeologist Ruth Carden has interpreted as having been made with a sharp stone tool while a fresh carcass was processed. If that interpretation is upheld, the bone would be evidence that Upper Palaeolithic people handled a reindeer in Ireland tens of millennia before the island's better-established terminal Pleistocene archaeology.

Its significance must be matched by caution. The bone does not come from a modernly excavated occupation floor with a hearth, stone-tool assemblage, dwelling remains and securely associated food debris. A date on the animal establishes when the animal lived, not necessarily when the mark was made, where it was killed, or how long any people remained nearby. No Palaeolithic flint tools have yet been securely recovered in Ireland in association with this proposed episode. The most careful conclusion is that Castlepook offers a plausible and potentially transformative trace of brief human activity, not proof of permanent settlement, a village, or continuous occupation.

## **Society Beyond the Evidence**

Because the human case is so limited, ordinary historical categories must be treated honestly. There is no evidence for Irish rulers, territories, diplomacy, warfare, law, trade networks, formal religion or artistic traditions at 30,967 BCE. Neither can domestic routines be recovered directly. If people did reach the island, the reindeer femur is consistent with a very small, mobile hunting party processing a carcass; that is an interpretation drawn from the mark, not a demonstrated social system. It cannot identify the hunters' sex, age, language, kinship, beliefs, origin or route of arrival.

Comparison with contemporaneous Upper Palaeolithic communities elsewhere in Europe can suggest possibilities—portable stone tools, close knowledge of animal behaviour, seasonal movement and reliance on clothing and fire in severe climates—but it cannot fill Ireland's evidential silence. Such practices must not be imported as facts. Ireland's record around this date has no securely identified camp, burial, artwork or manufactured object from which culture and learning can be described. The most defensible story is one of ecological opportunity and uncertainty at Europe's north-western edge.

## Ice Was Approaching


This uncertainty mattered because the physical stage was changing rapidly. The later Last Glacial Maximum, conventionally placed around 27,000–23,000 calendar years BP in Irish reconstructions, saw the British–Irish Ice Sheet cover Ireland and extend across much of its continental shelf. Around the present chronological horizon, the ice sheet was in a period of growth and reorganisation, while evidence for exactly how far ice had reached in every Irish region remains debated. It would be misleading to portray all of Ireland as either wholly ice-free or wholly ice-covered in 30,967 BCE.

What can responsibly be said is that Derryvree preserves evidence of an earlier or broadly comparable cold freshwater interval, Castlepook preserves a remarkable MIS 3 fauna, and the expanding ice ultimately erased much of the land surface on which people and animals might otherwise have left traces. Ireland at this point was not yet a historical society in the documentary sense. It was a shifting Pleistocene landscape of wetlands, open ground, reindeer and predators, with one disputed-looking but serious clue that humans may briefly have entered the picture before the great ice advance closed this window of evidence.

# Chapter 035 of 100

## 30966 BCE

### Maguirebridge's Frost Garden<sup>[35]</sup>



The label 30,966 BCE gives a useful point of reference, but it must not be mistaken for a date in the historical sense. No event, journey, ruler or settlement in Ireland can be assigned to this individual calendar year. This was deep within the Late Pleistocene, during Marine Isotope Stage 3 (MIS 3), a long and climatically volatile part of the last glacial cycle. In conventional archaeological terms, 30,966 BCE lies roughly 32,915 years before 1950, the reference year used for “BP” dates. Yet evidence from this age normally comes with uncertainties measured in centuries or millennia. The responsible task is therefore to describe the environmental horizon around the date, not to invent an Irish episode for it.

## A Date Inside a Wider Interval

The strongest Irish evidence relevant to this horizon comes from Derryvree, near Maguiresbridge in County Fermanagh. In 1969 a road cutting exposed sediments inside a drumlin: glacial till below, freshwater silts and fine sands in the middle, and later till above. The sequence matters because it records an interval when this particular place was not buried beneath moving ice, before a subsequent ice advance sealed the deposits. Organic material from the freshwater bed produced the conventional radiocarbon determination BIRM-166, 30,500 radiocarbon years BP, with a substantial laboratory uncertainty. Published calibration places the deposit broadly within later MIS 3, rather than pinning it to a single calendar year.

That distinction is fundamental. A radiocarbon determination is not an anniversary. It dates carbon in sampled organic material, subject to measurement limits, sample history and later calibration against changing atmospheric radiocarbon. Nor does a deposit accumulate instantaneously. The Derryvree bed

may represent years, generations or longer phases of sedimentation, while the fossil material within it need not all be exactly contemporary. Its calibrated range overlaps the general era represented by 30,966 BCE, but cannot demonstrate what happened in Ireland in that numbered year.

Even so, Derryvree is exceptionally revealing. It shows that, during part of this cold period, freshwater and wet ground existed in south Fermanagh between episodes of glaciation. Ireland was not simply an unchanging white blank on the edge of an ice sheet. It contained highly local environments shaped by water, frozen ground, wind, seasonal thaw and advancing or retreating ice. The island's landscape was unstable in geological as well as climatic terms.

## **A Treeless Wetland Landscape**

The fossil evidence from Derryvree points to open tundra or tundra-like vegetation in a periglacial climate. Plant pollen is poorly preserved, but the surviving record is dominated by herbs rather than woodland trees. Macrofossils, including mosses, sedges and aquatic or wetland plants, provide the more vivid evidence. Bogbean, mountain-avens, dwarf willow and other cold-adapted taxa indicate a mosaic of shallow water, marshy hollows, damp ground and sparsely vegetated mineral soils. Juniper may have occurred locally, but there is no sound basis for imagining forest.

This was a landscape of sharp constraints but not biological emptiness. In summer, melting snow and seasonal runoff could feed pools and sedge margins. Mosses and small flowering plants could exploit sheltered, waterlogged ground; insects occupied the same restricted habitats. Beyond the wet hollows, vegetation was probably patchy. Frost action disturbed soils, and prolonged winter cold curtailed growing seasons. The modern phrase “mammoth steppe” can be useful as a broad northern Eurasian comparison, but it should not conceal local variety. Derryvree records a particular freshwater setting in Fermanagh, not a complete map of every Irish region.

Crag Cave in County Kerry offers complementary, though different, evidence for climatic instability. Episodes of stalagmite growth there during MIS 3 required liquid water to percolate through the cave and are interpreted as phases when mean annual conditions rose above freezing. Their alternation with breaks in growth reflects abrupt millennial-scale swings between relatively milder and markedly colder conditions. At a horizon such as 30,966 BCE, Ireland's climate should therefore be understood as fluctuating within a severe glacial world, not as a single uniform “Ice Age climate”.

## **Animals on a Changing Island**

Cave deposits in southern Ireland demonstrate that a richer late-Pleistocene fauna entered Ireland at various times before the Last Glacial Maximum. Castlepook Cave, near Doneraile in north County Cork, has produced remains attributed to woolly mammoth, reindeer, giant deer, brown bear, wolf, Arctic fox, lemmings and spotted hyaena. The cave is an important archive because these animals reveal the kind of open, cold-country habitats that could exist in Ireland during MIS 3.

But a cave bone is not a census entry. Many Castlepook finds were excavated in the late nineteenth and early twentieth centuries, when recording methods were uneven. Cave floors can be disturbed by animals, water, collapse, earlier digging and redeposition; bones from different centuries or millennia can consequently lie close together. Modern redating has shown that several earlier determinations from Castlepook and neighbouring caves were too young, changing the chronology of the fauna substantially. The evidence supports intermittent animal presence in Ireland during MIS 3, but it cannot securely reconstruct a single herd, predator population or food web for 30,966 BCE.

Nevertheless, the ecological implications are important. Reindeer and lemmings are consistent with cold, open country; mammoth and giant deer imply enough forage and traversable terrain during favourable seasons; hyaenas, wolves and bears indicate that the island's animal communities could include large carnivores and scavengers as well as herbivores. Such animals would have moved through a landscape broken by wet basins, uplands, river valleys and ice margins. Their presence also reminds us that Ireland's later historic fauna is a poor guide to its Pleistocene past.

## **No Demonstrable Irish Society**

There is no accepted evidence for a human community, camp, hearth, burial, tool-making site or political group in Ireland at this date. Consequently, there can be no responsible account of Irish government, diplomacy, warfare, religion, learning, trade or social hierarchy for 30,966 BCE. These categories belong to human societies; the evidence presently available for Ireland at this horizon is overwhelmingly environmental and faunal.

A reindeer bone from Castlepook has been discussed as potentially bearing a human-made cut mark and has encouraged renewed attention to the possibility of an earlier Upper Palaeolithic visit. It is an important question, not a licence to populate Ireland with hunters. A single contested or contextually insecure mark cannot prove sustained occupation, establish a route of arrival, or reveal a culture. The first firmly dated evidence of human activity currently accepted for Ireland is much later: cut marks on a brown-bear bone from Alice and Gwendoline Cave in County Clare, dated to about 12,800–12,600 calibrated BP. Permanent or repeated settlement is later again, in the Early Mesolithic.

That silence is historically meaningful. Around 30,966 BCE, groups of *Homo sapiens* certainly occupied parts of Europe and Britain was connected to wider continental landscapes during periods of lower sea level. Yet proximity is not evidence of arrival. Whether any people reached Ireland during a particular MIS 3 interval remains unresolved, and the sea, exposed shelves, glaciers and shifting coastlines would all have affected possible routes. Ireland's archaeological record is also incomplete: acidic soils preserve little bone, later ice has removed or buried landscapes, and caves have been investigated unevenly. Absence of evidence is not proof that no person ever entered the island, but it does prevent claims of occupation.

## **Ice, Water and Regional Difference**

The numbered year also falls near a crucial transition in the wider British–Irish Ice Sheet story. Recent reconstructions indicate that major ice-sheet growth accelerated around 32,000–30,000 years ago in parts of Britain and Ireland's northern approaches, before the Last Glacial Maximum later brought far more extensive ice across Ireland. The timing, direction and extent of individual advances remain matters of active research. Derryvree's position between two tills demonstrates glacial change at one Fermanagh locality; it does not prove that all of Ireland was ice-free simultaneously.

Regional differences were therefore decisive. A freshwater basin in south Fermanagh, a limestone cave in Cork, and a karst system in Kerry each preserve different fragments of the past. Their value lies precisely in their incompleteness: together they show that Ireland contained refuges of water, vegetation and animal life during phases of the last glacial cycle, while ice repeatedly altered the terrain and erased evidence elsewhere. There were no recognisable provinces, peoples or borders. The most consequential "politics" of the time were the movements of ice and the opening or closing of habitable ground.

## What This Year Can Mean


For Ireland, 30,966 BCE is best treated as a window onto a cold, dynamic and largely humanly undocumented world. In and around the relevant date range, open vegetation and wetland communities existed at Derryvree; large mammals and carnivores occurred in Ireland during the broader MIS 3 interval; and the British–Irish Ice Sheet was entering a period of expansion and reorganisation. These are observations supported by sediments, plant remains, cave fauna, radiocarbon measurements and cave mineral deposits. Any fuller picture—how animals migrated, whether people briefly visited, or precisely how far ice lay from a given valley—is interpretation, necessarily provisional.

The enduring image should therefore be neither an empty frozen wasteland nor an invented Palaeolithic Ireland of camps and clans. It is a frost-bound but living landscape: sedges and mosses around shallow Fermanagh water, sparse plants gripping disturbed ground, animals moving when habitat permitted, and glaciers capable of returning to cover and preserve the evidence. That is the scale on which Irish history can responsibly be written for this remote point in time.

# Chapter 036 of 100

## 30965 BCE

### BIRM-166's Bogbean Seed<sup>[36]</sup>



30,965 BCE is a modern chronological label, not a year that can be observed in the Irish archaeological record. There are no written sources, settlements, graves or artefact assemblages that can be assigned to that single year. In calendar terms it falls roughly 32,900 years before AD 1950, within the later part of Marine Isotope Stage 3 (MIS 3), a climatically volatile interval of the last Ice Age. The responsible approach is therefore to use broad calibrated ranges, not to invent an episode for an exact date. Ireland's evidence consists chiefly of sediments sealed beneath later glacial deposits, cave faunas and changing ice-sheet landforms. Together they illuminate a severe, treeless and shifting environment, while leaving human presence at this time uncertain.

## Dating a Calendarless Landscape

Radiocarbon years are not calendar years. A laboratory determination must be calibrated against changing atmospheric carbon levels, and results this old commonly produce wide ranges. The key Irish deposit is at Derryvree near Maguiresbridge, County Fermanagh, where roadworks in 1969 cut through a drumlin. Beneath its surface lay two separate sheets of glacial till, with freshwater silts, sands and organic layers caught between them. The organic deposit, known as BIRM-166, produced a conventional radiocarbon result of 30,500 years BP with a substantial uncertainty. Published calibration places the episode broadly around 36,900–31,700 calibrated years BP. The notional date of 30,965 BCE falls within that broad window; it does not identify the precise moment when a particular pond formed, a seed fell or an animal crossed the ground.

This is nevertheless unusually valuable evidence. The lower till shows that glacier ice had previously occupied the locality. The organic bed records an intervening period in which freshwater and vegetation existed there. The upper till shows that ice later returned or expanded across the area. Derryvree therefore

disproves any simple picture of Ireland as continuously ice-covered throughout the whole last glacial cycle. It does not, however, supply a detailed island-wide map. A protected sediment lens under a Fermanagh drumlin preserves a local sequence; later glaciers removed or disturbed much else. At Greenagho near Belcoo, also in Fermanagh, organic material beneath till has been dated broadly to 37,200–35,700 calibrated years BP, reinforcing the conclusion that parts of north-central Ireland remained ice-free during earlier MIS 3 intervals.

## Wet Ground Beneath a Drumlin

Derryvree's fossils depict a tundra wetland rather than a forest or a familiar Irish bog. Pollen was poorly preserved, but plant macrofossils, mosses and insect remains point to open, cold country with pools and waterlogged ground. Sedges and grasses were important components, alongside small hardy plants adapted to short growing seasons. The recovery of bogbean, *Menyanthes trifoliata*, is especially striking: it is a plant of shallow freshwater margins and marshy pools, and its fossil seed gives the article its title. Mosses and aquatic plants indicate that this was not a lifeless frozen waste. Yet their presence should not be mistaken for a mild climate. The wider setting was periglacial: repeatedly affected by freezing and thawing, with long cold winters, sparse dry-ground cover and little or no tree growth.

The available evidence suggests a mosaic rather than uniform tundra. Low-lying hollows could hold water, organic matter and sheltered vegetation; exposed ground would have been colder, windier and more thinly covered. Summer thaw may have made soft ground around pools, while winter frost transformed the same landscape. Such conditions controlled where animals could graze, where predators could find prey and where any people might travel. They also left a record that is more ecological than scenic. We can responsibly identify freshwater plants, cold-adapted insects and glacial sediments. We cannot reconstruct a particular day's weather, name a river crossing, or assume that every part of Ireland resembled Derryvree.

## Cork's Cave Fauna

County Cork provides the other major window onto Ireland's MIS 3 world. Castlepook Cave, near Doneraile, yielded a remarkable collection during excavations led by Richard Ussher in the early twentieth century. The bone assemblage includes woolly mammoth, reindeer, giant deer, brown bear, wolf, Arctic fox, hare, lemmings and spotted hyaena. Re-dating has demonstrated that some older radiocarbon determinations from Irish caves needed revision, but Castlepook remains the principal evidence for a pre-Last Glacial Maximum mammal community in Ireland. It documents an open landscape capable of supporting large herbivores as well as formidable carnivores, not an island wholly locked beneath permanent ice.

The cave must be read carefully. A cave bone collection is not a census of every animal alive together at one moment, nor a straightforward picture of a hunting camp. Castlepook's deposits accumulated through water movement, animal activity, excavation disturbance and long periods of use. Hyenas appear to have been important agents in the assemblage: their presence indicates that carcasses and bones could have been dragged, chewed and scattered by carnivores. Mammoth, reindeer and giant deer demonstrate the availability of large grazers and browsers across the wider region at some point in this cold phase. The absence of a species from a particular deposit cannot prove its absence from Ireland, particularly where fossil survival is patchy and later glaciation was destructive.



## The Human Question

A reindeer femur from Castlepook has been publicised as bearing a deep mark consistent with stone-tool butchery and as potentially indicating human activity in Ireland about 33,000 years ago. It is an important claim, but it remains insufficient by itself to establish a settled population, a named culture or even a repeatedly occupied camp. The bone has no securely associated hearth, lithic assemblage, dwelling surface, human burial or concentration of butchered prey. Moreover, recent reassessment of Irish cave dates has shown why old collections and their chronologies require renewed testing. The strongest securely evidenced Palaeolithic human activity presently recognised in Ireland is much later, at Alice and Gwendoline Cave in County Clare during the terminal Pleistocene.

For 30,965 BCE, the prudent conclusion is that people may have reached Ireland intermittently, perhaps following mobile animal resources during favourable climatic intervals, but their presence is not established by a robust archaeological settlement record. Ireland was separated from Britain by sea, although lower sea levels altered coastlines and narrowed crossings. Neither a land bridge nor a route used by people can be asserted for this exact time from the surviving Irish evidence. If small parties did visit, they would have needed exceptional knowledge of weather, animals, fuel and shelter. That is a plausible inference from the environment, not evidence for a permanent community.

## No Politics, No Proven Exchange

There is no basis for describing political affairs, diplomacy, warfare, leadership, territory or institutions in Ireland at this date. There are likewise no demonstrated farms, herds, fields, houses, trade networks, mines or craft workshops. Terms such as ‘economy’ can only be used in the most limited ecological sense: animal movements, usable freshwater, seasonal vegetation and access to sheltered ground set the material possibilities of life. The cave fauna suggests food webs centred on large mammals and their predators, while Derryvree records productive wetland niches on a much smaller scale. It does not show that humans controlled these resources.

Religion, art and learning are equally beyond recovery here. No Irish ritual site, figurative art, musical instrument, burial practice or symbolic object can be reliably assigned to around 30,965 BCE. It would be misleading to import the famous cave art, burials or tool traditions of continental Europe and treat them as Irish evidence. The people who made such works elsewhere demonstrate the cultural capacities of Upper Palaeolithic populations, but they do not prove comparable activity on this island. Ireland’s own archive is environmental first, archaeological only in the most tentative sense.

## Approaching Greater Ice

The wider significance of this period lies in transition. Major growth of the British–Irish Ice Sheet followed during the succeeding millennia, while its fullest Last Glacial Maximum extent came later, broadly between about 27,000 and 21,000 years ago in many reconstructions. At 30,965 BCE, Ireland stood in neither a timeless frozen void nor a settled prehistoric homeland. It was a region of unstable cold climates, locally ice-free terrain, freshwater hollows and open animal country, increasingly vulnerable to renewed glaciation. BIRM-166’s bogbean seed, preserved beneath a later drumlin, captures that fragile interval: evidence of living water and tundra vegetation before the ice altered the landscape again.

# Chapter 037 of 100

## 30964 BCE

### Castlepook's Fossil Corridor<sup>[37]</sup>



Modern calendar-year precision is not available for Ireland in 30,964 BCE. No written calendar, settlement sequence or securely dated event can identify that particular year, and it would be misleading to pretend otherwise. The label is a modern chronological convenience: it falls roughly 32,913 years before AD 1950, the reference point conventionally used for “before present” dating. The responsible subject is therefore a broad Late Pleistocene interval, not an annual chronicle. Ireland lay within Marine Isotope Stage 3, a climatically unstable part of the last Ice Age, and the evidence comes chiefly from buried environmental deposits and animal remains rather than from human sites.

## A Date Within a Range

The closest important Irish environmental record is at Derryvree, near Maguiresbridge in County Fermanagh. Roadworks exposed a drumlin whose internal layers preserved a striking sequence: an older glacial till below, freshwater sands and organic silts in the middle, and a later till above. Till is the unsorted debris left directly by glacier ice. The sequence therefore establishes a simple but valuable order of events: ice had covered the locality; an ice-free interval allowed water, sediment, plants and small animals to accumulate; then glacier ice returned and sealed the deposit beneath fresh debris.

Organic material from the Derryvree bed yielded the radiocarbon determination BIRM-166, conventionally reported as 30,500 radiocarbon years BP, with a substantial uncertainty. A radiocarbon age is not a calendar age. Atmospheric carbon-14 has varied through time, so results must be calibrated against independently dated records. At this depth of time, both the laboratory uncertainty and the shape of the calibration curve create broad probability ranges. Published discussion places the Derryvree deposit broadly around 36,900–31,700 calibrated years BP; a more recent regional ice-sheet model places its age

at about  $33,500 \pm 1,200$  calibrated years BP. The modern label 30,964 BCE lies within this general chronological window, but does not date the formation of a single pool, plant, animal death or human visit.

That distinction matters. The evidence can illuminate conditions across a long phase of late Ice Age change. It cannot supply a named leader, a battle, a ritual calendar or even a reliably reconstructed season for this numbered year.

## **Wet Ground Between Glaciers**

Derryvree is especially important because it offers a local landscape rather than a bare list of fossils. Its plant and animal remains indicate an open, treeless environment under periglacial conditions: ground shaped by intense cold, seasonal freezing and thawing, but not permanently covered by ice at the site. The deposit has been described as tundra or muskeg, a waterlogged mosaic of shallow pools, sedgy ground, mosses and low herbs. Fossil pollen, seeds and mosses include plants suited to cold, damp, exposed settings, among them bogbean, sedges, mountain-avens, dwarf willow, juniper and clubmoss.

This was not an Irish landscape of dense woodland, enclosed fields or familiar coasts. Its vegetation was low and patchy, responding to waterlogging, frost disturbance and short growing seasons. Insects and plant remains indicate freshwater habitats amid open ground. Yet Derryvree should not be treated as a miniature map of the whole island. It records one lowland location in Fermanagh during an interval that may have lasted many centuries or longer. Upland districts, western coasts and areas nearer active ice could have differed sharply.

The wider climate was not static. Marine Isotope Stage 3 was marked by abrupt shifts in temperature and ice extent across the North Atlantic world. Ireland was heading towards the much more extensive glaciation of the Last Glacial Maximum, but that maximum lay later. Around the broad horizon represented by Derryvree, conditions could include locally ice-free terrain, cold wetlands and open animal range, while glaciers persisted or re-advanced elsewhere. The apparent contradiction is the point: Ice Age Ireland changed rapidly by region and through time.

## **The Castlepook Animal World**

For the larger animals of this period, the key Irish archive is Castlepook Cave, also known as Mammoth Cave, near Doneraile in north County Cork. Early twentieth-century excavations recovered more than 2,000 bones from its passages and chambers. The National Museum of Ireland and Geological Survey Ireland regard it as Ireland's richest known cave assemblage for vertebrate life leading towards the Last Glacial Maximum.

The collection includes woolly mammoth, reindeer, giant deer, brown bear and spotted hyaena; other cold-stage finds include wolf, Arctic fox, Norwegian lemming, collared lemming and mountain hare. Together they demonstrate that Ireland was periodically accessible to a varied Pleistocene fauna. They do not prove that every species lived side by side, or even in the same century. Castlepook was a cave repository, not a neatly sealed campsite. Carnivores carried material in, water disturbed deposits, and excavations took place before modern recovery standards. Radiocarbon results from individual bones also span a long interval rather than one episode.

Spotted hyaena is particularly revealing. Its remains, including chewed bones and a skull, suggest that the cave functioned at least partly within a carnivore landscape: a place where carcasses could be dragged in, consumed, scattered and later reworked. A mammoth or reindeer bone in the cave is evidence that such

animals reached southern Ireland; it is not automatically evidence that people hunted them there. The best reconstruction is of shifting open country supporting mobile herbivores and predators, with caves preserving only a distorted fraction of that world.

## **A Reindeer Bone and Human Possibility**

One Castlepook find has transformed discussion of Ireland's earliest human presence. A fragment of reindeer femur bears a deep mark interpreted by palaeozoologist Ruth Carden as having been made on fresh bone by a stone tool during butchery. It has been publicly reported as dating to about 33,000 years ago. If that interpretation is sustained, it is evidence that one or more people handled a reindeer carcass in Ireland during the wider period under consideration, far earlier than the formerly accepted post-glacial evidence for people on the island.

But the correct conclusion is deliberately narrow. A marked bone can indicate carcass processing; it cannot by itself demonstrate a permanent settlement, a population of known size, a language, an ethnic identity or an established route of migration. No associated hearth, stone-tool assemblage, dwelling floor, burial or art has yet been recovered from a securely dated Irish context of this age. Nor can the mark tell us whether people killed the animal, scavenged it, or processed it elsewhere before the bone entered the cave deposits.

It is tempting to imagine Upper Palaeolithic hunters following reindeer across a wide exposed plain. Such people elsewhere in north-west Europe possessed sophisticated stone technologies and deep knowledge of seasonally changing animal landscapes. Yet those wider European comparisons remain context, not direct proof for Ireland. At Castlepook, the evidence supports a possible fleeting human action, not a securely documented Irish community.

## **Society Without a Chronicle**

Accordingly, political affairs, diplomacy and organised warfare are beyond the reach of the evidence. There are no polities to name and no grounds for projecting later Irish identities, "tribes" or territories into the Late Pleistocene. Religion, formal learning and artistic culture are equally undocumented in Ireland at this date. Absence of evidence does not prove that visitors had no beliefs, stories, skills or social ties; it means that the surviving Irish record cannot responsibly describe them.

The same caution applies to economy and trade. If the cut-mark interpretation is correct, the practical value of a reindeer is clear: meat, fat, hide, sinew and bone were potentially useful resources, and a sharp stone edge could divide tissue. This is an inference from the mark and from well-attested hunter-gatherer practices elsewhere, not proof of a local Irish hunting economy. There is no evidence for farming, herding, metalworking, pottery, markets or sustained exchange networks. Nor is there a basis for claiming a land bridge. Lower sea levels and changing ice altered the geography of the Irish Sea region, but the exact routes by which animals, and perhaps people, reached Ireland remain unresolved.

## **What This Horizon Means**

For Ireland around the notional date of 30,964 BCE, the largest development was environmental. A cold, largely treeless island or archipelago contained wetlands such as Derryvree and, during suitable intervals, supported a remarkable large-mammal fauna in the south. The approaching growth of the


British–Irish Ice Sheet would later bury, scour and destroy much of this evidence. That geological violence helps explain why the record is so sparse and why one silt bed or incised bone carries unusual weight.

This is not a year of kings, monuments or recorded decisions. It is a horizon revealed by silt beneath a Fermanagh drumlin and fossils in a Cork cave: evidence for a changing Ice Age environment, for animal movement into Ireland, and perhaps for one exceptionally early human encounter with a reindeer. The uncertainty is not a weakness to be edited away. It is the central historical fact.

# Chapter 038 of 100

## 30963 BCE

### The Castlepook Cut Mark<sup>[38]</sup>



**Modern calendar-year precision is not available for Ireland in 30,963 BCE. Nobody on the island left a written calendar, a named ruler, a settlement sequence or an event that can be assigned to that particular year. The number is a modern chronological label, equivalent in simple arithmetic to about 32,912 years before the radiocarbon convention of AD 1950, but it should not be confused with an archaeological date. The responsible setting is the later part of the Late Pleistocene, during Marine Isotope Stage 3 (MIS 3): a long, climatically unsettled phase of the last Ice Age before the fullest expansion of the Last Glacial Maximum.**

The evidence is fragmentary, local and often difficult to date. Yet it shows that Ireland was not simply an empty sheet of ice throughout this era. In particular, buried freshwater sediments in County Fermanagh record an ice-free interval with cold-adapted plants and insects, while cave deposits in County Cork preserve the bones of animals that moved through a very different Irish landscape. One reindeer bone from Castlepook Cave has also raised the possibility of a much earlier human visit than was once accepted. It is an important possibility, not a licence to invent an Ice Age Irish community.

## **A Date Within a Broad Interval**

The closest securely relevant environmental sequence is at Derryvree, near Maguiresbridge in County Fermanagh. Roadworks cut through a drumlin there in 1969 and exposed organic silts and fine sands trapped between two layers of till: the unsorted sediment deposited by glacier ice. The order of events is clear. Ice first occupied the locality and left the lower till; an interval without overriding ice allowed freshwater and organic sediment to accumulate; then a later ice advance buried the deposit beneath another till.

Organic material from the freshwater series produced a conventional radiocarbon determination of about 30,500 radiocarbon years before present, with a large uncertainty. Using modern calibration, this has been discussed as broadly about 36,900–31,700 calibrated years BP, or approximately 34,950–29,750 BCE. The requested year lies inside that wide span, but cannot be located in a particular layer, season or human lifetime. Calibration is essential because radiocarbon years are not identical to calendar years; at this depth of time, ranges are necessarily broad and liable to refinement as methods improve.

This distinction matters. Derryvree supplies direct evidence for a local sequence of water, sediment, vegetation and invertebrate life. It does not date an island-wide episode, prove that all of Ireland was ice-free at once, or identify what occurred in 30,963 BCE specifically. It is best understood as a rare surviving window into conditions between glacial episodes, preserved precisely because later ice sealed it.

## **Fresh Water Beneath the Drumlin**

The Derryvree fossils make the Ice Age tangible. Pollen, plant macrofossils and insects indicate cold, open, wet ground rather than the oak-and-hazel woodland associated with much later Irish prehistory. Mosses, sedges, low herbs and dwarf shrubs could occupy saturated margins and exposed soil; aquatic plants signal standing or slowly moving fresh water. The deposits have been interpreted as a periglacial wetland or muskeg-like mosaic of pools, sedgebeds and waterlogged ground.

That reconstruction is an interpretation built from direct remains, stratigraphy and comparison with northern environments. The firm evidence is more limited but still impressive: a freshwater basin existed at Derryvree, plants grew around it, insects lived in and near it, and the locality was not then covered by glacier ice. Short growing seasons, severe winters, frost action and a generally treeless terrain are consistent with the fossil assemblage and wider glacial context. Familiar Irish fields, woodland, peat bog and settled lakeshore are not.

Other inter-till deposits in Fermanagh, including sites near Belcoo, support the larger conclusion that ice cover during the Midlandian cold stage was episodic and regionally varied. They do not make the regional picture simple. Much evidence has been eroded, redeposited or hidden beneath later glacial sediment, and the timing, thickness and extent of ice before the Last Glacial Maximum remain matters of active research. A wetland in Fermanagh is therefore not evidence for a uniformly hospitable Ireland from Cork to Donegal.

## **The Animal World of Castlepook**

Far to the south, Castlepook Cave near Doneraile in north County Cork provides a complementary, though equally complicated, record. Excavations beginning in the early twentieth century produced an extraordinary collection of Late Pleistocene animal bones. Subsequent radiocarbon work by the Irish Quaternary Fauna Project demonstrated that Ireland supported a considerably richer mammal fauna between at least about 45,000 and 20,000 years ago than survives today.

Castlepook has yielded remains attributed to reindeer, woolly mammoth, giant deer, brown bear, wolf, Arctic fox, mountain hare, lemmings and spotted hyaena. This is not a roll call from one day, one season or one perfectly preserved ecosystem. Cave deposits accumulated over long periods. Carnivores dragged in carcass parts, gnawed bones and disturbed deposits; water, sediment movement and early excavation methods added further complications. A mammoth bone proves that mammoths reached the wider Irish landscape during the relevant broad interval, not that mammoths and every other recorded species stood together outside the cave in 30,963 BCE.

Even so, the assemblage demonstrates that cold-stage Ireland could sustain grazing animals, browsing animals, predators and scavengers. Reindeer in particular point to open country and seasonal mobility. Mammoth and giant deer evoke an extensive terrestrial world beyond the cave entrance, while hyaena remains warn against treating caves as straightforward human food stores. The cave was part of a landscape used and re-used by animals, not an excavated village.

## **The Reindeer Femur Question**

Castlepook is especially important because a reindeer femur has been presented by palaeozoologist Ruth Carden and County Cork heritage publications as bearing a deep mark made with a sharp stone tool during butchery. The object is assigned approximately to 31,000 BCE, close to the modern label considered here. If the interpretation of the mark is correct, it would indicate that a person or people processed a reindeer in Ireland during the Upper Palaeolithic, vastly earlier than the long-established record of post-glacial settlement.

The finding must be described cautiously. The bone is a single artefact from an old cave assemblage, not a sealed camp floor. No securely associated stone tools, hearth, dwelling, burial, human remains or substantial concentration of butchered food waste of comparable age has been recovered. Nor does the bone establish whether hunters killed the animal, processed it at the cave, arrived as a larger group, stayed for days or weeks, or ever returned. Carcass remains may have been moved after butchery by carnivores or other natural processes.

The direct evidence is therefore a reindeer bone and a proposed stone-tool modification. A brief visit by mobile hunters following animal herds is a reasonable hypothesis, but it remains an inference. There is no basis for identifying a resident population, language, ethnicity, named archaeological culture or biological identity for any possible visitors. Later Ice Age glaciation probably destroyed or buried much of the evidence that might have resolved those questions.

## **Movement Without Known Routes**

At this date, global sea levels were lower than today because immense volumes of water were held in continental ice sheets. This altered coastlines and widened some coastal plains. It does not, however, prove an easy, permanent land bridge between Ireland and Britain. The Irish Sea basin, changing relative sea level, local glaciers and the changing shape of exposed land complicate every proposed route. Animals evidently reached Ireland during the Late Pleistocene, but precisely how particular herds, predators or potential human visitors crossed remains unresolved.

There is no evidence for trade, maritime exchange, cultivated crops, domestic livestock or permanent farming settlements. Nor is there evidence from which to reconstruct political authority, diplomacy, warfare, formal religion, artistic traditions or systems of learning in Ireland at this point. Their absence from the account reflects the nature of the record, not a claim that all human thought or social relations were absent if people did visit. Archaeology simply cannot recover them from a possible cut mark and scattered environmental archives.



## Approaching a Colder Ireland


Thirty thousand years ago, Ireland was moving towards the severe conditions of the Last Glacial Maximum, conventionally placed around 26,500–19,000 calibrated years BP. Later ice sheets reshaped much of the island, scouring bedrock, depositing till and erasing vulnerable surfaces. Modern reconstructions show that the growth and maximum extent of the British–Irish Ice Sheet varied between sectors rather than occurring as one instantaneous national event. The Fermanagh wetland and Cork fauna belong to the unstable pre-maximum world from which that later, more extensive glaciation emerged.

For Ireland around 30,963 BCE, the most defensible history is therefore environmental and provisional. Cold freshwater lay in at least one northern basin between episodes of ice. Open habitats supported plants and animals adapted to a demanding climate. Large mammals ranged across parts of the island over the wider period, and a reindeer femur from Cork may preserve Ireland's earliest known trace of human action. Beyond that, silence is not a gap to be filled with invented chiefs, camps or ceremonies. It is the defining condition of Ireland's deep past.

# Chapter 039 of 100

## 30962 BCE

### Derryvree's Moss Assemblage<sup>[39]</sup>



**Modern calendar-year precision is not available for Ireland in 30,962 BCE. Nobody on the island used a calendar of BCE years, and the surviving evidence cannot identify an event, a visit or an environmental change in one particular year. The date is best treated as a convenient point within the Late Pleistocene, during Marine Isotope Stage 3 (MIS 3), a long and climatically unsettled portion of the last glacial cycle. In calendar terms it is about 32,912 years before AD 1950. The strongest directly relevant Irish record is a dated environmental deposit whose calibrated range includes that point, rather than an annual historical chronicle.**

## **A Date Within a Broad Range**

The key evidence comes from Derryvree, near Maguiresbridge in County Fermanagh. Road works in 1969 cut through a drumlin and revealed freshwater silts, fine sands and organic muds lying between two substantial layers of till: unsorted debris laid down by glacier ice. The sequence establishes a clear relative history. Ice had occupied the locality; an interval then followed in which water, plants and small animals could leave deposits; later ice advanced and sealed the evidence beneath another till sheet.

Organic material from the freshwater series produced radiocarbon determination BIRM-166, 30,500 +1,170/-1,030 radiocarbon years BP. This is not the same thing as a calendar age. Atmospheric carbon-14 levels changed through time, so radiocarbon measurements must be calibrated using independently constructed curves. Published discussion of this determination gives a broad calibrated span of about 36,900–31,700 calendar years BP, or roughly 34,950–29,750 BCE. More recent ice-sheet modelling uses the deposit as evidence for ice-free conditions around this broad horizon. Thus 30,962 BCE falls plausibly within the Derryvree interval, but it cannot be assigned to a particular layer, plant, animal or day of wetland life.

## **Fresh Water Beneath the Drumlin**

Derryvree is valuable precisely because so little evidence of this antiquity survived later glaciation. Its organic beds preserve pollen, plant macrofossils, mosses and invertebrate remains. Together, these indicate cold, largely open tundra vegetation and a periglacial regime: a landscape shaped by severe frost, seasonal freezing and thaw, saturated ground and short growing seasons, but not necessarily covered by glacier ice at that particular locality.

The record should not be turned into a photograph of the whole island. Pollen was poorly preserved, and isolated grains of pine and hazel do not demonstrate nearby woodland; wind transport or redeposition are possible. The firmer evidence is for herbaceous and wetland vegetation. Mosses, sedges and grasses accompanied plants associated with cold, open ground and shallow freshwater habitats, including mountain-avens, dwarf willow, lesser clubmoss, bogbean and water-milfoil. These remains suggest low vegetation around pools, marshy hollows and slow-moving water. They do not permit a detailed reconstruction of every slope or season.

For people accustomed to later Ireland's wooded landscapes, Derryvree offers a strikingly different prospect. There were no oak woods, hazel scrublands, farm fields or blanket bogs of the familiar Holocene kind. Ground conditions may have changed rapidly across short distances: wetter vegetation in sheltered depressions, sparse herbs and grasses on better-drained surfaces, and frost-disturbed soil where winter cold penetrated deeply. Productive summer months could support plants and insects, while winter imposed far harsher constraints.

## **Ice Was Advancing, Not Yet Supreme**

This was not the Last Glacial Maximum, the later period when the British–Irish Ice Sheet attained its greatest extent. The main maximum in and around Ireland came thousands of years afterwards, broadly between about 27,000 and 20,000 years BP, with important regional differences in timing and ice behaviour. At the horizon represented by Derryvree, Ireland was instead part of an unstable North Atlantic world in which glaciers, sea level, drainage and vegetation changed repeatedly.

Other evidence reinforces that caution. Uranium–thorium dating of broken and reworked speleothems at Crag Cave in County Kerry shows that cave calcite formed episodically during MIS 3. Calcite growth required percolating water and conditions not dominated by continuous deep permafrost or overriding ice above that cave. It is evidence for recurring milder phases in south-west Ireland, not proof that Crag Cave and Derryvree had identical weather or that the entire island was ice-free simultaneously. The responsible conclusion is regional variability: ice-free ground and freshwater habitats existed in some places during parts of MIS 3, while glacier growth was becoming increasingly important.

## **Castlepook's Animal Archive**

County Cork supplies a different kind of evidence. Castlepook Cave, also known as Mammoth Cave, near Doneraile contains Ireland's richest known assemblage of vertebrate remains from the period leading towards the Last Glacial Maximum. More than 2,000 bones have been recovered from its passages and chambers. The assemblage includes woolly mammoth, reindeer, giant deer, brown bear, wolf, fox, mountain hare, collared lemming, Norwegian lemming and spotted hyaena.

These animals support the broader picture of a cold-stage landscape capable of sustaining large herbivores and formidable carnivores. Reindeer and lemmings particularly fit open, cold-adapted habitats; mammoth and giant deer indicate that, at least during suitable phases, Ireland contained enough forage and connected territory for large mammals. Spotted hyaena remains are especially significant because the cave seems to have served, at least in part, as a carnivore repository or den. A hyaena skull from Castlepook is held by the National Museum of Ireland.

Yet the cave must not be read as a single moment or a single living herd. Its fossils accumulated over a long period, were affected by carnivores and water movement, and were excavated under early twentieth-century methods that did not meet modern stratigraphic standards. Individual dates span many millennia. Castlepook therefore demonstrates a varied Late Pleistocene fauna in Ireland, but does not show that every recorded species lived together in 30,962 BCE, or that the Cork fauna precisely matched the Fermanagh wetland.

## **The Reindeer Bone Question**

One Castlepook object has particular importance for human history: a reindeer femur reported to carry a deep mark interpreted as having been made on fresh bone by a sharp stone tool during butchery. The bone has been publicised as being about 33,000 years old. If the modification is confirmed as a human-made cut or chop and is contemporary with the animal's death, it would be evidence that people reached Ireland in the Upper Palaeolithic, far earlier than the long-established record of post-glacial settlement.

The limits of that inference matter. A marked bone is not a settlement. Castlepook has not yielded a securely associated hearth, stone-tool assemblage, dwelling surface, burial, food store or repeated concentration of butchered animals of this age. Nor does one possible butchery episode reveal whether a person or small group stayed briefly, hunted repeatedly, crossed from Britain by a route now altered by sea-level change, or left descendants. The date of the animal is also not a calendar date for the cut itself. Around 30,962 BCE, human presence in Ireland must therefore be described as a significant but limited claim under continuing archaeological investigation, not as an established population history.

## **What Cannot Yet Be Written**

There is no evidence for political affairs, named leaders, diplomacy, territorial states, warfare, organised religion, formal learning or trade networks in Ireland at this time. There are no known Irish houses, villages, farms, cultivated crops, pottery, monuments, graves or written records belonging securely to this horizon. It would be misleading to supply invented hunters' camps, tribal identities, rituals or social rules merely because comparable practices are known elsewhere in Ice Age Europe.

If people did enter Ireland, the most that can responsibly be inferred is that they possessed the practical knowledge needed to survive in a cold, mobile landscape and perhaps to process a large animal with a stone edge. Even that inference rests upon the disputed interpretation of one bone modification. Derrynree, by contrast, records everyday ecological life more securely than human society: wet-ground plants growing, organic matter collecting in freshwater, insects inhabiting the margins, and winter cold repeatedly reshaping the terrain.

## A Landscape of Evidence


The greatest development relevant to this date was environmental rather than political. Ireland was entering a phase of profound glacial transformation. Later ice would scour, bury and rearrange much of the surface on which any animals or people had moved, helping explain why the archaeological record is so fragmentary. The Derryvree beds survived because they were sealed within a glacial sequence; Castlepook's bones survived because limestone caves protected them. Both are exceptional archives rather than typical samples of the ancient landscape.

For 30,962 BCE, then, Ireland is best understood through this conjunction of wetland silt, mosses, plant fossils, cave fauna, ice deposits and carefully qualified dating. The evidence establishes an intermittently ice-free, cold and ecologically active island region within MIS 3. It does not furnish a year-by-year narrative in the usual sense. Its history is the history of what endured: a Fermanagh freshwater world trapped beneath a drumlin, and a Cork cave preserving traces of animals—and perhaps, though not yet conclusively, people—on the threshold of a much larger advance of ice.

# Chapter 040 of 100

## 30961 BCE

### Maguirebridge's Frostwater Basin<sup>[40]</sup>



30,961 BCE is not a recoverable Irish year. It is a modern calendar label for a point about 32,911 years before AD 1950, within the Late Pleistocene and Marine Isotope Stage 3 (MIS 3). No Irish inscription, settlement layer or dated event permits an annual narrative at this depth of time. The responsible approach is therefore to ask what deposits, fossils and glacial evidence can say about a broad interval encompassing that notional year. Radiocarbon measurements of this antiquity require calibration and normally yield ranges rather than a precise calendar point; IntCal20 extends the Northern Hemisphere calibration curve to 55,000 calibrated years before present, but does not turn a single Irish find into a historical date.

## An Intertill Window

The key Irish evidence comes from Derryvree near Maguiresbridge in County Fermanagh. During roadworks, geologists exposed fine freshwater sediments and organic material sandwiched between two layers of glacial till. This sequence is exceptionally important because its order records change rather than merely a chance fossil discovery: an earlier ice advance deposited the lower till; ice-free freshwater conditions followed; then a later advance sealed the wetland below fresh glacial debris. Organic material gave a radiocarbon age of 30,500 +1,170/-1,030 radiocarbon years BP. When calibrated, it belongs to a wide late-MIS-3 interval, broadly extending through the period around 30,961 BCE. It cannot establish what happened in one year, one season or even one human lifetime, but it securely demonstrates that this part of Fermanagh was not continuously under ice throughout the period represented.

Derryvree was not an early version of Ireland's familiar green, wooded countryside. Its pollen, plant macrofossils and insect remains indicate cold, open ground with freshwater pools and waterlogged vegetation: a periglacial wetland or muskeg-like mosaic. Grasses and sedges were prominent, alongside

juniper and herbs. Mosses were abundant. Fossil evidence includes bogbean, water-milfoil, mountain-avens, dwarf willow and lesser clubmoss—plants consistent with shallow water, saturated margins, sparse cover and exposed terrain. Insects added a complementary signal: not a forest community, but cold northern conditions with organic-rich pools and mossy ground. This is direct environmental evidence from one locality. It supports a landscape of tundra-like wetland around Maguiresbridge, not an assertion that every Irish valley, coast and upland looked identical.

## Cold Country, Moving Ice

The wider island was undergoing profound environmental instability. MIS 3 was neither a uniformly mild interval nor the final maximum of the last glaciation. Ice masses, sea levels, vegetation belts and animal ranges altered repeatedly across north-west Europe. The British–Irish Ice Sheet was beginning a major phase of growth in the broad period from about 31,000 years ago, though its margins did not advance everywhere at the same speed or reach a single simultaneous maximum. Reconstructions place its greatest overall extent later, principally around 27,000–23,000 years ago. Consequently, Ireland around the date represented here should be understood as a changing borderland of ice, meltwater, exposed ground and local refuges—not as a wholly ice-covered island, but not as a stable ice-free homeland either.

That distinction matters for regional change. Derryvree’s buried freshwater deposits show that northern inland habitats existed during a cold phase before renewed glaciation. Offshore and coastal records, meanwhile, indicate that the Irish ice mass had a longer and more complicated pre-Last Glacial Maximum history than older simple models allowed. Lower global sea level exposed more continental shelf than today, reshaping coastlines and possible routes between Ireland, Britain and mainland Europe. Yet exposed shelf does not prove a convenient, continuous land bridge at a particular moment, nor does it prove that people or every animal species used it. Routes could have been interrupted by seawater, ice, rivers, marshes and changing ice margins.

## The Cave Fauna of Cork

Southern Ireland supplies another vital, if different, archive. Castlepook Cave near Doneraile, County Cork—also called Mammoth Cave—has produced a remarkable assemblage of Late Pleistocene animal remains. Improved radiocarbon pretreatment has shown that some bones formerly thought much younger are in fact substantially older, placing part of the fauna in MIS 3. The broader pre-Last Glacial Maximum Irish record includes reindeer, woolly mammoth, giant deer, horse, brown bear, wolf, Arctic fox, mountain hare, lemmings and spotted hyaena. These animals do not constitute a single herd observed on a single day. Cave deposits can be accumulated by carnivores, water, natural deaths, sediment movement and nineteenth- or early twentieth-century excavation. Their significance lies in showing that Ireland, at different points in this broad cold interval, formed part of a north-west European ecological world capable of supporting large grazing animals, small cold-adapted mammals and formidable predators.

For everyday life in the animal world, this meant mobility and risk. Reindeer could exploit open country and seasonal vegetation; hyaenas and wolves were predators and scavengers; mammoths and giant deer required substantial feeding grounds. Wet hollows such as Derryvree may have concentrated water, plant foods and animal traffic, while exposed ridges and gravelly surfaces offered very different conditions. But the evidence cannot furnish population figures, migration calendars or a complete food web. Nor should the popular image of a single “mammoth-steppe” be imposed mechanically on every

Irish locality. Derryvree records wet tundra-like ground; Castlepook records faunal remains in a limestone cave system. Together they reveal varied habitats, not a map of an entire island frozen in one ecological moment.

## **A Possible Human Trace**

The possibility of people in Ireland around this horizon rests principally on a reindeer femur from Castlepook. County Cork heritage material reports that the bone, recovered from the cave's historic collections, was radiocarbon dated to roughly 33,000 years ago and bears deep modifications interpreted as stone-tool marks made while fresh bone was being processed. If that interpretation is sustained, it is highly important: it would indicate a brief Upper Palaeolithic human encounter with a reindeer carcass far earlier than Ireland's better-established terminal-Pleistocene evidence. Yet its limits are equally important. A date on the animal establishes when it died, not the duration of a human visit; a marked bone is not a house, hearth, stone-tool assemblage, burial ground or village. The cave's complex depositional history prevents the reconstruction of a campsite or a named community.

Accordingly, political affairs, diplomacy and organised conflict are unknown for Ireland at this time. There is no evidence for rulers, territorial polities, alliances or warfare. There is likewise no secure Irish evidence for religion, ritual, cave art, formal burial, long-distance trade or a distinctive learned tradition around 30,961 BCE. It would be reasonable only in the most general sense to note that mobile Upper Palaeolithic groups elsewhere in Europe possessed sophisticated stone technologies and cultural traditions; it would not be reasonable to assign those particular practices to Ireland without an Irish assemblage. The most defensible social interpretation is modest: if the Castlepook mark is human-made, one or more people may have reached or moved through this changing landscape and processed animal tissue. Whether they stayed, returned, travelled by land or water, or left descendants is not known.

## **History Before History**


This was therefore not a year of kings, monuments or recorded battles, but a threshold in Ireland's deep past. At Maguiresbridge, freshwater silts, mosses, seeds and insects preserve evidence of an open, cold wetland between episodes of glaciation. At Castlepook, bones preserve the presence of a changing Ice Age fauna and a tantalising, still limited possible sign of human butchery. Subsequent ice advances could erode landscapes, redistribute sediments and destroy or conceal evidence, helping to explain why the record is so sparse. Around 30,961 BCE, Ireland can responsibly be pictured as environmentally alive but climatically precarious: a land of frostwater pools, sedges, low shrubs, wandering animals and encroaching ice, with human presence possible but far from demonstrated as permanent settlement.



# Chapter 041 of 100

## 30960 BCE

### Dryas Beneath the Drumlin<sup>[41]</sup>



**“30,960 BCE” is a modern archival label, not a year from which Ireland preserves an event, ruler, settlement or calendar. It corresponds approximately to 32,910 years before AD 1950, the conventional ‘present’ used in radiocarbon science, but no archaeological evidence can be assigned to that individual year. The responsible subject is therefore Ireland during a broader late Middle Midlandian, Marine Isotope Stage 3 (MIS 3) interval of the last Ice Age. Dates at this depth are expressed as radiocarbon measurements and calibrated ranges, often with uncertainties of centuries or millennia.**

At this point Ireland was approaching, rather than living through, the fullest expansion of the last British–Irish Ice Sheet. The ice sheet did not form everywhere at once, nor did it have a single neat edge. Its sectors advanced and retreated differently in response to climate, topography and the behaviour of fast-flowing ice. Later reconstructions place substantial growth in the wider Irish–British ice complex around this period, while emphasising that large parts of the chronology remain inferred from scattered geological constraints. The maximum ice volume came much later, around 23,000 years ago. Around the notional date, Ireland was a changing mosaic of ice, ice margins, exposed ground, caves and cold-water environments rather than a uniform frozen island.

## A Landscape Recorded Between Tills

The strongest local window is Derryvree, near Maguiresbridge in County Fermanagh. Roadworks in 1969 cut through a drumlin and revealed silts, fine sands and organic deposits trapped between two distinct layers of glacial till. This was an exceptional discovery: the lower till testified to an earlier ice advance, while the upper till showed that ice later returned and overrode the landscape. Between them lay evidence for a period when freshwater accumulated in a hollow and life persisted in, beside and above it.

The principal radiocarbon measurement from Derryvree was 30,500 radiocarbon years BP, with a quoted uncertainty of roughly a thousand years. It is not a calendar date and should not be mechanically equated with 30,500 BCE. Calibration is necessary because atmospheric carbon-14 has varied through time; modern calibration curves extend to 55,000 calibrated years BP, but their result at this antiquity is a probability distribution rather than a date on a single day or year. Derryvree is consequently evidence for a broad cold-stage interval relevant to 30,960 BCE, not proof that its pond existed in that exact year.

Its fossils make the point vividly. Mosses, sedges and herbaceous pollen, together with macrofossils including mountain avens, dwarf willow and bogbean, indicate open, cold vegetation. Aquatic evidence, including water-milfoil, demonstrates that shallow freshwater was available locally. Insects reinforced the picture of a northern, full-glacial fauna. The careful conclusion is not that every part of Fermanagh was identical, but that a periglacial wetland existed within an exposed tundra-like landscape. Periglacial means shaped by intense frost, seasonal freezing and thawing, and sparse plant cover near ice; it does not mean that the site lay permanently under glacier ice.

## Open Ground, Moving Ice

The Derryvree record corrects an easy misconception about Ice-Age Ireland. Cold conditions did not make the whole island biologically empty. Wet hollows could support aquatic plants and mosses, while sedges, grasses, low shrubs and Arctic-alpine herbs occupied surrounding ground. Yet this was not the wooded Ireland familiar from later prehistory. The few tree-pollen grains recovered from such deposits cannot securely demonstrate nearby woodland: pollen can travel far on the wind or be redeposited. The more robust inference is a generally open landscape, with localised water and vegetation providing small ecological refuges amid severe conditions.

Other Fermanagh deposits at Hollymount and Greenagho likewise show that parts of northern Ireland experienced cold, non-glacial intervals during the Middle Midlandian. Their chronological limits differ and are imperfect, so they should not be combined into an imaginary island-wide scene for a single year. Together, however, they show that Ireland's interior contained episodes of exposed land and freshwater habitats before later ice advances buried or eroded much of that evidence.

The physical geography was also unlike that of the modern republic and Northern Ireland. Sea level was lower globally because enormous volumes of water were locked in continental ice, and coastlines lay farther out in many places. But lower sea level alone cannot prove a particular route for humans or animals into Ireland at this time. The character, timing and duration of possible connections or crossings in the Irish Sea region remain subjects requiring local evidence. A fossil animal in Ireland demonstrates that an animal reached the island; it does not by itself reveal whether it came over land, sea ice, a short water crossing or a route now destroyed by later glaciation and rising seas.

## Animals Before the Maximum

Cave collections, especially those from southern Ireland, indicate a richer pre-Last Glacial Maximum mammal community than later Ireland possessed. Castlepook Cave near Doneraile, County Cork, is especially important. Its old excavations produced remains attributed to reindeer, giant deer, mammoth, brown bear, wolf, Arctic fox, lemming and spotted hyaena. Such a list evokes an open, cold-steppe or tundra-margin ecosystem in which herds and predators could range across suitable terrain.

It must nevertheless be read cautiously. Caves are complicated archives. They can be dens used by carnivores, natural traps, conduits for water and sediment, shelters, and places disturbed by earlier excavation. Bones recovered from different chambers or depths may not belong to one moment, one habitat or even one intact deposit. Improved ultrafiltration methods have also shown that several older Irish cave radiocarbon determinations were too young, underlining the need to reassess collections rather than repeat inherited chronologies.

Direct calibrated dates provide firmer but still limited anchors. Two pre-Last Glacial Maximum red-deer specimens from caves in County Waterford were dated to 32,930–31,280 and 30,297–29,594 calibrated years BP. The earlier range overlaps the modern label represented by 30,960 BCE. These finds demonstrate that cervids were present in southern Ireland during the broad period, but they do not establish a continuous population, migration route or an annual hunting season. Reindeer and other cold-adapted mammals are more frequently represented in the wider Irish Pleistocene cave record, though each specimen requires its own dating and contextual assessment.

## **The Castlepook Human Question**

This period has acquired special significance because of a reindeer femur from Castlepook. County Cork heritage material reports that the bone, held in the National Museum of Ireland's Natural History collections, was dated to about 33,000 years ago and bears a deep mark interpreted by zooarchaeologist Ruth Carden as a sharp stone-tool mark made while the bone was fresh. If that diagnosis and association are sustained, it would be a remarkable indication that a person handled a reindeer in Ireland long before the Last Glacial Maximum.

That is an important possibility, but not a licence to invent an Irish Palaeolithic community. The dated object is an animal bone, not an excavated occupation floor. No securely associated hearth, stone-tool assemblage, dwelling, burial, workshop or repeated food-processing area of comparable age has yet been identified at Castlepook. A cut mark could indicate carcass processing, but cannot tell us whether people killed the animal, found it dead, removed meat or hide, visited once or lived nearby. Nor can it establish political groups, kinship, language, art, ritual, trade or a permanent settlement.

The contrast with later evidence is useful. A butchered brown-bear patella from Alice and Gwendoline Cave in County Clare has two independent calibrated dates of 12,810–12,590 and 12,810–12,685 cal BP, making it the published, securely dated evidence for Late Upper Palaeolithic human activity in Ireland. It is nearly twenty millennia later than the horizon considered here. The distinction matters: established evidence for a brief later human presence should not be projected backwards to fill the silence at 30,960 BCE.

## **Society Beyond Recovery**


There are therefore no recoverable political affairs, conflicts, diplomatic contacts, named peoples or religious institutions for Ireland around this point. There is no evidence for agriculture, domestic animals, metalworking, pottery, writing, exchange networks or a settled economy. If people were present, their subsistence would most plausibly have depended upon highly mobile foraging and the opportunistic use of animal and plant resources; that is an inference from the broader Upper Palaeolithic world, not an established description of an Irish society.

The most meaningful history of Ireland at this horizon is environmental and evidential. Freshwater silts beneath a Fermanagh drumlin record a cold wetland capable of supporting hardy plants and insects. Cave bones in Cork attest to mammals that later vanished from the island. A marked reindeer femur raises a serious question about human activity but does not yet answer it. Above all, advancing ice would later scour, bury and rearrange much of the landscape, helping to explain why the archive is so fragmentary. Ireland at 30,960 BCE is not a blank past, but it is a past known in traces: pollen, seeds, mosses, insects, sediment, bone and the disciplined uncertainty that connects them.

# Chapter 042 of 100

## 30959 BCE

### Maguirebridge Fresh-Water Series <sup>[42]</sup>



**30,959 BCE is not a recoverable year in Irish history. It is a modern calendar label placed roughly 32,900 years before the conventional radiocarbon baseline of AD 1950, within the Late Pleistocene and Marine Isotope Stage 3. No Irish calendar, written testimony, settlement sequence or dated archaeological layer can tell us what occurred in that particular year. The responsible history is therefore one of broad, calibrated and radiocarbon-dated ranges: changing ice, water, plants, animals and a possible, still unconfirmed trace of human activity.**

The evidence is exceptionally fragmentary. Much of Ireland was later overridden or reshaped by ice during the Last Glacial Maximum, while coastlines have altered radically and any former lowland sites may now lie beneath the sea. What remains comes principally from deposits trapped between glacial sediments, from cave bones, and from painstaking reassessment of old museum collections. These sources are more informative about environment and animal movement than about politics, communities or beliefs.

## A Point Within Deep Time

The nearest major environmental anchor is Derryvree near Maguiresbridge in County Fermanagh. Roadworks exposed a remarkable sequence within a drumlin: a lower till, organic-rich freshwater sediments and fine sands, then a later upper till. Till is material deposited by glacier ice. The order of these layers demonstrates that ice covered the locality, retreated or ceased to occupy it locally long enough for water and organic sediment to gather, and later advanced again. It records environmental instability on a scale of millennia, not an annual episode.

Organic material from the Derryvree freshwater deposits produced a radiocarbon determination of 30,500 radiocarbon years before present, with a substantial uncertainty. Radiocarbon ages are not calendar ages: atmospheric carbon-14 has varied through time, so measurements must be calibrated against independently dated records. IntCal20 provides a calibration curve extending to 55,000 calendar years before present, but uncertainty remains considerable at this depth. The Derryvree deposit is consequently best treated as evidence for a broad cold-stage interval around the later Middle Midlandian, not proof that its pools, plants or insects were alive in 30,959 BCE exactly.

This distinction matters. The numbered year lies in a phase of repeated climatic shifts before the fullest development of the last British–Irish Ice Sheet. Modern reconstructions show that expansion, maximum extent and retreat were neither simple nor simultaneous across Ireland and Britain. A local wetland in Fermanagh cannot supply a weather report for every valley, coast or upland on the island. Yet Derryvree establishes an important fact: parts of Ireland could sustain an ice-free terrestrial and freshwater environment during an otherwise cold and increasingly glacial age.

## **Wet Tundra Between Glaciers**

Derryvree's plant and insect remains indicate an open, treeless landscape of northern aspect. Fossil mosses, sedges and aquatic plants, including bogbean and mountain avens, point to shallow freshwater, wet ground and patches of low vegetation rather than woodland. Pollen and macrofossils support the interpretation of a muskeg-like tundra wetland: waterlogged places rich in plant matter, interspersed with pools and surrounded by cold-country vegetation. Insects reinforce the picture of severe conditions, especially harsh winters, while also showing that this was not a lifeless sheet of ice.

Such evidence permits a restrained reconstruction of everyday ecology. During a short growing season, plant cover would have taken advantage of saturated soils, meltwater and open ground. In winter, freezing and thawing would have affected drainage, soil stability and vegetation. Wind exposure and seasonal contrasts were likely important. The familiar wooded and farmed countryside of later Irish history did not exist. Neither did the blanket of bog, hedgerow, field and settlement that now gives so much of Ireland its character.

It would be wrong, however, to picture every part of the island as identical tundra at once. Derryvree is a local archive preserved by unusual geological circumstances. Cave deposits in Munster and other scattered sites record different moments in long, complicated histories of deposition. The most secure conclusion is not that Ireland had one fixed Ice Age landscape, but that habitats expanded, contracted and changed as ice margins, temperature, precipitation and sea level changed.

## **Castlepook's Animal Archive**

At Castlepook Cave, near Doneraile in north County Cork, animal remains offer a second and very different window. The cave system produced a striking Pleistocene assemblage during excavations led by the naturalist Richard J. Ussher in the early twentieth century and from later discoveries. Its recorded fauna includes woolly mammoth, reindeer, giant deer, brown bear, wolf, Arctic fox, lemmings, hare and spotted hyaena. Direct dates and later reassessments indicate that some of this material belongs to the period before the Last Glacial Maximum, broadly overlapping the wider world relevant to this article.

These bones demonstrate that cold-adapted and large-ranging mammals reached Ireland at different points during the Late Pleistocene. They do not prove that all listed species lived together at Castlepook in one year, or even one century. Caves are complex archives. Carnivores may drag in prey; animals can die

naturally, bones can be carried by water, and excavators may disturb or remove the sedimentary sequence. The old investigations also left incomplete contextual records by modern standards. A cave fauna is therefore evidence of presence and deposition, not an instant photograph of a living community.

Even so, the range of animals is historically significant. Reindeer and mammoth evoke open country with extensive grazing potential; hyaena and wolf indicate predators and scavengers within that food web. Small mammals such as lemmings help identify cold conditions. Giant deer, bears and foxes remind us that the island's Pleistocene fauna was unlike its later historic fauna. The animals' presence also implies intermittent connections, whether through changing coastlines, sea ice, narrow marine passages or other routes that remain debated. Low sea level altered the geography of the Irish Sea region, but there is no safe basis for imagining a simple, permanent land bridge or a single migration corridor at this exact date.

## **The Reindeer Femur Question**

One Castlepook object carries exceptional potential. A reindeer femur fragment, recovered in 1972 and later examined by the zooarchaeologist Ruth Carden, has been publicly reported as approximately 33,000 years old. It bears a deep linear modification interpreted as damage made by a sharp stone implement while the bone was fresh. If that identification and its association with the animal's death are upheld through full specialist publication and further contextual evidence, it may represent human processing of a reindeer in Ireland far earlier than the formerly accepted record.

That possibility must not be inflated into a settled Ice Age Ireland. The radiocarbon result dates the animal bone, rather than automatically dating the incision or identifying who made it. The mark itself requires taphonomic judgement: specialists must distinguish tool damage from carnivore activity, breakage, sediment abrasion and other processes. Nor has Castlepook produced a securely associated hearth, stone-tool assemblage, dwelling floor, burial, food-preparation area or undisturbed occupation surface of comparable age. The femur is, at most, evidence for a possible act of carcass processing; it is not evidence for a village, a permanent population or a named people.

If people did reach Ireland during this broad interval, they were likely highly mobile hunter-gatherers operating within wider north-west European social and ecological networks. That is an inference from the period's wider archaeology, not a demonstrated Irish social structure. A successful visit to a cold and variable landscape would have required practical knowledge: animal behaviour, seasonal movement, shelter, fire, clothing, stone-working and cooperation. Yet none of these can be assigned to a particular group in Ireland from the present evidence.

## **No Politics, No Recorded Beliefs**

There were no identifiable Irish kingdoms, borders, diplomatic relations, rulers or wars in 30,959 BCE. Nothing supports claims about tribes, languages, law or ethnic identities. "Ireland" itself is used here only as a geographical convenience for the landmass that later became the island, not as a political or cultural community. Similarly, there is no direct Irish evidence from this date for ritual monuments, formal burial practice, cave art, religious institutions, teaching or written learning.

Upper Palaeolithic communities elsewhere in Europe possessed rich cultural traditions, sophisticated stone technologies and, in some regions, remarkable art. Those comparisons provide context for what a short human incursion into Ireland might have involved, but cannot fill the Irish evidential silence. To import continental art, beliefs or named archaeological cultures into Castlepook without Irish finds would be speculation.

## **An Economy of Landscapes, Not Markets**

There is likewise no evidence for farming, herding, metalworking, long-distance trade or permanent economic institutions. The only possible subsistence activity directly relevant is the contested processing of a reindeer carcass at Castlepook. If human, it suggests the acquisition of meat, marrow, hide, sinew or other animal resources, but it cannot reveal whether the animal was hunted, scavenged, killed elsewhere or brought to the cave. Derryvree's wetland plants and insects tell us about available habitats, not ownership or exchange.


The most important development around this notional date was therefore environmental. Ireland was part of a fluctuating Ice Age world, sometimes capable of supporting freshwater wetlands and cold-adapted mammals, but moving towards the major glaciation that would transform the landscape and erase or bury much earlier evidence. The Derryvree sediments and Castlepook bones preserve brief, uneven glimpses across that transformation. They offer a compelling prehistory precisely because they demand caution: a living landscape can be recovered in outline, but a calendar year, a human community and its story cannot.



# Chapter 043 of 100

## 30958 BCE

### BIRM-166's Arctic Marsh<sup>[43]</sup>



The label 30,958 BCE is a modern point on a modern calendar, not a date that can be recovered from Ice Age Ireland itself. No Irish community then used a written calendar, left an annal, or can be tied to an individual year. In archaeological terms it falls at roughly 32,900 calibrated years before present (cal BP, where “present” is 1950), late in Marine Isotope Stage 3. The appropriate evidence is therefore not an event narrative but a set of deposits, bones and cave minerals dated in broad ranges. The most relevant Irish archive is a buried freshwater sequence at Derryvree near Maguiresbridge, County Fermanagh, while caves in Cork and Kerry reveal the wider ecological and climatic setting.

## A Wetland Beneath a Drumlin

Derryvree was exposed during roadworks in 1969, when a cutting through a drumlin revealed a remarkable sandwich of deposits. A lower glacial till – stony sediment laid down by ice – was overlain by organic muds, silts and fine sands, which were themselves sealed below a later till. This order matters. It demonstrates that an earlier phase of glaciation was followed locally by an interval in which ice had withdrawn or disappeared, allowing water, plants and animals to occupy the ground, before a later glacier overrode and buried the landscape.

Organic material from the Derryvree freshwater bed returned a conventional radiocarbon determination of about 30,500 BP, with a large uncertainty. Later calibration places the deposit broadly within about 36,900–31,700 cal BP. The modern label 30,958 BCE lies inside that wide bracket, but it cannot identify a particular season, pool, plant or animal in that precise year. The range is the evidence;

the numbered year is merely a useful place from which to describe it. Radiocarbon dating measures the age of organic material, and calibration converts it into an estimated calendar range because atmospheric carbon levels have changed through time.

The Derryvree sequence is consequently one of the strongest reasons not to picture all of Ireland as permanently buried beneath ice at this point in the last glacial cycle. It shows that part of north-central Ireland experienced an ice-free freshwater and periglacial phase during later MIS 3. It does not prove that every region of the island was ice-free simultaneously. Ice extent changed repeatedly, and much earlier evidence was later eroded, reworked or concealed by the expanding British–Irish Ice Sheet. The deposits instead provide a carefully limited but precious view of one local landscape before a subsequent glacial advance.

## Cold Water, Open Ground

The buried muds contain an assemblage consistent with cold, open tundra-like country. Mosses and sedges grew on wet ground, while plant remains include bogbean (*Menyanthes trifoliata*), an aquatic or marsh plant, and water-milfoil, indicating standing or slow-moving freshwater. Mountain-avens and lesser clubmoss point towards exposed, cold conditions. Insects also suggested a northern, periglacial environment. This was not the wooded Ireland familiar from later prehistory: there is no basis for imagining oak forest, farmland, hedges or settled valleys. It was a severe landscape of shallow water, sedge margins, mineral-rich silt, low vegetation and seasonal freezing.

Yet “tundra” should not be mistaken for empty ground. The Derryvree evidence records a functioning wetland ecosystem. Plants rooted, decayed and became trapped in sediment; insects occupied terrestrial and aquatic niches; water carried fine sand and organic matter through the basin. A nineteenth-century image of a desolate frozen plain would be as misleading as a modern green pastoral view. The available evidence supports a patchwork: wet hollows and pools within broader treeless terrain, subject to intense winter cold and brief growing seasons.

Climate in MIS 3 was unstable on a scale difficult to grasp from a single date. Greenland ice cores record abrupt shifts between colder stadials and relatively milder interstadials. Irish evidence cannot resolve every one of those changes at Derryvree, but the sequence accords with a climate capable of altering ice cover, drainage and vegetation markedly over millennia. At Crag Cave in County Kerry, uranium-thorium dating of stalagmites shows repeated episodes of cave-mineral growth during the last glacial period. Because such growth requires liquid water percolating through the cave, it independently indicates intervals of climatic amelioration, though not modern warmth.

## Animals at Europe’s Western Edge

The broader Irish animal record makes this landscape more tangible, but it must also be handled cautiously. Cave collections, especially from Castlepook Cave near Doneraile in north County Cork, preserve remains attributed to mammoth, reindeer, giant deer, wolf, Arctic fox, lemmings, brown bear and spotted hyaena. The Irish Quaternary Fauna Project showed that a varied mammal fauna reached Ireland at different points between at least about 45,000 and 20,000 years ago. These animals did not necessarily all live together, and a cave assemblage may combine bones accumulated over long spans by predators, water, collapse and excavation.

Re-dating has made this caution more important. Improved pretreatment of bone samples demonstrated that several older radiocarbon determinations from Castlepook were thousands of years too young. The revised work confirms that elements of the south-Irish cave fauna belong in MIS 3, but it also warns against treating an old museum collection as a neatly sealed campsite. At around 30,958 BCE, reindeer, giant deer and cold-adapted smaller mammals are reasonable components of the wider late-Pleistocene world illuminated by Irish evidence; it is not responsible, however, to assert that a particular herd stood at a named place in that year.

The presence of large herbivores and carnivores is significant for the environment rather than for any supposed Irish “kingdom” or population. Reindeer and lemmings favour open, cold habitats. Hyaenas, wolves and bears show that Ireland could support a complex food web during suitable phases of the glacial period. Mammoth and giant deer remains speak to an open-country fauna whose ranges depended on forage, migration and changing access across north-west Europe. Lower sea levels made surrounding coasts very different, but the exact routes by which animals reached Ireland, and whether crossings were continuous, seasonal or episodic, remain matters for reconstruction rather than certainty.

## **The Human Question**

Human presence is the most debated subject. A reindeer femur from Castlepook has been reported as bearing a deep mark interpreted by zoologist Ruth Carden as damage from a sharp stone tool used during butchery. County Cork heritage material presents the find as possible evidence for Palaeolithic hunters in Ireland around 31,000 BCE. If the interpretation is sustained, it would be exceptionally important: it would imply that people reached Ireland much earlier than the securely accepted terminal-Pleistocene evidence from County Clare.

But the claim must not be enlarged beyond the object. The bone comes from an older cave collection, rather than an undisturbed excavation containing a hearth, stone-tool assemblage, shelter floor, butchered refuse and repeated occupation layers. Its radiocarbon age dates the animal’s death within a range, not automatically the making of the surface mark. Nor does one possibly modified bone establish a resident population, a settlement, or continuous occupation. Carnivore action, sediment movement, weathering and old excavation practices all complicate cave taphonomy. The responsible conclusion is that Ireland may have been visited by Upper Palaeolithic people in this broad period, while permanent human occupation at this date remains unproven.

## **No Politics, but Real Connections**

There is no evidence from which to describe political affairs, diplomacy, organised conflict, religion, named languages, formal learning, trade networks or social ranks in Ireland around this date. Those are not omissions in the record waiting to be filled with imagination; they are questions for which the surviving evidence does not yet provide answers. If people did visit, comparisons with Upper Palaeolithic communities elsewhere in north-west Europe suggest small, mobile hunter-gatherer groups using stone technology and exploiting seasonal resources. That is a contextual inference, not a demonstrated description of an Irish community.


Likewise, no Irish settlement, house, grave, shrine, exchanged object or cultivated field can responsibly be assigned to 30,958 BCE. The economy visible in the evidence is ecological: wetland plants growing and dying, herbivores feeding in open country, predators scavenging or hunting, and ice, water and sediment reshaping the ground. The most important regional change was climatic and glacial. During

the following millennia the last Irish ice sheet would expand dramatically, transforming landscapes and destroying or entombing many older traces. Derrynree survived because its short-lived freshwater world was sealed between tills. Its value lies precisely in that accident of preservation: a small archive of life from an Ireland that was cold, open, changeable and only intermittently accessible to the creatures – perhaps including people – moving along Europe’s far western margin.

# Chapter 044 of 100

## 30957 BCE

### BIRM-166's Tundra Horizon<sup>[44]</sup>



The label 30,957 BCE is a modern chronological peg, not a recoverable Irish year. No calendar, written source, named community or datable event allows historians to describe what happened in Ireland in that particular twelve-month interval. At this depth of time, precision comes in broad probability ranges, not anniversaries. The most responsible frame is the later part of Marine Isotope Stage 3 (MIS 3), within the Midlandian, Ireland's last glacial cycle. Evidence from Irish cave deposits and buried sediments shows that parts of the island supported cold-stage life before the Last Glacial Maximum, but it does not provide an annual narrative.

The most revealing environmental archive for this period lies at Derryvree, near Maguiresbridge in County Fermanagh. In 1969, roadworks cut through a drumlin and exposed freshwater silts and fine sands sealed between two thick layers of glacial till. The organic bed, catalogued as BIRM-166, returned a radiocarbon age of 30,500  $\pm$  1,170/–1,030 radiocarbon years BP. Modern calibration translates a radiocarbon determination into a broader calendar-age estimate rather than a single date; one published conversion places the Derryvree deposit around 35.9  $\pm$  1.1 thousand calendar years BP. It is therefore an invaluable guide to an Irish cold-stage landscape, but it cannot be equated exactly with 30,957 BCE.

## A Date Without Annals

It is tempting to turn an ancient date into a conventional historical entry: to ask who ruled, where people lived, or whether a conflict occurred. None of those questions can be answered for Ireland at this point. There is no evidence for states, chiefs, diplomatic relations, permanent settlements, social ranks or named peoples. Nor is there a securely excavated dwelling, hearth, tool-making floor or burial that can be

assigned to this modern calendar year. The absence is meaningful: later glaciation, erosion, changing shorelines and the very small scale of any possible human presence have left an exceptionally fragmentary record.

Radiocarbon science also requires caution. A result expressed in radiocarbon years before present uses AD 1950 as its reference point and reflects past atmospheric carbon levels, not a direct calendar count. Calibration curves such as IntCal20 are necessary because atmospheric radiocarbon varied markedly through the Ice Age. At more than thirty millennia' distance, a date may have a wide calibrated range. Moreover, a date on bone establishes when an animal died, within statistical limits; it does not automatically date a mark on the bone, the entire cave deposit, or a human visit to the site.

## **Wet Ground Beneath the Drumlin**

Derryvree offers the clearest local picture. Before a later glacier overran the site and helped form the drumlin, shallow freshwater conditions allowed silts, fine sand, plant remains and animal traces to accumulate. Pollen was poorly preserved, but the surviving record included herbaceous taxa, while plant macrofossils and mosses indicated a treeless, open landscape. Sedges, grasses, dwarf shrubs and cold-adapted plants belonged to a tundra or muskeg-like mosaic of wet ground, pools and sparsely vegetated drier patches.

This was not the modern, green Ireland of enclosed fields, oak woods and peat bogs. Trees were absent locally or extremely scarce. The tiny quantity of pine and hazel pollen was judged likely to have been reworked from older deposits rather than evidence of nearby woodland. The study's climatic interpretation was severe: a periglacial environment with a short cool summer and very cold winters. Moss beds and aquatic sediments nevertheless show that this was not lifeless frozen desert. Water moved, plants grew during the season, and sheltered wet places supported a specialised flora.

That conclusion applies securely to the Derryvree locality during the formation of its deposit, not automatically to every valley, coast and upland across Ireland at once. Ireland's terrain, proximity to the Atlantic and shifting ice margins made local conditions varied. Still, the Derryvree sequence is important precisely because it demonstrates that at least one part of the island experienced an ice-free interval between glacial advances and preserved a functioning cold-climate ecosystem.

## **Animals at Europe's Edge**

The animal record from southern Irish caves expands the picture. Castlepook Cave, also known as Mammoth Cave, near Doneraile in County Cork is Ireland's richest known assemblage of vertebrate remains from the period leading towards the Last Glacial Maximum. Excavations in the early twentieth century recovered more than 2,000 bones from complex cave deposits. Direct dates on individual specimens span a long interval rather than one occupation. The cave has yielded remains of woolly mammoth, giant deer, reindeer, brown bear and spotted hyena, as well as later cold-adapted animals including lemmings, Arctic fox and wolf.

These finds demonstrate that Ireland was connected, ecologically at least, to the broader north-west European world in which large herbivores and predators moved through open cold-country habitats. They do not prove that all those species shared one valley, season or moment. Cave assemblages mix material introduced by water, carnivores and earlier excavators as well as by animals dying or sheltering underground. Re-dating has shown that several older Irish cave determinations were substantially too young, reinforcing the need to date individual bones and assess each find's context.

Spotted hyenas are especially instructive. Their bones and the character of some deposits indicate that caves could be carnivore places, not simply natural cupboards preserving the debris of human hunters. A cave might have been a den, a refuge, a trap, a water-affected sediment chamber or several of these at different times. The Ice Age landscape was therefore dangerous as well as productive: reindeer and giant deer supplied prey for carnivores, while mammoth remains evoke a much larger ecological network than survives in Ireland today.

## **The Castlepook Human Question**

One reindeer femur from Castlepook has made this era historically significant. The specimen bears a deep linear modification interpreted by zooarchaeologist Ruth Carden as a cut or chopping mark made with a sharp stone tool while the bone was fresh. It has been publicly associated with an age of about 33,000 radiocarbon years BP. If the interpretation and contextual relationship are sustained, it may represent the earliest known trace of human activity in Ireland: not a village or a population, but a brief episode of carcass processing by one or more Upper Palaeolithic people.

The limits are as important as the possibility. Castlepook's principal excavations pre-dated modern recording, systematic sieving, microscopic use-wear analysis and accelerator mass spectrometry. Its deposits have also been disturbed by water and animal activity. A possible stone-tool incision is not the same as a securely stratified tool assemblage, and a dated femur is not evidence for continuous residence. It cannot establish the hunters' language, identities, beliefs, route into Ireland, group size or duration of stay.

Yet even this restrained conclusion changes the scale of the question. Ireland need not have been wholly beyond the reach of Upper Palaeolithic foragers during the wider MIS 3 period. A visit may have been seasonal, opportunistic or tied to movements of game; any such explanation remains interpretation rather than demonstrated fact. There is no basis for describing an Irish hunting society, trade system or ritual life at 30,957 BCE. Nor can art, religion or learning be recovered from a single modified bone.

## **Economy, Settlement and Mobility**

For humans, if present, the only defensible economic inference is immediate use of wild resources, most plausibly animal carcasses. The marked femur may indicate meat removal, dismemberment or marrow-related processing, but even the precise action is uncertain. There is no evidence for farming, herding, pottery, metalworking, exchange networks or permanent buildings. In a treeless periglacial setting, fuel, shelter and transport would have posed major practical problems, but reconstructing solutions from mainland European Upper Palaeolithic communities would be analogy, not direct Irish evidence.

Mobility is easier to infer for animals than for people. Mammals reached Ireland during intervals when sea level, ice extent and coastal geography differed greatly from those of today, although the precise routes and degree of terrestrial connection remain debated. The Irish Sea was not a fixed modern barrier, but neither should it be casually imagined as a simple land bridge. Changing ice margins, relative sea level and exposed shelves created a complex, shifting frontier. Animal bones establish that dispersal occurred; they do not reveal every route or guarantee that people followed it.

## Approaching the Great Ice

The great advance of the British–Irish Ice Sheet lay ahead or was developing unevenly across the wider region. Recent reconstructions show that maximum extent and retreat varied between sectors, with major advance and ice-sheet growth occurring over millennia rather than in one sudden event. By the Last Glacial Maximum, broadly after this MIS 3 interval, ice covered all or almost all of Ireland’s low ground. The till sealing Derryvree’s freshwater bed is physical evidence of that environmental reversal: an inhabitable wet tundra landscape was buried beneath glacier-derived sediment.


Thus the most important development illuminated around this notional year is neither a battle nor a dynasty. It is the fragility of an Irish Ice Age refuge. Derryvree records plants and shallow water between ice advances; Castlepook preserves the bones of a wider cold-steppe fauna and a provocative, still limited hint of people. Together they show an island of changing ecological opportunities on the north-western edge of Europe, before advancing ice erased much of the evidence by which its earliest visitors might otherwise be known.



# Chapter 045 of 100

## 30956 BCE

### Derryvree's Frozen Ledger<sup>[45]</sup>



**30,956 BCE is a modern chronological label, not a date that people then living in Ireland could have named or recorded. No written calendar, settlement sequence or excavated event permits history at the precision of a single year. In archaeological terms, it falls roughly 32,905 calendar years before AD 1950, within the Late Pleistocene and broadly within Marine Isotope Stage 3 (MIS 3), an interval of abrupt climatic fluctuations. The responsible approach is therefore to use evidence with calibrated ranges that overlap this notional year, rather than to invent a ruler, migration, battle or human community for it.**

The clearest Irish evidence relevant to this horizon comes from Derryvree, near Maguiresbridge in County Fermanagh. Roadworks exposed a sequence inside a drumlin: glacial till below, freshwater sands and organic silts in the middle, and a later till above. This is an unusually eloquent geological order. Ice had deposited the lower till; at some later point the place was free of overriding ice long enough for shallow freshwater, sediment and living communities to develop; renewed glaciation then buried the record. Derryvree is not an annual chronicle, but it is a rare archive of an Irish landscape between glacial advances.

## Dating a Deep-Time Landscape

Organic material from the Derryvree freshwater deposits produced a conventional radiocarbon age of 30,500 +1,170/-1,030 radiocarbon years before present. Radiocarbon years are not calendar years: atmospheric carbon-14 has varied through time, and laboratory determinations must be calibrated against independently dated records. Published calibration places the Derryvree material broadly at about 36,900–

31,700 calibrated years BP, approximately 34,950–29,750 BCE. The requested year lies within that broad range. It cannot, however, be attached to a particular season, individual plant, animal movement or phase of use of the water body.

This distinction matters because the last Ice Age was neither a single winter nor a uniform blanket of ice. MIS 3 contained sharp oscillations between colder stadial conditions and relatively milder interstadials. At Derryvree, the organic bed demonstrates local ice-free conditions and freshwater life; it does not prove that every Irish region was simultaneously ice-free, nor that the island's later familiar coastlines and river systems existed in their modern form. Equally, the later Last Glacial Maximum had not yet reached its principal Irish extent. Large-scale British–Irish Ice Sheet growth and maximum conditions lay ahead, though ice margins and upland ice could already have made the wider region highly variable.

## **Water, Mosses and Sedges**

Derryvree's importance lies in the biological detail trapped in its sediments. Freshwater mosses and sedges, together with pollen, plant remains and insects of cold northern character, indicate open, treeless or almost treeless wet ground. Earlier researchers used the term “muskeg” for this waterlogged setting: a mosaic of shallow pools, organic mud, saturated vegetation and frost-affected ground rather than an unbroken snowy waste. Such a landscape could include sedge beds and mossy margins, low herbs and dwarf shrubs, with patches of open water where fine sediment settled.

The fossils support a picture of short growing seasons, severe winters and low vegetation. They do not provide a complete species list for the whole island. Pollen can travel long distances on the wind, be redeposited, or represent vegetation beyond the immediate basin; a local wetland is not a weather station for Ireland. Nevertheless, the combined plant and insect evidence securely shows that one part of Fermanagh sustained a cold freshwater ecosystem during an interval between ice incursions. In environmental terms, this is the most substantial story available for the date: life persisted in sheltered, wet and locally ice-free ground while climate and ice cover changed on larger scales.

## **An Animal Landscape**

Southern Irish caves add a separate, more fragmentary record. Castlepook Cave near Doneraile, County Cork, has produced remains attributed to a Late Pleistocene fauna including reindeer, woolly mammoth, giant deer, brown bear, wolf, Arctic fox, mountain hare, lemmings and spotted hyaena. This assemblage conveys the ecological breadth of open cold-country habitats: grazing and browsing herbivores, smaller prey animals, scavengers and predators. Reindeer are especially compatible with the idea of mobile herds moving through exposed seasonal country, while lemmings and Arctic fox point towards cold conditions.

Yet Castlepook must be handled with care. Many bones were recovered in early excavations from complicated cave deposits, and the cave accumulated material over long spans of time. Improved radiocarbon pretreatment has shown that some fossils are considerably older than earlier determinations implied, but it does not make every specimen contemporary. A dated bone establishes the age of that animal within a range; it does not automatically date every bone nearby, the formation of the cave sediment, or an episode of human activity. Derryvree and Castlepook can therefore be placed in a broadly comparable MIS 3 world without being compressed into one imagined day in the life of Ireland.

## The Human Question

The possibility of people in Ireland at this depth of time is important but unsettled. A reindeer femur from Castlepook has been reported as bearing a mark interpreted as having been made by a sharp stone tool during carcass processing, and it has attracted attention as possible evidence for human activity around 33,000 years ago. If the diagnosis survives continued microscopic, chronological and contextual scrutiny, it would suggest that Upper Palaeolithic people reached Ireland far earlier than the securely dated Late Upper Palaeolithic evidence from Alice and Gwendoline Cave in County Clare, dated to roughly 12,810–12,590 calibrated years BP.

For 30,956 BCE, however, the Castlepook find cannot responsibly be converted into a settled population, a named hunting band or a permanent occupation. No securely associated hearth, stone-tool assemblage, dwelling floor, burial or repeated camp has yet demonstrated such a community in Ireland at this time. The cut-mark interpretation concerns the modification of one bone; the radiocarbon result concerns the animal's age; the excavated context is an older cave collection requiring further testing. At most, the evidence raises the prospect of a brief human visit or butchery episode on the western edge of the wider European Upper Palaeolithic world.

## No Politics, No Monuments

There is no basis for describing political affairs, diplomacy, warfare, law, religious institutions or learning in Ireland at this date. There are no chiefs, territories, alliances or sacred monuments recoverable from the evidence. Nor is there evidence for agriculture, domesticated animals, pottery, metalworking, weaving, writing or long-distance trade. These absences are not minor gaps in an otherwise familiar history: they define the limits of the record. The Ireland illuminated by Derrynvree was tens of millennia before the Mesolithic hunter-gatherer settlements, Neolithic farming communities and monuments normally associated with Irish prehistory.

If people did occasionally reach the island, their social world cannot be reconstructed from Ireland alone. Comparisons with Upper Palaeolithic societies elsewhere in north-west Europe may suggest small, mobile groups able to exploit animal resources and move through dangerous seasonal environments, but comparison is interpretation, not direct Irish evidence. The same caution applies to sea crossings and routes. Lower sea level altered the surrounding shelf, while ice, changing relative sea level and shifting coastlines complicated access. The mere presence of animals in Ireland does not demonstrate a simple, continuously dry land bridge or identify how humans, if present, travelled.

## Regional Change as History


The most meaningful regional history around this point is one of changing habitability. In Fermanagh, sediments between tills record freshwater conditions after an earlier glacial phase and before a later one. In Cork, cave deposits preserve a cold-stage animal record whose chronology has been repeatedly revised. Across the Irish sector of the British–Irish Ice Sheet, researchers continue to debate the timing, extent and behaviour of pre-maximum ice. This is why firm statements must remain local: Derrynvree proves an ice-free wetland at Derrynvree during its dated interval, not a wholly ice-free Ireland.

It is tempting to make prehistoric history depend upon a dramatic first arrival, but the better evidence gives a different emphasis. Derryvree preserves the underlying conditions that made any animal or human movement possible: unfrozen freshwater, vegetation, insects, exposed ground and ecological corridors amid instability. Its silts are a ledger of persistence rather than a record of events. Around 30,956 BCE, Ireland was not yet a political landscape. It was a climatically volatile, sparsely documented environment in which ice, water, plants and animals left the durable traces from which the earliest chapters of Irish history must be written.

# Chapter 046 of 100

## 30955 BCE

### Castlepook's Two Thousand Bones<sup>[46]</sup>



Modern calendar precision cannot be carried back to 30,955 BCE. No written calendar, dated settlement, named individual or identifiable episode allows historians to isolate that single year in Ireland. The number is best treated as a point on a modern chronological scale: roughly 32,900 years before 1950, within the later part of the Pleistocene and broadly within Marine Isotope Stage 3 (MIS 3), a long, climatically unstable phase before the Last Glacial Maximum. What can responsibly be said concerns date ranges, environmental evidence and a small but important body of animal remains, especially from Castlepook Cave near Doneraile in north County Cork.

Ireland at this depth of time was not the familiar island of later history. Sea levels, coastlines, ice margins and connections between Ireland, Britain and continental north-west Europe changed repeatedly as global ice volume rose and fell. The archaeological and geological record is fragmentary, and researchers continue to debate the extent and timing of ice in and around Ireland before the Last Glacial Maximum. Around this broad period, therefore, the safest picture is not of a fixed frozen island but of a northern Atlantic landscape subject to pronounced cold, shifting ice fronts, open habitats and rapid environmental change.

## A Date Without an Event

The most relevant chronological framework is radiocarbon dating, expressed in years before present, where “present” conventionally means 1950. Such dates must be calibrated to produce calendar ranges, and the calibration process does not yield a direct, exact equivalent for an invented-looking BCE year. A bone can date an animal’s death; it cannot automatically date a human action on it, an occupation of a

cave, or a particular season. This distinction is essential at Castlepook, also known as Mammoth Cave, whose deposits were excavated largely in the early twentieth century and whose bones have been moved, mixed and affected by water and carnivore activity.

Nevertheless, Castlepook is exceptional. Geological Survey Ireland describes it as Ireland's richest known site for vertebrate fauna in the period leading towards the Last Glacial Maximum. More than 2,000 surviving bones represent a long span of the Ice Age, while earlier excavation removed vastly more. Direct dates and later re-dating show that the cave archive includes animals from well before, during and after the interval represented by this article. The lesson is not that all its creatures lived together in one moment. Rather, Castlepook offers a time-depth record of repeated animal use of a limestone cave system in an increasingly severe Ice Age world.

## **Cold Country, Changing Ice**

MIS 3, extending broadly from about 57,000 to 29,000 years ago, contained abrupt swings between comparatively milder interstadials and colder stadials. At c. 30,955 BCE, Ireland was approaching, but had not yet reached, the most extensive phase of the last British–Irish Ice Sheet, generally placed after about 26,000 calibrated years ago. This matters because the later ice sheet would scour, bury and rearrange much of the earlier land surface, leaving relatively few places where older soils, plants, campsites or animal tracks could survive.

It would be misleading to draw a sharp national boundary around the evidence. The present Irish Sea was a different, lower-sea-level region, and Ireland's ecological connections depended on changing coastlines and glacial barriers. Some recent research argues for significant ice-sheet activity and high relative sea levels around the Irish and British coasts during MIS 3; other reconstructions stress uncertainty in the evidence before the Last Glacial Maximum. The practical conclusion is cautious: particular districts could have been ice-free, periglacial, seasonally harsh or close to calving ice margins at different times, while conditions changed faster than a single date can express.

Where ground was available, the vegetation was not forest of the later Holocene. The relevant comparison is a mosaic of herb-rich grassland, dwarf-shrub tundra, sparse willow and birch in better intervals, wet ground, exposed mineral soils and rocky shelter. Pollen, plant macrofossils, sediment layers and insect remains elsewhere in Ireland show how sensitive cold-stage landscapes were to moisture, temperature and glacial disturbance. They do not provide a weather report for 30,955 BCE. They do, however, make clear that Ireland possessed habitats capable of supporting large grazing and browsing mammals during parts of the pre-maximum Ice Age.

## **The Animals of Castlepook**

Castlepook's faunal record gives this period its strongest Irish texture. Its Pleistocene assemblage includes woolly mammoth, reindeer, giant deer, brown bear and spotted hyena; later cold-stage material includes lemmings, Arctic fox and wolf. Not every species belongs to precisely the same date range, and their presence in a cave need not mean the cave was their ordinary habitat. Still, the accumulation demonstrates that southern Ireland formed part of a wider north-west European zone through which cold-adapted and open-country animals moved.

Reindeer are especially informative. Their mobility, grazing and browsing habits suited open, seasonal landscapes. Mammoths evoke the productive but treeless grass-and-herb communities often termed mammoth steppe, though that label should not be allowed to erase local variation in wetness, topography

and vegetation. Giant deer, bears and carnivores indicate additional ecological niches. Spotted hyenas are important because caves could function as dens or places to which carnivores dragged prey and scavenged carcasses. A bone in Castlepook may thus record an animal's death outside the cave, the work of a predator, a fall into a fissure, water movement or later disturbance rather than a single local scene.

That taphonomic caution is central to everyday life in this landscape. There is no evidence for farming, domestic animals, permanent villages, fields, pottery, metalworking or managed woodland. The economy visible in the Irish record is ecological rather than human: wild herds exploiting seasonal plant growth, predators following prey, and caves periodically gathering the remains. Any people present would have encountered a dangerous, resource-rich terrain in which animal movement, shelter, fuel and access to stone mattered more than the territorial patterns familiar from later prehistory.

## **The Reindeer Femur Question**

A reindeer femur from Castlepook has made this interval newly significant for Irish archaeology. County Cork heritage material identifies it as a Palaeolithic bone of about 31,000 BCE and reports a deep linear mark interpreted by zooarchaeologist Ruth Carden as damage made by a sharp stone tool during butchery. If that diagnosis and broad chronology withstand continuing scrutiny, it is potential evidence that people processed reindeer in Ireland far earlier than the securely documented terminal-Pleistocene traces from County Clare.

The claim deserves attention, but not embellishment. The mark is evidence for a possible act of carcass processing, not proof of a settlement at Castlepook, a year-round Irish population, or an established migration route. No securely associated hearth, stone-tool assemblage, dwelling surface, burial, food store or repeated butchery floor has yet been recovered for this age in Ireland. The date belongs to the bone, not necessarily to the incision; early cave excavations also left limited contextual documentation. Re-dating work has shown that some older Irish cave radiocarbon determinations can be thousands of years too young when measured by methods now superseded, reinforcing the need to revisit collections rather than treat inherited dates as final.

The most responsible interpretation is consequently modest but consequential. Ireland may have received small, mobile Upper Palaeolithic parties during favourable windows before the Last Glacial Maximum, perhaps linked to wider hunting landscapes extending through Britain and north-west Europe. Such visitors would not yet constitute a demonstrable resident society. Their presence is plausible from the faunal and geographic context, while the Castlepook femur provides a specific, still limited archaeological lead. It should be described as potential early evidence of human activity, not as an established founding moment.

## **No Politics, No Recorded Beliefs**

Political affairs, diplomacy and organised warfare cannot be recovered for Ireland in this period. There were no Irish kingdoms, tribes with recorded names, borders, laws or diplomatic institutions. Likewise, there is no Irish evidence from around this date for formal shrines, burials, art or ritual that could identify beliefs or learning. Projecting Celtic languages, Gaelic society or later ideas of sacred landscape backwards by tens of millennia would be an anachronism.

That silence is evidence in its own right. It marks the gulf between a Pleistocene environment known mainly through geology and animal remains, and the later human histories of Ireland. If visitors did cross into the Irish landscape, their knowledge was practical and social: reading weather and ground conditions,

remembering routes, sharing food, maintaining tools and responding to the movements of animals. Such capacities are reasonable inferences from Upper Palaeolithic lifeways elsewhere, but they are not directly documented as a distinct Irish culture at 30,955 BCE.

## **An Archive Rather Than a Chronicle**


The principal development illuminated by this date is therefore environmental and evidential. Ireland was part of a volatile Ice Age world inhabited, at different times, by mammoths, reindeer, giant deer, bears and formidable carnivores. Castlepook Cave preserves an unusually rich archive of that world, while its marked reindeer femur raises the prospect of a human encounter with it. The cave does not yet give Ireland a securely mapped Palaeolithic community. It gives something more scientifically valuable: a testable question, preserved in bone, sediment and chronology, about how far people and animals ranged across the changing north-western edge of Europe before the great ice advance.



## Chapter 047 of 100

### 30954 BCE

#### The Derryvree Fossil Flora<sup>[47]</sup>



**The label 30,954 BCE is a modern filing device, not a recoverable Irish calendar year. No people in Ireland then recorded years, and no archaeological deposit can be dated to this particular season or generation. In conventional scientific terms, the date falls roughly 32,900 calendar years before AD 1950, within the Late Pleistocene and Marine Isotope Stage 3 (MIS 3), a fluctuating phase of the last Ice Age. The responsible history of Ireland at this depth of time is therefore a history of deposits, calibrated ranges and carefully limited conclusions rather than of named rulers, battles or events.**

The closest evidence is not an annal but a buried wetland at Derryvree, near Maguiresbridge in County Fermanagh. It provides an exceptional, though local, glimpse of an Irish environment broadly relevant to this notional date. Farther south, Castlepook Cave near Doneraile in County Cork preserves a time-mixed collection of animal remains, including animals that crossed into Ireland during different cold-stage episodes. Together these sites show a landscape of open ground, freshwater pools, severe winters and intermittent ecological connections with north-west Europe. They do not provide proof of a settled human population.

### Dating a Landscape, Not an Event

Radiocarbon ages are not identical to calendar ages. Atmospheric carbon-14 has varied through time, so laboratory results must be calibrated against independently dated environmental records. The current IntCal20 Northern Hemisphere curve reaches back to 55,000 calendar years before present, but uncertainty is substantial at this antiquity. A conventional radiocarbon date may consequently translate into a wide calibrated interval rather than a single year.

At Derryvree, road works in 1969 cut through a drumlin and exposed organic silts and fine sands between two thick sheets of glacial till. The lower till was laid down by an earlier ice advance. Then, when ice no longer occupied that locality, water and organic sediment accumulated in a freshwater setting. A later advance deposited the upper till, sealing the older wetland beneath the drumlin. Organic material from the freshwater series produced a radiocarbon determination of 30,500  $\pm$  1,170/–1,030 radiocarbon years BP. Calibration places its broad age within approximately 36,900–31,700 cal BP, a range that includes the modern point conventionally called 30,954 BCE.

That range must be handled honestly. It does not prove that every Derryvree fossil lived in 30,954 BCE, nor does it reveal the exact date at which a pool formed or froze. It does, however, establish that a biologically active, locally ice-free environment existed in south Fermanagh during a cold interval broadly comparable with this one. The sequence is especially valuable because later ice covered, compressed and preserved it.

## Wet Ground Beneath the Drumlin

The Derryvree fossils replace the popular image of an Ice Age Ireland as an unbroken, featureless sheet of snow. Pollen, plant macrofossils, mosses and insect remains indicate open, largely treeless country under periglacial conditions. The vegetation included grasses, sedges, herbs, juniper and cold-tolerant mosses. Fossil finds of bogbean (*Menyanthes trifoliata*), water-milfoil and mountain avens are particularly informative: they point to shallow freshwater, wet margins and nearby open ground rather than dense woodland.

This was probably a patchwork landscape. Low hollows and pools held water during favourable seasons. Mossy and sedgy ground bordered them, while exposed surfaces had sparse cover and poorly developed soils. The insect assemblage supports the interpretation of harsh, northern conditions and a muskeg-like environment: waterlogged, organic-rich ground with open pools and plant material. Winter freezing, strong winds, short growing seasons and frost-disturbed soils would have shaped daily life for every organism in it.

There is an important geographical qualification. Derryvree is evidence for one locality in what is now County Fermanagh, not a complete map of Ireland. Conditions could differ sharply with altitude, distance from ice, coastal exposure and local water supply. The island's position on the edge of the North Atlantic made its climate sensitive to shifts in oceanic and atmospheric circulation. Nevertheless, the Derryvree sequence makes one conclusion secure: parts of Ireland supported freshwater and tundra-like ecosystems before the later expansion of the last Irish Ice Sheet.

## Animals and Changing Connections

Castlepook Cave, near Doneraile in north County Cork, is the principal Irish archive for large mammals from the long interval before and during the approach to the Last Glacial Maximum. Its collections include remains attributed to woolly mammoth, reindeer, giant deer, brown bear, wolf, fox, hare, lemming and spotted hyaena. These species demonstrate that Ireland was, at intervals, part of a wider north-west European ecological zone. Cold-adapted animals reached the island, found usable habitat and sometimes died or were accumulated in caves.

The cave is not a snapshot of one year. Much of its material was recovered in antiquarian excavations, often without the recording standards now expected, and the deposits were affected by water, carnivores and later disturbance. Direct radiocarbon dating has shown that its bones belong to episodes spread across

many millennia. Earlier work dated a mammoth bone and a spotted-hyaena bone to around 33,500 and 34,300 radiocarbon years BP respectively; later reassessment has warned that some older cave-bone determinations require caution because radiocarbon pretreatment methods have improved.

It would therefore be misleading to picture mammoths, giant deer, hyaenas and reindeer all occupying one Cork valley at precisely the same moment. The defensible conclusion is narrower but still striking: southern Ireland repeatedly supported varied Late Pleistocene fauna before the climatic and glacial changes of the Last Glacial Maximum transformed much of the island. Cave assemblages are records of animal movement, carnivore behaviour, death and preservation; they are not population censuses.

Lower global sea levels changed the geography around Ireland. Much of the present sea floor was dry land or shallow coastal plain at different stages of the Ice Age, reducing distances and altering routes between Ireland, Britain and continental Europe. Yet lower sea level did not automatically create a simple, continuous land bridge available at every moment. Relative sea level, ice margins, rivers and local topography also mattered. The arrival of mammals is firm evidence of ecological connection at intervals; the precise routes and timings remain subjects for investigation.

## **The Human Question at Castlepook**

The most consequential human clue near this broad period is a reindeer femur from Castlepook Cave. It has been reported as roughly 33,000 years old and bears a deep mark interpreted by the palaeozoologist Ruth Carden as damage made by a sharp stone tool during butchery. If this interpretation is confirmed, it would represent extraordinarily early evidence that people handled a reindeer in Ireland during the Upper Palaeolithic—far earlier than the securely documented post-glacial settlement record.

But the distinction between evidence and interpretation is decisive. The bone is real, its direct date is important, and the mark warrants serious study. Yet it was not recovered from a recently excavated hearth, occupation floor or sealed living surface. No associated stone-tool assemblage, dwelling, human bone, grave or securely contemporary fire has been found at Castlepook. The cave's deposits contain material from multiple periods, and its excavation history complicates contextual reconstruction. A marked bone can support the possibility of a brief human incursion or carcass processing episode; it cannot demonstrate a permanent community, a camp at the cave or continuous occupation of Ireland.

This uncertainty is unsurprising. Later ice advances eroded landscapes, buried sediments and disturbed or destroyed many places where people might once have stopped. Coastal plains that could have offered routes or hunting grounds are now largely submerged. Absence of known camps is not proof that no person ever entered Ireland, but neither may the gaps be filled with imagined villages, migrations or hunting territories.

## **Society, Belief and Economy: What Cannot Be Claimed**

There is no evidence from Ireland around this date for political institutions, diplomacy, warfare, chiefs, named groups, farming, trade networks, formal religion, art, language or teaching. There are no houses, fields, monuments, graves, pottery, metalwork or written records. It would be anachronistic to invent an Ice Age Irish society with fixed borders or tribal leadership simply because Upper Palaeolithic communities elsewhere in Europe made tools, ornaments and images.

If people did reach Ireland, the most plausible interpretation is of small, mobile hunter-gatherer parties operating in a demanding seasonal landscape, perhaps drawn by animal movements and the resources of open country. That is an inference from the wider European Upper Palaeolithic and from the


possible Castlepook butchery mark, not a demonstrated description of Irish social life. Even a successful hunt would not establish residence. At present, the best-documented inhabitants of Ireland at this horizon remain its plants, insects and mammals.

The principal development was environmental. Derryvree records fresh water, mosses, sedges and herbs in an open periglacial setting; Castlepook records a wider world of large mammals and predators; glacial geology records an island moving towards a major reorganisation of ice, coast and habitat. Around 30,954 BCE, Ireland was not yet a historical community with a year-by-year story. It was a changing Ice Age landscape whose fragile evidence sets both the possibilities and the limits of its earliest human past.

# Chapter 048 of 100

## 30953 BCE

### Greenland Stadial Five<sup>[48]</sup>



The label 30,953 BCE is a modern calendrical convenience, not a date that people in Ireland could have recorded or that archaeology can isolate to a particular year, season or lifetime. In scientific terms, it falls roughly 32,900 calendar years before present, within the Late Pleistocene and Marine Isotope Stage 3 (MIS 3), a long and climatically unstable part of the last Ice Age. The closest responsible account is therefore not a chronicle of events, rulers or settlements, but an assessment of the evidence for Irish landscapes, animals and possible human activity across broad calibrated ranges.

## A Cold Interval, Not a Recorded Year

At this approximate point in time, the Greenland ice-core chronology places the North Atlantic in Greenland Stadial 5, a colder interval between relatively milder interstadials. Greenland Stadial 5 is conventionally bracketed at about 33,600–32,500 years before AD 2000, although its precise boundaries depend on the chronology used. That framework is valuable because Ireland lay on the Atlantic fringe, where climate was strongly shaped by changes in ocean circulation, sea ice and the growth of the British–Irish Ice Sheet. It does not mean that every shift registered in Greenland can be translated directly into a temperature or weather report for Ireland.

Ireland was not uniformly buried beneath ice throughout MIS 3. Its ice cover expanded and contracted over many millennia, while local conditions varied sharply between uplands, lowlands, coasts and sheltered basins. The important long-term development was the mounting environmental pressure that would eventually culminate in far more extensive glaciation during the Last Glacial Maximum, broadly after 30,000 calendar years ago. Around 30,953 BCE, however, the island's history was still one of unstable cold-stage habitats rather than one simple image of an entirely ice-covered land.

## Derryvree's Buried Freshwater Record

The most revealing Irish evidence for this broad phase comes from Derryvree near Maguiresbridge, County Fermanagh. There, a road cutting through a drumlin exposed a remarkable sequence: glacial till, then freshwater silts and fine sands containing organic material, followed by another thick till. The middle deposit was dated conventionally to  $30,500 \pm 1,100$  radiocarbon years BP, laboratory number BIRM-166. This is not identical to 30,953 BCE, and an old radiocarbon measurement cannot be converted into a single exact BCE year. Yet it securely demonstrates an important point: between glacial advances, part of Fermanagh contained open, ice-free freshwater environments during the Middle Midlandian, the regional term used for this part of Ireland's last cold stage.

Plant and sediment evidence from Derryvree indicates a treeless, cold wetland or muskeg landscape. Sedges, mosses, aquatic plants and other cold-tolerant vegetation could exploit shallow water, saturated ground and summer thaw. Such evidence records organisms and habitats, not a picturesque frozen wilderness without life. The water must have remained seasonally available; fine sediment accumulated; plants grew, shed pollen and left identifiable remains. But the setting was open and exposed, not wooded countryside. Long winters, short growing seasons, frost action and strong seasonal contrasts would have placed severe limits on plant cover and animal food supplies.

The Derryvree sequence also explains why caution is essential. The freshwater layer survived because later ice and sediment sealed it between tills. It is a fortunate geological archive, not a complete cross-section of Ireland. It cannot establish that every region was simultaneously ice-free, nor can it tell us that a particular animal drank from a particular pool in 30,953 BCE. Its significance lies in demonstrating environmental possibility: cold, locally habitable wet ground existed in Ireland before renewed and more extensive ice-sheet expansion transformed the landscape again.

## Mammals on an Open Island

Cave collections, especially from Castlepook Cave near Doneraile in north County Cork, add a different kind of evidence. They show that large mammals and carnivores reached Ireland during portions of the Late Pleistocene. Castlepook has produced remains attributed to reindeer, woolly mammoth, giant deer, brown bear, wolf, Arctic fox, hare, lemmings and spotted hyaena. This is an extraordinary assemblage by Irish standards, but it must not be treated as a single herd living together on one day. Cave bones can accumulate through natural deaths, carnivore activity, water movement, collapse and excavation over long periods.

Recent re-dating has changed the chronology of southern Irish cave faunas substantially. Improved bone pretreatment showed that several older radiocarbon determinations had underestimated their true age; some Castlepook specimens proved between roughly 5,000 and 12,000 radiocarbon years older than earlier results suggested. The revised work places important parts of the fauna within MIS 3 and suggests that giant deer and spotted hyaena may have disappeared locally before the Last Glacial Maximum, perhaps around 40,000 calibrated years BP. Consequently, Castlepook illuminates the ecological world that preceded and overlapped the long approach to glacial maximum, but it cannot securely furnish a species list for this one numbered year.

Even so, the evidence supports a broad reconstruction. Open ground, grass- and herb-rich patches, sparse shrub cover, wetlands and exposed mineral soils could support grazing or browsing animals and the predators that followed them. Reindeer were particularly suited to cold, open country; mammoth and giant deer signal a very different Ireland from the later wooded Holocene island. The presence of both

herbivores and large carnivores indicates connected ecological opportunities, not permanent abundance. Animal populations may have moved repeatedly as ice margins, snow cover, vegetation and accessible ground changed.

## **The Castlepook Human Question**

One reindeer femur from Castlepook has made this period unusually important for Irish human history. Re-examination identified a deep mark interpreted by palaeozoologist Ruth Carden as having been made with a sharp stone tool while a fresh carcass was being butchered. Public heritage accounts date the bone broadly to about 33,000 years ago. If the interpretation is confirmed, it would be evidence that one or more Upper Palaeolithic people handled a reindeer in Ireland vastly earlier than the island's long-established post-glacial record.

The qualification matters. The bone was recovered from an older cave collection, not from a modernly excavated occupation floor with an unbroken stratigraphic sequence. A radiocarbon date indicates when the animal lived, not necessarily the precise moment at which a surface mark was made. Nor does one marked limb bone demonstrate that people killed the animal, camped in the cave, resided nearby or returned seasonally. Natural abrasion, trampling, carnivore damage and excavation damage all require careful exclusion when marks on bone are assessed. Renewed work at Castlepook has located stratified Pleistocene deposits, but no securely associated hearth, dwelling, human burial or stone-tool assemblage has yet established a settlement of this age.

The strongest conclusion is correspondingly modest. There may have been a brief episode of human carcass processing in Ireland during MIS 3. A more ambitious story – a named population, a regular reindeer-hunting territory, families living in Cork, or a migration route from Britain – remains interpretation rather than demonstrated fact. Lower sea levels altered the geography of north-west Europe, but the existence, timing and practicality of any land connection between Ireland and Britain remain debated; there is no basis for depicting an assured overland corridor at this date.

## **Society Beyond the Evidence**

No political affairs, diplomacy, warfare, leaders, tribes or territorial boundaries can responsibly be described for Ireland around 30,953 BCE. There is no writing, no human skeleton securely dated to this time, no settlement plan and no material record from which language, kinship, belief or social rank can be recovered. Likewise, there is no evidence for farming, stock-keeping, fields, pottery, metalwork, monuments, formal burial rites, exchange networks or organised trade. These absences are not proof that no person ever crossed the island; they are limits on what the present record can show.

If Castlepook's cut mark is human-made, it implies only the practical knowledge needed to use a sharp lithic edge on a large animal. Meat, hide, sinew, fat and bone would all have been valuable resources to mobile hunter-gatherers elsewhere in Ice Age Europe, but it cannot be shown which were taken in Ireland, by whom, or where they were consumed. European Upper Palaeolithic comparisons may help readers imagine the capabilities of contemporary people, yet they must not be imported as Irish evidence. Ireland has not yielded contemporary art, ornament, tailored clothing, ritual object or structure.

## **An Environmental History in Motion**

The chief Irish development around this notional date was therefore environmental change. Derryvree preserves cold freshwater life between advances of ice. Castlepook preserves a time-depth of mammals suited to open Ice Age landscapes, alongside a provocative but still limited possible human trace. Together they show that Ireland was neither timelessly empty nor securely populated: it was a difficult, changing northern environment in which wetland, open ground, large animals, predators and ice margins repeatedly reshaped the conditions for life.

That is the appropriate scale for 30,953 BCE. Modern calendar precision gives the year an apparent sharpness that the evidence does not possess. Calibrated ranges, buried sediments, dated bones and contested surface marks provide something more valuable than invented certainty: a cautiously recoverable glimpse of Ireland before the Last Glacial Maximum, when the island's later human history was still far in the future.



# Chapter 049 of 100

## 30952 BCE

### Derryvree's Silted Basin<sup>[49]</sup>



The label 30,952 BCE is useful for organising a modern chronology, but it cannot identify a recoverable Irish year. No calendar, written record, named community or datable event survives from Ireland at this depth of time. In archaeological terms, the point falls at approximately 32,900 calibrated years before present, with “present” conventionally fixed at 1950. It belongs to the Late Pleistocene, within Marine Isotope Stage 3, a long and climatically unstable part of the last Ice Age. The responsible history of Ireland at this date must therefore be told through broad calibrated ranges, geological sequences and probabilities, not through imagined annual events.

## A Landscape Between Ice Advances

The closest Irish chronological anchor is Derryvree, near Maguiresbridge in County Fermanagh. There, road works exposed a remarkable sequence buried within a drumlin: glacial till at the base, freshwater sands and organic silts in the middle, and a later till above. The order matters. It proves that ice had occupied the site, that an interval followed in which open water and living communities developed, and that a renewed ice advance subsequently sealed the evidence. The organic deposit produced a radiocarbon determination of about 30,500 radiocarbon years before present, with a substantial laboratory uncertainty. Its calibrated age is generally placed broadly between about 36,900 and 31,700 calibrated years before present. That range encompasses the modern label 30,952 BCE, but does not date every particle of mud, plant remain or insect to that notional year.

Derryvree is consequently a window rather than a photograph. Its freshwater sediments indicate that at least part of Fermanagh was ice-free during a cold phase of MIS 3. The site does not establish that all Ireland was free of ice, nor can it draw a precise island-wide ice margin. Conditions differed between

uplands, coasts, basins and the changing fringes of glaciers. Yet the sediments decisively reject a simple picture of an island continuously entombed beneath ice throughout this period.

The landscape around the basin was harsh but biologically active. Pollen, plant macrofossils, mosses and insect remains point towards open, largely treeless terrain with sedges, grasses, herbs and low-growing shrubs. Wet hollows and shallow pools supported aquatic and waterside vegetation; exposed ground was likely frost-affected, thinly vegetated and vulnerable to wind. Terms such as tundra and muskeg are useful descriptions of this mosaic, provided they are not mistaken for an exact modern ecological equivalent. The evidence supports cold, open and locally waterlogged country, not a uniform plain of permanent snow.

## **Water, Plants and Short Seasons**

For everyday life in the landscape, the strongest evidence is non-human. Derryvree's plants and insects show that summer growing seasons, although short, were sufficient for wetland communities to flourish. Sedges and mosses occupied damp margins; herbs and grasses colonised more open ground; freshwater habitats offered food and shelter for invertebrates. Such environmental detail is historically important because later glaciation erased or buried so much of Ireland's older surface. The organic silts survived largely by chance, protected between deposits left by separate ice advances.

Comparable sites in the north of Ireland, including Hollymount and Greenagho in County Fermanagh, reinforce the wider conclusion that glaciation was episodic. Their dates and correlations are not precise enough to turn them into a simple annual sequence, and scholars have long debated how individual deposits fit into the rapidly shifting climate pattern recorded in Greenland ice cores. Still, they demonstrate that Ireland experienced alternating cold, non-glacial and glacial conditions during MIS 3. Crag Cave in County Kerry adds a different form of evidence: phases of speleothem growth show that liquid water intermittently reached caves during this climatically variable period.

The main development relevant to 30,952 BCE was therefore environmental change. Ireland was approaching the fuller expansion of the last British–Irish Ice Sheet, but had not yet entered its final maximum phase. Large-scale reconstructions place the last maximum advance of the Irish Ice Sheet later, broadly between about 27,000 and 23,000 calibrated years before present. As ice expanded, it would scour bedrock, redistribute enormous quantities of sediment, alter drainage and destroy or conceal many traces of earlier land surfaces. The future drumlin country of Fermanagh was not yet the hedged agricultural landscape now familiar: it was a changing terrain of frost, water, sparse vegetation and encroaching ice.

## **Castlepook's Mixed Fauna**

Southern Ireland supplies a complementary but more complicated record. Castlepook Cave near Doneraile in north County Cork has produced Ireland's richest known assemblage of mammals from before the Last Glacial Maximum. Its collections include remains attributed to reindeer, woolly mammoth, giant deer, brown bear, wolf, fox, hare, lemmings and spotted hyaena. These animals show that Ireland was intermittently part of a wider north-west European ecological world, capable of supporting cold-adapted grazers, predators and scavengers.

They should not, however, be placed together in a single imagined herd at 30,952 BCE. Castlepook was excavated principally in the late nineteenth and early twentieth centuries, before modern standards of stratigraphic recording, and cave deposits can combine material introduced at different times by carnivores, water movement and excavation. The Irish Quaternary Fauna Project demonstrated that the

cave fauna represents more than one phase. More recent radiocarbon work, using improved collagen preparation, has revised several dates substantially older and suggests that some species, notably giant deer and spotted hyaena, disappeared locally before the Last Glacial Maximum. Castlepook records succession and accumulation over millennia, rather than one perfectly preserved Ice Age scene.

Nevertheless, the faunal evidence makes an important point about regional change and connectivity. Reindeer, mammoth and carnivores did reach Ireland at intervals during the Late Pleistocene. Lower global sea levels changed coastlines and exposed wider coastal shelves, but it would be unsafe to claim a permanent, easy land bridge at this particular date. The Irish Sea basin, local ice, shifting sea levels and changing topography made routes variable. Mammal remains demonstrate connection in some form; they do not reveal exactly where every animal crossed, how frequently movements occurred, or whether human travellers followed identical paths.

## **The Reindeer Femur Question**

One Castlepook object gives this period its greatest archaeological significance: a reindeer femur reported as bearing a deep modification made by a sharp stone tool while the bone was fresh. The bone has been presented as dating to roughly 33,000 years ago, broadly close to the interval represented by 30,952 BCE. If the mark is correctly identified as a butchery cut, it may be evidence that one or more Upper Palaeolithic people processed a reindeer in Ireland long before the better-established terminal-Pleistocene human evidence at Alice and Gwendoline Cave, County Clare.

The distinction between evidence and interpretation is crucial. The direct evidence is a dated animal bone with a proposed anthropogenic mark. The interpretation is that people used a stone tool to butcher the carcass. Even if that interpretation is confirmed, it would demonstrate an episode of human activity, not a settled population. No securely associated hearth, stone-tool assemblage, dwelling floor, burial, human remains or repeated occupation sequence of comparable age has yet been published from Castlepook. Nor can the bone tell us whether hunters killed the animal, processed it beside the cave, visited once or returned repeatedly. Carnivores may have moved discarded remains into the cave after butchery elsewhere.

A brief visit by mobile hunter-gatherers exploiting reindeer is a plausible hypothesis, especially given the wider Upper Palaeolithic world of north-west Europe. It is not proof of a permanent Irish community, a named archaeological culture, language, ancestry or migration route. Later ice-sheet activity provides one reason why traces of temporary camps may be scarce, but loss of evidence cannot be used to invent what has not been found.

## **What Cannot Be Recovered**

There is no basis for reconstructing political affairs, diplomacy, warfare, territorial rule or formal institutions in Ireland at this date. Equally, there is no Irish evidence for farming, domestic livestock, cereal cultivation, permanent villages, long-distance trade networks, metalworking, ritual monuments, art, writing or systems of formal learning. If people briefly entered the island, they certainly possessed social relationships, practical knowledge and beliefs; all humans do. But the Irish record at 30,952 BCE does not allow those things to be described responsibly.

The economy visible in the evidence is ecological rather than societal. Wetlands produced plant and insect communities; open ground could support grazing mammals; caves served, at least at times, as carnivore dens and traps for bone preservation. Reindeer and other animals were part of a mobile food


web, not demonstrably the stock of a human hunting economy in Ireland. The possible Castlepook cut mark offers a tantalising exception, but it is too slight to support a wider narrative of trade, leadership or regular seasonal settlement.

Ireland around this point in deep time was thus neither an empty stage nor a known human homeland. Derryvree preserves a cold freshwater world between glacial episodes. Castlepook preserves scattered evidence of Ice Age animals, accumulated across a much longer span, and perhaps a single human encounter with a reindeer. Together they reveal a shifting western edge of Pleistocene Europe: locally ice-free, wet in hollows, open to cold winds, inhabited by animals, and increasingly vulnerable to the advance of ice that would transform the island's landscapes and obscure much of their earlier history.

# Chapter 050 of 100

## 30951 BCE

### Birm-166 Freshwater Find<sup>[50]</sup>



**“30,951 BCE” is a modern label, not a year that could have been recognised in Ireland at the time. There were no written calendars, named rulers, states or chronicles from which a year-by-year narrative might be recovered. In the archaeological convention that counts backwards from AD 1950, the label corresponds to roughly 32,900 years before present. That places it in the Late Pleistocene, broadly within Marine Isotope Stage 3 (MIS 3), a long and climatically unstable part of the last Ice Age. Modern calendar-year precision is not available: the responsible evidence is a set of broad, calibrated ranges, not an event dated to a particular season or generation.**

## **A Date Within a Range**

The closest important Irish chronological anchor is a freshwater deposit exposed at Derryvree, near Maguiresbridge in County Fermanagh. Road works in 1969 cut through a drumlin and revealed silts and fine sands trapped between two separate sheets of glacial till. Organic material in this deposit produced the conventional radiocarbon measurement Birm-166: 30,500 radiocarbon years BP, with a substantial published uncertainty. A radiocarbon measurement is not the same thing as a calendar age. Calibration against changing atmospheric carbon levels places the deposit broadly in a range of approximately 36,900–31,700 calibrated years BP. The notional date of 30,951 BCE falls within that wide interval.

That is valuable, but it must not be exaggerated. The range does not show that conditions on one modern calendar date were known, or that every part of Ireland shared Derryvree’s landscape. It records an episode of freshwater sedimentation and life between glacial advances in one locality. The numerical year is therefore best treated as a doorway into a prehistoric environmental horizon, rather than as a date on which an Irish political, military or cultural event occurred.

## Water Beneath the Drumlin

Derryvree is exceptional because the later ice preserved a small archive of an earlier cold landscape beneath the drumlin. Pollen, plant macrofossils, mosses, insect remains and freshwater sediments point to a treeless, periglacial wetland. The vegetation was not a familiar Irish woodland. It included grasses, sedges and herbs, with plants suited to cold, open ground and wet hollows; mosses, bogbean, water-milfoil, mountain-avens, dwarf willow and juniper feature among the remains reported from the sequence. Some pollen was poorly preserved, and individual plant occurrences require cautious reading, but the combined evidence strongly supports open tundra-like vegetation around shallow water and saturated ground.

This was a landscape shaped by frost, meltwater and short growing seasons. A modern visitor would not have found peat bogs, oak woods or enclosed green fields. Instead, there were likely pools, muddy margins, sedge beds and sparse vegetation across exposed ground. Such a setting could support insects, waterfowl, small mammals and grazing animals, yet it was environmentally demanding. The phrase sometimes used by researchers, “muskeg”, conveys the mixture of wet, organic-rich ground and harsh cold conditions, though no modern northern landscape is an exact replica of Pleistocene Fermanagh.

The evidence also has a larger geological meaning. Freshwater deposits lying between tills demonstrate that ice did not simply cover Ireland in one unbroken, uniform episode. There were intervals in which ice margins retreated or conditions locally permitted open ground and standing water before renewed glaciation buried the evidence. At around 32,900 years ago, the British–Irish Ice Sheet had not yet reached its better-established Last Glacial Maximum extent. Its later expansion, broadly between about 27,000 and 23,000 calibrated years BP, covered Ireland and much of its continental shelf. Derryvree preserves a fragile glimpse of an earlier, changeable phase before that maximum.

## Animals in the Southern Caves

County Cork provides a second, very different line of evidence. Castlepook Cave, near Doneraile in the Awbeg valley, has yielded remains of Ice Age animals from antiquarian excavations and more recent investigation. The wider assemblage includes cold-stage species such as reindeer, brown bear, fox, hare, lemmings and spotted hyaena, alongside remains attributed to larger mammals including mammoth and giant deer. Revised accelerator radiocarbon dating has shown that some southern Irish faunal remains belong to MIS 3, while other specimens and deposits have different ages. Ireland was therefore not a sterile or permanently ice-bound place throughout this earlier portion of the last glacial cycle.

Nevertheless, a cave collection is not a photograph of a single ecosystem. Carnivores can drag prey into caves; water and sediment can move bones; early excavators did not always record layers to modern standards; and bones recovered together may have accumulated over many thousands of years. It would be wrong to picture all Castlepook species standing together in the Awbeg valley in 30,951 BCE. The assemblage establishes repeated animal presence over a long period, not one precisely dated local fauna.

Reindeer matter especially because one Castlepook femur has a deep linear mark that has been interpreted as damage made on fresh bone by a sharp stone edge. The bone has been redated to roughly 33,000 years ago. If that interpretation is upheld, it may indicate that people butchered a reindeer in Ireland during MIS 3, vastly earlier than the previously secure evidence for human activity on the island. But the wording matters: it is a potentially human modification, not a settled conclusion. The bone does not identify who made the mark, where they lived, what language they spoke or whether they returned.

## People: A Possibility, Not a Population

There is no securely dated house, hearth, stone-tool assemblage, burial or occupation surface in Ireland from this horizon. Excavations at Castlepook have sought undisturbed deposits and unequivocal cultural material, but have not yet produced a stone or bone tool that can certainly be assigned to a human presence of this age. The proper historical conclusion is therefore restrained. Ireland may have been visited intermittently by Upper Palaeolithic hunter-gatherers; it cannot presently be described as having had a known resident human population in 30,951 BCE.

If people did reach the island, they would have required intimate practical knowledge of cold weather, animal movement, shelter and food. A reindeer carcass, if processed by people, would have offered meat, marrow, hide, sinew and bone. Yet this is an inference from the potential cut mark and wider knowledge of hunter-gatherer economies elsewhere in Europe, not direct evidence for an Irish camp or trading system. No exchange networks, imported materials, boats, tents, clothing or tools can responsibly be assigned to Ireland at this point.

Lower global sea levels altered the geography of the Irish Sea basin, but low water alone does not demonstrate a land route that people or herds could simply walk across. Ice extent, local relative sea level, coastlines and seasonal hazards changed over time. Research on Irish insularity has repeatedly warned against treating a supposed land bridge as an uncomplicated fact. Whether animals and possible people arrived via short water crossings, exposed coastal terrain, temporary island chains or other routes remains unresolved for this date.

## No Politics, No Known Creed

Political affairs, diplomacy and warfare leave no identifiable trace in the evidence for this period. There is no basis for naming a community, territory, leader, alliance or conflict. Equally, there is no Irish cave art, portable art, shrine, grave or ritual deposit securely belonging to the Derryvree–Castlepook horizon. Religion, language, kinship and learning are not absent because prehistoric people necessarily lacked them; they are absent from the surviving Irish record. To invent them would substitute modern expectation for evidence.

The strongest cultural lesson is instead methodological. Ireland's deep past is recovered from a road cutting, cave bones, laboratory dating, pollen grains and microscopic plant remains. Birm-166 does not tell a story of kings or monuments. It records water, vegetation and cold in an interval later hidden by ice. Castlepook broadens that picture with animals adapted to open, severe conditions and with a single, consequential but disputed clue to human activity. Together they show an Ireland that was environmentally active, geographically variable and vulnerable to rapid climatic change, while remaining almost silent about individual lives.

## An Ice-Age Threshold

The importance of 30,951 BCE lies not in a documented event but in its position near an environmental threshold. The Derryvree wetland demonstrates that parts of Ireland supported freshwater habitats and tundra vegetation during MIS 3. The southern cave faunas demonstrate that large and small mammals reached the island during the wider period. Subsequent growth of the British–Irish Ice Sheet would scour, bury and fragment many earlier landscapes, helping to explain why the record is so sparse. What survives is enough to reject an empty Ireland, but not enough to write a conventional national


history. Around this notional year, Ireland is best understood as a cold, open, intermittently habitable edge of north-west Europe, known through deposits rather than dates and through probabilities rather than certainties.



## Chapter 051 of 100

### 30950 BCE

#### Derryvree's Coldwater Silt<sup>[51]</sup>



30,950 BCE is a modern chronological label, not a date that can be recovered from Ireland's archaeological record with calendar-year precision. No written calendar, named community, political event or excavated settlement can be assigned to this particular year. In simple chronological terms it falls about 32,900 years before AD 1950, the conventional "present" used in archaeological dating. The responsible setting is the later part of the Late Pleistocene, within Marine Isotope Stage 3 (MIS 3), a long and climatically volatile interval before the fullest growth of the last British–Irish Ice Sheet.

For Ireland, the closest useful evidence is not a village or monument but a buried wetland at Derryvree near Maguiresbridge, County Fermanagh. Organic silt and fine sand, sealed between two separate glacial tills, produced a conventional radiocarbon determination of 30,500  $\pm$  1,170/–1,030 years BP. Published calibrations place this broadly at roughly 36,900–31,700 calibrated years BP. The modern label 30,950 BCE therefore falls within that wide range, but it does not identify a single season, generation or event at Derryvree. It allows the deposit to illuminate the environmental world of this broad period.

### A Wetland Between Glaciers

Derryvree is important precisely because it preserves a pause between advances of ice. Beneath later glacial deposits, its freshwater sediments retain pollen, plant macrofossils and insect remains. These are direct traces of organisms that lived in or close to the water, while the enclosing tills show that glaciers occupied the district before and after the wetland formed. The evidence indicates local ice-free ground, liquid water and a cold periglacial environment; it does not prove that every part of Ireland was simultaneously ice-free or environmentally identical.

The plant record points to treeless, open country. Mosses, sedges and other herbaceous taxa suggest damp ground, pools and fen-like surfaces rather than woodland. The assemblage included cold-adapted plants such as dwarf willow, mountain-avens, lesser clubmoss and bogbean or water-clover. Some plants grew in or beside water, others on wet margins or exposed mineral soils. Insect evidence similarly has a northern, cold-climate character. Together, the proxies support an interpretation of tundra or muskeg: a patchwork of shallow water, sedgy marsh, mossy ground and sparse vegetation, subject to frost and short growing seasons.

This was not a featureless wasteland. Summer light, meltwater and wetland vegetation could make such places biologically productive on a local scale. Yet the scene would have been severe by modern Irish standards. There is no evidence of the dense oak, elm, hazel or ash woods of later millennia. Nor is there evidence for fields, grazing livestock, managed burning or cultivation. The Derryvree sequence is an ecological archive, not proof of a settled landscape.

## **Animals in an Open Landscape**

Caves in southern Ireland, particularly Castlepook Cave near Doneraile in County Cork, provide a second kind of evidence. Their mixed deposits have yielded a remarkable Late Pleistocene fauna, including woolly mammoth, reindeer, giant deer, horse, brown bear, Arctic fox, mountain hare, lemmings and large carnivores such as spotted hyaena. The collections were excavated mainly in the late nineteenth and early twentieth centuries, often before modern recording standards. Bone accumulations may reflect animals dying in caves, carnivore activity, water movement and disturbed excavation deposits. They cannot be treated as a single, neatly contemporary herd list.

Even so, revised radiocarbon work has shown that important elements of the Castlepook fauna are substantially older than some earlier measurements suggested and belong to MIS 3, before the Last Glacial Maximum. Reindeer, mammoth and hyaena fit an open, cold and varied landscape rather than a forested island. Their presence demonstrates that, during portions of this long interval, Ireland was part of a north-west European world in which large mammals and predators could reach and survive in suitable habitats. It does not demonstrate that all these species occupied one valley at once, or that they were present everywhere on the island in 30,950 BCE.

The environmental picture is therefore one of regional contrast and continual change. Derryvree supplies a northern freshwater locality; Castlepook supplies a southern cave archive. Between them lies a large geographical and chronological gap. Their combined value is to show the range of conditions and animals that could occur in Ireland before the ice sheet reached its later maximum, not to create a detailed map for a particular year.

## **Ice, Land and Changing Routes**

At this time the British–Irish Ice Sheet was not yet at its better-documented Last Glacial Maximum extent. Research on the ice sheet places major expansion and its maximum phases later, chiefly after about 31,000 years ago and into MIS 2. Derryvree’s organic layer, protected beneath a later till, is one of the clues that parts of north-central Ireland remained ice-free during an earlier cold interval. Subsequent glacial growth repeatedly transformed the terrain, eroding deposits and covering much of the evidence that earlier people or animals might have left.

Global sea level was lower than today because much water was held in continental ice sheets, but this must not be simplified into a certain land bridge or an easy walking route to Ireland. Coastlines, ice margins, rivers and channels changed over long periods, and the exact practical routes available to animals or people varied with climate and geography. The evidence supports connection and movement within a changing north-west European borderland; it does not establish a permanent road from Ireland to Britain or the continent.

## **The Reindeer Femur Question**

Castlepook also raises the most tantalising human question for this period. A reindeer femur from the cave has been publicly reported as bearing a deep mark interpreted as a fresh-bone cut or chop made by a sharp stone tool. The bone has been presented as about 33,000 years old, broadly close to the chronological horizon considered here. If microscopic and taphonomic assessment ultimately confirms that the mark was made by a person while the bone was fresh, it would be evidence that a human visitor processed a reindeer in Ireland during the Upper Palaeolithic.

That is a significant possibility, not an established account of Irish settlement. The specimen comes from an old and complex cave collection, not a sealed occupation floor. Its radiocarbon date concerns the death of the animal, rather than automatically dating the mark, the place of killing or the duration of any human visit. No securely associated hearth, stone-tool assemblage, dwelling, burial, food store or repeatedly occupied camp of comparable antiquity has been published from Castlepook. A single modified bone cannot tell us whether people hunted locally, scavenged a carcass, arrived in a small party, stayed briefly or returned.

The contrast with the better-supported terminal Pleistocene evidence is instructive. At Alice and Gwendoline Cave in County Clare, a butchered brown-bear bone has yielded two closely agreeing calibrated ranges around 12,800–12,590 cal BP, many millennia later than this article's horizon. That find is evidence of human action, but it too does not make a cave itself a permanent home. For 30,950 BCE, the Castlepook femur should remain a proposed early trace, open to further testing rather than a foundation for confident narratives about an Ice Age Irish population.

## **What Cannot Be Reconstructed**

There is no responsible evidence for political authority, chiefs, kingdoms, diplomacy, warfare or territorial boundaries in Ireland at this point. Nor can archaeologists identify a language, personal name, religious rite, artistic tradition, school of learning or formal trade network. If people were present, they would have belonged to mobile foraging societies comparable in broad economic principle to Upper Palaeolithic groups elsewhere in Europe: reliant on knowledge of seasonal animals, weather, materials and routes. But that comparison is an interpretative framework, not direct proof of a camp, community or technology in Ireland.

Accordingly, everyday life remains mostly beyond recovery. No Irish hearth can be placed securely in 30,950 BCE; no dwelling tells us how people sheltered; no tool assemblage records work, hunting or ornament. There is equally no evidence for farming, domesticated animals, pottery, metal, long-distance commerce or seafaring. What can be said is narrower but consequential: freshwater wetlands existed in at least one northern locality; cold-adapted vegetation occupied open ground; large mammals and predators moved through parts of the island during MIS 3; and advancing ice would later erase or bury many traces of that world.

The central development around this notional year was environmental rather than political. Ireland was a shifting cold-stage landscape, capable at intervals of sustaining wetlands and a diverse Pleistocene fauna, but increasingly constrained by climatic deterioration and expanding ice. Derryvree's silts and Castlepook's bones are fragments of that history. They offer a valuable, evidence-based glimpse of an Ireland long before recorded history, while firmly marking the limits of what the surviving record can bear.

# Chapter 052 of 100

## 30949 BCE

### Mosses, Tills and Reindeer <sup>[52]</sup>



30,949 BCE is a modern numerical label, not a date that can be recovered with calendar-year precision from Irish evidence. It falls roughly 32,900 years before AD 1950, within the later Pleistocene and Marine Isotope Stage 3 (MIS 3), a prolonged but highly unstable phase of the last Ice Age. No written record, settlement sequence, ruler, battle or ceremonial event can be assigned to this particular year. Ireland's history at this depth in time is reconstructed instead from layers of mud and till, pollen and moss fragments, insect remains, animal bones, cave sediments and the changing results of radiocarbon dating.

The most responsible account is therefore one of ranges rather than anniversaries. The closest dated Irish environmental archive, at Derryvree near Maguiresbridge in County Fermanagh, belongs broadly to this part of the Late Pleistocene. Its conventional radiocarbon result of 30,500  $\pm$  1,170/–1,030 radiocarbon years BP calibrates to a wide interval, commonly placed at approximately 36,900–31,700 calibrated years BP. The modern label 30,949 BCE sits within that broad range; it does not identify a particular day, season or episode in the deposit.

## A Freshwater Interval at Derryvree

Derryvree provides the clearest direct evidence for conditions in part of Ireland around this remote period. Roadworks in 1969 cut through a drumlin, exposing an unusual sequence. A lower sheet of glacial till lay beneath silts and fine sands deposited in freshwater, while another thick till sheet sealed the organic sediments above. Till is the unsorted mixture of clay, stones and debris laid down directly by ice. The sequence demonstrates, at minimum, that glacier ice affected the district before the freshwater beds formed and returned afterwards.

Between those ice advances, however, this part of Fermanagh was not buried beneath an ice sheet. Water collected in a shallow basin or wetland, fine sediment accumulated, and plants and small animals left traces capable of preservation. This is important negative evidence as much as positive evidence: it disproves any simple picture of Ireland as continuously and uniformly ice-covered throughout the later Ice Age. It does not, however, furnish an island-wide map. A waterlogged hollow near Maguiresbridge recorded its own local conditions, shaped by drainage, shelter, seasonality and sediment supply. Other regions may have differed greatly in altitude, exposure, ice cover and access to the sea.

The Derryvree layers are also a lesson in archaeological timekeeping. Radiocarbon years are not identical to calendar years because the concentration of carbon-14 in the atmosphere has changed. Results must be calibrated, and the further back in time one goes, the broader and more contingent the calendar ranges become. Later ice furthermore eroded or buried much of the older land surface. Consequently, even a well-known deposit cannot be made to speak for one named year in the way a medieval annal might.

## **Wet Tundra, Not Woodland**

The biological evidence from Derryvree points to a cold, open and largely treeless environment. Herb pollen, plant macrofossils, mosses and insect remains indicate tundra or muskeg: waterlogged ground, sedges and grasses, low-growing herbs, moss-rich margins and shallow pools. Some plants had northern or alpine affinities. Seasonal thaw was plainly sufficient to maintain fresh water and wet ground, but the broader climate was periglacial, with long severe winters and short growing seasons.

This was no empty white wilderness. The freshwater deposit preserves a living ecological mosaic: standing or slowly moving water, muddy margins, damp vegetation and exposed ground beyond. Yet it was not a forested Irish landscape, and there is no evidence for agricultural clearances, fields, livestock, cereal cultivation or permanent villages. Occasional pollen grains from trees do not overturn that conclusion; such grains can travel long distances or be reworked from older deposits. The local evidence overwhelmingly favours sparse, low vegetation.

In everyday ecological terms, plants had to exploit a brief summer, animals had to find food across a fragmented terrain, and freeze-thaw processes continually disturbed soils and slopes. Rivers and lakes were likely seasonally variable, while snow cover, frozen ground and meltwater governed movement. These processes, more than human engineering, were then remaking the routes, basins and surfaces from which later Irish landscapes would develop.

## **Castlepook and the Faunal Record**

In southern Ireland, Castlepook Cave near Doneraile, County Cork, is another major source of evidence, although of a different kind. Cave deposits and collections from older excavations have yielded remains attributed to animals including reindeer, giant deer, mammoth and spotted hyaena. Such finds establish that Ireland was reached by a varied cold-stage fauna during parts of MIS 3. They also suggest food chains in which large herbivores, scavengers and predators used open country and caves.

But the cave fauna must not be compressed into a single imagined herd wandering past the entrance in 30,949 BCE. A cave collection can accumulate over many millennia. Carnivores may carry bones into a den; water, disturbance and nineteenth- or early twentieth-century excavation can mix materials; and individual bones can receive revised dates when laboratories apply improved methods. Re-dating

published in 2020 showed that several Castlepook and other southern Irish cave determinations were substantially older than earlier results had indicated. The secure conclusion is a long and complex animal history, not a single frozen scene.

Reindeer are particularly evocative because they suit an open, cold landscape and are central to the question of human activity. Their presence demonstrates neither annual migration on a known route nor a stable resident herd in every part of Ireland. Mammoth and giant deer similarly show that large mammals could reach or inhabit suitable Irish environments, but their remains cannot tell us how numerous they were at one time, nor whether they occupied every county simultaneously.

## **The Reindeer Femur Question**

A reindeer femur from Castlepook has made this period exceptionally important for Irish prehistory. Zooarchaeologist Ruth Carden has interpreted a deep mark on the bone as a cut or chop made by a sharp stone tool during carcass processing. County Cork heritage material places the object at about 31,000 BC. If that reading of the modification is sustained, it may be evidence that people handled a reindeer in Ireland during the Upper Palaeolithic, far earlier than the well-established post-glacial settlement record.

The qualification matters. One marked bone is not a camp. Ireland has not produced a securely associated stone-tool assemblage, hearth, dwelling floor, burial, human bone, repeated butchery area or durable settlement of comparable antiquity. The femur cannot reveal whether people killed the animal, found it dead, removed meat or sinew elsewhere, or left the limb where carnivores later carried it into the cave. Nor can it establish the size, identity, language, kinship or duration of any visiting group. The National Museum of Ireland accordingly continues to stress that clear evidence for human presence in Palaeolithic Ireland has not yet emerged.

The prudent interpretation is that the femur presents a significant, debated indication of possible human butchery, not proof of an established Irish population. It is evidence for an action if the mark is anthropogenic; settlement, seasonal return and social organisation remain inferences that the present record cannot securely support.

## **No Politics, but a Changing Geography**

There were no demonstrable Irish kingdoms, diplomatic communities, borders or political institutions at this date. There is likewise no recoverable religion, art tradition, language, system of learning or trade network specific to Ireland around 30,949 BCE. If people did make brief visits, they would have belonged to wider Upper Palaeolithic worlds known elsewhere in Europe, but importing those societies wholesale into Ireland would exceed the evidence.

What can be said is that geography and climate created the setting in which animal and perhaps human movement occurred. Global sea level was lower during the glacial period, while ice sheets and changing coastlines altered the shape of the Irish Sea region. This did not automatically create one simple, permanently usable land bridge between Ireland and Britain: ice, water, sea ice, changing channels and local topography all mattered. Routes could open, close or become hazardous over long intervals. The evidence supports connectivity as a problem to investigate, rather than a fixed corridor to assume.

The period also preceded the later Last Glacial Maximum, when the British–Irish Ice Sheet reached its greatest Late Pleistocene extent. Current syntheses place widespread maximum ice expansion broadly between about 27,000 and 23,000 calibrated years BP, after the interval represented at Derryvree. The

approaching growth and reorganisation of ice would transform drainage, scour older deposits and leave the patchy survival record on which modern reconstruction depends.

## **An Environmental History Before History**

The defining development for Ireland around this notional year was therefore neither a named human event nor a political turning point. It was the existence, in at least some places, of cold but viable ice-age habitats: freshwater pools in Fermanagh, open vegetated ground, large herbivores and carnivores in the wider landscape, and landscapes subject to abrupt climatic and glacial change. Derryvree gives direct local evidence for that world; Castlepook gives a powerful but chronologically complicated faunal archive; the marked reindeer femur raises a potentially transformative question about people.

These sources make Ireland's deep past vivid precisely because they require restraint. Mosses, silts, a reindeer bone and glacial debris do not furnish a yearly chronicle. They instead record a landscape in motion, inhabited certainly by plants and animals, and perhaps touched by people, shortly before later ice-sheet expansion concealed or destroyed much of the evidence. That is the most defensible history available for 30,949 BCE.



# Chapter 053 of 100

## 30948 BCE

### Castlepook Reindeer Horizon<sup>[53]</sup>



30,948 BCE is a useful modern label, not a date at which an event in Ireland can be placed. No written calendar, settlement sequence or annually resolved archaeological record allows historians to describe this particular year. In scientific terms it falls about 32,897 years before AD 1950, within the Late Pleistocene, Marine Isotope Stage 3 (MIS 3), during the last glacial cycle. At this depth in time, even radiocarbon results must be calibrated into broad probability ranges; they cannot supply a dependable Irish history for a single year. The responsible account is therefore one of landscapes, animal remains, sediments and the limited possibility of human activity across an interval around the early-to-mid 30,000s calibrated years before present.

## A Date Without a Diary

Modern calendar precision is especially misleading here. Radiocarbon years are not calendar years, and a measurement from a bone dates the death of that animal, not necessarily the formation of a deposit, the arrival of a predator, or a human encounter. Calibration curves such as IntCal20 extend back to 55,000 calibrated years before present, but uncertainties increase greatly in this period. A conventional radiocarbon determination from organic deposits at Derryvree, near Maguiresbridge in County Fermanagh, of roughly 30,500 radiocarbon years BP, with an error of more than a millennium, is informative precisely because it belongs to a broad interval rather than a pinpoint.

The same caution applies to the famous Pleistocene fauna of Castlepook Cave near Doneraile, County Cork. Some of its bones have yielded Middle Midlandian, or MIS 3, dates, while recent redating has shown that parts of the southern Irish cave fauna are substantially older than formerly believed.

Castlepook was excavated largely in the early twentieth century, before modern recovery and recording standards. Its bone-bearing sediments were formed through more than one process and at more than one time. They are a remarkable archive, but not a sealed snapshot of one season or one community.

## **An Unstable Ice-Age Ireland**

Ireland around this broad horizon was in neither a simple 'Ice Age' uniformity nor the later Last Glacial Maximum. The climate of the North Atlantic shifted abruptly between colder stadials and relatively milder interstadials, recorded particularly clearly in Greenland ice cores. Such shifts could occur over decades in Greenland records, although their local effects in Ireland varied with ocean circulation, latitude, relief and the changing extent of ice. It is safer to describe Ireland as cold, open and environmentally unstable than to assign a precise temperature or snowfall total to 30,948 BCE.

The British-Irish Ice Sheet was developing on a long and regionally varied timescale. Later, during the maximum phase roughly between 27,000 and 21,000 years ago, ice profoundly reshaped much of the island and its surrounding shelf. At the date considered here, however, researchers continue to debate the extent, timing and behaviour of earlier ice advances. Some land lay ice-free at least intermittently; other areas may have been affected by expanding local or regional ice. Subsequent glaciation also erased, buried or reworked many deposits that might otherwise preserve campsites, trackways and shorelines.

Sea level was lower than it is today, but that fact should not be converted into an easy map of a walkable Ireland. The Irish Sea basin, changing ice margins and exposed shelves created a complicated geography. Any people or animals reaching Ireland may have crossed landscapes now submerged, moved along temporary coastal corridors, or negotiated water and ice barriers. The evidence does not identify a route. Nor can it establish whether Ireland was occupied continuously, visited occasionally, or empty of people for long stretches.

## **Wet Ground at Derryvree**

Derryvree offers a different kind of evidence. There, organic silts and fine-grained freshwater sediments were discovered between two tills beneath a drumlin. Till is the unsorted debris left by moving glacier ice; the deposits trapped between tills demonstrate that an interval of open water, wet ground and vegetation occurred between glacial episodes. Fossil plant remains include cold-tolerant taxa such as dwarf willow, mountain avens, sedges, mosses and bogbean. Water-milfoil points to freshwater conditions. Together these remains indicate a treeless or very sparsely wooded tundra-like wetland mosaic, not the familiar green, enclosed Ireland of recent centuries.

That inference has limits. Derryvree was a local basin in Fermanagh, not a weather station for the entire island. Plant macrofossils and pollen show what grew in and around a particular sedimentary environment; they do not map every valley, coast or upland. Nevertheless, they establish something important: parts of Ireland could support freshwater ecosystems during MIS 3. There were pools, saturated soils, sedge-rich margins and patches of low vegetation capable of sustaining insects, small mammals and larger herbivores. In a glacial world, such places would have been ecological refuges, though 'refuge' should not be mistaken for warmth or ease.

## The Castlepook Fauna

The strongest Irish evidence for the wider animal world comes from Castlepook and a small number of other southern caves. The Castlepook assemblage includes reindeer, woolly mammoth, giant deer, brown bear, wolf, fox, Arctic fox, hare, lemmings and spotted hyaena, although not all specimens need be contemporary. This is not a roll-call for one mythical Irish ‘mammoth-steppe’ scene. It is a time-averaged collection accumulated under changing climatic conditions, and cave deposits can be affected by carnivores, water, collapse, later disturbance and antiquarian excavation.

Even so, the fauna establishes that Ireland was connected, at least intermittently, to wider north-west European ecological networks. Reindeer and lemmings fit cold, open conditions; mammoth and giant deer evoke extensive grazing landscapes; hyaenas, wolves and bears show that large carnivores also used the country. Caves were not necessarily peaceful shelters. They could be dens, scavenging places, traps for animals or repositories into which bones were washed and dragged. A bone in a cave therefore does not automatically mean that its owner lived nearby, still less that a human group occupied the cave.

The presence of giant deer deserves particular care. The animal conventionally called the ‘Irish elk’ was neither restricted to Ireland nor an elk. Its imposing antlers are well known, but its Castlepook remains are more significant as evidence of a large herbivore surviving in a cold and variable landscape. Recent reassessment suggests that giant deer and spotted hyaena may have disappeared locally before the Last Glacial Maximum. That is an interpretation based on dated samples, not proof of an island-wide extinction year.

## The Reindeer Bone Question

The most arresting possible human evidence is a reindeer femur from Castlepook reported as about 33,000 years old and bearing a deep mark interpreted as having been made by a sharp stone edge while fresh bone was processed. If that reading is confirmed, it would suggest that people reached Ireland far earlier than the securely documented terminal-Pleistocene human evidence from County Clare. It would be a major discovery: not an origin story for a permanent nation, but a trace of a fleeting Upper Palaeolithic encounter with an animal.

It remains a proposition requiring stringent testing. A cut mark must be distinguished microscopically from damage by carnivore teeth, trampling, sediment movement, excavation tools or later handling. Moreover, the precise relationship between the mark, the bone’s date and its original cave context needs to be demonstrated. No securely associated stone-tool assemblage, hearth, dwelling floor, burial, structured refuse deposit or human bone of this age has yet been published from Ireland. Current work at Castlepook has located undisturbed Pleistocene deposits in parts of the cave, offering the prospect of better-contextualised evidence in future.

Accordingly, it would be wrong to write of an Irish tribe, chief, migration, language or settled hunting territory in 30,948 BCE. There is no basis for political affairs, diplomacy, law or warfare. Nor is there evidence for organised religion, ritual monuments, art, textile production, farming, trade or formal learning. Absence of evidence is not proof that people could never have been present; it is a statement about what the current archaeological record can support.

## Life, If Visitors Came

If people did visit, their economy would have been that of mobile hunter-gatherers, reliant on knowledge of animal movements, weather, fuel, stone and safe routes. But this is a conditional comparison with Upper Palaeolithic communities elsewhere in Europe, not a description of a documented Castlepook camp. One possible butchered reindeer bone cannot tell us whether the animal was hunted, scavenged, carried from elsewhere, shared between people, or processed by a party that stayed for hours, days or longer. It cannot reveal kinship, belief, language or identity.

What can be said is that survival would have depended on close attention to a demanding environment. Open vegetation supported grazers; freshwater patches provided resources and movement corridors; caves offered terrain of practical importance but also danger from carnivores and unstable deposits. The human story, if there was one, was probably intermittent and vulnerable to rapid climatic deterioration. Later ice expansion would have made continuity still less likely and would have destroyed much of the evidence needed to establish it.

## Evidence Before Narrative

The principal development relevant to Ireland around 30,948 BCE was environmental: a changing Late Pleistocene landscape in which cold wetlands, open ground, large herbivores and predators existed before more extensive glaciation. Derryvree preserves the ecological detail of freshwater tundra-like ground; Castlepook preserves the island's richest known pre-Last Glacial Maximum vertebrate archive. The marked reindeer femur introduces the serious possibility of a very early human visit, but not yet a settled human history.

This is why the period matters. It places Ireland within the fluctuating climates and animal movements of Ice-Age north-west Europe while exposing the fragility of its evidence. Beneath later tills, in cave mud and in museum collections, a few sediments and bones are enough to change large questions. They are not enough to fill a year with invented events. For this remote point in time, intellectual honesty means allowing the archive to remain both extraordinary and incomplete.

# Chapter 054 of 100

## 30947 BCE

### Maguiresbridge Under Permafrost <sup>[54]</sup>



**“30,947 BCE” is a modern calendar label, not a date that can be matched to an event in Ireland. At this depth of time, an individual calendar year is beyond archaeological resolution. The label places us roughly 32,900 calendar years before AD 1950, in the later part of the Late Pleistocene and within Marine Isotope Stage 3, a long, climatically unstable phase of the last glacial cycle. Ireland’s evidence is sparse, local and unevenly dated. The responsible history of this moment is therefore not a chronicle of rulers or happenings, but a reconstruction assembled from glacial sediments, fossil plants, animal bones and the changing reliability of radiocarbon measurements.**

The closest substantial Irish environmental archive is not necessarily contemporary with this particular numbered year. It is the Derryvree freshwater sequence near Maguiresbridge, County Fermanagh, where roadworks in 1969 exposed silts, fine sands and organic deposits enclosed between two thick sheets of glacial till. The organic material returned a conventional radiocarbon determination of 30,500 +1,170/–1,030 years BP. Calibration and later chronological synthesis place it broadly in the middle-to-later 30th millennium calibrated BP, rather than on a single date. It offers a valuable window onto a cold pre-Last Glacial Maximum Irish environment, but cannot prove that the wetland, its plants or its animals existed in 30,947 BCE itself.

## A Landscape Between Ice Advances

Derryvree matters because its structure records change. Till is debris deposited directly by glacier ice: a dense, unsorted mixture of clay, stones and larger fragments. At Derryvree, a lower till was followed by freshwater and organic sediments, then by another till. The simplest reading is that glacier ice had occupied the locality, withdrew or ceased to cover it for a time, and was later replaced by renewed ice.

This is not evidence for an entirely ice-free Ireland. It is evidence that at least parts of the northern landscape could, during the wider glacial cycle, contain exposed ground, standing or slow-moving water and living ecosystems between episodes of ice advance.

The fossil evidence from the intervening sediments indicates open tundra and a periglacial regime: ground subject to severe seasonal freezing and thawing rather than a forested landscape. Pollen was badly preserved, yet it was dominated by herbaceous plants. Plant macrofossils and mosses add sharper detail. Sedges, grasses, mountain-avens, dwarf willow, juniper and other low-growing plants point towards a treeless mosaic of wet hollows, mossy ground, shallow pools and drier exposed patches. A seed of bogbean, a wetland plant still familiar in Ireland, is especially vivid evidence that freshwater habitats persisted locally despite the cold.

This was not an empty, uniformly white wilderness. In summer, long daylight and meltwater could support a short but productive growing season. In winter, however, frozen ground, wind exposure, limited plant cover and deep seasonal snow would have made conditions exacting. The word “muskeg”, used in descriptions of the Derryvree setting, conveys a moss-rich, waterlogged tundra rather than a peat bog identical to a modern Irish bog. It is an interpretation based on plant, insect and sediment evidence, not a claim that the entire island possessed one unchanging habitat.

## **Animals in a Fragmentary Record**

County Cork provides a complementary, though chronologically complicated, archive. Castlepook Cave, also called Mammoth Cave or Doneraile Cave, near the Awbeg valley, has yielded Ireland’s richest known collection of pre-Last Glacial Maximum mammal remains. Historical excavations recovered bones of woolly mammoth, reindeer, giant deer, brown bear, wolf, Arctic fox, mountain hare, lemmings and spotted hyaena. The combination evokes a cold, open-country fauna very different from modern Ireland, including predators and scavengers now absent from Europe or confined to much warmer regions.

Yet Castlepook is not a census of animals seen together on one day, nor a ready-made reconstruction of 30,947 BCE. Much of the assemblage was excavated in the late nineteenth and early twentieth centuries, when recording standards were inconsistent; deposits had also been disturbed by water, carnivores and earlier digging. Thousands of bones reported from the cave are no longer available for re-examination. The Irish Quaternary Fauna Project used accelerator radiocarbon dating to improve the chronology, while more recent work has shown that some older measurements substantially underestimated the age of specimens. A bone proves that a species reached Ireland; it does not automatically demonstrate that every listed species shared the same place, season or generation.

The cautious conclusion is nevertheless important. During the broader MIS 3 interval, Ireland was repeatedly accessible enough for cold-adapted mammals to colonise it. Their presence implies routes of movement through a markedly altered north-west European geography, but it does not settle the old question of precisely when dry land, ice, sea ice or narrow-water crossings connected Ireland with Britain. Lower global sea levels changed coastlines dramatically, while the form and timing of any usable passage remained dependent on ice, relative sea level and local terrain. There is no warrant for turning this complex palaeogeography into a simple permanent land bridge.

## Ice Sheet Build-Up and Regional Change

By around this broad period, the British–Irish Ice Sheet was entering a phase of major growth. Reviews of glacial evidence place its build-up after roughly 35,000–32,000 years ago, with its maximum extent later, approximately 27,000–21,000 years ago. Those ranges are models constructed from many sites, rather than a timetable that can identify conditions in every Irish valley in 30,947 BCE. Still, they explain why the Derryvree sequence is so significant: it preserves a biologically active interval before later ice advanced across or near much of Ireland and scoured, buried or redeposited older evidence.

For people living much later, drumlins, tills, altered drainage and smoothed rock would become conspicuous features of the Irish landscape. At this date, many of the processes that made those landforms were underway or lay ahead. The regional contrast was probably sharp. Uplands, coasts, exposed plateaux, river valleys and lowland basins did not respond alike to advancing ice or thawing ground. Derryvree cannot be projected unchanged onto Cork, Connacht or the east coast; nor can Castlepook's cave fauna be treated as a map of all Ireland. The strongest lesson is environmental instability, not uniformity.

## The Human Question

The human history of Ireland at this depth remains unresolved. A reindeer femur from Castlepook has been reported to bear a deep mark consistent with cutting or chopping by a sharp stone tool, and public accounts have associated the bone with an age of about 33,000 years. If confirmed as deliberate modification of fresh bone, it would be extraordinarily early evidence that people handled an animal in Ireland during the Upper Palaeolithic. It would not, by itself, establish a permanent settlement, a named culture, a local population or continuous occupation.

That distinction is essential. No securely associated hearth, dwelling, stone-tool assemblage, human burial, repeated occupation surface or clearly organised butchery site of comparable age has yet been identified in Ireland. Natural damage, carnivore action, sediment movement and the uncertain histories of old cave collections all require close scrutiny. The Castlepook mark is therefore best treated as a significant research question rather than as proof of a settled community. It is unlike the later, independently dated butchered brown-bear bone from Alice and Gwendoline Cave in County Clare, which provides evidence for human activity at about 12,810–12,590 calibrated BP, near the end of the Pleistocene.

If people did visit Ireland around the wider Castlepook period, they would have been mobile hunter-gatherers whose survival depended on practical knowledge of animals, weather, stone, fuel, shelter and movement through dangerous terrain. That is a reasonable inference from Upper Palaeolithic lifeways elsewhere in north-west Europe. It cannot be promoted to direct Irish evidence. We do not know what language such visitors spoke, whether they came seasonally or briefly, how many there were, or whether they returned. Nor does Ireland preserve art, ornaments, ritual structures or graves from this supposed horizon.

## No Politics, But a Material World

There is consequently no evidence for political authority, diplomacy, territorial states, organised warfare or trade in Ireland at this time. To write of chiefs, tribes, alliances or a conflict over hunting grounds would be invention. Even “society” can only be discussed conditionally: small travelling groups may have shared food, skills and seasonal knowledge if people were present, but the Irish record does not reveal their social rules, kinship, beliefs or relationships with other groups.

Religion and learning are equally silent in the direct evidence. The Derrynvree sediments preserve neither ritual nor memory; Castlepook’s bones preserve neither mythology nor language. Their value lies elsewhere. They demonstrate that Ice Age Ireland was part of a wider ecological world in which plant communities, large herbivores, carnivores and advancing ice repeatedly reshaped the possibilities for life. The economy visible in the evidence is an ecological one: plants colonising wet ground, herbivores exploiting open vegetation, predators and scavengers moving through the same landscapes, and—only possibly—humans making brief use of animal resources.

## A Date Without an Event


The most truthful account of 30,947 BCE is therefore a history of limits as well as discoveries. Ireland was not yet the familiar green, wooded island of later millennia. In places, cold, treeless wetlands and open tundra supported specialised plants and animals; elsewhere, ice and periglacial processes constrained or erased the evidence. Derrynvree supplies the clearest local testimony for that world, while Castlepook shows that remarkable mammals reached the island during the wider interval. Whether people were also present remains an important but unproven possibility. This is not a blank page in Irish history: it is a damaged, deeply buried archive, read cautiously through mud, moss, bone and ice.



# Chapter 055 of 100

## 30946 BCE

### Maguirebridge's Fossil Bogbean<sup>[55]</sup>



30,946 BCE is not a date at which Ireland can be described year by year in the ordinary historical sense. No written record, settlement sequence or securely dated human event permits that precision. The number is a modern calendar convention projected deep into prehistory; it corresponds broadly to a late phase of Marine Isotope Stage 3, during the Midlandian cold stage. The responsible picture is therefore one of ranges, deposits and changing environments. It is a view assembled chiefly from a freshwater bed beneath a drumlin at Derryvree near Maguiresbridge in County Fermanagh, and from animal remains preserved in limestone caves, especially Castlepook Cave near Doneraile in County Cork.

## A Date Within a Wider Horizon

Radiocarbon years, calendar years and BCE labels are not interchangeable at this depth of time. The vital Derryvree organic deposit produced a conventional radiocarbon age of 30,500 +1,170/-1,030 years BP, BP meaning before AD 1950. Calibration converts such measurements into a broad calendar-age probability range rather than one secure year; the uncertainty is enlarged by the age of the sample and by the character of the old radiocarbon curve. The date 30,946 BCE should therefore be treated as lying near, rather than exactly within, the environmental world illuminated by Derryvree and other late-MIS-3 evidence. It cannot establish that a particular plant, animal or person was present in that numbered year.

That distinction matters because Ireland's record is fragmentary. Later glaciers scoured, redeposited and buried much of the landscape. Caves preserve bones, but bones may have been brought in by carnivores, water or sediment movement; open-air surfaces are even less likely to survive. Consequently,

the evidence is far stronger for an ice-age environment and its animals than for human communities. It does not support a named people, a polity, a battle, a leader, a religion or a diplomatic order. The appropriate political history for this moment is, bluntly, silence.

## Water Beneath a Drumlin

Derryvree is exceptional because roadworks in 1969 cut through a drumlin and exposed freshwater silts and fine sands sealed between two thick tills. In other words, the deposit formed after one episode of glacier activity and before another laid down the material above it. Its preservation offers direct evidence that this part of Fermanagh was locally ice-free long enough for water, sediment, plants and small creatures to accumulate. It does not prove that all Ireland shared the same conditions at precisely the same time, but it is one of the clearest Irish windows onto the cold landscape of this broad period.

The recovered plant evidence describes an open, treeless periglacial wetland, often termed muskeg: saturated ground with pools, mossy vegetation and seasonally frozen soils. Pollen was poorly preserved, yet grasses, sedges, herbaceous plants and juniper were identified. Plant macrofossils and mosses included bogbean (*Menyanthes trifoliata*), dwarf willow, mountain-avens, Arctic-alpine clubmoss and aquatic water-milfoil. Together they indicate neither a featureless snow desert nor familiar Irish woodland. Instead, low vegetation occupied damp ground beside shallow, slow-moving or standing fresh water, while drier patches could have been sparse and exposed.

This was a severe but living landscape. Cold winters, frost action and short growing seasons constrained plant cover. Insects and other small faunal remains reinforce the wetland interpretation, while the mixture of aquatic and terrestrial species suggests a patchwork of pools, sedge-rich margins and open tundra beyond. Such evidence is especially valuable because it records what was growing in Ireland itself. It is not merely an inference from climate records in Greenland or from British sites, although those wider North Atlantic archives show that MIS 3 was marked by abrupt climatic oscillations.

## An Open Country Fauna

At Castlepook, also known as Mammoth Cave, the evidence takes a different form. Excavation and later study recovered a striking cold-climate fauna: woolly mammoth, reindeer, giant deer, brown bear, wolf, Arctic fox, mountain hare, lemmings and spotted hyena. These animals did not necessarily coexist in one season, or even in one undisturbed deposit. The cave accumulated material over a long period, and modern re-dating has shown that some older determinations needed revision. Nevertheless, the assemblage demonstrates that parts of Ireland supported, at different points before the Last Glacial Maximum, a fauna now unimaginable on the island.

Reindeer and lemmings are particularly important indicators of open, cold habitats; mammoth and giant deer add to the picture of extensive grazing country rather than closed forest. Spotted hyena, represented at Castlepook by bones and a skull, points to a richer predator-scavenger community. A cave was not necessarily anyone's home: carnivores may have used it as a den or carried in bones, and animals could die in or near its entrances. The fauna therefore tells us much about regional ecology, but less about the exact appearance of a single valley on a single day.

In practical terms, the economy of the landscape was ecological rather than human. Plant growth fed herbivores; herbivores supported predators and scavengers; wetlands supplied specialised plant and insect habitats. Seasonal movement is plausible for grazing animals, especially reindeer, but remains an interpretation, not a mapped migration route. There is no evidence for farming, herding, cereal cultivation,

pottery, metalworking, permanent houses or long-distance exchange among people in Ireland at this time. Nor can animal presence alone demonstrate a land route, sea crossing or continuous connection with Britain or continental Europe at any particular moment.

## The Human Question

The most provocative object relevant to this era is a reindeer femur from Castlepook reported to bear a deep linear mark consistent with a sharp stone tool used on fresh bone. The bone has been presented publicly as approximately 33,000 years old, raising the possibility of very early human handling or butchery in Ireland. If the mark proves to be a contemporary human cut mark, it would be remarkable evidence for a brief Upper Palaeolithic presence: perhaps a small mobile party processing an animal, whether hunted or scavenged.

But possibility is not settlement history. A radiocarbon age dates the animal bone, not automatically the incision, its maker, the location where the animal died, or the duration of any visit. Castlepook has not produced a securely associated hearth, dwelling floor, burial, tool assemblage or repeated occupation surface of comparable age. Carnivore teeth, sediment abrasion, excavation damage and later disturbance must always be excluded in assessing a marked bone. The sensible conclusion is that late-MIS-3 Ireland may have been visited by people, but sustained human occupation around 30,946 BCE has not been demonstrated.

This caution becomes clearer when set beside firmer later evidence. At Alice and Gwendoline Cave in County Clare, a brown-bear patella with convincing cut marks has calibrated dates of about 12,890–12,678 cal BP, at the beginning of the Younger Dryas. That is much later than the period considered here, but it establishes that the island's earliest securely evidenced Palaeolithic human activity remains a terminal-Pleistocene question. It should not be retrojected tens of millennia into the Derryvree or Castlepook horizon.

## Approaching Greater Ice

The environmental background was unstable. Research on the British–Irish Ice Sheet indicates broad ice growth from about 31,000 to 26,000 years BP, with maximum volume reached much later, around 23,000 BP in one major reconstruction. Ireland around this broad horizon was not simply “under ice”, nor was it safely outside glacial influence. Different regions experienced different conditions, while ice margins, permafrost, meltwater and exposed ground shifted through time. Derryvree's buried wetland confirms a locally ice-free interval; the tills enclosing it show that this respite belonged to a longer history of glaciation.

Regional change, then, was the central drama. In Fermanagh, freshwater life briefly left a record below later ice-worked ground. In Cork, caves accumulated traces of a cold-adapted animal world. Elsewhere, evidence has been erased, remains undetected or cannot yet be dated closely enough. The future Irish landscape of forests, farms, monuments and kingdoms was not merely absent: the environmental conditions required for it did not yet exist.

For society, culture and learning, the honest record is negative but meaningful. There are no known communities from which to infer households, kinship, language, ritual or artistic traditions. If humans did enter Ireland, their knowledge would have been practical and mobile: reading weather, animals, stone, shelter and seasonal danger. Yet that is a model drawn from wider Upper Palaeolithic Europe, not a fact

established by an Irish campsite. Around 30,946 BCE, Ireland's history is best told through its surviving witnesses: a fossil bogbean seed, a moss bed, a reindeer bone, cave sediments and the advancing shadow of ice.

# Chapter 056 of 100

## 30945 BCE

### Fermanagh Pools, Cork Hyenas <sup>[56]</sup>



**The label 30,945 BCE is a modern chronological convenience, not a recoverable Irish calendar year. It lies roughly 32,894 years before the conventional archaeological reference point of AD 1950, within the Late Pleistocene and Marine Isotope Stage 3 (MIS 3). No writing, named people, political units or dated events survive from Ireland at this depth of time. Nor can the evidence identify the weather, a journey or an encounter in one particular year. Radiocarbon determinations must be calibrated into calendar ranges and carry sizeable uncertainty; deposits and bone assemblages therefore illuminate a broad horizon rather than a single year.**

## **A Cold Interval, Not a Chronicle**

For Ireland, the responsible frame is the later Middle Midlandian, the regional name often applied to part of this fluctuating glacial period. The island was not simply an unbroken white wilderness, nor was it the wooded country familiar from later prehistory. Its environments changed with climate, ice margins, drainage and sea level. The British–Irish Ice Sheet was already an important force, but its growth was regionally uneven and its ultimate maximum lay later. Reconstructions place complete ice cover of Ireland and its continental shelf during the Last Glacial Maximum, broadly c. 27,000–23,000 calibrated years BP. That later episode would erase, bury or disturb much older evidence.

Around this nominal date, therefore, the central historical development was environmental instability. Ice expanded and retreated over long timescales; exposed ground could support plants and animals in some districts, while other areas were glaciated, periglacial or rendered inhospitable by severe cold. The surviving record is necessarily patchy. Northern Fermanagh and north Cork matter not because they describe all Ireland at once, but because they preserve two unusually valuable and very different windows onto conditions before the ice sheet's fullest spread.

## Derryvree Between the Tills

The clearest environmental archive is Derryvree, near Maguiresbridge in County Fermanagh. Road works in 1969 exposed organic-rich freshwater silts and fine sands trapped between two separate till sheets: compact glacial sediment below, a wetland sequence, then later glacial sediment above. The sequence establishes an important fact. After the earlier ice had deposited its till, local conditions allowed standing or slow-moving freshwater, plants, insects and fine sediment to accumulate; a renewed advance later sealed that record beneath another till.

The organic layers produced radiocarbon determination BIRM-166, conventionally dated to 30,500 radiocarbon years BP, with an uncertainty of +1,170 and –1,030 years. Calibration does not convert this into an exact BCE date. Published treatments place the deposit broadly within the middle and later thirty-thousands of calibrated years BP, approximately 36,900–31,700 cal BP. That wide interval overlaps the horizon represented by 30,945 BCE, but it cannot demonstrate that Derryvree's pools existed in that numbered year. It is evidence for a type of Irish landscape and climate, not a dated episode.

Its contents are nevertheless vivid. Plant remains, pollen and insects indicate cold, open, treeless country around freshwater. Mosses and sedges grew in wet ground; aquatic plants show the presence of pools or quiet water. Juniper, grasses and herbs belonged to a vegetation mosaic more akin to northern tundra and muskeg than to modern Irish pasture or woodland. Insect evidence likewise points towards a northern, cold-adapted setting. This was not lifeless terrain. It was a low-productivity but functioning wetland ecosystem, shaped by short growing seasons, prolonged winters and ground affected by frost.

## Animals at Castlepook

Castlepook Cave, also called Mammoth Cave, near Doneraile in north County Cork provides the complementary faunal record. The cave has yielded one of Ireland's richest Pleistocene bone collections, including woolly mammoth, reindeer, giant deer, brown bear, fox, hare, lemmings and spotted hyaena. A mammoth bone has produced a conventional radiocarbon age of  $33,500 \pm 1,200$  BP, while a spotted-hyaena bone was dated to  $34,300 \pm 1,800$  BP. These determinations make the assemblage directly relevant to the broad period, even though they cannot be assigned to 30,945 BCE.

The collection must be handled carefully. Cave deposits can accumulate over very long periods. Carnivores may drag in remains; water, excavation and disturbance can mix material; and older investigations often left limited contextual information. Castlepook is thus not a snapshot of one herd, one hunt or one season. It does show, however, that southern Ireland at times supported a diverse cold-stage fauna. Mammoth and reindeer suggest open landscapes with substantial grazing; hyaena demonstrates the presence of a major scavenger and predator. The National Museum of Ireland retains a Castlepook spotted-hyaena skull, a tangible reminder that animals now associated with African grasslands once ranged in Pleistocene Cork under very different climatic conditions.

## The Human Question

Human presence is the most tempting and the most uncertain subject. A reindeer femur from Castlepook, recovered during earlier cave work and re-examined with modern methods, has been reported as about 33,000 years old and as bearing a deep linear modification interpreted by some researchers as a

cut made with a sharp stone tool while the bone was fresh. If that interpretation is upheld, it could indicate a brief Upper Palaeolithic human visit to Ireland far earlier than the previously accepted evidence.

It does not yet establish a settled community. No securely associated stone-tool assemblage, hearth, dwelling, burial ground or occupation surface has been demonstrated for this horizon at Castlepook. The bone's old excavation context also limits what can be inferred. A cautious conclusion is that people may have reached Ireland and processed an animal during the pre-Last Glacial Maximum period; a stronger claim of permanent occupation, a named hunting band or a regular migration route would go beyond the evidence. Recent excavations at the cave, supported by the Royal Irish Academy, are important precisely because undisturbed deposits may allow such questions to be tested rather than answered by assumption.

## **Society Beyond Recovery**

There is no evidence from Ireland around this date for political affairs, diplomacy, leaders, warfare, law or territorial states. If humans did visit, they would have belonged to small, mobile hunter-gatherer communities of the wider north-west European Upper Palaeolithic world, but that is an inference from comparable societies and cannot identify an Irish group. Hunting may have involved cooperation and seasonal knowledge of animal movement, yet no Irish campsite from this time permits a reconstruction of family life, gender roles, language or social organisation.

For the same reason, religion and learning remain beyond direct observation. Cave bones do not demonstrate ritual, mythology, art, music or formal teaching. Nor is there evidence of farming, herding, metalworking, pottery, weaving, trade networks or exchange between communities. The most defensible 'economy' is ecological: animals grazed, browsed, hunted, scavenged and competed across open ground and wetlands; any humans present would have depended on mobile resources, fuel and shelter in a demanding environment. This is a landscape of subsistence possibilities, not a documented economy.

## **Routes, Coasts and an Approaching Ice Age**

Lower global sea levels altered the geography around Ireland, exposing wider shelf lands in places, but that fact alone does not prove a dry land bridge or an easy crossing from Britain or continental Europe. Local relative sea level was affected by the weight of nearby ice, while glaciers, cold seas, river systems and changing coastlines shaped access. The British–Irish Ice Sheet was itself dynamic during MIS 3. Modern reviews find evidence for advance–retreat behaviour before the Last Glacial Maximum, but also stress that the chronology of these earlier phases remains less securely resolved than the later retreat.

Regional contrast is therefore essential. Derryvree records freshwater wetland in Fermanagh between ice advances. Castlepook records animals in a Cork limestone cave over a prolonged and probably mixed timespan. Neither permits the conclusion that all of Ireland was open tundra, ice-free, occupied or connected by a traversable route at once. The island's history at this point is best understood as a shifting mosaic, in which suitable habitat may have appeared temporarily and then been lost as climate deteriorated and ice expanded.

## What This Date Can Mean


30,945 BCE cannot supply the conventional landmarks of a year-by-year history. Its importance lies instead in the evidence that Ireland was part of the wider Ice Age ecology of north-west Europe before later glaciation reached its greatest extent. Derryvree preserves cold freshwater life beneath the drumlins of Fermanagh; Castlepook preserves the bones of grazing animals and carnivores in Cork; one marked reindeer bone raises, but does not settle, the possibility of very early human activity. Those traces are fragmentary, yet they are more historically meaningful than an invented event: they reveal an Ireland in which water, frost, animals and advancing ice determined the limits of life.



# Chapter 057 of 100

## 30944 BCE

### Castlepook's Deep Bone Archive<sup>[57]</sup>



**“30,944 BCE” is a modern chronological label, not a year that can be recovered from Ireland’s Ice Age record. No calendar, named community, political event or individual can be placed in that precise year. In archaeological terms it falls about 32,893 years before AD 1950, the conventional radiocarbon ‘present’, during the Late Pleistocene and Marine Isotope Stage 3 (MIS 3). At such depth in time, radiocarbon determinations, sediment layers and climatic correlations yield ranges measured in centuries or millennia, not annual dates. The responsible history of Ireland at this point is therefore one of landscapes, animal populations, ice and rare deposits rather than rulers, settlements or historical episodes.**

## **A Date Within a Broad Range**

The closest important Irish environmental sequence is at Derryvree, near Maguiresbridge in County Fermanagh. Road works exposed fine sands and organic freshwater silts trapped between two tills: stony sediments left by glaciers. A radiocarbon determination from the organic deposits of c. 30,500 ± 1,100 radiocarbon years BP was historically calibrated to a wide interval of roughly 36,900–31,700 calendar years BP. That range encompasses the modern label 30,944 BCE, but does not date the entire deposit, still less an event in a particular year. Calibration itself has improved since the original research; IntCal20 confirms that radiocarbon ages must be converted through a curve and retain substantial uncertainty at this antiquity. Derryvree is consequently a securely valuable window on a broad cold-stage environment, not a diary of a single Irish year.

Its preservation is exceptional. Later glacier advance buried the wetland beneath fresh till, protecting an interval that ice otherwise might have scoured away. Much of Ireland’s evidence for this part of the Pleistocene has been lost, redeposited or concealed by later glacial action, sea-level change and modern

landscapes. The Derryvree sequence accordingly has an importance beyond its small original exposure: it demonstrates that, during part of the wider period relevant to this date, biologically active, locally ice-free freshwater ground existed in inland Ulster. It cannot establish that all of Ireland was similarly open, nor trace the exact position of every ice margin.

## **Wet Ground in a Cold Country**

Plant remains, pollen and fossil insects from Derryvree indicate open, largely treeless country. The published interpretation is a cold-phase muskeg or tundra-like wetland, with mosses, sedges, grasses and herbs around shallow water and damp ground. Low shrubs, including juniper, may have occurred locally. Such evidence corrects the misleading picture of Ice Age Ireland as either a featureless white wilderness or an unbroken plain of grass. It was a mosaic: waterlogged hollows, pools, sedgy margins, frost-affected soils and more exposed mineral ground. The vegetation was sparse by later Irish standards, but it was ecologically productive during favourable seasons.

Seasonality mattered greatly. Winter cold, frozen or saturated surfaces, limited woody fuel and short growing seasons would have restricted plant growth and animal movement. Summer thaw, however, could create feeding grounds for insects and herbivores and replenish pools and streams. The deposits do not tell us the weather on a given day in 30,944 BCE, and they do not prove continuous habitation by any species. They do show that a living wetland developed between phases of glaciation. In the Irish story for this period, that environmental fact is more securely known than any human activity.

## **The Castlepook Fauna**

The other principal archive lies far to the south at Castlepook Cave, also known as Mammoth Cave or Doneraile Cave, in north County Cork. Excavations between 1904 and 1918 recovered more than 2,000 bones from its narrow limestone passages and chambers. Castlepook is Ireland's richest known source for vertebrate remains dating to the long interval before the Last Glacial Maximum. Direct radiocarbon dates on individual bones span approximately 45,700 to 19,950 years BP, meaning that the cave collection is a time-depth archive, not the remains of one animal community or one moment of occupation.

Its mammals include woolly mammoth, giant deer, reindeer, brown bear and spotted hyena, alongside wolf, Arctic fox, mountain or Arctic hare, and lemmings. The presence of such animals shows that Ireland was intermittently connected to wider north-west European ecological systems before the sea reached its later extent. It also reveals a landscape capable, at different times within MIS 3, of sustaining large grazers, browsers, scavengers and predators. Spotted hyena is particularly striking: Castlepook is the only Irish site known to have produced it. Hyenas probably helped accumulate and modify bones in the cave, while water movement and early excavation disturbed other deposits. These processes are essential to interpretation. A bone in a cave need not record where an animal died, and bones of very different ages can lie together.

Recent redating has made that caution more important. Improved pretreatment and ultrafiltration have shown that some 1990s radiocarbon dates for southern Irish cave fauna were too young, in certain Castlepook cases by thousands of radiocarbon years. The revised evidence places important elements of the fauna more firmly within MIS 3 and suggests that some, including giant deer and spotted hyena, disappeared locally before the Last Glacial Maximum. Thus Castlepook supports a broad picture of a cold, open-country fauna in Ireland around the wider period of 30,944 BCE, but it does not permit a precise census of which animals stood outside the cave in that notional year.

## People: Possibility, Not Settlement

The question of human presence needs especially careful treatment. A reindeer femur from Castlepook has been presented in public discussion as bearing a deep mark compatible with stone-tool butchery and as dating to about 33,000 years ago. If that interpretation is ultimately sustained, it may indicate a brief human encounter with an animal during the broader era considered here. It would not, by itself, demonstrate a camp, a resident population, a family group or a route of regular migration. The object derives from an old cave collection with limited modern stratigraphic context, while carnivore activity and sediment movement complicate the setting.

There is, moreover, no securely excavated hearth, stone-tool assemblage, dwelling, burial, art or other directly associated material that can currently establish human occupation of Ireland around 30,944 BCE. Renewed excavation at Castlepook in 2022 identified surviving deposits and recovered animal remains, but found no cultural artefacts. The earliest published evidence widely accepted as humanly modified in Ireland remains much later: a butchered brown-bear patella from Alice and Gwendoline Cave, County Clare, dated to c. 12,810–12,590 cal BP. That later find proves that people reached Ireland in the terminal Pleistocene; it cannot be projected backwards twenty millennia. For 30,944 BCE, the sound conclusion is that human visits remain possible, perhaps even plausible in a wider European context, but unconfirmed as settlement.

## No Politics, No Diplomacy

Accordingly, there is no evidence for political affairs, warfare, diplomacy, chiefs, territorial boundaries or institutions in Ireland at this date. Nor can archaeology identify religion, language, ritual practice, teaching, family structure, exchange networks or a domestic economy. It would be misleading to supply them by analogy with Upper Palaeolithic societies elsewhere in Europe. People in other regions demonstrably made sophisticated stone tools, ornaments and cave art, but no such Irish material belongs securely to this period. Absence of evidence is partly a consequence of later glaciation and difficult preservation; it is not proof that people could never have arrived. Yet historical reconstruction must distinguish that possibility from evidence.

The only economy that can be responsibly described is ecological. Wetland plants captured sunlight; insects occupied the damp margins; herbivores used the open country; and carnivores and scavengers followed them. Mammoth, reindeer and giant deer did not constitute an ‘Irish economy’ unless people hunted or processed them, which remains unproven for this date. If small human parties did reach the island, their survival would have depended on mobile hunting, careful knowledge of season and terrain, and access to fuel and shelter. That is an inference from comparable environments, not a discovery from Derryvree or Castlepook.

## Approaching Greater Ice

At the scale of the British–Irish Ice Sheet, this was a period of climatic instability and developing glaciation rather than the later maximum of ice extent. BRITICE-CHRONO reconstructions begin at 31,000 years ago and show that ice growth could be rapid, though the timing and extent of Irish ice in earlier MIS 3 remain complex and locally debated. The important long-term development was the approach of a more severe glacial world. Subsequent ice reshaped drainage, stripped surfaces, carried


debris across the island and sealed a few fortunate deposits such as Derryvree. The record's patchiness is therefore part of the history: Ireland's oldest recoverable landscapes survive not because they were typical, but because they escaped destruction by chance.

For this point in deep time, then, Ireland was neither a documented society nor an empty abstraction. It was a changing northern landscape in which freshwater wetlands could exist between glacial advances and large Ice Age mammals moved through open country. Castlepook's bones and Derryvree's silts offer different kinds of testimony: one a long, mixed animal archive; the other a local environmental sequence. Together they illuminate conditions around a broad chronological horizon that includes 30,944 BCE. They do not supply a year-specific event. Their enduring value lies in making that limit clear while revealing how much life persisted on the edge of advancing ice.

# Chapter 058 of 100

## 30943 BCE

### Derryvree's Ice-Free Interval<sup>[58]</sup>



**“30,943 BCE” is a modern chronological label, not a year for which Ireland preserves an event, ruler, battle, settlement or dated human life. At this depth in time, calendar-year precision is unavailable. The responsible setting is the later Pleistocene, in the closing part of Marine Isotope Stage 3 (MIS 3), when climate across the north Atlantic changed sharply over centuries and millennia. Archaeological and environmental records can illuminate broad intervals, but not a particular Irish day or season. The evidence most relevant to this point comes from fossil-bearing caves in the south and buried freshwater deposits in Fermanagh, supplemented by the geological record of the growing British–Irish Ice Sheet.**

## **A Date Within a Long Interval**

The date lies about 32,900 calendar years before the conventional radiocarbon reference year of AD 1950. That arithmetic does not make it equivalent to a radiocarbon age. Radiocarbon years must be calibrated against independently dated records of past atmospheric carbon, and the resulting calendar ranges may be broad or irregular so far back in time. The Derryvree freshwater deposit near Maguiresbridge, County Fermanagh, produced a conventional radiocarbon determination of 30,500 +1,170/–1,030 BP. It has been placed broadly in a calibrated late-MIS-3 interval, roughly c. 37,000–32,000 calibrated years BP. Thus 30,943 BCE falls near the younger end of a long environmental window rather than identifying the moment when the sediment was laid down.

The useful historical question is therefore not “what happened in Ireland in 30,943 BCE?” but “what sort of Irish landscape is securely attested around this phase?” The answer is neither an unbroken ice sheet nor a familiar green island of woodland and farms. At some times and in some regions, there were ice-free

tracts of cold, open ground, freshwater hollows and large-mammal habitat. At other times, glaciers advanced, altered drainage, buried sediments and erased evidence. The patchiness of the record is itself central to the story.

## Fresh Water Between the Tills

Derryvree is the clearest local archive. Road works in 1969 cut through a drumlin about two kilometres north-east of Maguiresbridge and exposed fine sands and organic freshwater silts sandwiched between two thick, distinct tills. Till is unsorted sediment left by glacier ice. The sequence therefore records a simple but powerful order: glaciation, an interval in which the locality supported freshwater sediment and living organisms, then renewed glaciation. It does not prove that every part of Ireland was ice-free simultaneously, nor does it establish a stable climate lasting unchanged for thousands of years.

The fossil contents reveal a severe but inhabited wetland landscape. Poorly preserved pollen, plant macrofossils, mosses and insects point to low, open vegetation: grasses, sedges, herbs, juniper and cold-adapted mosses rather than forest. Finds including bogbean, water-milfoil, mountain-avens, dwarf willow and lesser clubmoss indicate shallow or slow-moving fresh water, wet margins and exposed ground nearby. The insect evidence is of northern, cold-climate character. Researchers have accordingly described the setting as tundra or a muskeg-like mosaic: saturated, organic-rich ground with pools, mossy margins and frost-affected soils.

That description needs care. “Tundra” is an environmental comparison, not a claim that Derryvree duplicated any modern Arctic landscape. The sediments represent one lowland locality, accumulated over time. Nevertheless, they decisively rule out an image of an entirely lifeless, permanently ice-covered Fermanagh. In the favourable season, water, sedge-rich forage and flowering plants existed. Winters were likely long and hard; freeze-and-thaw processes disturbed soil and restricted trees. Windswept ridges and drier mineral ground may have looked very different from sheltered wet hollows only a short distance away.

## Castlepook’s Faunal Record

County Cork supplies the other major line of evidence. Castlepook Cave, near Doneraile and sometimes called Mammoth Cave, has yielded Ireland’s most important pre-Last Glacial Maximum assemblage of large vertebrates. Its documented fauna includes woolly mammoth, reindeer, giant deer, brown bear, wolf, foxes including Arctic fox, mountain hare, lemmings and spotted hyaena. This is a striking reminder that Ireland could at intervals form part of a wider north-west European world of cold-stage mammals, very different from the island’s later fauna.

But a cave collection is not a census of one landscape in one year. Castlepook was excavated principally in the early twentieth century under Richard J. Ussher, before modern standards of controlled excavation, and bones could have entered its passages through carnivore activity, natural deaths, water movement and later disturbance. New accelerator radiocarbon work has shown that several earlier determinations were too young, while also confirming that Castlepook accumulated remains over a very long span. Individual animals from different chambers, layers and generations should not be assembled into a single imagined herd.

Even so, the broad ecological conclusion is secure. Reindeer and mammoth require a landscape capable of supporting large herbivores; wolves and hyaenas indicate predators and scavengers within that wider food web. Hyaena-chewed bones also warn against mistaking every concentration of broken bone

for a human food deposit. The cave's significance lies in showing repeated animal access to southern Ireland during MIS 3, not in proving that all recorded species occupied north Cork in 30,943 BCE itself.

## **The Human Question**

The most provocative object connected with this period is a reindeer femur from Castlepook reported to bear a sharp mark consistent with stone-tool butchery. Modern dating and reassessment have made it a potentially important indication that people may have handled a carcass in Ireland before the Last Glacial Maximum. If the modification is confirmed as human-made and contemporary with the bone, it would push Irish human activity far earlier than the well-established Late Glacial evidence from Alice and Gwendoline Cave in County Clare.

Yet the claim must remain qualified. Ireland has produced no human bone, unequivocal lithic assemblage, hearth, dwelling floor, burial or securely excavated camp dating to this broad early period. One marked bone cannot reveal whether a small group visited briefly, hunted locally, scavenged an animal, crossed from neighbouring lands, or established any recurring presence. Nor does it identify a named people, language, religion or social order. The safest interpretation is narrow: the bone is an important but still limited possible trace of human carcass processing, deserving further microscopic study, dating and controlled excavation.

Modern humans were present elsewhere in Europe during the Upper Palaeolithic, using stone tools and pursuing mobile subsistence strategies in cold and fluctuating environments. That continental context makes a short-lived visit to Ireland conceivable. It does not turn possibility into evidence of a permanent Irish population. Later glacier growth would in any case have made long-term continuity highly unlikely, while it also destroyed or concealed many potential traces.

## **No Politics, No Known Conflict**

There is no evidence for political affairs, diplomacy, organised warfare, leaders, territories or institutions in Ireland at this date. There are likewise no known settlements from which everyday domestic routines can be reconstructed. If people entered the island, they were almost certainly few in number and highly mobile, but that is an inference from the sparse evidence and wider Upper Palaeolithic comparison, not a fact demonstrated by an Irish camp.

For the same reason, religion, art, learning and language are archaeologically silent. No cave art, portable art, grave, shrine or ritual deposit of this age is securely known from Ireland. It would be misleading to furnish the period with imagined shamans, clan chiefs or ceremonies merely because such themes are familiar from later prehistory. The intellectual achievement visible here belongs instead to modern science: geologists, palaeoecologists, zooarchaeologists and radiocarbon specialists reading a fragmentary record of mud, pollen, mosses, bones and marks on bone.

## **Movement, Coast and Economy**

There was no Irish economy in the later historical sense: no farming, markets, coinage, metalworking or documented exchange network. The economy of the landscape was ecological. Wetlands produced plant matter and freshwater; open vegetation supported herbivores; carnivores and scavengers fed on

those herbivores. A visiting hunter might have valued meat, marrow, hide, sinew, antler and bone from reindeer, but Castlepook does not prove which resources, if any, people took from the individual represented by the marked femur.

Sea level was lower than today because vast quantities of water were locked in northern ice sheets, and the geography around Ireland differed greatly from the modern coastline. However, it is unsafe to picture an uninterrupted, permanent land bridge to Britain or continental Europe. Ice margins, sea passages, exposed shelves, river systems and coastlines changed through time; routes usable by animals or humans may have opened and closed. The animal record establishes connection at intervals, but not the exact route travelled by any species.

## **Approaching a Major Transformation**

By the broader transition from MIS 3 towards MIS 2, the British–Irish Ice Sheet was expanding into the conditions that culminated in the Last Glacial Maximum. Different sectors reached their maxima at different times, and the timing and extent of Irish ice remain subjects of active research. For Ireland, the important point is that the Derryvree wetland and Castlepook fauna belong to a world vulnerable to profound reorganisation. Ice could advance across former habitat, reroute water and entomb the very deposits through which the earlier landscape is now known.


Around 30,943 BCE, then, Ireland is best seen through Derryvree’s freshwater silts and Castlepook’s cave bones. The evidence supports cold, mostly treeless and varied environments; intermittent ice-free ground; pools and sedge-rich wetlands in Fermanagh; and a wider Irish fauna that included reindeer, mammoth and hyaena. It permits a cautious possibility of human presence, but no history of settlement or society. Far from being empty of historical meaning, this sparse record shows how Ireland’s later human story was preceded by deep environmental instability, animal movement and landscapes repeatedly remade by ice.



## Chapter 059 of 100

30942 BCE

Derryvree's Permafrost Wetland <sup>[59]</sup>



**Modern calendar-year precision is not available for Ireland in 30,942 BCE. This is a retrospective date in a modern numbering system, not a year that any person in Ice Age Ireland recorded or recognised. It corresponds roughly to 32,892 years before AD 1950, the conventional reference point for “before present” chronology, but that conversion does not turn the evidence into an annual record. The responsible historical setting is the later part of Marine Isotope Stage 3 (MIS 3), a cold and highly variable interval of the Late Pleistocene, before the fullest expansion of the last British–Irish Ice Sheet.**

The closest Irish evidence is measured in sediment layers, animal bones, pollen, plant fragments and cave minerals, and is dated in broad ranges. A particularly useful range comes from Derryvree, near Maguiresbridge in County Fermanagh: organic freshwater sediments there produced the legacy radiocarbon determination Birm-166, 30,500 +1,170/–1,030 radiocarbon years BP. Using modern calibration, this is generally treated as a wide interval of roughly 36,900–31,700 calibrated years BP, or about 34,950–29,750 BCE. The requested year falls within that span, but cannot be placed at a particular point in the deposit. It would be misleading to invent a dated event, a leader, a settlement or a journey for it.

### **An Island in a Changing Ice Age**

Ireland at this time was neither a familiar green island nor necessarily a single, uniform sheet of ice. The last glacial cycle produced sharp climatic shifts, changing ice margins and major differences between regions. The later Last Glacial Maximum, broadly centred on the interval after about 27,000 calibrated years BP, would bring far more extensive ice across much of Ireland and its surrounding shelf. Around the

notional date considered here, however, the surviving evidence instead points to a shifting mosaic: local glacier ice in some places and times; exposed, frost-shattered ground in others; meltwater channels, lakes and wetlands where conditions permitted.

That distinction matters. The sediments at Derryvree demonstrate that one locality in south Fermanagh was ice-free long enough for freshwater deposits and organic material to accumulate between two separate layers of till, the unsorted debris left by glacier ice. They do not prove that all Ireland was simultaneously free of ice, nor do they supply a map for one specific century. Equally, evidence from caves in Cork or Kerry cannot simply be projected across the island. Late Pleistocene Ireland must be understood as a changing landscape whose records are scattered and often damaged by later glaciation.

Crag Cave near Castleisland, County Kerry supplies another, different kind of clue. Uranium-thorium dates show episodes of stalagmite growth during the last glacial period. Such growth requires water to percolate through the limestone and, in this shallow cave system, is associated with intervals when average annual temperatures were sufficiently mild for liquid water. The record reinforces the conclusion that climatic conditions were not static. Yet it is not a weather diary: cave-calcite episodes constrain broad environmental phases, not the conditions on one day in 30,942 BCE.

## **Fresh Water Beneath a Drumlin**

Derryvree is the clearest environmental window onto this part of Irish deep time. Road excavations in 1969 cut through a drumlin and revealed silts and fine sands between lower and upper tills. The sequence gives a secure relative story. First, glacier ice deposited the lower till. Later, at least locally, ice was absent and a freshwater environment formed. Finally, renewed glacial action overrode and sealed that environment under the upper till. Much of the landscape visible in Ireland today was subsequently shaped or obscured by these and later movements of ice.

The plants and animals preserved in the intervening freshwater series indicate an open tundra or tundra-like setting and a severe periglacial regime. Pollen preservation was poor, but the identifiable pollen was principally herbaceous. Macrofossils included mosses, while aquatic and wetland plants included water-milfoil, bogbean, sedges, mountain-avens, dwarf willow and lesser clubmoss. This was not forest: there is no evidence here for oak, hazel woodland, farms or meadow pasture. The better comparison is with a cold, treeless wetland of shallow water, mossy ground, sedge-rich margins and sparse vegetation on drier exposed surfaces.

In practical terms, seasonal thaw was as important as winter cold. Water could pond above frozen or impermeable ground; meltwater could sort sand and silt; and short summers allowed hardy plants and invertebrates to complete their life cycles. Fossil beetles and other insects are consistent with a northern, open-country environment. The phrase “muskeg” has been used as an analogy for the wet, mossy terrain, but it should not conceal uncertainty. The deposit documents a local wetland community, rather than a complete reconstruction of every hill, shore and valley in Ireland.

## **Animals, Caves and Missing Landscapes**

Animal bones from Irish caves show that large mammals entered and used Ireland during favourable phases of the Late Pleistocene. Castlepook Cave, also known historically as Mammoth Cave, in the Awbeg Valley near Doneraile in north County Cork is especially important. Its old collections include

woolly mammoth, reindeer, giant deer, brown bear, wolf, fox, hare and spotted hyaena, alongside smaller mammals. Direct dates on some material place elements of the fauna before the Last Glacial Maximum, broadly within the wider time horizon relevant here.

These creatures should not be assembled into an imagined single herd passing Castlepook in one season. Cave deposits commonly form over long periods through carnivore denning, animals dying in or near cavities, water movement, scavenging and sediment disturbance. Much of Castlepook was excavated in the early twentieth century, before present-day standards of stratigraphic recovery and recording. The fauna therefore establishes that cold-adapted and open-country mammals occurred in Ireland at different times, but it cannot reliably specify which species met each other, or precisely when.

Nevertheless, the combined evidence suggests productive, if harsh, habitats. Reindeer could exploit lichens, sedges and other open-country forage; hyaenas and wolves followed prey or scavenged carcasses; mammoths and giant deer required extensive landscapes rather than isolated pockets of ground. Their presence implies routes into Ireland when geographical and climatic circumstances allowed, though the exact routes remain uncertain. Lower global sea levels altered the form of the Irish Sea basin, but ice loading, relative sea level, coastlines and water crossings changed through time. No simple claim that Ireland was joined to Britain by a permanent land bridge is justified for this particular date.

## **A Possible Human Trace**

The question of people in Ireland is more contentious still. A reindeer femur from Castlepook has been publicised as approximately 33,000 years old and bears a deep mark that zooarchaeologist Ruth Carden has interpreted as damage made by a sharp stone tool during butchery. If that diagnosis is upheld, it may represent the earliest known indication of human activity in Ireland and would show that a person or small party handled a reindeer during the Upper Palaeolithic.

Its significance is real, but narrow. The bone comes from an old collection rather than a securely excavated occupation surface. Its radiocarbon age dates the animal, not necessarily the moment at which the mark was made. No associated stone-tool assemblage, hearth, dwelling floor, burial, food store or repeated sequence of butchered bones has established a camp of this age. The sound conclusion is therefore possibility, not a settled colonisation: Ireland may have received a brief human visit or visits during this broad period, but permanent occupation cannot be demonstrated around 30,942 BCE.

If people did arrive, their social and economic world would have been that of highly mobile hunter-gatherers, equipped with perishable gear and stone cutting tools, moving through a risky cold environment where animal migrations, shelter and seasonal access mattered greatly. This is an inference from the possible cut-mark and wider European Upper Palaeolithic context, not direct evidence for a named Irish community. There is no basis for discussing tribes, rulers, diplomacy, organised warfare, territorial states, formal religion, monuments, trade networks or learned traditions in Ireland at this date. None is attested.

## **History Without a Chronicle**

For this point in the Irish past, environmental change is not merely background to history: it is the surviving history. Political affairs and conflict cannot be reconstructed because no evidence identifies political communities. Religion and culture leave no secure artefacts or ceremonial places. Economy is


visible only in the most limited sense: cold-adapted plants and animals used a landscape of seasonal water, exposed ground and shifting ice, while the Castlepook bone raises the prospect of human use of animal resources. Exchange and diplomacy are unknown.

The essential development was instability. At Derryvree, freshwater life occupied a brief space between glacial episodes; at Crag Cave, mineral growth registers intervals of thaw; at Castlepook, bones preserve fragments of a mobile Ice Age fauna, perhaps with one tantalising human intervention. Later ice advance buried, eroded and rearranged much of this world. What remains is necessarily incomplete, but it is enough to replace the old image of an entirely empty, permanently frozen Ireland with a more careful one: a cold, regionally varied and repeatedly transformed country, intermittently capable of sustaining wetlands, animals and perhaps fleeting human passage.

## Chapter 060 of 100

### 30941 BCE

#### BIRM-166's Sedgewater<sup>[60]</sup>



**The label 30,941 BCE gives an appearance of precision that the evidence cannot sustain. No written calendar, settlement layer or dated human action allows Ireland's past to be resolved to this single year. In archaeological terms, it falls roughly 32,890 calibrated years before AD 1950, during the Late Pleistocene, in Marine Isotope Stage 3 (MIS 3), a long and climatically unstable part of the last Ice Age. The responsible history of Ireland at this depth of time is therefore one of dated ranges, buried sediments and cautiously interpreted bones rather than named people or events.**

The best evidence relevant to this notional year comes from two very different archives: organic freshwater deposits exposed beneath a drumlin at Derryvree, near Maguiresbridge in County Fermanagh, and animal remains from Castlepook Cave near Doneraile in north County Cork. Neither is a snapshot of 30,941 BCE. Together, however, they show that parts of Ireland supported cold-adapted plants and animals before the great expansion of the last British–Irish Ice Sheet, and they raise—without yet conclusively answering—the question of whether people briefly reached the island.

## A Date Without a Diary

Radiocarbon ages are not calendar dates. They measure the diminishing radioactive carbon in once-living material and must be calibrated against independently dated records of past atmospheric carbon variation. At around thirty-three millennia ago, a single radiocarbon determination can calibrate to a broad, sometimes irregular, span of calendar years. The conversion from a modern BCE label to “years before present” also uses the scientific convention that “present” means AD 1950, not today.

Derryvree provides the closest Irish chronological anchor. Road works in 1969 cut through a drumlin and revealed fine sands, silts and organic layers trapped between two thick tills: deposits laid down by separate episodes of glacial ice. The organic material produced the radiocarbon determination BIRM-166,

30,500 radiocarbon years BP, with a sizeable statistical error. Published discussion places the deposit broadly within a calibrated interval of about 36,900–31,700 cal BP. That interval encompasses the approximate calendar position of 30,941 BCE, but it does not date a particular season, animal, journey or human visit in that year.

## **Freshwater Beneath a Drumlin**

The Derryvree succession is important because it records a period when the Fermanagh locality was not buried beneath the later ice that moulded the drumlin. Its silts accumulated in or beside slow-moving freshwater. Pollen, plant macrofossils, mosses and insect remains survived in the sediment, making this one of Ireland's rare windows into an older Ice Age landscape subsequently concealed or scoured by glaciation.

The evidence supports open, largely treeless tundra or muskeg-like wetland, not forest. Grasses, sedges, herbs and juniper were represented, alongside a rich moss flora. A fossil seed of bogbean, a plant of shallow freshwater and wet ground, is especially evocative. Insect evidence indicated pools with abundant plant material and mossy margins. These are direct observations from the deposit. The wider reconstruction—a patchwork of sedgy wet ground, shallow pools, frost-affected soils and exposed terrain—is an interpretation, but a well-supported one.

Such a place was not lifeless. Wet hollows could hold water during the brief growing season; mosses and sedges bound saturated ground; herb-rich areas supported grazing animals. Yet the conditions were severe. Earlier researchers inferred harsh winters and a periglacial climate, meaning a cold environment shaped by seasonal freezing and thawing around, rather than necessarily beneath, permanent ice. There is no warrant for imagining a uniform white wilderness. Nor is there evidence for a milder wooded Ireland. Derryvree instead suggests a local cold wetland within an open northern landscape.

## **Ice Was Advancing, Not All-Present**

The island's glacial history is more complicated than a simple advance and retreat. Recent reconstructions show that the British–Irish Ice Sheet developed through changing regional patterns, with evidence for earlier growth and retreat phases during MIS 3 as well as its better-dated expansion towards the Last Glacial Maximum. The major maximum came later, around 26,000–23,000 years ago. At the time represented by Derryvree, some Irish areas could preserve ice-free deposits while ice masses and glacier-fed seas affected other parts of the wider archipelago.

Accordingly, Derryvree must not be used to claim that the whole of Ireland was simultaneously ice-free, nor should later glacial landforms be projected unchanged backwards onto its landscape. Renewed ice advance eventually covered the freshwater sequence with till. That physical relationship is the central fact: an episode of wet, open country was followed by glaciation powerful enough to bury and preserve its remains. The landscape of 30,941 BCE was dynamic, with climate, ice margins, drainage and coastlines changing on timescales far longer than a human lifetime but sometimes startlingly quickly in geological terms.

## Reindeer Country in Cork

Castlepook Cave, also known as Mammoth Cave, offers a complementary record from the south. Its old collections contain remains attributed to reindeer, giant deer, woolly mammoth, brown bear, wolf, fox, hare, lemmings and spotted hyaena. Improved radiocarbon methods have shown that some earlier dates from southern Irish caves were substantially too young, reinforcing the importance of MIS 3 fauna in Ireland. The cave demonstrates that Ireland formed part of a wider north-west European Ice Age ecological zone at least intermittently.

A cave bone, however, is not automatically a record of the place where an animal lived or died. Carnivores may drag carcass parts into dens; water and sediment can move bones; successive occupations may become mixed; and antiquarian excavation removed much of the original context. Castlepook's assemblage therefore cannot responsibly be treated as one herd, one hunting episode or one year's animal community. The animals represent a long and complicated accumulation.

Even so, the faunal evidence makes the Derryvree landscape more intelligible. Reindeer were suited to open, cold terrain and could range widely in search of seasonal grazing. Hyenas, wolves and bears indicate predators and scavengers within the food web. Mammoth and giant deer show that large herbivores also entered Ireland in at least some pre-maximum phases. Their presence does not prove a permanently connected land route at the specific date in question, but it does demonstrate ecological links sufficient for animals to colonise or recolonise suitable ground.

## The Single Cut-Mark Question

The most consequential possible human evidence is a reindeer femur from Castlepook. County Cork heritage material identifies it as dating to approximately 31,000 BCE and describes a deep mark interpreted by zooarchaeologist Ruth Carden as made by a sharp stone tool during butchery. If that interpretation is upheld, it would be evidence that Upper Palaeolithic people handled a reindeer in Ireland broadly near the period considered here—far earlier than the long-established post-glacial record of human presence.

Its implications must remain proportionate. The specimen comes from an old cave collection rather than a modern excavation of an intact occupation floor. A radiocarbon measurement dates the animal's death, not necessarily the instant a surface mark was made; recognising a stone-tool cut is a separate taphonomic judgement. No securely associated hearth, stone-tool assemblage, dwelling, burial, human bone or repeated butchered assemblage of comparable age has established a resident community at Castlepook. The bone may indicate carcass processing, but cannot reveal whether people killed the reindeer, encountered it dead, took only hide or sinew, removed meat and marrow, or processed it elsewhere before carnivores brought the bone to the cave.

## Society Beyond Recovery

There is no evidence from Ireland at this date for political institutions, leaders, territories, diplomacy, warfare, religion, language, art or formal learning. Equally, there is no basis for assigning a modern ethnic label or a named continental archaeological culture to any possible visitors. A single potential butchery mark cannot carry that weight.

If people did reach Ireland, the most economical interpretation is of a very small, mobile party familiar with sharp stone cutting edges and with the practical opportunities offered by large animals in a cold landscape. Such people may have moved according to animal movements, weather and accessible routes across a changing north-west European margin. This is an inference from the bone, the fauna and comparable hunter-gatherer economies, not a documented Irish social system. Permanent settlement, sustained population and regular exchange or trade remain unproved.

For everyday life, the environmental record gives firmer ground than archaeology. Survival for any visiting people would have depended on clothing, fire, shelter, food preservation and knowledge of terrain, but none of these has been recovered in Ireland from this period. The country's known evidence is too sparse to describe a camp, household or ritual practice. The appropriate historical emphasis lies instead on the natural setting: watery sedge beds in Fermanagh, open cold ground, large grazing mammals in Cork, predators in caves, and advancing ice that would later erase or bury much of the record.

## **What This Year Can Mean**


Thirty thousand years before the familiar monuments and manuscripts of Ireland, the island's history survives chiefly as mud, pollen, moss, insect fragments and bone. Derryvree establishes an ice-free freshwater and tundra environment within a broad calibrated range that includes this notional date. Castlepook establishes a rich Ice Age fauna and preserves a potentially transformative, but still limited, clue to human activity. Neither permits a year-specific event. Together they reveal an Ireland of ecological possibility, climatic instability and profound archaeological silence—one in which further excavation, improved dating and renewed study of museum collections may yet change the story.



# Chapter 061 of 100

## 30940 BCE

### BIRM-166's Cold-Stage Silts<sup>[61]</sup>



**Modern calendar-year precision is not available for Ireland in 30,940 BCE. No community on the island recorded years, events or rulers in a calendar that can be correlated with this label, and no excavated deposit can be dated closely enough to describe one particular season, let alone one day. The date is best treated as a modern point on a deep-time scale: roughly 32,900 calendar years before AD 1950, within the Late Pleistocene and Marine Isotope Stage 3 (MIS 3), a climatically unstable part of the last Ice Age.**

The responsible history of Ireland at this horizon is therefore a history of ranges, sediments and fossils rather than of named people or events. The most informative evidence is a buried freshwater sequence at Derryvree, near Maguiresbridge in County Fermanagh, supplemented by cave-fauna evidence from Castlepook Cave near Doneraile, County Cork, and by cave-mineral records from Crag Cave in County Kerry. These sources do not provide a countrywide snapshot. Together, however, they show that Ireland's environment was changing sharply as cold conditions intensified and the British–Irish Ice Sheet grew.

## **A Date Within a Range**

The key Derryvree sample, BIRM-166, came from organic mud and fine sediment exposed in a road cutting through a drumlin in 1969. It returned a conventional radiocarbon age of 30,500 years BP, with a substantial uncertainty of +1,170 and –1,030 years. A radiocarbon measurement is not identical to a calendar age: atmospheric carbon-14 has varied through time, so results must be calibrated against an independently constructed curve. At this antiquity the outcome is necessarily a broad probability range, not an annual date.

Published calibrations and later discussions place the Derryvree organic deposit broadly around 36,900–31,700 calibrated years BP, approximately 34,950–29,750 BCE. The nominal year 30,940 BCE falls within that wide interval. This does not mean the sediment formed in that precise year, or that its plants and insects were all alive together. It means that Derryvree is the closest securely dated Irish environmental archive capable of illuminating conditions around this chronological horizon.

The layers at Derryvree make its importance especially clear. Beneath the organic beds lies one body of till, the unsorted debris left by glacier ice. Above them lies another. Between the two, freshwater silts, fine sands and moss-rich mud accumulated. The sequence demonstrates a local order of events: glacier ice had occupied the site; a period followed in which open water, vegetation and animal life left traces; then a later advance of ice buried and preserved the record. It is strong evidence for an ice-free interval at this part of Fermanagh, but not proof that all Ireland was simultaneously free of ice.

## **Wet Ground in an Open Country**

Derryvree was not the familiar wooded Ireland of later prehistory. Its pollen, plant macrofossils, mosses and insect remains point instead to a cold, exposed and largely treeless wetland landscape. Grasses and sedges were important, with juniper and herbs on open ground. Aquatic and waterside plants, including bogbean and alternate water-milfoil, indicate shallow freshwater. Mosses and lesser clubmoss, together with the sedimentary setting, support the interpretation of saturated ground, pools and marshy margins: a tundra-like or muskeg environment shaped by short growing seasons and severe winters.

That description is an interpretation assembled from ecological evidence, not a literal view of every valley. A buried wetland is a local archive. It tells us what grew in and around this particular waterlogged hollow, not that every Irish coast, upland and basin looked identical. Yet the deposit's cold-adapted flora and fauna show that even during a harsh glacial phase, water and vegetation persisted in suitable places. Ireland was not simply a blank white expanse. It contained habitats with their own small-scale variety: open soil, wet sedge beds, mossy pools, shallow water and frost-affected ground.

Crag Cave provides a different kind of evidence from south-west Ireland. Stalagmites and other cave calcite grew episodically during MIS 3, then ceased growing during colder intervals. Growth required liquid water to percolate through the limestone and so indicates episodes when the ground above was neither sealed by glacier ice nor continuously frozen. Such records underline the instability of the climate. They do not establish the conditions of Derryvree in a particular year, but they show that the island was subject to repeated shifts between relatively milder interstadial phases and much more severe cold.

## **Animals at the Atlantic Edge**

Castlepook Cave preserves the most striking Irish evidence for the animal communities of this wider period. Its historical collections include remains attributed to woolly mammoth, reindeer, spotted hyaena, brown bear, fox, hare, lemmings and other animals. Earlier dates on mammoth and hyaena material fall broadly in the Middle Midlandian, before the fullest expansion of the last ice sheet. The assemblage demonstrates that Ireland was connected ecologically to north-western Europe at intervals when these mammals could reach and occupy suitable habitats.

A cave bone collection must, however, be handled with care. Many Castlepook specimens were recovered during antiquarian excavations, before modern stratigraphic methods. Carnivores, especially hyaenas, could have carried carcass material into the cave; water, digging and later disturbance could mix

material of different ages. The bones therefore do not describe one simultaneous herd or a single hunting episode. They establish the presence of particular species during a broad span, and they suggest an open landscape capable of supporting grazing animals, predators and scavengers.

There is no sound basis for identifying a fixed animal population, a managed hunting territory or a seasonal migration route within Ireland at 30,940 BCE. Nevertheless, the faunal record is important because it confirms opportunity as well as constraint. Reindeer and mammoth required plant food across open country; large carnivores relied on prey and carrion; cave shelter offered a focus for carnivore activity. The Irish landscape around this time could support more life than later maximum-glacial conditions would allow, even though that life was vulnerable to swiftly changing climate and expanding ice.

## **The Human Question**

One reindeer femur from Castlepook has made this period archaeologically exceptional. A deep linear modification on the bone has been interpreted by zooarchaeologist Ruth Carden as a mark made on fresh bone by a sharp stone tool, and modern radiocarbon work has placed the animal at about 33,000 years ago. If the mark is confirmed as human-made, it would indicate that people processed a reindeer in Ireland during MIS 3, far earlier than the island's previously accepted evidence for human activity.

That is a consequential possibility, but it remains a possibility rather than a settled population history. The dated bone does not come from a securely excavated occupation floor with associated stone tools, hearths, shelters, repeated activity surfaces or human remains. Its age dates the reindeer, not automatically the making of the mark or the identity of its maker. A sharp-edged break, carnivore damage or other natural process must be excluded through continuing specialist analysis. The appropriate conclusion is that Castlepook raises a serious question about an early human visit; it does not demonstrate a permanent settlement, named culture or island-wide community.

Accordingly, everyday social life cannot responsibly be reconstructed for Ireland itself. There is no direct Irish evidence here for families, language, dress, ritual, art, burial practice, teaching or formal leadership. If people did reach the island, their survival would presumably have depended on knowledge of weather, animal behaviour, fuel, shelter and stone-working, as among Upper Palaeolithic hunter-gatherers elsewhere in Europe. But that is a comparative inference, not a fact recovered from an Irish camp.

## **No Politics, No Trade Records**

Political affairs, diplomacy and organised conflict are beyond the evidence. There were no states, written agreements, rulers or frontiers identifiable in Ireland at this date. Nor is there direct evidence for trade: no confirmed Irish assemblage of tools or ornaments can be used to chart exchange routes, and no securely attested settlement allows an economy to be described. It would be misleading to turn the changing position of sea, ice and land into a confident account of human crossings. These were environmental conditions that may have enabled or obstructed movement at different times, not proof of a regular route into Ireland.

What can be stated with greater confidence is that environmental change was the dominant historical force. Recent reconstructions of the British–Irish Ice Sheet indicate substantial growth from about 31,000 years ago, followed by more extensive glaciation in the succeeding millennia. Ireland's ice cover did not


advance as one perfectly uniform front: uplands, basins, coasts and neighbouring marine sectors responded differently. Still, the broader trajectory was towards a colder world in which advancing ice, altered drainage and periglacial processes repeatedly erased, buried or rearranged older landscapes.

For that reason, Derryvree's silts are more than a technical geological curiosity. They preserve an interval that later ice almost obliterated: freshwater among drumlins, cold-climate vegetation on wet ground, and insects in a treeless landscape. Castlepook preserves a complementary animal record, while Crag Cave registers climatic interruption and recovery. Around 30,940 BCE, Ireland cannot be given a conventional annual chronicle. It can be understood, more faithfully, as a changing Late Pleistocene island whose sparse archives reveal living wetlands and large mammals on the threshold of much greater glaciation.

# Chapter 062 of 100

## 30939 BCE

### Derryvree's Intertill Wetland<sup>[62]</sup>



The label 30,939 BCE cannot describe a recoverable year in Irish history. No calendar, written record, settlement sequence or securely dated event enables archaeologists to isolate a particular season, person or occurrence at this depth of time. It is a modern numerical label placed within the Late Pleistocene, broadly Marine Isotope Stage 3 (MIS 3), when climate and ice margins changed repeatedly. The responsible account is therefore one of deposits, fossils and calibrated ranges, not an annual chronicle.

## A Date Within a Range

The most useful Irish evidence comes from Derryvree, near Maguiresbridge in County Fermanagh. Roadworks exposed a drumlin cut by a sequence of deposits: a lower glacial till, then fine sands and organic freshwater sediments, and finally an upper till. Till is unsorted material laid down by glacier ice. The order is consequently secure even where absolute dating is broad: ice had occupied the site; an ice-free interval allowed water, plants and animals to leave traces; later ice sealed that evidence beneath fresh debris.

Organic material from the intervening Derryvree deposits produced the conventional radiocarbon determination Birm-166, 30,500  $\pm$  1,170/–1,030 radiocarbon years before present. “Present” in radiocarbon convention is AD 1950, not the present day. Radiocarbon ages of this antiquity are not calendar years and must be calibrated against changing atmospheric carbon levels. Scholarship using modern calibration places the deposit broadly at about 36,900–31,700 calibrated years BP, or roughly 34,950–29,750 BCE. The requested date falls inside that wide interval, but it cannot be assigned to a particular layer, pool, animal or human lifetime. The range is evidence; a precise year is not.

Derryvree is important because it demonstrates that at least one part of Fermanagh experienced a cold, non-glacial interval during the long build-up towards the Last Glacial Maximum. It does not prove that all Ireland was ice-free at once. Nor should it be treated as a weather station for the whole island. Nevertheless, its unusually rich plant, insect and sedimentary record gives a rare, local view of an Ireland very different from the familiar wooded and farmed landscape of later millennia.

## Cold Water, Open Ground

The fossil assemblage points to a treeless, periglacial wetland mosaic. Pollen, seeds, plant fragments and mosses include grasses and sedges, juniper, herbs and species associated with shallow freshwater or saturated ground. Bogbean, water-milfoil, mountain-avens, dwarf willow and lesser clubmoss have all been identified or reported from the Derryvree record. Together with insects of cold northern character, they support an interpretation of pools, wet margins, mossy ground and sparse open vegetation rather than mature temperate woodland.

“Tundra” is a useful shorthand, provided it is not made too uniform. The evidence suggests patches of water, sedge-rich marsh, low-growing plants and exposed mineral ground, responding to local drainage, relief and season. A drumlin landscape could create sheltered hollows as well as wind-swept rises. Summer growth may have been intense but brief; winters were severe, and frost action shaped the ground. The organic beds preserve a living wetland because later ice covered and protected them. Their survival is exceptional, not proof that comparable deposits once remained everywhere.

Regional records reinforce the larger conclusion that the late Ice Age was not one uninterrupted freeze. Organic deposits at Hollymount near Maguiresbridge and Greenagho near Belcoo, as well as other sequences in Northern Ireland, show that cold, ice-free or less heavily glaciated phases occurred between episodes of glacial advance. Yet the chronology of individual Irish cold stages remains debated. Correlations made from old regional names such as the Fermanagh, Derryvree and Maguiresbridge substages remain useful descriptive tools, but modern ice-sheet research warns against treating them as a single, island-wide timetable.

## An Island Approaching Glaciation

At this point in the wider last glacial cycle, Ireland lay in an unstable north-west European zone. The Last Glacial Maximum itself came later, conventionally around 26,500–19,000 years ago globally, although advances and retreat differed markedly from one sector of the British–Irish Ice Sheet to another. Large modern dating programmes show ice expansion across Ireland and its continental shelves occurring asynchronously between about 30,000 and 22,000 years ago, with maximum ice volume around 23,000 years ago.

For the period encompassing 30,939 BCE, that means neither a simple picture of an entirely ice-covered Ireland nor one of a mild, continuously habitable island is warranted. Derryvree shows ice-free freshwater conditions in Fermanagh during the broad calibrated interval. Elsewhere, glaciers, permafrost-like ground conditions, meltwater and changing sea levels altered routes, habitats and preservation. Later ice eroded many older landscapes and buried others under till. This geological violence is one reason why the archaeological record is so fragmentary: absence of a camp is not automatically proof that no person ever entered Ireland, but it is also not evidence that people lived there.

Sea level was considerably lower than today because water was held in northern ice sheets. Ireland was therefore not necessarily separated from Britain by the familiar modern sea channels throughout every part of MIS 3. But coastlines, rivers and potential land connections shifted over long intervals, and much of any former lowland terrain now lies beneath the Irish Sea or has been reworked by later ice and water. It is responsible to say that movements of animals and, potentially, people were geographically more possible than under modern conditions; it is not responsible to map a precise route for a journey in this notional year.

## **Cave Fauna and a Cautious Human Question**

Castlepook Cave, also called Mammoth Cave, near Doneraile in County Cork, provides the principal Irish faunal counterpoint to Derryvree's wetland record. Excavations begun in the early twentieth century recovered a remarkable collection that includes reindeer, woolly mammoth, giant deer, brown bear, wolf, Arctic fox, lemmings and spotted hyena. The National Museum of Ireland holds, among other specimens, an incomplete spotted-hyena skull from the cave. Such animals show that Ireland was reached, at different times during the Late Pleistocene, by mammal communities now unimaginable in the island's fauna.

These cave deposits must be handled carefully. A cave bone collection is not a snapshot of a single landscape or year. Carnivores may have dragged prey into dens; animals died at different times; water and sediment moved material; and the early excavations pre-dated present-day standards of contextual recording. Radiocarbon work by the Irish Quaternary Fauna Project showed that Irish mammals colonised during a long span, at least between about 45,000 and 20,000 years ago. Individual species and bones from Castlepook cannot therefore all be assumed contemporary with Derryvree.

One reindeer femur from Castlepook has an especially consequential, but limited, relevance. Zooarchaeologist Ruth Carden has interpreted a deep linear mark on it as damage made by a sharp stone tool while fresh bone was being processed. County Cork heritage material presents the object as dating to about 31,000 BCE. If that interpretation and association are sustained, it would indicate Upper Palaeolithic people handled a reindeer in Ireland during a broad period near this date.

That is not evidence for a settled Irish population. No securely associated hearth, stone-tool assemblage, dwelling, burial, art object or repeatedly occupied surface of comparable age has been recovered at Castlepook. Recent excavation has sought surviving Pleistocene deposits but reported no cultural artefacts. A single marked bone cannot determine whether people hunted the animal, scavenged it, took hide or sinew, stayed for hours or weeks, travelled in a party, or returned. The securely dated cut-marked brown-bear bone from Alice and Gwendoline Cave in County Clare is much later, around 12,800–12,600 calibrated years BP. It remains the firmer direct archaeological evidence for human activity in Ireland.

## **Society Beyond the Evidence**

There were no states, kings, borders, treaties or recorded political affairs in Ireland at this time. Equally, the evidence does not permit the reconstruction of clans, languages, religious observance or named cultural traditions. There is no basis for claiming that any group held a permanent territory in Fermanagh or Cork, traded across a particular route, or practised a known ritual. Those are questions archaeology can sometimes approach through camps, tools, burials and repeated settlement traces; the Irish evidence for this period does not yet provide them.

If humans did visit, their everyday priorities would have resembled those of mobile Upper Palaeolithic groups elsewhere in north-west Europe: warmth, shelter, fresh water, animal food, hides, fuel and workable stone. Reindeer and other herbivores would have been potential resources, while wolves and spotted hyenas were formidable competitors and scavengers. But this is comparative interpretation, not a description of an excavated Irish camp. No evidence currently demonstrates agriculture, domesticated animals, metalworking, long-distance commerce or permanent villages on the island.


The strongest history for 30,939 BCE is thus environmental. Beneath a Fermanagh drumlin, freshwater sediments preserve a cold wetland alive with plants, insects and seasonal change. In Cork caves, bones testify to animal movements through an intermittently connected Ice Age world. Together they reveal an island of shifting habitats at the threshold of more extensive glaciation. They also define the limits of knowledge: Ireland can be placed within a broad calibrated interval, but no responsible account can turn that interval into a dated human drama.



# Chapter 063 of 100

## 30938 BCE

### Derryvree's *Menyanthes* Bed<sup>[63]</sup>



Modern calendar precision is not available for Ireland at this depth in time. “30,938 BCE” is a useful modern label, roughly 32,887 calendar years before AD 1950, not a date that anyone living then recognised or that archaeology can resolve into a single season, event or generation. The responsible setting is the Late Pleistocene, within Marine Isotope Stage 3 (MIS 3), a long and climatically unstable part of the last Ice Age. Around this broad horizon, Ireland’s history is environmental rather than political: the evidence consists of buried sediments, fossil plants, insects, cave bones and changing ice margins, not written records, settlements or named peoples.

That distinction matters. There is no basis for describing an Irish government, tribe, war, diplomacy, religion or established culture in this particular year. Nor is there secure evidence for a permanent human community on the island. What can be reconstructed, cautiously, is a changing northern landscape in which ice, water, frost and mobile animals repeatedly altered the possibilities for life. The best evidence is local and discontinuous, but it establishes that parts of Ireland could support living ecosystems during MIS 3 before the far more extensive glaciation of the Last Glacial Maximum.

## A Number Within Deep Time

The Late Pleistocene chronology requires care. Radiocarbon ages are conventionally expressed as years “before present”, where present means AD 1950; they are not direct calendar ages. Changes in atmospheric carbon-14 mean that a laboratory determination must be calibrated against independent records, and the result is normally a probability range rather than one exact year. At more than 30,000 years ago, those ranges can be broad. Accordingly, 30,938 BCE should not be treated as the date of a specific Irish archaeological occurrence, but as a point within an interval of major environmental change.

The island's relevant archaeological-period label is Upper Palaeolithic Europe, but that label must not be mistaken for proof of an Upper Palaeolithic settlement in Ireland. In continental Europe and Britain, people of this era were mobile hunter-gatherers using stone, bone and antler technologies, with rich evidence of camp sites, hunting and symbolic culture. Ireland has not yielded a comparable securely dated habitation site from this time. Its record is both thinner and more vulnerable to later glacial erosion, sediment movement and the disturbance of old cave excavations.

## The Derryvree Wetland Archive

The most illuminating Irish evidence comes from Derryvree, near Maguiresbridge in County Fermanagh. Road works in 1969 exposed a drumlin cut by a sequence of deposits: thick glacial till below, freshwater silts and organic material in the middle, and another till above. The order is crucial. It shows that glacier ice had occupied the site, that an interval of open water and vegetation followed, and that later ice advanced across the area and sealed the deposit. This is not a historical narrative, but an exceptionally valuable geological record of an ice-free episode within the wider glacial cycle.

Organic sediment from Derryvree produced the radiocarbon determination BIRM-166, 30,500 with an uncertainty of  $+1,170/-1,030$  radiocarbon years BP. Later scholarly compilations have expressed it approximately as  $35.9 \pm 1.1$  thousand calibrated years BP, demonstrating both its antiquity and its substantial chronological uncertainty. The deposit cannot therefore be assigned neatly to 30,938 BCE. It is, however, directly relevant to the same later-MIS-3 world: a time before the Last Glacial Maximum, when parts of Ireland were not continuously buried beneath an ice sheet.

Its fossils describe a cold, treeless and waterlogged setting. Grasses and sedges, juniper, hardy herbs and a distinctive moss flora point to open vegetation rather than closed woodland. Plant remains include mountain-avens, dwarf willow, lesser clubmoss, bogbean (*Menyanthes trifoliata*) and water-milfoil. Together they indicate saturated ground, shallow pools and freshwater margins within a frost-affected landscape. Insect evidence supports the interpretation of muskeg-like wetland: wet, peaty or mossy ground with open water and abundant decaying vegetation. The evidence is strongest for the Derryvree locality itself; it should not be expanded into a detailed map of every Irish valley or coast.

## Cold Country, Not Permanent Ice

The Derryvree sequence corrects two misleading extremes. Ireland at this time was not the wooded, temperate island familiar from later prehistory, but neither was it necessarily a single, unchanging expanse of permanent ice. MIS 3 involved abrupt climatic oscillations across the North Atlantic world. In south-west Ireland, uranium-thorium dating of broken cave stalagmites at Crag Cave demonstrates that calcite was deposited episodically during warmer interstadials, when liquid water could circulate through the shallow cave system. That does not date a particular mild spell to this numbered year, but it confirms a climate capable of rapid shifts between more and less favourable conditions.

The approach of heavier glaciation remained the great regional development. Reconstructions of the last Irish and British-Irish ice sheets place their maximum expansion later, broadly around 27,000–23,000 calibrated years BP in Ireland and its surrounding shelf seas. Around the horizon represented by this article, ice-sheet growth, local glacier advances, periglacial frost and changes in drainage were already reshaping the island. Subsequent ice would erode older deposits in some places while preserving others beneath till. Much of what can be known today is therefore an accident of survival: Derryvree endured because it was buried, while many former land surfaces did not.

## Caves and Travelling Animals

County Cork's Castlepook Cave, also called Mammoth Cave, offers a different kind of archive. Cave excavations there produced bones of animals associated with late Pleistocene cold-stage environments, including reindeer, woolly mammoth, giant deer, brown bear, wolf, Arctic fox, lemmings and spotted hyaena. The National Museum of Ireland regards Castlepook as the country's most important site for mammal remains from the last cold stage. Such animals reveal that Ireland was connected ecologically to the wider north-west European world, able at intervals to receive or sustain species now absent from the island.

Yet the cave assemblage must not become a single imagined scene. Many of its deposits were excavated long ago, are mixed or disturbed, and contain material accumulated over a long period. Modern ultrafiltration radiocarbon work has shown that several older dates from southern Irish caves were substantially too young, changing interpretations of when particular animals were present. The revised work suggests that some species, notably spotted hyaena and giant deer, may have disappeared locally before about 40,000 calibrated years BP. A mammoth bone, a hyaena skull and a reindeer bone therefore demonstrate the broader MIS-3 faunal world, but do not prove that all these creatures shared one Cork landscape in 30,938 BCE.

For everyday life, animals provide stronger evidence than people. Reindeer are especially suggestive of open country with extensive grazing, while lemmings, mountain hare and Arctic fox indicate severe cold-stage conditions. Predators and scavengers such as hyaenas, wolves and bears imply food webs far more varied than later Irish faunas. There is no evidence, however, for herding, cultivation, cereal growing, livestock, pottery, metalwork, built villages or regular commerce. Any economy then present was ecological: plants grew in short seasons, herbivores moved through available habitats, and carnivores followed prey and carrion.

## The Human Question

A reindeer femur fragment from Castlepook has attracted particular attention because a surface mark has been interpreted as having been made by a sharp stone tool during carcass processing. County Cork heritage material has presented the bone as possible evidence for human activity around 33,000 years ago. If that interpretation is confirmed, it would be exceptionally important: it would show that one or more Upper Palaeolithic people reached Ireland much earlier than the formerly accepted post-glacial settlement record.

The correct conclusion remains deliberately limited. One marked bone is not a settlement, camp, hearth, burial, tool assemblage, hunting territory or continuous population. It cannot tell us whether people killed the reindeer, found it dead, removed meat or hide, remained nearby, or returned. Crucially, the National Museum of Ireland continues to state that no clear evidence has yet emerged for human presence in Ireland during the Palaeolithic. The apparent tension reflects the state of the evidence: a significant claim is being investigated against a record that is extremely fragmentary. Around 30,938 BCE, human visitation is a possibility requiring further secure excavation and publication, not an established annual fact.

## No Politics, Only Landscapes


Political affairs, conflict and diplomacy leave no identifiable trace for Ireland at this date. There are no names, boundaries, leaders, monuments, shrines or objects from which a religion can responsibly be reconstructed. Culture and learning cannot be described in specifically Irish terms either. If people were present, they may have belonged to wider mobile foraging networks of north-west Europe, but that is an inference from regional archaeology, not direct evidence of an Irish society. Likewise, lowered sea levels may have altered coastlines and routes, but neither a land crossing nor seafaring connection can be assumed for one moment in MIS 3.

The important development was instead the unstable relationship between land, climate and living things. Derrynree preserves a wetland that existed between glacial episodes; Crag Cave records intervals when water again made stalagmites; Castlepook preserves traces of a changing cold-stage fauna. Together, these archives show an Ireland of tundra-like vegetation, freshwater pools, periglacial ground and episodic ecological opportunity. They also demonstrate the limits of historical storytelling at such depth. This was not a year of recorded Irish events. It was a point within a long Ice Age transformation, whose surviving evidence is powerful precisely because it is sparse, local and carefully resistant to invention.

# Chapter 064 of 100

## 30937 BCE

### The Derryvree Bogbean Seed<sup>[64]</sup>



**30,937 BCE is not a year that can be recovered from the Irish record as an eventful point on a calendar. It is a modern calendrical label, approximately 32,886 years before AD 1950, used here to examine a much broader prehistoric interval. No annals, objects with inscribed dates, settlements or graves permit an annual history. The responsible framework is the later part of the Pleistocene, within Marine Isotope Stage 3 and the Irish “Middle Midlandian” cold stage. The most useful evidence is environmental and geological: freshwater deposits sealed beneath glacial sediments in County Fermanagh, and animal remains preserved in caves, particularly in north County Cork.**

The closest dated Irish sequence is at Derryvree near Maguiresbridge, County Fermanagh. A conventional radiocarbon measurement from its organic deposits, BIRM-166, gave  $30,500 \pm 1,100$  radiocarbon years BP. Radiocarbon years are not calendar years: changing atmospheric carbon levels mean that they must be calibrated, and at this depth of time the result is necessarily a broad probability range. Modern recalibration places the Derryvree horizon broadly around 36,900–31,700 calibrated years BP, or approximately 34,950–29,750 BCE. Thus 30,937 BCE can reasonably be treated as lying within the wider period illuminated by Derryvree, but not as the date when a particular seed fell, an animal passed by, or a human act occurred.

## **A Freshwater Interval Between Ice Advances**

Derryvree matters because of its physical arrangement. Roadworks exposed a section through a drumlin: a lower deposit of till, laid down by glacier ice; fine sands, silts and organic freshwater sediments above it; and another body of till sealing the sequence. This was not a normal soil horizon. It

was a buried environmental archive, formed after one phase of glaciation and before another. The organic bed establishes that, for a period, this locality was not overridden by ice and contained standing or slow-moving fresh water. Subsequent glacier advance then covered and protected the deposit.

That simple sequence is the strongest evidence available for regional change around this notional year. It shows alternation rather than a single, uniform “Ice Age” landscape. Ireland was not necessarily either entirely ice-covered or entirely ice-free. Local ice margins shifted, drainage changed and exposed ground could support ponds, wet hollows and vegetation before renewed glaciation transformed the terrain. The later Last Glacial Maximum was still to come: reconstructions indicate major expansion of the British–Irish Ice Sheet in the following millennia, with maximum ice extent broadly in the period after about 27,000 years ago. Derryvree is therefore a rare glimpse of a cold but locally ice-free phase before that more extensive glaciation.

## Wet Ground in a Treeless Country

The most vivid detail from Derryvree is modest in scale: a fossil seed of bogbean, *Menyanthes trifoliata*. Bogbean is a plant of wet ground and freshwater margins. Alongside it, the deposit has yielded evidence of mosses, sedges, aquatic plants and cold-adapted species including mountain avens and dwarf willow. These remains support a picture of pools and marshy fringes set within open, frost-affected ground. They do not justify imagining Ireland as a continuous bog, nor do they provide a botanical map for the whole island. They document conditions in and close to one northern basin.

Pollen and plant macrofossils are especially valuable because they correct later, familiar images of Ireland. This was not the green, wooded island of the recent past. The evidence points instead to a largely treeless landscape, with herbaceous cover, low shrubs and wetland communities able to survive short growing seasons and severe cold. “Tundra-like” is a useful comparison, provided it is not treated as an exact modern analogue. The island’s Atlantic setting, local relief, watercourses and nearby ice would have created a mosaic of exposed slopes, sediment-laden channels, marshes and shallow water.

Seasonal freezing and thawing probably shaped exposed surfaces. Periglacial conditions do not mean that the ground lay under a glacier; they describe the intense cold, frost action and sparse cover associated with terrain near ice or within a cold-stage climate. In such settings, meltwater could be vital. The freshwater sediments at Derryvree record a functioning local ecosystem, not a sterile wasteland, yet it was an ecosystem vulnerable to abrupt climatic and glacial change.

## Animals at Ireland’s Western Edge

County Cork supplies a different body of evidence. Castlepook Cave, also known as Mammoth Cave or Doneraile Cave, near the Awbeg Valley, produced Ireland’s richest known assemblage of pre-Last Glacial Maximum vertebrate remains. The cave material includes mammoth, reindeer, giant deer, brown bear, wolf, fox, Arctic fox, mountain hare, lemmings and spotted hyaena. Together, these fossils demonstrate that Ireland was connected ecologically to the wider north-west European world. Large mammals and predators could reach, or persist in, parts of the island during favourable phases.

But a cave assemblage must not be read as a census from one day. Castlepook’s bones accumulated through complex processes: animals may have died naturally, been dragged in by carnivores, entered through openings, or been moved by water and sediment. Much of the material was excavated in the late nineteenth and early twentieth centuries, before modern recording methods. Later material entered parts of the system too. Radiocarbon dates and species identifications are therefore essential, but they cannot

eliminate every problem of mixing and context. The secure conclusion is that a varied cold-stage fauna occupied Ireland over a considerable span; it is not that all listed animals shared one landscape at 30,937 BCE.

Nevertheless, Castlepook makes Derryvree's wetland less isolated. Reindeer and mammoth imply open country with substantial grazing resources somewhere in the wider region, while hyaenas and wolves show that large carnivores were present. These animals did not create a human economy, but their remains reveal the ecological possibilities of a periodically accessible western peninsula. The sea was much lower than today during glacial conditions, and the geography of the Irish Sea basin differed greatly from the modern island setting. Connections to Britain and continental Europe changed as ice, sea level and coastlines changed.

## **The Human Question**

There is no securely excavated house, hearth, stone-tool assemblage, burial, artwork or settlement in Ireland that can be assigned to 30,937 BCE. Accordingly, there is no basis for describing a resident population, a language, a tribe, political authority or an Irish Upper Palaeolithic society at this date. Political affairs, diplomacy and organised conflict are simply beyond the evidence. So too are religion, formal learning, exchange systems and social rank. Their absence from this account is not an invitation to fill the silence with Celtic myth, later folklore or assumptions drawn from other countries.

There is, however, an important and unresolved clue. A reindeer femur from the Castlepook material has been reported as bearing a sharp mark interpreted as stone-tool butchery, and it has been associated with an age of roughly 33,000 years ago. If that interpretation is upheld by continuing specialist study, it would indicate that a person, or a very small party, handled and perhaps processed a reindeer in Ireland during this broad interval. It would be a major extension of the island's human record.

Yet the claim must remain provisional. One possible cut mark on a bone recovered from an old, complicated cave excavation cannot establish permanent occupation. It cannot identify a cultural group, prove a camp nearby, or show that people returned regularly. Carnivore damage, trampling, breakage, excavation disturbance and the challenge of tying a specimen to a precise layer all demand caution. Recent excavation at Castlepook has sought surviving deposits that may improve the chronology and context. Until fuller published evidence resolves the question, the most accurate formulation is that brief human visitation is possible, while settled human presence in Ireland around this time remains unproven.

## **Everyday Life, If Visitors Came**

It is possible to offer a carefully limited comparison. In north-west Europe, Upper Palaeolithic people were generally mobile hunter-gatherers whose lives depended on knowledge of animals, seasons, stone, shelter and routes through changing landscapes. If people reached Ireland during the Derryvree–Castlepook horizon, they would probably have travelled in very small groups and made short-term decisions around food, weather and movement. This is an inference from the wider European archaeological record, not a demonstrated account of an Irish community.

No trade can be shown in the ordinary sense. There are no known imported ornaments, exchanged raw materials or recognisable tool industries from Ireland at this date. Nor can farming, herding, pottery, metalworking or monument-building be projected backwards from later prehistory. The only economy

directly visible is the ecology of the landscape: vegetation taking hold in wet ground; herbivores feeding across open terrain; carnivores hunting or scavenging; water carrying silt; and ice repeatedly remaking the land.

The cultural significance of caves is equally unknowable here. Later Irish communities used caves for burial, ritual, storage and shelter, but later practice cannot be transferred to the Pleistocene. Castlepook was certainly a place where bones accumulated; whether any people regarded it as shelter, a butchery location, a landmark or simply a hazard in the landscape cannot yet be said.

## **What This Date Can Mean**

The most important development around 30,937 BCE was environmental instability. In Fermanagh, a freshwater wetland existed long enough to preserve bogbean, mosses and other cold-adapted life between episodes of glaciation. In Cork, cave deposits preserve evidence that substantial mammals and formidable predators had reached Ireland during the wider cold stage. These two archives are separated by geography and formed through different processes, but together they replace the misleading image of an unchanging frozen island with one of regional variety and repeated transformation.


Derryvree's bogbean seed is therefore a better guide to this date than an invented human drama. It is direct evidence for water, plants and a locally ice-free interval; it is not evidence for a named event. Castlepook's fauna is direct evidence for animals; a human presence remains a serious but unsettled interpretation. The broader lesson is one of preservation as much as history. Later ice sheets eroded, buried and rearranged much of the earlier record. What remains is fragmentary, but it is enough to show that Ireland, nearly thirty-three millennia before AD 1950, was a cold, open, environmentally dynamic place at Europe's far western edge.



# Chapter 065 of 100

## 30936 BCE

### BIRM-166's Periglacial Ledger<sup>[65]</sup>



**30,936 BCE is a modern chronological label, not a recoverable year in Irish history. No calendar, written record, named person, settlement surface or annual environmental sequence can tell us what happened in Ireland in that particular year. In the conventional archaeological system it lies roughly 32,885 years before AD 1950, but that arithmetic does not make it a precise prehistoric date. The evidence comes instead from deposits and bones measured with substantial uncertainty, then compared with calibration curves. The responsible subject is therefore a broad Late Pleistocene interval, within Marine Isotope Stage 3 (MIS 3), rather than an event of 30,936 BCE itself.**

This was part of the Midlandian cold stage: a long, uneven episode of the last Ice Age, marked by sharp climatic shifts, changing sea levels and repeated advances and retreats of ice. Ireland was not simply a white, permanently frozen island. Nor was it a familiar green island inhabited by established communities. Its surviving record indicates a variable and often severe environment in which locally ice-free ground, wet hollows, caves, animals and glaciers existed at different times and in different regions. Later ice movement destroyed, buried or reworked much of the evidence. What remains is fragmentary, but exceptionally informative when read cautiously.

## A Date Within a Range

The closest major Irish environmental archive is the Derryvree freshwater series near Maguiresbridge in County Fermanagh. Road construction in 1969 cut through a drumlin and exposed organic silts and fine sands between two layers of till, the unsorted debris deposited directly by glacier ice. The stratigraphy

establishes an important sequence: ice had affected the locality; then freshwater, sediment and vegetation accumulated during an interval when ice was absent locally; later ice advanced again and sealed the deposit.

Organic material from this intervening bed, catalogue number BIRM-166, produced a conventional radiocarbon determination of 30,500 +1,170/-1,030 radiocarbon years BP. Radiocarbon years are not calendar years. Using modern calibration, discussions of the deposit place it broadly at about 36,900–31,700 calibrated years BP. That is a wide span, and the notional date of 30,936 BCE falls within it only in the broadest chronological sense. It cannot be assigned to a particular pool, plant, animal, season or human action represented at Derryvree.

The distinction is more than technical. A sediment bed may have formed over generations or centuries; its organic matter can be mixed, transported or imperfectly preserved; and calibration curves at this depth of time retain wide uncertainties. Derryvree is consequently not an annual diary. It is evidence that south Fermanagh contained a freshwater and periglacial environment during part of later MIS 3, between glacial episodes. It is one of the clearest Irish windows onto the environmental world relevant to this date.

## **Fresh Water Beneath a Drumlin**

The Derryvree plant and animal evidence points to an open, treeless landscape of cold wet ground rather than forest. Pollen was poorly preserved, but the dominant signal is herbaceous. Mosses, grasses and sedges occurred with plants associated with cold or alpine conditions and shallow freshwater habitats, including mountain-avens, dwarf willow, lesser clubmoss, bogbean and water-milfoil. A bogbean seed is especially evocative: it confirms standing or slow-moving fresh water in a landscape otherwise shaped by cold and frost.

Researchers have interpreted the setting as tundra-like muskeg or fen: saturated ground, mossy vegetation, pools, sedge-rich margins and low plants able to endure short growing seasons. Periglacial does not mean that a glacier lay over the spot. It means a landscape strongly influenced by freezing and thawing, frost action and a cold climate near ice. The freshwater bed itself proves that Derryvree was not continuously ice-covered. It does not prove that all of Ireland was ice-free, or that the same vegetation extended without interruption across the island.

This regional qualification matters because Ireland's terrain, coastlines and ice margins were changing. Geological reconstructions show that the British-Irish Ice Sheet was entering a phase of major growth around and after 31,000 years ago. The later maximum was not reached until much later, but the approach to it was neither neat nor synchronous. Ice centres, valley glaciers and marine margins could expand or contract at different rates. A cold wetland in Fermanagh therefore belongs beside, rather than replaces, evidence for ice elsewhere.

## **Caves, Carrion and Grazing Animals**

Southern Irish caves provide a second, quite different archive. Castlepook Cave near Doneraile in north Cork has yielded an important collection of Late Pleistocene bones, much of it excavated in the late nineteenth and early twentieth centuries and later reassessed by the Irish Quaternary Fauna Project and more recent investigators. The assemblage includes remains attributed to reindeer, woolly mammoth, giant deer, brown bear, wolf, Arctic fox, mountain hare, lemmings and spotted hyaena. These animals demonstrate that Ireland could support, or at least be reached by, varied cold-stage fauna during MIS 3.

That list should not be turned into a single painted scene. Cave deposits can accumulate through scavenging, carnivore denning, water movement, natural deaths, excavation disturbance and collection practices extending over a long period. The fauna at Castlepook does not establish that every species lived together, at one moment, around 30,936 BCE. It does, however, undermine the notion of an ecologically empty Ireland before the last glacial maximum. Open country supplied grazing for herbivores, while predators and scavengers used the same wider landscapes and caves.

Reindeer are particularly compatible with a cold, largely open setting, though their bones do not disclose the route, size or seasonal behaviour of a particular herd. Mammoths and giant deer likewise signal substantial animal movement through Ireland at some points in the Late Pleistocene, not permanent residence in every region. Spotted hyaena remains are a reminder that caves were not neutral shelters: they could be places where carnivores carried prey, gnawed bones and created deposits later difficult to disentangle.

## **The Castlepook Human Question**

The most consequential possible human evidence is a reindeer femur from Castlepook, reported as dating to roughly 33,000 years ago and bearing a deep mark interpreted as a stone-tool cut made while fresh tissue was being removed. If that interpretation and association are confirmed, it would indicate that a person or very small group processed a reindeer in Ireland during MIS 3, far earlier than the formerly accepted evidence for human presence.

Yet the limits are decisive. The specimen derives from an old cave collection rather than a modern excavation of an intact occupation floor. No securely associated hearth, lithic assemblage, dwelling, burial, food-preparation area or repeated activity surface of comparable age has been identified. A modified bone may record a brief visit; it cannot demonstrate a permanent settlement, continuous population, named cultural group, language or migration route. The cut-mark interpretation is a taphonomic judgement requiring continued scrutiny, separate from the laboratory age of the bone itself.

Accordingly, society and everyday life cannot be reconstructed directly for Ireland at this date. If people reached the island, their subsistence may plausibly have involved highly mobile hunting and butchery, as among Upper Palaeolithic groups elsewhere in north-west Europe, but that is an inference from wider comparison, not a fact observed at Castlepook. There is no responsible evidence for Irish villages, families, leadership, territory, clothing traditions, art or ceremonial practice in this specific period.

## **No Politics, No Trade Network**

There were no recorded political affairs, warfare, diplomacy or institutions to describe. Even the existence of a durable human population remains unproven. Nor can archaeology identify an Irish economy in the later historical sense. There is no evidence for farming, herding, metalworking, exchange systems or organised trade. The only secure economic processes were ecological ones: plants exploiting brief growing seasons, herbivores feeding across open terrain, carnivores and scavengers competing for carcasses, and glacier ice repeatedly transforming drainage and landforms.

Low global sea levels exposed areas now submerged around north-west Europe, but that does not licence a simple picture of an easy land bridge from Britain to Ireland. The Irish Sea basin, local ice, sea level, islands and marine channels formed a changing and still debated geographical problem. Animal

arrivals demonstrate that routes existed at intervals, whether across exposed ground, ice, short water crossings or combinations of these. They do not establish one continuous corridor, and they say still less about any route used by people.

## **Learning From an Incomplete Record**

The principal development illuminated around this notional year was environmental instability. Derryvree records a locally ice-free freshwater refuge in Fermanagh; Castlepook documents an intermittently rich fauna in Cork; Crag Cave in County Kerry preserves speleothem evidence for repeated milder episodes during MIS 3; and ice-sheet research shows a rapidly changing glacial system moving towards larger expansion. Together these sources describe an Ireland of regional contrasts, not a uniform island-wide climate.


There was no religion or learning in a recoverable documentary sense, and no material evidence from this horizon securely identifies ritual or symbolic culture in Ireland. The intellectual achievement belongs to modern research: stratigraphy establishes the order of deposits; palaeobotany identifies plant remains; zooarchaeology reads animal bones; radiocarbon and uranium-thorium methods provide chronologies; and glacial geomorphology reconstructs ice movement. Each method has limits, but together they permit a disciplined account of a landscape otherwise almost erased.

For 30,936 BCE, then, Ireland's history is not a narrative of rulers or events. It is the history of cold water held between tills, low vegetation surviving on frost-worked ground, animals entering a shifting Atlantic borderland, and possible human contact that remains tantalising rather than proven. BIRM-166 is valuable precisely because it teaches restraint: it preserves a real Ice Age environment, but not an exact year, and certainly not a lost prehistoric society waiting to be named.

# Chapter 066 of 100

## 30935 BCE

### The Incised Castlepook Femur<sup>[66]</sup>



30,935 BCE is a useful modern label, but it was not a year that anybody in Ireland could have named, recorded or remembered in a calendar. It lies roughly 32,900 calendar years before AD 1950, within the Late Pleistocene and Marine Isotope Stage 3 (MIS 3), a long, climatically unstable interval of the last Ice Age. No excavated Irish layer can be assigned responsibly to this individual year. The evidence instead consists of wide calibrated ranges, glacial sequences, animal bones and plant remains. It can illuminate conditions in and around Ireland, but not a dated political event, a named community or an annual chronicle.

## Dating a Calendarless Landscape

The closest local chronological anchor is the Derryvree freshwater deposit near Maguiresbridge in County Fermanagh. Roadworks in 1969 cut through a drumlin and exposed organic silts and fine sands between two distinct sheets of till, the unsorted debris left by glacier ice. The sequence establishes an important order of events: ice deposited the lower till; an ice-free freshwater and wetland environment developed; later ice covered and sealed the deposit beneath the upper till. It does not supply a single moment in time.

Organic material from Derryvree produced the conventional radiocarbon determination Birm-166, 30,500  $\pm$  1,170/–1,030 radiocarbon years BP. Radiocarbon years are not the same as calendar years, because atmospheric carbon-14 has varied through time. Later calibration places the deposit broadly at about 36,900–31,700 calibrated years BP, or approximately 34,950–29,750 BCE. Thus 30,935 BCE falls within a large scientific range associated with the deposit, but it is not the date of a particular Derryvree season, settlement or encounter. The uncertainty is not a defect to be concealed: it is the proper scale of resolution for Irish evidence this deep in time.

## Derryvree's Open Wetland

Derryvree is the strongest direct environmental witness for this broad period. Its flora and fauna indicate a treeless, open tundra or muskeg landscape under periglacial conditions. Mosses, sedges, grasses, herbs, dwarf shrubs and aquatic plants occurred around shallow water, saturated ground and small pools. Fossil remains include bogbean (*Menyanthes trifoliata*) and mountain avens (*Dryas octopetala*), species consistent with cold, open environments. Insects strengthen the picture of wet ground rich in plant matter rather than a barren expanse of continuous snow or bare stone.

This was not modern Fermanagh transplanted into an Ice Age. There is no evidence for the familiar dense woodland, hedged fields, peat-cutting landscape or settled lakeshores of later millennia. Trees were absent locally, and winters were severe. Yet the freshwater silts show that water persisted and plants colonised sheltered low ground. The reasonable interpretation is a mosaic: wet hollows and pools, sedge-rich margins, mossy patches and exposed open ground, varying across short distances according to drainage, wind and snow cover. Derryvree should not, however, be treated as a complete map of Ireland. It records one northern locality, accumulated over time, not every coast, upland or valley on the island.

## Castlepook and the Animal World

County Cork provides a different but complementary archive. Castlepook Cave, also called Mammoth Cave, near Doneraile, yielded a major assemblage of Pleistocene animal remains during excavations in the early twentieth century. The surviving collection includes reindeer, woolly mammoth, giant deer, brown bear, wolf, Arctic fox, hare, lemmings and spotted hyena. Modern redating has shown that at least part of this fauna belongs to MIS 3, although old cave collections require particular caution: bones came from complex deposits, some earlier determinations have been reassessed, and not every specimen necessarily represents the same episode.

The Castlepook animals demonstrate that Ireland was connected, ecologically and at least intermittently, to the wider north-west European cold-stage world. Reindeer and Arctic fox suit open cold country; mammoth, giant deer and predators imply substantial grazing landscapes and food chains. Spotted hyena is especially significant. The National Museum of Ireland identifies Castlepook as Ireland's principal last-cold-stage mammal site and places hyena and associated mammals in a migration episode from Britain to Ireland broadly between 45,000 and 30,000 years ago. That conclusion concerns animal movement, not a permanent human population.

## A Bone and a Question

The article's title refers to a reindeer femur from Castlepook that has been publicly presented as about 33,000 years old and bearing a deep incision interpreted by zooarchaeologist Ruth Carden as a chop or cut made by a sharp stone implement. If that interpretation is sustained, it would be potentially momentous: a person may have processed reindeer in Ireland during MIS 3, far earlier than the long-established record of post-glacial occupation. The notional year 30,935 BCE lies close enough to this broad horizon for the bone to matter greatly to any account of the period.

But the distinction between evidence and interpretation is crucial. Radiocarbon dating determines the age of the animal bone, not automatically the date or cause of every mark on its surface. A mark may be anthropogenic, carnivore-related, produced during excavation, or altered after burial; its form must be

assessed taphonomically. Moreover, Castlepook has not produced a securely associated hearth, stone-tool assemblage, dwelling floor, human remains or a stratified butchery area of comparable age. The femur is therefore important possible evidence of a brief human visit, not proof of a settled Ice Age society in Ireland.

## **Society Without a Settlement Record**

For political affairs, diplomacy and conflict, the responsible answer is silence. There are no named peoples, leaders, territories, alliances, fortifications, weapons assemblages or burial rites from Ireland securely attributable to this date. It would be misleading to imagine tribes governing the island, battles over reindeer grounds, or relations between an “Irish” population and neighbours. Ireland as a modern nation had no relevance to the people, if any, who may have entered this landscape.

The same caution applies to everyday life, religion, culture and learning. No contemporary house, camp, hearth, artwork, grave, ornament, pottery vessel, textile, boat or written mark is known from Ireland. There was no farming, stock keeping, metalworking, village economy or trade network demonstrated by Irish evidence at 30,935 BCE. If people did reach Castlepook, a short hunting or scavenging visit is a plausible inference from the proposed modification of the reindeer femur and the available fauna. It remains an inference, not an excavated household or an enduring community.

Across the water, Upper Palaeolithic groups in Britain and continental Europe used stone technologies and hunted cold-stage animals. That wider context makes a human arrival in Ireland conceivable, particularly when sea level was lower and animal dispersal was possible. It cannot fill the Irish evidential gap. Lower seas did not automatically create a simple dry land bridge across every channel, and no Irish Palaeolithic seafaring craft is known. Any crossing, whether over ice, water or changing coastal terrain, remains unobserved in the Irish archaeological record.

## **Ice Building Beyond the Horizon**

The Derryvree interval preceded the full Last Glacial Maximum, but it belonged to a world moving towards much greater ice-sheet growth. Recent reconstructions show the British–Irish Ice Sheet building rapidly from about 31,000 to 26,000 years ago, with regional margins advancing and retreating asynchronously. The later maximum transformed much of Ireland and its surrounding shelves. Deposits such as Derryvree survived precisely because they were buried between tills: living wetland sediment became a sealed archive beneath later glacial action.

For 30,935 BCE, then, Ireland is best understood not as an empty page but as a fragmentary Ice Age archive. Fermanagh preserves cold freshwater life between episodes of glaciation; Cork preserves an unexpectedly rich animal world and a disputed hint of human butchery. Together they show a place of open wetlands, grazing animals, carnivores and advancing ice. They do not yet reveal a calendar year, a community’s name or a continuous human past. That restraint is what makes the evidence valuable.

# Chapter 067 of 100

## 30934 BCE

### Castlepook's Unfound Hearth<sup>[67]</sup>



**Modern calendar-year precision is not available for Ireland in 30,934 BCE. The label is useful only as a point within a very long prehistoric interval: roughly 32,883 years before AD 1950, the conventional ‘present’ of radiocarbon dating. It falls in the later part of Marine Isotope Stage 3 (MIS 3), a climatically unstable phase of the Last Glacial period. No Irish chronicle, calendar, settlement sequence or event can be assigned to this numbered year. The responsible history is therefore one of calibrated ranges, fossils, sediment layers and carefully qualified inference rather than a dated narrative.**

The nearest archaeological and environmental evidence places parts of Ireland in a cold, changing world before the fullest expansion of the last British–Irish Ice Sheet. Crucially, this was not necessarily an island sealed beneath continuous ice at every moment. Nor was it the wooded, temperate country familiar from later prehistory. Local ice margins, frozen ground, open vegetation, wetlands and animal movements altered over centuries and millennia. Evidence from northern and southern Ireland illuminates different places and spans; it cannot be compressed into a single island-wide weather report for one year.

## **A Range Rather Than a Year**

The best closely relevant environmental sequence comes from Derryvree, near Maguiresbridge in County Fermanagh. Roadworks in 1969 exposed organic freshwater silts and fine sands trapped between two thick layers of glacial till within a drumlin. The order of deposits is revealing. Ice had affected the locality before the freshwater bed formed; plants, small animals and sediment accumulated during an ice-free interval there; later glacial action buried the bed beneath another till. That makes Derryvree an unusually valuable record of environmental change, not a frozen instant in time.



Organic material from the bed produced a conventional radiocarbon age of 30,500 years BP, with a large uncertainty of +1,170 and -1,030 years. Later calibration places the deposit broadly around 36,900–31,700 calibrated years BP, approximately 34,950–29,750 BCE. The article's notional year falls within that wide range, but no individual plant, pool or occupation can be tied to 30,934 BCE. The proper conclusion is narrower: during part of this span, south Fermanagh supported a cold freshwater ecosystem between episodes of glaciation.

## **Water Beneath the Drumlin**

Derryvree's pollen, plant macrofossils, mosses and invertebrate remains indicate open tundra vegetation and a periglacial regime: ground affected by intense frost, seasonal thaw and short growing seasons. The deposit includes evidence for sedges, mosses and cold-adapted plants such as dwarf willow, mountain avens, lesser clubmoss and bogbean, alongside aquatic or wetland plants including water-milfoil. This was not a featureless snowfield. Around shallow or slow-moving freshwater, low vegetation could take hold; beyond it, exposed ground was likely sparse, cold and wind-swept.

Some pollen was poorly preserved, and isolated grains of tree pollen do not establish nearby forest. They may have travelled far or been redeposited. The stronger evidence supports an open, largely treeless landscape. Terms such as 'tundra' are useful shorthand but should not imply that every region of Ireland looked identical. Derryvree describes a particular northern locality and its catchment. It does, however, demonstrate that life persisted in ice-age Ireland in habitats where wet ground and freshwater were available.

## **Fauna on a Cold Landscape**

Southern cave deposits provide a second, larger-scale view. Castlepook Cave, also known as Mammoth Cave, near Doneraile in north County Cork, has yielded one of Ireland's most important Pleistocene animal collections. The Irish Quaternary Fauna Project showed that a broad range of mammals reached Ireland at various times between at least about 45,000 and 20,000 years ago. Improved radiocarbon pretreatment has also shown that several Castlepook specimens were substantially older than previously believed, placing significant elements of the assemblage in MIS 3.

The cave record includes reindeer, woolly mammoth, giant deer, brown bear, wolf, Arctic fox, mountain hare, collared lemming, Norwegian lemming and spotted hyaena. These animals do not all prove to have lived together at the exact same moment: Castlepook accumulated bones across a long period. Yet the assemblage firmly establishes that Ireland participated in the wider north-west European cold-stage fauna. Grazing animals suggest expanses of herb-rich open country; wolves and hyaenas indicate predators and scavengers following such resources. Spotted hyaena is especially notable, with Castlepook the principal Irish record.

Caves are not straightforward food stores. Carnivores can drag in carcass parts, gnaw bones and leave them exposed to trampling, water movement, collapse and later excavation. A mammoth or reindeer bone in a cave therefore demonstrates the animal's presence in the surrounding landscape, not necessarily human hunting, cooking or residence in the cave. This distinction is central to responsible interpretation of Ireland's very early past.

## The Marked Reindeer Femur

One Castlepook object makes this broad period especially important for Irish history. A reindeer femur in the National Museum of Ireland's natural-history collection bears a deep surface mark interpreted by zooarchaeologist Ruth Carden as having been made with a sharp stone tool during butchery. County Cork heritage material dates the bone broadly to about 31,000 BC, close to the date represented here; it also considers it likely that the butchered remains entered the cave later, perhaps carried by scavengers. If the interpretation of the mark is upheld, it would be Ireland's earliest presently claimed trace of human activity.

That claim must remain conditional. The femur comes from an old cave collection rather than a modern excavation of a sealed occupation surface. A radiocarbon determination dates the animal bone, not automatically the moment it was marked, the place where the carcass was processed or the number of people involved. Identifying a cut mark is a separate taphonomic judgement, requiring the exclusion of carnivore damage, abrasion and other natural or modern alterations. No securely associated stone-tool assemblage, hearth, shelter floor, human burial or human remains of comparable age has yet been recovered in Ireland.

The evidence can therefore support a limited but remarkable proposition: one or more people may have processed a reindeer in Ireland during the Upper Palaeolithic. It cannot establish a permanent settlement at Castlepook, a continuous population on the island, a named people or a particular route of arrival. A visiting hunting party, seasonal movement after game, or a short-lived incursion from the wider north-west European world are reasonable interpretations, not demonstrated facts.

## Society Beyond Recovery

There is no evidence for political institutions, rulers, territories, diplomacy or organised warfare in Ireland at this date. There is likewise no Irish evidence for agriculture, herding, metalworking, market exchange, monuments, formal religion, writing or schools. The absence of such evidence should not be mistaken for a claim that any visitors lacked social bonds, knowledge or belief. Upper Palaeolithic communities elsewhere in Europe possessed sophisticated stone technologies and rich cultural practices. But mainland comparisons provide context only: they cannot supply an Irish language, identity, ritual or artistic tradition where Irish finds do not.

Everyday life is recoverable only in the most general terms. If people did reach Ireland, they were mobile hunter-gatherers rather than farmers. Reindeer could have offered meat, hide, sinew, fat, marrow and bone, but the single marked femur cannot reveal which resources were taken, whether the animal was hunted or scavenged, or whether processing occurred at the cave. There is no evidence for trade in the later prehistoric sense. Mobility across the sea and adjacent landmasses may have connected people, animals and raw materials, but no securely identified imported object or exchange network belongs to this Irish horizon.

## Ice Yet to Come

The later Last Glacial Maximum is essential to understanding the sparse record. Research on the British–Irish Ice Sheet shows that its major expansion and maximum extent varied between sectors, with much of the best-dated Irish evidence for maximum conditions later than this article's period, broadly

after about 27,000 years ago and into the 20,000s BP. Southern Ireland was extensively glaciated during that later phase. Advancing ice eroded landscapes, remodelled drainage and buried or destroyed many earlier deposits.

Glaciation helps explain why evidence of any earlier human presence might be exceptionally slight, but it cannot be used to invent lost camps or populations. The balance of evidence around 30,934 BCE is both evocative and restrained: an Ireland of open, frost-affected wetlands in Fermanagh; cold-country mammals in Cork; and one reindeer bone whose possible cut mark may record a fleeting human action. Castlepook's hearth remains unfound. That is not a failure of the record, but its most important historical fact.

# Chapter 068 of 100

## 30933 BCE

### Derryvree's Winter Pond<sup>[68]</sup>



**30,933 BCE is a modern chronological label, not a year that can be recovered from an Irish archive. No contemporary calendar, written record, settlement sequence or securely dated human event allows Ireland to be described at annual resolution so far back. The responsible frame is therefore a broad one: approximately 32,880 years before AD 1950, in the Late Pleistocene, during Marine Isotope Stage 3 (MIS 3), a cold but highly variable interval of the last Ice Age. Radiocarbon results of this antiquity must be calibrated and expressed as ranges. The evidence can illuminate environments, animals and the possibility of human movement; it cannot supply a king, battle, treaty or named community for this particular numbered year.**

## **A Date Inside a Range**

The most valuable Irish environmental record close to this nominal date lies at Derryvree, near Maguiresbridge in County Fermanagh. Roadworks in 1969 cut into a drumlin and exposed a remarkable sequence: freshwater silts and fine sands, containing organic material, lay between two thick deposits of till. Till is unsorted debris laid down by glacier ice. The order of the layers is decisive evidence that ice had earlier affected the site, that an ice-free interval then permitted water, sediment and living things to accumulate there, and that a later advance buried the deposit beneath further glacial material.

Organic material from the Derryvree freshwater bed produced a conventional radiocarbon determination of 30,500 years BP, with a wide uncertainty of +1,170/–1,030 years. “BP” means before AD 1950, the standard reference point for radiocarbon dating; it does not mean calendar years. Published calibration has placed the deposit broadly around 36,900–31,700 calibrated years BP, approximately

34,950–29,750 BCE. The notional year 30,933 BCE falls inside that broad span, but it cannot be tied to a particular sediment layer, season, animal or human action. Derryvree is a time-averaged natural archive, not a diary.

This distinction matters. The date supports an interpretation of northern Ireland during part of the Middle Midlandian cold stage; it does not prove that every Irish region had identical weather, vegetation or ice cover in 30,933 BCE. Nor can a range spanning millennia decide whether one individual animal and one patch of sediment were contemporaneous. Yet the sequence provides unusually direct evidence that, before the Last Glacial Maximum, at least part of Ireland contained a cold, ice-free freshwater landscape.

## Open Ground and Shallow Water

Derryvree was not woodland. Pollen, seeds, mosses and other plant macrofossils point instead to open tundra or periglacial wetland: a landscape influenced by severe cold, repeated freezing and thawing, short growing seasons and seasonally saturated ground. The assemblage included sedges, grasses and herbs, alongside plants associated with cold open environments. Fossil remains of bogbean, a wetland plant, and mountain avens, a familiar Arctic-alpine species, are especially vivid indicators of shallow freshwater, marshy margins and exposed mineral ground.

Such a setting should not be reduced to an empty white wilderness. The freshwater silts imply pools or slow-moving water; mosses and sedges indicate ground that could retain moisture through the brief productive season. In summer, insect life and plant growth would have concentrated around wet places. Away from them, bare sediment, frost-shattered ground and sparse vegetation may have been common. Winter conditions were undoubtedly hard, but the Derryvree evidence shows ecological variety rather than uninterrupted ice. The older term “muskeg”, sometimes applied to this type of moss-rich, wet terrain, conveys something of its uneven, waterlogged character.

Crag Cave in County Kerry supplies a separate kind of environmental evidence. Uranium-thorium dating shows that speleothems there formed episodically during MIS 3. Because cave calcite needs liquid water moving through the rock, these growth episodes indicate intervals in which local conditions permitted groundwater circulation rather than continuous deep freezing. They do not demonstrate a uniformly mild Ireland, and Crag Cave is far from Fermanagh, but they reinforce the central point: the island experienced pronounced climatic oscillations during this long cold age.

## Cave Fauna in County Cork

At Castlepook Cave, near Doneraile in north County Cork, fossil assemblages preserve another window onto this world. The cave, also known historically as Mammoth Cave, yielded remains attributed to animals of cold open country, including reindeer, woolly mammoth, giant deer, wolf, Arctic fox, mountain hare, lemmings, brown bear and spotted hyaena. Redating programmes have shown that several older radiocarbon determinations from southern Irish caves were too young, placing part of the Castlepook fauna securely within MIS 3, before the Last Glacial Maximum.

These remains must be handled carefully. A cave is not a simple snapshot of one living community. Carnivores could drag carcass parts inside; water, sediment movement, excavation methods and later disturbance could mix material from different episodes. The presence of a mammoth bone, for example,

does not prove that mammoth, reindeer, hyaena and every other recorded species stood together in one Cork valley in a single year. What the broader assemblage securely demonstrates is that Ireland supported, at intervals during MIS 3, a cold-adapted fauna more diverse than that of the island today.

For everyday ecology, the implication is powerful. Reindeer and giant deer required forage across open ground; carnivores followed prey and scavenging opportunities; caves could serve as dens, shelters or traps in the landscape. Animals themselves moved through territories far larger than any modern county. Their routes would have followed the seasonal availability of browse, grasses, sedges and water. This was not an agricultural countryside and there is no evidence for managed herds, fields, permanent villages or domesticated animals.

## **The Castlepook Human Question**

A reindeer femur from Castlepook has made this period particularly significant. It has been reported as bearing a deep mark interpreted as damage made by a sharp stone tool while the bone was fresh, and it has been publicised as dating to roughly 33,000 years ago. If that interpretation is sustained, it is evidence that people processed a reindeer in Ireland during the Upper Palaeolithic, much earlier than the well-established post-glacial record of human settlement.

It is nevertheless evidence of a very limited kind. The bone is not a house floor, a hearth, a burial, a camp, a stone-tool assemblage or a human skeleton. No unquestioned Palaeolithic occupation site of comparable age has yet been found in Ireland. Nor can the mark establish whether one person, a small hunting party or a recurring group visited the island. The cave context also leaves open the possibility that carnivores later transported or disturbed discarded bone. A reported cut mark and a dated animal bone are important observations; the reconstruction of a hunt, a camp or a population is an interpretation that needs further corroboration.

The cautious historical conclusion is that short human incursions are plausible, not that Ireland possessed a continuous resident population. Modern humans were present elsewhere in western Europe during this broad period, and a reindeer-focused visit would fit a mobile foraging economy. But Ireland's record does not yet reveal the technologies used, the route taken, the duration of a stay, the size of any group or its cultural affiliations. Continued work at Castlepook, including renewed excavation and scientific examination of stored and newly recovered material, is important precisely because the original evidence is so fragmentary.

## **No Politics, but Real Connections**

Political affairs, diplomacy and organised warfare cannot responsibly be written into this Irish horizon. There are no known states, chiefs, territorial boundaries, monuments or formal institutions. Even if people reached Ireland, their social world would have been that of small, highly mobile foraging groups whose connections were expressed through kinship, seasonal movement, shared practical knowledge and access to animal and plant resources. That is a general inference from Upper Palaeolithic lifeways elsewhere, not a fact demonstrated by a settlement in Ireland.

The same caution applies to religion, learning and culture. No Irish art, ornament, grave, shrine or symbolic object securely belongs to around 30,933 BCE. It would be unreasonable to infer an absence of belief, teaching, language or ritual from this absence: such practices rarely survive without favourable

archaeological contexts. Yet there is no basis for describing their local forms. The surviving record is environmental and faunal, with one tantalising possible trace of butchery; it does not disclose an Irish spiritual or artistic tradition.

Economy and exchange were likewise governed by landscape rather than markets. The accessible evidence suggests no trade network, production centre or seaborne commerce. If a small group entered the island, food procurement would have depended on seasonal knowledge, hunting, scavenging, gathering and the transport of portable equipment. The possible worked reindeer bone points towards animal processing, perhaps for meat, marrow, hide or other products, but none of those uses can be proved from the mark alone. The most substantial economy visible at Derryvree and Castlepook is ecological: plants, herbivores, predators, water and ice interacting in a demanding northern environment.

## **Before the Great Ice Advance**


Regional change is the main story. Around this broad period, Ireland was approaching the more extensive glaciation of the Last Glacial Maximum, conventionally placed later, around 26,000–21,000 years ago. Research on Irish landforms, coastal deposits and offshore sediments shows that the eventual Irish Ice Sheet was large and dynamic. Its later growth and movement eroded landscapes, reworked deposits and destroyed much evidence that might once have documented earlier animal and human activity. The rarity of Irish MIS 3 sites is therefore partly a history of preservation as well as discovery.

Derryvree's freshwater bed survived because later sediment sealed it between tills. Castlepook's bones survived because a limestone cave protected at least some material from the most destructive surface processes. Together they offer a restrained but compelling view of Ireland around the notional date: not a land with recoverable annual history, but a changing cold landscape of wetlands, open ground, grazing animals and predators, with a possible fleeting human encounter. The evidence is sparse, but it is enough to replace the idea of an unchanging, wholly ice-bound island with a more dynamic and scientifically honest picture.

# Chapter 069 of 100

## 30932 BCE

### Cave Earth at Castlepook <sup>[69]</sup>



The label 30,932 BCE gives an appearance of annual precision that the evidence cannot sustain. No written calendar, named community, political boundary or dated human event survives from Ireland at this depth of time. In conventional archaeological arithmetic, the nominal year falls about 32,881 years before AD 1950, within the later part of the Late Pleistocene and Marine Isotope Stage 3 (MIS 3). It is best treated as a point within a broad environmental horizon, not as a recoverable twelve-month chapter. The responsible history of Ireland at this moment is therefore one reconstructed from cave bones, freshwater sediments, fossil plants, insects and the traces left by advancing and retreating ice.

## A Date Within Deep Time

Radiocarbon measurements do not translate directly into modern calendar years. The amount of carbon-14 in the atmosphere has changed through time, while very old samples carry substantial measurement and calibration uncertainties. Modern calibration curves make better comparisons possible, but they do not turn a deposit formed over centuries or millennia into a dateable diary entry. The most relevant Irish sequences provide ranges. They can show that a landscape or animal community existed during a particular phase of the last Ice Age; they cannot establish what happened in Ireland in the notional year 30,932 BCE.

This was a world before the Last Glacial Maximum, rather than one after it. The island was not yet defined by the familiar green, wooded and maritime landscape of later prehistory. Nor should it be imagined as uniformly buried beneath ice. Climate in north-west Europe changed sharply during MIS 3, and Irish evidence records local differences between ice, meltwater, exposed ground and cold wetlands. A



landscape may have been open and habitable in one district while glaciers, permanent snowfields or barren ground dominated another. The British–Irish Ice Sheet was developing unevenly, and its eventual large-scale expansion lay in the future.

## **Derryvree Between the Tills**

The strongest Irish environmental evidence close to this broad date comes from Derryvree near Maguiresbridge in County Fermanagh. Roadworks in 1969 cut through a drumlin and revealed a remarkable sequence. A lower till, deposited by glacier ice, was overlain by freshwater silts, fine sands and organic material; these in turn were sealed beneath a later till. The order is crucial. It proves that ice had occupied the locality, that an interval followed in which standing or slow-moving freshwater and wetland vegetation developed, and that later glaciation again overrode and buried the deposits.

Organic material from the Derryvree sequence produced a radiocarbon determination of about 30,500 radiocarbon years before present, with a wide uncertainty. Calibrated treatment places the deposit broadly within later MIS 3, rather than securely in a single century. Its significance is nevertheless considerable. The sediments preserve plant macrofossils, pollen, insects and freshwater evidence from an Irish landscape largely erased elsewhere by subsequent ice. They demonstrate a cold, locally ice-free Fermanagh environment during part of the period, not an all-Ireland climatic map and not proof that people occupied the district.

## **Wetlands, Tundra and Animals**

Derryvree's biological remains point towards sparse, open vegetation with wet ground, pools and sedge-rich margins. Mosses, sedges, bogbean, water-milfoil, dwarf willow, mountain avens and other cold-adapted plants indicate conditions very different from later Irish woodland. The exact mixture changed according to drainage, exposure and season. A sheltered hollow beside freshwater could sustain more plant growth than an exposed ridge, while permafrost and repeated freezing disturbed soils. The evidence supports a patchwork of wetland and tundra-like ground rather than a featureless frozen plain.

Such habitats mattered because vegetation governed the movement and survival of animals. Ireland's MIS 3 fossil record, especially from limestone caves in Cork, includes reindeer, woolly mammoth, giant deer, brown bear, wolf, Arctic fox, mountain hare, lemmings and spotted hyaena. These remains were not necessarily all contemporary, and they do not prove that every species stood together in one valley in 30,932 BCE. Yet collectively they show that the island could support a much richer cold-stage fauna than modern Ireland. Reindeer and mammoth especially evoke broad grazing country; predators and scavengers reveal a food web in which carcasses, caves and seasonal movement were important.

## **An Island in Climatic Transition**

The physical geography of Ireland was changing as decisively as its vegetation. Glacial ice had already shaped parts of the land, and renewed ice would later destroy or conceal much of the evidence now sought by archaeologists. The later British–Irish Ice Sheet grew rapidly between roughly 31,000 and 26,000 years ago, although its timing and extent varied from sector to sector. That wider reconstruction should not be projected too simply onto every Irish valley. Derryvree itself is valuable precisely because it records a non-glacial interval between tills, preserving a local environmental window amid an unstable glacial history.

Lower sea levels altered coastlines and shallow seas, but they did not automatically make Ireland a simple extension of Britain or continental Europe. The precise geography of routes across the Irish Sea changed with sea level, crustal movement, sediment and ice margins. There is no evidence for regular maritime traffic, organised migration corridors or sustained interregional exchange at this date. If animals and perhaps people reached Ireland, their movements occurred in a changing north-west European landscape whose barriers and connections cannot be reconstructed in detail for one nominal year.

## **The Castlepook Question**

Castlepook Cave near Doneraile, County Cork, gives this period its most arresting archaeological possibility. Excavations begun in the early twentieth century recovered a large and mixed assemblage of Ice Age animal remains from the cave system once known as Mammoth Cave. Subsequent research by the Irish Quaternary Fauna Project and later radiocarbon reassessment showed that the southern Irish fauna was older and more chronologically complex than had once been supposed. Cave deposits are invaluable but difficult evidence: carnivores carry bones into dens, animals die in fissures, water moves sediments, and early excavation rarely preserved the contextual information expected today.

One reindeer femur from Castlepook has been dated to approximately 33,000 years ago and carries a deep surface mark interpreted by zooarchaeologist Ruth Carden as damage from a sharp stone implement during butchery. If that interpretation is confirmed, it would be Ireland's earliest known indication that a person processed an animal, vastly earlier than the secure evidence for post-glacial settlement. The bone is therefore directly relevant to the broad period around 30,932 BCE. But it is not a settlement site in the usual archaeological sense: no securely associated hearth, stone-tool assemblage, dwelling floor, human burial or undisturbed occupation surface has yet demonstrated a camp of this age.

## **People: Possibility, Not Population**

The marked femur permits a carefully limited conclusion. It may record a human encounter with a reindeer in Ice Age Ireland, perhaps during carcass processing. It cannot identify the number of people involved, their sex, age, language, ancestry, homeland, route of arrival or length of stay. It does not establish an enduring population on the island. A small, mobile hunting party could leave little material evidence, particularly where later glaciation and cave disturbance have removed or mixed deposits; equally, further work may revise the interpretation of the mark or its archaeological implications.

If people were present, comparisons with Upper Palaeolithic hunter-gatherers elsewhere in north-west Europe suggest a mobile life shaped by animal movements, weather and access to sheltered places. That is an interpretation from wider regional evidence, not a demonstrated social portrait of Castlepook. Reindeer could potentially provide meat, marrow, hide, sinew, antler and bone, while wood was likely scarce in an open cold landscape. Yet there is no Irish evidence from this horizon for specific hunting weapons, clothing, tents, food stores or seasonal camps. The past must remain smaller than the possibilities it invites.

## **No Politics, No Diplomacy**

Political affairs, diplomacy and warfare cannot responsibly be reconstructed for Ireland at this date. There were no known states, rulers, territorial institutions, written agreements or named peoples. Nor is there evidence for organised conflict. The closest equivalent to a regional history of power is

environmental constraint: ice sheets redirected movement; freshwater and plant cover concentrated animal life; caves offered shelter to predators and perhaps passing humans. Any social relationships that existed are archaeologically invisible. It would be misleading to supply tribes, chiefs or rival groups merely because later Irish history contains them.

## **Culture Without Records**

Religion, art and learning are likewise beyond direct recovery in Ireland around this point. No ritual site, grave, figurative art or musical object has been securely assigned to this Irish horizon. The cave fauna and the Derrynvree wetland sequence are cultural evidence only in the broadest modern sense: they show the environmental setting in which cultural acts may have occurred. The absence of evidence is partly a consequence of preservation. Organic objects, temporary shelters and surface activity are especially vulnerable to decay, erosion and glacial disturbance. Still, absence cannot be converted into claims about beliefs or ceremonies.

## **Economy and Regional Change**

There was no agriculture, animal husbandry, market economy, metalworking or demonstrated long-distance trade in Ireland. If the Castlepook mark is human-made, it points to direct acquisition or processing of wild animal resources rather than farming. The principal economic facts were ecological: animals required forage; predators followed prey; freshwater wetlands created local resources; and cold conditions restricted plant growth and travel. Ireland's regional variation was pronounced. Fermanagh preserves a freshwater tundra archive beneath a drumlin, while north Cork preserves cave accumulations from a faunally rich, open-country setting. Neither locality stands for the whole island.

For 30,932 BCE, then, Ireland's history is best understood as a threshold landscape. Fossil wetlands show that life persisted locally between episodes of glaciation. Cave deposits show that cold-adapted mammals reached the island. A single marked reindeer bone raises the serious possibility of a human visit, but not yet of settlement. The most important development was not a recorded event but the continuing remaking of the land by climate, water, animals and ice.

# Chapter 070 of 100

## 30931 BCE

### Maguirebridge's Winter Waters<sup>[70]</sup>



30,931 BCE is a modern chronological label, not a year that can be recovered from Ireland's archaeological record. No calendar, written account, settlement sequence or securely dated event allows historians to identify what happened in this particular year. In radiocarbon terms it lies roughly 32,880 years before the conventional present of AD 1950, but radiocarbon results at this depth must be calibrated and are expressed as broad probability ranges rather than single calendar years. The most responsible account is therefore of Ireland during the later part of Marine Isotope Stage 3 (MIS 3), a climatically unstable phase of the last Ice Age, rather than of an imagined annual history.

## A Date Within a Broad Interval

The best Irish environmental evidence close to this notional date comes from Derryvree, near Maguiresbridge in County Fermanagh. Roadworks in 1969 cut through a drumlin and revealed fine sands, silts and organic freshwater deposits enclosed between two layers of till, the debris left by glacial ice. The sequence is decisive in one important respect: ice had occupied the locality, then a period without overriding ice allowed water, sediment, plants and small animals to accumulate, before a later advance deposited the upper till and sealed the record.

Organic material from the Derryvree freshwater series produced a conventional radiocarbon age of 30,500 +1,170/-1,030 radiocarbon years BP. Calibration produces a much broader calendar-age estimate, commonly discussed as approximately 36,900–31,700 calibrated years BP. The label 30,931 BCE falls within that wide span, but cannot be attached to a particular bed, season, plant or animal at Derryvree. The deposit documents a cold-stage interval lasting far longer than a human lifetime, not a dated occurrence in a named year.

This distinction guards against a misleadingly simple picture. Ireland was not yet necessarily blanketed everywhere by the later Last Glacial Maximum ice sheet, but neither was it a green, wooded island. Ice margins, mountain glaciers, sea level, rivers and coastlines changed on regional and millennial scales. The British–Irish Ice Sheet was entering a major phase of growth and reorganisation around this broad period, while its precise extent varied from place to place. A wetland at one Fermanagh locality cannot supply a weather report for Cork, the western uplands or every intervening lowland.

## **Wet Ground Between Glacial Advances**

Derryvree nevertheless gives an unusually tangible glimpse of life in part of Ireland. Pollen, plant macrofossils, mosses and insect remains point to a cold, open, largely treeless environment. Grasses, sedges, herbs and juniper formed much of the vegetation. Fossil remains of bogbean, water-milfoil, mountain-avens and lesser clubmoss are particularly informative: some indicate shallow or slow-moving freshwater and wet margins, while others are characteristic of exposed, cold-climate ground. Mosses and insects reinforce the interpretation of saturated, plant-rich hollows and pools.

Earlier investigators used the word “muskeg” for this landscape. The term should not conjure a modern Irish bog transplanted unchanged into the Ice Age. It is better understood as a mosaic of wet, organic ground, shallow pools, sedgy margins, sparse vegetation and frost-disturbed surfaces. Winters were severe, the growing season short, and trees were absent or extremely scarce around the deposit. A few poorly preserved pollen grains from trees cannot securely demonstrate local woodland: pollen can travel far and older material may be reworked. The combined evidence, however, strongly supports open tundra-like country rather than forest.

Such ground could be biologically active despite its severity. Water remained available at least seasonally; aquatic and wetland plants grew; insects completed their life cycles; and grazing mammals could use patches of herbage. Yet productivity was strongly seasonal, shelter limited and weather exposure acute. The landscape was not an empty white plain, but it was a demanding environment whose habitable patches may have shifted as watercourses, snow cover, frozen ground and nearby ice changed.

## **Animals at Ireland’s Western Edge**

Late Pleistocene cave deposits, especially at Castlepook Cave near Doneraile in north County Cork, show that Ireland supported or received a striking range of mammals during MIS 3. The cave assemblages include reindeer, woolly mammoth, giant deer, brown bear, wolf, Arctic fox, mountain hare, lemmings and spotted hyaena. These animals should not be presented as a single herd or a perfectly contemporary community. Cave deposits accumulated over long periods, and bones may have been introduced by carnivores, water, collapse, excavation disturbance and human collection. Modern redating has also shown that some older radiocarbon determinations from Irish caves were too young.

Even with those cautions, the faunal record establishes a changing northern environment connected, at intervals, to wider north-west European animal ranges. Reindeer and lemmings suit the image of open, cold terrain; mammoth and giant deer point to the capacity of parts of the landscape to sustain large herbivores; hyaenas and wolves reveal predators and scavengers within the food web. Caves were not neutral census sites. A hyaena den, for example, records where bones were carried and consumed rather than a balanced sample of every animal beyond its entrance. But taken with the Fermanagh wetland evidence, the bones make clear that severe conditions did not mean lifelessness.

## The Reindeer Femur Question

One object from Castlepook has made this era especially important for Irish archaeology: a reindeer femur from the historic cave collection, reported as around 33,000 years old and bearing a deep mark that zooarchaeologist Ruth Carden has interpreted as damage from a sharp stone tool during carcass processing. County Cork's heritage publication dates the bone broadly to about 31,000 BC. If that assessment is upheld, it would be the earliest presently claimed indication that people handled an animal in Ireland, far earlier than the securely documented terminal-Pleistocene human evidence.

The claim deserves serious attention but not embellishment. The bone dates the death of the reindeer, not necessarily the instant when the mark was made. The femur was recovered in early twentieth-century cave work, not from a modern sealed excavation in which stone tools, a hearth, butchered remains and occupation surfaces lay together. Caves are especially difficult contexts because carnivores may transport, gnaw and scatter bones, while sediment movement and old excavation practices may disrupt associations. Identifying a cut mark requires specialist comparison with natural breakage, teeth, trampling and other damage.

If the incision was made by a person, the direct conclusion is modest but remarkable: someone used a sharp lithic edge on a reindeer carcass in Ireland during this broad period. It does not demonstrate a permanent population, a village, a named people, a language or a continuous lineage leading to later inhabitants. It cannot tell us whether the animal was hunted, scavenged, processed elsewhere, or carried into the cave by predators after people had removed meat, hide, sinew or marrow. A brief visit by highly mobile Upper Palaeolithic hunter-gatherers following seasonal resources is a reasonable interpretation, but it remains interpretation rather than established fact.

## No Politics, No Proven Settlements

There is no evidence from Ireland around this time for political institutions, rulers, diplomacy, warfare, territorial states, trade networks, farming, domestic livestock or permanent settlements. Nor is there material evidence from which to reconstruct religious ceremonies, artistic traditions, education or formal systems of learning. These absences reflect the thinness and survival of the record. Later ice repeatedly eroded surfaces, buried old landforms and altered drainage; falling sea levels changed coastlines, while subsequent sea-level rise drowned former lowlands. Potential campsites may have been destroyed, concealed beneath sediments or lost offshore.

Should the Castlepook femur represent human activity, the most that can responsibly be said about everyday economy is that a mobile party may have exploited a large animal using a stone cutting implement. Reindeer would have offered meat, hide, sinew, fat, antler and bone, but none of these uses is independently demonstrated at Castlepook. There is no Irish assemblage of tools from which to identify a particular Upper Palaeolithic tradition. Equally, there is no basis for assuming people remained through worsening glacial conditions. The evidence permits a possible encounter; it does not establish settlement.

## An Island Not Yet Familiar

The Ireland evoked by Derryvree and Castlepook was therefore neither the island of later farmers nor a timeless frozen wilderness. It was a changing edge-land of freshwater pools, mossy wet ground, sparse herbs, exposed mineral soils and animal movements, increasingly affected by expanding ice. Fermanagh


preserves the environmental detail because a later glacier sealed it beneath till. Cork's caves preserve bones because limestone cavities sheltered them, although often in complicated and mixed deposits. Both are fortunate survivals from a landscape whose ordinary surfaces have largely vanished.

For 30,931 BCE, the central historical fact is uncertainty disciplined by evidence. Calibrated ranges, glacial stratigraphy, fossil plants, insects and animal bones can illuminate the conditions of a broad Late Pleistocene interval. They cannot yield an annual chronicle. Ireland was capable of supporting cold-adapted ecosystems, and perhaps of receiving occasional human visitors, before the major glacial expansion that would later transform the island again. That is already a profound chapter of Irish deep history, even though it contains no names, no dates remembered at the time, and no securely known human community.

# Chapter 071 of 100

## 30930 BCE

### Castlepook Hyaena Toothmarks<sup>[71]</sup>



**30,930 BCE is not a date at which Ireland can be described year by year. No written record, settlement sequence or event horizon permits that kind of precision. Indeed, this modern calendar label is only a retrospective waypoint: it falls roughly 32,900 years before AD 1950, the conventional baseline for “before present” dating. At this depth in time, radiocarbon determinations must be calibrated and normally yield ranges rather than a single calendar year. The responsible history of Ireland at this point is therefore one of deposits, bones, pollen and changing ice, not rulers, peoples or dated events.**

The closest evidence comes from two very different archives. At Derryvree, near Maguiresbridge in County Fermanagh, a road cutting exposed freshwater silts and organic material sealed between glacial deposits. At Castlepook Cave near Doneraile in north County Cork, excavations recovered a large but time-mixed collection of Ice Age animal remains. Neither archive is a snapshot of 30,930 BCE. Together, however, they illuminate a Late Pleistocene Ireland within Marine Isotope Stage 3 (MIS 3), a long, climatically unsettled part of the last glacial period before the maximum expansion of the British–Irish Ice Sheet.

## **A Date Without a Calendar**

It is important not to turn the numbered year into false certainty. The Derryvree organic deposit produced a conventional radiocarbon age of  $30,500 \pm$  roughly 1,100 radiocarbon years before present. Modern calibration places such an age broadly in the mid-30,000s calibrated years before present, with a substantial range rather than a point on a calendar. Castlepook animals have likewise been dated across a



long interval. Improved chemical pretreatment of bone collagen has shown that some earlier results were too young by several thousand radiocarbon years. These revisions are a warning: scientific dates are evidence to be assessed, not labels to be copied unchanged into a timeline.

For this reason, 30,930 BCE should be treated as approximately within, or near, the environmental world represented by Derryvree and the older part of the Castlepook faunal record. It does not establish that material from Fermanagh and Cork was deposited in the same century, season or generation. The sites are separated by more than 250 kilometres and record different processes: fine sediment settling in freshwater at one, animal bones entering a limestone cave at the other.

## **Fermanagh's Treeless Wetland**

Derryvree supplies the clearest direct evidence for conditions on part of the Irish landmass. Beneath the drumlin were silts and fine sands laid down in freshwater, containing fossil pollen, plant macrofossils and insects. The assemblage indicates open, treeless tundra or tundra-like vegetation in a periglacial climate. Mosses, sedges and cold-adapted herbs mattered more in this landscape than woodland. Finds including bogbean, mountain-avens, dwarf willow and lesser clubmoss have been used to reconstruct a mosaic of shallow water, wet ground and exposed mineral soil.

This was not an unchanging white desert. "Periglacial" means a land shaped by severe cold and seasonal freezing near ice, not necessarily a place permanently buried beneath it. Water could pool, plants could grow during short summers, and insects could occupy particular ecological niches. Yet trees were absent locally or extremely scarce. A few pollen grains from tree species cannot securely demonstrate nearby forest: pollen may travel far, be redeposited, or survive unevenly. The stronger conclusion is that south Fermanagh supported sparse open vegetation and freshwater habitats at some point during a cold, non-glacial interval.

The sediments also preserve a larger geological argument. Because the organic bed lay between deposits interpreted as tills, it has long been understood as evidence for an ice-free or less heavily glaciated interlude between phases of ice advance in the north of Ireland. The extent, timing and character of early Midlandian glaciation remain debated, partly because tills are difficult to correlate over long distances and good absolute dates are scarce. What can safely be said is that the later Last Glacial Maximum, when ice covered almost all Ireland, still lay in the future. What cannot safely be said is that every region of the island was simultaneously free of ice in 30,930 BCE.

## **Castlepook's Time-Mixed Fauna**

At Castlepook, also called Mammoth Cave, the evidence is more dramatic but less neatly stratified. The cave yielded remains attributed to woolly mammoth, reindeer, giant deer, brown bear, wolf, Arctic fox, stoat, mountain hare, lemmings and spotted hyaena. This is not a complete list of animals living together in one place on one day. Cave assemblages are formed by many agencies: animals die, carnivores carry portions of carcasses into dens, water moves sediment, roof openings admit material, and excavators recover bones from deposits that may have accumulated over millennia. Early twentieth-century excavation methods also recorded context less precisely than modern fieldwork would require.

Nevertheless, the fauna shows that Ireland could support an intermittent cold-stage animal community before the Last Glacial Maximum. Reindeer and lemmings point to open, cold environments; mammoth and giant deer evoke extensive grazing country; predators demonstrate that food webs included scavenging and hunting carnivores. Spotted hyaena is especially significant, both because it is rare in the

Irish record and because hyaenas can alter and transport bones. A mammoth bone bearing marks consistent with hyaena tooth damage offers a reminder that carnivores, not people, may explain much of what reached the cave.

These animals should not be imagined as inhabitants of a single uniform “mammoth steppe”. The Derryvree wetland and the Castlepook cave represent different local settings, while MIS 3 climates fluctuated repeatedly across centuries and millennia. Open grass-herb terrain, wet hollows, rocky limestone ground and patchy sheltered vegetation could coexist. The island’s position on Europe’s Atlantic edge also meant that weather, sea level, ice margins and routes for animal movement were constantly consequential.

## **The Marked Reindeer Bone**

Castlepook has particular importance because a reindeer femur in the National Museum of Ireland’s Natural History collections carries a deep linear mark interpreted by zooarchaeologist Ruth Carden as damage made by a sharp stone tool during carcass processing. The bone has been publicly associated with an age of about 31,000 BCE. If the interpretation is upheld, it is evidence that a person handled a reindeer carcass in Ireland during the Upper Palaeolithic, vastly earlier than the island’s formerly accepted human record.

That is a major possibility, but its limits must be kept clear. The femur is not a human skeleton, a dwelling, hearth, occupation floor, stone-tool assemblage, burial or repeatedly used camp. No tool responsible for the mark has been recovered with it. The animal bone came from an old cave collection rather than a freshly excavated, securely layered archaeological context. Nor can the date of the animal’s death automatically date the moment when a mark was made. The most cautious statement is that one modified reindeer bone raises a serious prospect of brief human activity, perhaps butchery, in pre-maximum Ireland; it does not demonstrate a permanent resident population.

Even if people did visit, nothing identifies their language, ancestry, social organisation or relation to later inhabitants of Ireland. They could have been a small and mobile Upper Palaeolithic party, operating at the far western edge of wider European worlds. A visit might have involved following migrating animals, exploiting a carcass, scouting terrain or sheltering briefly. Those are interpretations based on the bone, the wider European record and the ecology of reindeer; they are not things directly observed in Ireland.

## **Life, Belief and Exchange Beyond the Evidence**

Political affairs, diplomacy and warfare cannot be recovered for Ireland at this date. There are no polities, leaders, territories, weapons caches or fortifications in the evidence. Likewise, there is no Irish evidence for religion, ritual, art, formal learning, trade networks or domestic life around 30,930 BCE. It would be misleading to supply them from later Irish prehistory, or to transfer them wholesale from better-preserved Upper Palaeolithic sites in France, Britain or central Europe.

There is also no evidence for farming, herding, pottery, metalworking, villages or maritime commerce. The only conceivable economy indicated locally is the ecological economy of wild animals and plants. If the Castlepook femur does record butchery, it implies the acquisition or processing of meat, hide, marrow or sinew from a reindeer. It does not reveal whether the animal was hunted, found dead, taken from another predator or processed by one person rather than a group. Derryvree, meanwhile, tells us about natural resources available in a wetland landscape, not about people using them.

## **An Island Before Its Ice Maximum**

The greatest development appropriate to this date is environmental. Ireland was not yet the wholly ice-dominated land of the later Last Glacial Maximum, but it was heading towards a much harsher glacial world. Across the following millennia, ice expanded and reworked the landscape so powerfully that it destroyed, buried or displaced much earlier evidence. This helps explain why the record is so fragmentary: absence of a camp or tool may reflect genuine absence, but it may also reflect erosion, later glaciation, submerged former coastlines and the rarity of suitable deposits.

Thus Ireland around the nominal year 30,930 BCE is best understood through disciplined uncertainty. Derryvree demonstrates a cold, open freshwater landscape in Fermanagh during a pre-maximum interval. Castlepook demonstrates that varied large mammals, including reindeer, occupied or reached southern Ireland over a broad span of MIS 3. One marked femur offers a potentially transformative trace of human action, while still falling short of proof of settlement. This is not a lost kingdom awaiting names and dates. It is a changing Ice Age environment, reconstructed from fragile evidence and still capable of revising Ireland's deepest human past.

## Chapter 072 of 100

### 30929 BCE

#### Derryvree's Silted Fen<sup>[72]</sup>



30,929 BCE is a modern calendar label, not a year that can be recovered from Ireland's prehistoric record. No written calendar, named ruler, settlement sequence or event can be placed in this particular year. In radiocarbon terms it falls about 32,878 years before AD 1950, within the Late Pleistocene and Marine Isotope Stage 3 (MIS 3). The responsible approach is therefore to use broad, calibrated ranges rather than pretend to annual precision. The best Irish environmental sequence for this horizon is at Derryvree, near Maguiresbridge in County Fermanagh: organic freshwater sediments there have been calibrated broadly to about 36,900–31,700 calendar years before present. That wide span includes 30,929 BCE, but it does not prove that the deposit records this exact year or that conditions were identical across the island.

### A Wetland Between Ice Advances

Derryvree was revealed by road-cutting through a drumlin, one of the streamlined hills which now characterise much of Fermanagh. Excavators found organic-rich silts and fine sands sandwiched between two substantial layers of till, the stony sediment left by glacier ice. The sequence has an unusually clear implication: after one phase of glaciation, freshwater and wetland sediments accumulated at the site; only later did ice return or expand across it, sealing the evidence below another till layer. It is a record of an interval and of environmental change, not a portrait of an individual year.

The plants preserved in these sediments point to a treeless, cold-stage wetland or muskeg landscape. Mosses, sedges and aquatic plants could thrive in shallow water, saturated ground and pools, while low-growing tundra vegetation occupied better-drained patches. Such evidence does not justify imagining a

single uniform plain: watercourses, small basins, exposed mineral ground and patches of snow or frost would have created a mosaic of habitats. Nor should the word “tundra” suggest permanent lifelessness. Short growing seasons could still sustain a productive summer flora, insects and grazing animals.

Derryvree also demonstrates why the old picture of an Ireland continuously smothered by ice throughout the later Ice Age is too simple. Around this broad period, glaciers, ice caps and ice-free terrain changed repeatedly and did not behave in the same way in every region. Syntheses of the British–Irish Ice Sheet suggest substantial growth after roughly 32,000–31,000 years ago, leading towards a far later maximum in the mid-twenties thousand years before present; yet the evidence for the opening stages remains sparse and regional. Models and field evidence consequently allow different local conditions at similar dates. Fermanagh’s buried wetland proves an ice-free episode at that locality, while it cannot map the state of every mountain, coast or sea channel in Ireland.

## The Cork Faunal World

County Cork supplies a second, very different window. Castlepook Cave, near Doneraile, has produced one of Ireland’s most important collections of Ice Age animal remains. Work on the cave’s faunas, including reassessment of older radiocarbon determinations, places significant parts of its pre-Last Glacial Maximum record in MIS 3, broadly around 34,000–35,000 years ago. These are not necessarily exactly contemporary with 30,929 BCE; nevertheless, they show the kinds of animals that occupied southern Ireland during the same long climatic phase.

Reindeer are central to this picture, but the assemblage was richer than a single herd species. Mammoth, giant deer, brown bear, wolf or other canids, fox, hare, lemming and spotted hyaena have all been identified among the Pleistocene remains associated with the cave’s wider record. The combination indicates open country capable of supporting grazers, browsers and large predators, alongside sheltered limestone terrain where caves could trap sediment and preserve bone. Cave deposits, however, are not straightforward inventories of a living landscape. Carnivores can drag carcass parts underground; water can move fragments; digging and later disturbance can mix deposits. A bone in a cave does not automatically show where an animal died, grazed or was killed.

For everyday life in the literal sense, this is the strongest direct evidence available: animals moved through a cold, open and hazardous landscape; predators competed for meat and shelter; seasonal water and vegetation shaped where grazing was possible. There is no basis for assigning a population size, estimating a human diet across Ireland, or imagining villages. The famous image of a settled “Ice Age Ireland” is especially misleading for this date. The Irish evidence is sparse because later ice sheets eroded, reworked and buried older deposits, as well as because any human visits may have been brief.

## The Reindeer Femur Question

Castlepook matters to human history because a reindeer femur has been radiocarbon dated to about 33,000 years ago and bears a deep mark interpreted by palaeozoologist Ruth Carden as a cut made with a sharp stone tool during carcass processing. County Cork’s heritage publication treats it as evidence that Stone Age hunters were present in the area around 31,000 BCE. If that interpretation is sustained, it would push the evidence for human activity in Ireland dramatically earlier than the well-attested Mesolithic settlement of the early Holocene.

Its limits are as important as its promise. The femur is not a house floor, hearth, stone-tool scatter, human burial or stratified camp. It cannot tell us whether people killed the reindeer, scavenged part of a carcass, processed it elsewhere before the bone entered the cave, or stayed in Ireland beyond a short visit. It certainly cannot establish a permanent population in 30,929 BCE. The mark is best understood as a potentially consequential trace of Upper Palaeolithic activity, not as proof of an Irish community with a continuous history from this time.

Even travel routes remain uncertain. Lower global sea levels altered the geography of the Irish Sea basin, but changing coastlines, glacial margins and subsequently submerged landscapes make it unsafe to draw a neat land bridge on a map for one notional year. A possible human presence implies that people could reach the territory now called Ireland, whether across exposed land, ice, water or a changing combination of these; it does not yet reveal their route, homeland or frequency of movement.

## **No Politics, No Proven Trade**

Political affairs, diplomacy and organised warfare are beyond the reach of the evidence. There are no named groups, leaders, boundaries, meeting places or weapons caches from Ireland at this horizon. The struggle visible in the record is ecological rather than political: large carnivores and scavengers, changing herds, freezing conditions and advancing ice. A humanly made cut mark, if confirmed, would show subsistence activity, not conflict between communities.

The same restraint is necessary for economy and trade. Reindeer and other animals could have offered meat, hide, sinew, bone, antler and fuel, but no Irish assemblage of this age demonstrates how such materials were shared or exchanged. No locally secure stone-tool industry has been identified, and no imported ornaments, raw materials or other evidence can demonstrate trade networks. Comparisons with contemporaneous hunter-gatherers elsewhere in north-west Europe can suggest that mobile groups often possessed sophisticated knowledge of animals, seasons, stone and routes; they cannot fill the Irish evidential gap with facts.

## **Culture Beyond Recovery**

There is likewise no responsible evidence for language, kinship, religion, art, ritual or formal learning in Ireland in this period. The absence of evidence does not mean that visiting people lacked beliefs, stories or skills. It means that Ireland has not yielded material traces from which their particular forms can be recovered. A marked bone is not an artwork; a cave is not automatically a shrine; and the impressive survival of mammoth or hyaena remains does not identify cultural meaning.

What can be said is that survival in such country demanded practical knowledge: reading animal movement, anticipating weather, finding water, navigating open ground and obtaining shelter. Those are interpretations grounded in the environmental setting rather than discoveries of named traditions. The nearest secure conclusion is modest but significant: Ireland was part of a wider Late Pleistocene world of fluctuating cold, open habitats and mobile fauna, with a possible fleeting human presence.

## **A Landscape Before the Maximum**


30,929 BCE therefore belongs neither to a wholly ice-covered Ireland nor to a settled prehistoric island. It belongs to an unstable threshold before the Last Glacial Maximum. At Derryvree, an intertill freshwater bed preserves the memory of pools, sedges and mossy wet ground in an interval when ice was

absent locally. At Castlepook, cave bones preserve a southern fauna of reindeer, predators and other cold-stage animals; one marked femur raises, but does not settle, the question of human hunters. Later glacier expansion transformed the island and obscured much of this earlier world. The history of this date is consequently a history of evidence itself: silt between tills, bones in caves, calibrated age ranges and the discipline of knowing where interpretation must stop.

# Chapter 073 of 100

## 30928 BCE

### Doneraile's Reindeer Record<sup>[73]</sup>



**“30,928 BCE” is a useful modern label, not a date that anyone living in prehistoric Ireland could have named or recorded. No event can responsibly be assigned to that single calendar year. The appropriate setting is the later part of Marine Isotope Stage 3, a long, unstable phase of the last Ice Age. Calendar conversion also needs care: radiocarbon measurements and ice-core chronologies are expressed in different systems, with uncertainties far wider than one year. The closest securely relevant Irish environmental evidence, the Derryvree freshwater deposits in County Fermanagh, has produced a conventional radiocarbon age of about 30,500 ± 1,100 radiocarbon years BP; calibration places the deposit broadly within roughly 36,900–31,700 calendar years BP, or about 34,950–29,750 BCE. Thus 30,928 BCE falls within a defensible environmental horizon, not within a pinpointable historical moment.**

## A Brief Ice-Free Interval

Ireland was not yet at the fullest expansion of the last British–Irish Ice Sheet. That came later, principally during the Last Glacial Maximum, when ice expanded dramatically between roughly 28,000 and 26,500 years ago and reached its greatest extent around 26,000–24,000 years ago in many sectors. Around the date represented here, however, parts of Ireland were ice-free or at least beyond an active ice margin. This does not mean mild conditions. It means a cold, exposed country in which glaciers had temporarily retreated or had not yet advanced over particular districts.

The most informative local record comes from Derryvree, near Maguiresbridge in County Fermanagh. A road cutting through a drumlin revealed freshwater silts and fine sands trapped between two thick sheets of glacial till. That sequence is unusually eloquent. The lower till records an earlier



glacial advance; the organic-rich sediments represent a period when open water, plants and small animals occupied the site; and the upper till shows that ice later returned and overrode the landscape. The deposit therefore preserves an interval of terrestrial life that would otherwise have been erased by later glaciation.

Plant macrofossils, pollen and animal remains from Derryvree indicate a treeless tundra or muskeg-like wetland. Sedges and aquatic plants grew around shallow water. Mountain avens, dwarf willow, lesser clubmoss, bogbean and other cold-adapted taxa point to a landscape of low vegetation rather than forest. The ground was probably seasonally frozen, locally waterlogged in summer and vulnerable to frost disturbance. It was an environment of pools, wet hollows, gravelly ground and sparse herb-rich cover, not a uniform white wilderness. The Irish landscape at this time was dynamic on a human timescale: slight shifts in temperature, snowfall, wind and summer thaw could transform what animals could graze and where water lay.

## **Cold Climate, Not a Single Season**

North Atlantic climate during Marine Isotope Stage 3 changed abruptly and repeatedly. Greenland ice cores record a succession of Greenland Stadials and Interstadials, episodes in which temperature and atmospheric circulation shifted substantially within decades. It is tempting to assign an Irish deposit neatly to one named Greenland event, but the Derryvree date range is too broad for secure year-by-year correlation. The responsible conclusion is narrower: the sediments formed during one of the oscillating cold phases before the Last Glacial Maximum, when northern Ireland could sustain open, periglacial freshwater habitats.

The scale of Ireland's ice cover at precisely this point remains debated. Ice-sheet reconstructions must combine deposits on land, marine sediments, exposure dating and models, and different regions of Ireland did not necessarily experience the same conditions simultaneously. Derryvree provides direct evidence that its locality was ice-free while the freshwater deposits accumulated. It cannot, by itself, prove that every coast, mountain and plain was similarly open. Equally, later evidence for thick ice in western and southern Ireland should not be projected backwards without qualification. At 30,928 BCE Ireland was moving towards a harsher glacial world, but it had not yet become the fully ice-dominated island of the maximum.

## **Castlepook and the Human Question**

County Cork supplies the most arresting, and most contested, clue to human activity. Castlepook Cave, also known historically as Mammoth Cave, lies near Doneraile in the Awbeg valley. Excavations begun under Richard J. Ussher in the early twentieth century recovered a vast collection of Pleistocene animal bones. Reassessment, direct radiocarbon dating and improved bone pretreatment have shown that some Castlepook fauna is considerably older than dates obtained in the 1990s suggested. The cave's assemblage includes reindeer, woolly mammoth, giant deer, wolf, brown bear, Arctic fox, hare, lemming and spotted hyena: animals suited to a cold, open north-west European environment.

One reindeer femur is particularly important. It has been assigned broadly to around 31,000 BCE and carries a deep surface incision interpreted by zooarchaeologist Ruth Carden as a cut made with a sharp stone tool while the bone was fresh. If that reading is correct, people processed a reindeer in Ireland during the Upper Palaeolithic, tens of millennia before the long-established evidence for post-glacial settlement. It would be a profound revision of the island's human story.

But the distinction between evidence and interpretation matters. The dated bone is real; the incision is real; and stone-tool butchery is a plausible interpretation. Yet the specimen comes from an old cave collection rather than a modern, sealed excavation context. No securely associated stone tool, hearth, dwelling, human bone, occupation floor or concentration of similarly dated butchered remains has yet been published from Castlepook. Nor can the femur establish whether people killed the animal, merely processed a carcass, stayed nearby for a season, or formed a lasting population. Later excavations, including work in 2022, demonstrate that the cave still has research potential, but they do not turn a single marked bone into proof of a settlement.

## **Animals, Movement and Survival**

The Castlepook fauna nevertheless makes the wider ecological setting vivid. Reindeer could have exploited lichens, sedges, grasses and herbs across open ground; hares and lemmings occupied comparable cold habitats; carnivores followed prey and scavenged carcasses. Spotted hyenas, now confined to Africa, used caves as dens and bone accumulators in Pleistocene Ireland. A cave assemblage is consequently not a straightforward menu of animals hunted by people. Hyenas, wolves, water, collapse and repeated occupations by animals can all move, gnaw, scatter and preserve bones. Its principal value is as evidence for the animal communities that reached Ireland during favourable windows, and for the complex processes by which their remains entered caves.

Those animals had to move through a changing geography. Sea level was lower than today because vast quantities of water were held in ice sheets, exposing areas now beneath the surrounding seas. Yet this should not be simplified into a certain, broad dry-land bridge connecting Ireland and Britain at the date in question. The existence, route and usefulness of any connection depended on ice position, relative sea level and local topography. Some reconstructions have envisaged exposed terrain or temporary northern connections; other studies stress that routes across the Irish Sea were discontinuous, glaciated or submerged. The careful conclusion is that animal and possible human movement from Britain or continental Europe was possible during some Pleistocene phases, but the exact route used around 30,928 BCE is unknown.

## **No Politics, No Proven Religion**

There is no evidence for political affairs, diplomacy, named communities or territorial authority in Ireland at this date. There are no farms, fields, monuments, cemeteries, houses, pottery assemblages or written traditions from which to reconstruct social hierarchy, belief or learning. It would be misleading to populate the tundra with clans, chiefs or ritual systems simply because hunter-gatherer societies existed elsewhere in Upper Palaeolithic Europe.

Nor is there evidence for an Irish economy in the later sense of farming, craft production or trade. If the Castlepook mark is human-made, it supports only the modest but significant inference that people had access to a sharp stone edge and animal food or materials. Reindeer carcasses could provide meat, fat, hide, sinew, bone and antler, but none of those possible uses can be demonstrated for Ireland from this object alone. The most economical reading is one of mobility: small groups may have entered a demanding, resource-variable landscape, perhaps following game or exploiting a short-lived opportunity. Permanent occupation remains unproven.

## **An Archive Beneath Later Ice**

The chief historical development around this notional year was environmental rather than political. Ireland contained ice-free ecological pockets where tundra plants, freshwater organisms and large mammals survived or passed through, while the climatic trajectory was towards renewed and more extensive glaciation. Derryvree's buried wetland and Castlepook's cave bones are fragments of that world, preserved precisely because sediment and ice sealed them away.

They also explain why certainty is limited. Later glaciers stripped soils, remodelled valleys and destroyed most surface traces of early human activity. Old cave excavations removed many deposits before modern recording standards, while bones held in museum collections may still be redated and reassessed. Ireland at 30,928 BCE is therefore not a blank page, but neither is it a narrative of recorded events. It is a cautiously reconstructed landscape: cold water among sedges, open tundra under unstable skies, reindeer and predators moving through southern and northern refuges, and one marked bone that may preserve the faintest trace of people at the edge of the known Irish past.

# Chapter 074 of 100

## 30927 BCE

### Derryvree's Drumlin Wetland <sup>[74]</sup>



**“30,927 BCE” is a useful label for organising deep time, but it was not a year that anyone in Ireland could have named, recorded or experienced as a date on a calendar. Modern calendar-year precision is unavailable at this depth. In archaeological terms, the point falls about 32,876 calibrated years before present, where “present” conventionally means 1950. The appropriate setting is the later part of Marine Isotope Stage 3 (MIS 3), a climatically unstable phase of the last Ice Age. Ireland’s evidence is not a narrative of rulers or events, but a sparse archive of sediments, plant remains, insects, animal bones and changing ice.**

The most illuminating Irish deposit for this notional year is at Derryvree, near Maguiresbridge in County Fermanagh. It does not prove what occurred on a particular day in 30,927 BCE. Rather, it preserves an environmental interval broad enough to include that date, and shows that at least one northern locality was, for a time, a cold freshwater wetland rather than ground sealed beneath glacier ice.

## **A Date Within a Range**

In 1969, roadworks cut through a drumlin at Derryvree and exposed fine sands, freshwater silts and organic sediment between two thick layers of till. Till is the unsorted debris left by moving glacier ice. The order of the deposits matters greatly. A lower till records an earlier glacial episode; sediments accumulated when ice no longer covered the locality; an upper till shows that later ice returned or expanded across it. The sequence is therefore evidence of profound environmental change, not a frozen snapshot of a single year.

Organic material from the freshwater series produced the radiocarbon determination Birm-166: 30,500 radiocarbon years before present, with a substantial uncertainty of +1,170 and –1,030 years. Such a measurement cannot simply be converted by subtracting from 1950. Atmospheric radiocarbon levels

changed through time, and calibration produces probability ranges rather than an exact historical date. Modern calibrations place the Derryvree horizon broadly within roughly 36,900–31,700 calibrated years before present, or approximately 34,950–29,750 BCE. The requested year lies inside that span, but cannot responsibly be pinned to a particular plant, pond margin or season within it.

This distinction is central. The evidence demonstrates that Derryvree was ice-free locally during part of a cold interval and supported freshwater life. It does not demonstrate that all Ireland was ice-free, that its climate was uniform, or that the entire deposit formed in 30,927 BCE. Ireland was an Atlantic island-region shaped by shifting ice margins, sea levels and drainage systems; conditions could differ sharply between Fermanagh, the southern lowlands, mountain uplands and the exposed continental shelf.

## **Cold Water Beneath the Drumlin**

Derryvree's fossils reconstruct a treeless, open landscape with wet ground and shallow freshwater. Mosses, sedges, grasses and other herbaceous plants dominate the evidence. The assemblage includes plants associated with northern and Arctic-alpine conditions, among them bogbean, dwarf willow, mountain avens and lesser clubmoss. Their presence does not mean that every one grew together in a neat modern plant community. Fossil assemblages accumulate over time and may draw material from different small habitats. Yet taken together they strongly support a cold, periglacial mosaic: damp hollows, sedge-rich margins, shallow pools and open ground, with sparse vegetation beyond the wetland.

“Periglacial” does not mean that Derryvree was simply a featureless snowfield. It describes a landscape shaped by severe cold and by the seasonal freezing and thawing of ground close to ice sheets. Summer warmth could briefly release meltwater and allow plants, insects and animals to exploit sheltered places; winter would have been long and exacting. The organic silts show that freshwater persisted long enough for biological remains to be trapped and preserved. The later upper till, however, is a reminder that this ecological opening was temporary in geological terms.

At this time the island's familiar wooded appearance did not exist. There were no oak woods, hedgerows, improved fields or peatlands of the later Holocene. Nor should the evidence be stretched into an image of continuous barren tundra across the whole island. The safest reconstruction is regional and local: open, cold country in and around Derryvree, with vegetation concentrated where water and sheltered soils allowed it.

## **Animals in an Unfamiliar Ireland**

Cave deposits in southern Ireland add a larger-animal dimension to the picture. Castlepook Cave, near Doneraile in County Cork, has yielded a notable Late Pleistocene fauna. Re-dating of selected bones has shown that some material once thought much younger belongs in MIS 3. The broader assemblage includes reindeer, woolly mammoth, giant deer, brown bear, wolf, Arctic fox, mountain hare, lemmings and spotted hyaena. Not every bone from the cave is necessarily the same age, and the cave was not a single undisturbed occupation floor. The fauna should therefore be read as a record of animals using, dying near, or being carried into a changing regional landscape over an extended period.

Even with that caution, the implications are striking. Reindeer indicate open grazing country and seasonal mobility; lemmings and Arctic fox point to cold conditions; hyaenas and wolves testify to a predator community absent from later Irish history. Mammoth remains show that very large grazers

reached Ireland during an earlier part of the last glacial cycle. Their presence is evidence of ecological connection with north-west Europe, but it does not reveal a permanent migration route, a stable land bridge, or the exact coastline at the notional year in question.

Sea levels were lower globally because immense quantities of water were held in ice sheets. The surrounding shelf was correspondingly more exposed in places than it is today. Yet the routes available to animals and people depended not only on sea level, but on local ice, rivers, marshes, coasts and the changing configuration of the Irish Sea basin. It is safer to say that Ireland was repeatedly connected ecologically to the wider western European world than to imagine an uncomplicated dry road to the continent.

## **The Human Question**

The greatest historical question is whether people entered Ireland during this phase. A reindeer femur from Castlepook Cave has been interpreted as bearing a deep mark made by a sharp stone implement while the bone was fresh. The animal has been presented as dating to around 33,000 years ago, and the mark has been proposed as evidence of carcass processing by Upper Palaeolithic hunters. If that interpretation is accepted, it would push evidence for human activity in Ireland far earlier than the well-established post-glacial settlement record.

But the claim must be kept in proportion. A modified bone is not a village, a people or a continuous occupation. There is no securely dated hearth, stone-tool assemblage, dwelling surface, burial, art object or settlement plan in Ireland that can be assigned to 30,927 BCE. The bone dates the animal, not necessarily the making of the mark; cave deposits may be disturbed; and distinguishing tool damage from carnivore action, trampling, weathering or excavation damage requires careful microscopic assessment. Castlepook is an important and provocative clue, not a licence to write a settled human history for Ice Age Ireland.

If visitors did reach the island, they were likely to have been highly mobile hunter-gatherers operating at the north-western edge of the Upper Palaeolithic world. That is an inference from the ecology and from comparable societies elsewhere in Europe, not a fact recovered directly from Derryvree or Castlepook. Such people would have needed intimate knowledge of animal movement, weather, fuel, stone and shelter. Reindeer, hides, bone, sinew and fat could have been valuable resources. A brief hunting visit, seasonal passage or small camp is more consistent with the present evidence than any claim of a large, permanent population.

## **No Kingdoms, No Known Wars**

There is no evidence for political institutions, chiefs, kingdoms, diplomacy, territorial frontiers or organised warfare in Ireland at this date. There are no names, languages, oral traditions that can be securely traced back to this moment, or material signs from which religion can responsibly be reconstructed. The dramatic animals of Castlepook do not prove ritual; the wetland plants at Derryvree do not reveal beliefs. Nor is there evidence for trade in the later sense of sustained exchange networks, specialised production or maritime commerce.

This is not an empty past. It is a past in which environment governed possibility with unusual force. Freshwater, seasonal grazing, shelter from wind, access to stone and the movements of predators and prey would have mattered more immediately than any political boundary. In the absence of direct human evidence, however, those are conditions of life rather than documented aspects of Irish society.

## An Island Approaching Ice


In the longer history of Ireland, Derryvree belongs to an interval before the fullest development of the Last Glacial Maximum. Later advances of the British–Irish Ice Sheet covered much of the island and reshaped its surface, leaving tills, drumlins, erratics and scoured rock. The two tills enclosing Derryvree’s organic bed make this sequence tangible: a cold wetland briefly occupied a gap between glacial phases, then became buried in the sediments of renewed ice.

That buried wetland is consequently more than a curiosity. It establishes that Ireland’s Ice Age history was not one unbroken freeze. Around the notional year 30,927 BCE, a northern Irish hollow supported freshwater plants and animals in a severe, open landscape. Elsewhere, large mammals moved through habitats unlike any seen in historic Ireland. People may have made a fleeting appearance, but the proof remains limited. The responsible story is therefore one of mosses, sedges, cold water, reindeer and advancing ice: a prehistoric Ireland known not through chronicles, but through the fragile traces that survived beneath a drumlin.

# Chapter 075 of 100

## 30926 BCE

### Derryvree's Drumlin Waters<sup>[75]</sup>



**“30,926 BCE” is a modern chronological label, not a recoverable year in Ireland’s deep past. No Irish calendar, settlement sequence, named person or event can be assigned to these twelve months. In relation to the conventional radiocarbon reference year of 1950, the label falls about 32,875 years before present. It belongs to the Late Pleistocene, broadly Marine Isotope Stage 3 (MIS 3): a long, climatically unstable interval before the Last Glacial Maximum. The responsible history of Ireland at this depth is therefore not an annal of political acts, but an account of landscapes, animal populations, sediments and the limits of what they can show.**

## **A Date Within a Long Cold Stage**

Ireland was not yet at the fullest extent of the last British–Irish Ice Sheet. Current syntheses place the major build-up of that ice sheet after roughly 35,000–32,000 years ago, with its maximum extent much later, about 27,000–21,000 years ago. Around the nominal date, then, the island was entering a period in which expanding ice, severe winters, changing sea levels and shifting routes of animal movement increasingly governed what life was possible. Conditions did not remain uniform from one century to the next, much less from one region to another. Shorter climatic oscillations could alter snow cover, vegetation, water supply and the viability of travel across the north-west European landmass.

The familiar map of a modern island should not be projected unchanged on to this world. Sea level was far lower than today because enormous volumes of water were locked in ice sheets. Ireland’s coastlines and the surrounding shelf were consequently very different, and marine barriers were reduced in some directions. Yet lower seas did not make movement easy. Any crossing or overland approach was constrained by cold, exposed terrain, unstable weather, rivers, ice margins and the availability of food. It



is safest to say that Ireland was intermittently connected ecologically to Britain and continental north-west Europe, allowing animals—and perhaps people—to reach it during favourable phases. The evidence does not permit a simple claim of a permanent land bridge, continuous occupation or unrestricted migration.

## The Derryvree Record

The clearest Irish environmental archive relevant to this broad period lies at Derryvree, near Maguiresbridge in County Fermanagh. Road works in 1969 cut through a drumlin and exposed an exceptional sequence: freshwater silts, fine sands and organic deposits sealed between two thick layers of glacial till. The lower till records an earlier advance of ice; the upper till demonstrates that ice later returned. Between them was the remnant of a time when ice was absent locally and shallow freshwater, wet ground and tundra vegetation existed in the hollow.

A radiocarbon determination from the Derryvree organic material, Birm-166, produced an age of  $30,500 \pm 1,100$  radiocarbon years BP. This is not equivalent to 30,500 BCE. Radiocarbon years must be calibrated because atmospheric carbon-14 has varied through time, and the uncertainty is substantial at this antiquity. Published treatments place the deposit broadly in the mid-to-late 30,000s calibrated years BP; one synthesis gives about  $35.9 \pm 1.1$  thousand calibrated years BP. It is thus evidence for a broad cold-stage environment, not proof that a specific pond, plant or animal was present in 30,926 BCE. The nominal year sits within the same larger climatic world, while remaining beyond calendar-year resolution.

Derryvree's fossils nevertheless provide an unusually vivid view of that world. Pollen, plant macrofossils, mosses and insects indicate open, treeless vegetation rather than forest. Grasses, sedges, juniper and herbs were important elements. Finds recorded from the deposit include dwarf willow, mountain avens and bogbean, while aquatic plants show that standing or slow-moving freshwater survived locally. The insect evidence likewise points to a cold, periglacial setting. "Periglacial" does not mean permanently buried beneath a glacier: it describes land strongly affected by frost, seasonal freezing and thawing, sparse cover and short growing seasons near an ice margin.

The most supportable reconstruction is therefore of a wet, open mosaic. Pools and sedgy margins lay amid low vegetation, mosses and frost-worked ground. In summer, long daylight may have supported a brief flush of growth; in winter, frozen soil, snow and wind would have imposed powerful limits. It was not a lush green Ireland, nor a featureless sheet of ice. The Derryvree deposits preserve local conditions in and around water, not a complete map of the island, but they establish that freshwater refuges and tundra-like vegetation occurred in Fermanagh during part of the pre-maximum glacial interval.

## Cork's Cave Fauna

In southern Ireland, Castlepook Cave near Doneraile in north County Cork offers a different kind of evidence. Excavations beginning in the early twentieth century recovered one of Ireland's richest Pleistocene vertebrate assemblages. The collection includes remains attributed to woolly mammoth, giant deer, reindeer, brown bear, wolf, fox, mountain hare, lemmings and spotted hyaena. Later radiocarbon work has shown that important parts of this fauna belong to MIS 3, and improved laboratory preparation has revised some earlier measurements substantially older. In particular, reassessment indicates that some species, including spotted hyaena and giant deer, may have disappeared locally before about 40,000 calibrated years BP.

This is crucial for interpreting 30,926 BCE. Castlepook demonstrates that Ireland could support a much richer cold-stage mammal community than later glacial Ireland, but it is not a census for one year. Cave bones accumulated over long spans. Carnivores could carry prey into passages; hyaenas may have used parts of the cave system as a den; animals could die near fissures; water and collapse could move remains. Early excavators did not have the stratigraphic methods, recording standards or dating techniques available now. A mammoth bone does not prove a mammoth herd in the adjacent valley at the same moment, and a species list does not prove all species were contemporaries.

Even so, the fauna indicates the scale of environmental change that shaped Ireland. Reindeer, Arctic fox, lemmings and mountain hare fit an open, cold landscape. Mammoth and giant deer point to the wider availability, at some times, of grazing and mixed open habitats capable of sustaining very large herbivores. Wolves and spotted hyaenas reveal a predator and scavenger community far removed from later Irish ecosystems. These animals were not merely picturesque Ice Age visitors: their arrival and survival depended on fluctuating habitats and access routes across the wider region.

## **The Human Question**

Human history at this date is possible, but not securely established. A reindeer femur from Castlepook has been reported as dating to around 33,000 years ago and as bearing a deep mark interpreted by zooarchaeologist Ruth Carden as a stone-tool cut or chop made while the bone was fresh. If that interpretation is confirmed, it would be important evidence that people briefly reached Ireland before the Last Glacial Maximum and processed a reindeer carcass there.

It must not, however, be enlarged into a settled Palaeolithic Ireland. The bone is an isolated find from a complicated old cave collection, without an associated hearth, stone-tool assemblage, dwelling surface, human burial or securely excavated hunting camp. Dating an animal bone and identifying a surface modification as human action are related but separate questions. Natural breakage, carnivore damage, sediment abrasion and excavation history all require close taphonomic assessment. The cautious conclusion is that Castlepook presents a serious, testable possibility of a fleeting human presence, not evidence for a permanent population, a named culture or a continuous ancestral community.

The secure evidence for later Upper Palaeolithic activity in Ireland comes from a butchered brown-bear patella at Alice and Gwendoline Cave in County Clare, dated to about 12,810–12,590 calibrated BP. That much later find shows why revisiting museum collections matters, but it cannot be used to fill the enormous chronological gap back to MIS 3. Nor may tools, shelters, art, clothing, language or ritual be inferred for Ireland specifically from better-known Upper Palaeolithic groups elsewhere in Europe. Such comparisons can suggest what travelling hunter-gatherers may have needed to survive, but they are interpretation, not Irish evidence.

## **No Politics, Only Constraints**


There is no evidence for political authority, warfare, diplomacy, formal religion, trade networks or learned traditions in Ireland at this date. Nor is there evidence for farming, livestock, permanent villages, fields, boats or monuments. These absences matter. They are not simply gaps waiting to be supplied from imagination; they define the kind of history that can honestly be written. If people did enter Ireland during MIS 3, they were most plausibly small and highly mobile groups operating within a severe seasonal environment. That is an inference from the wider Upper Palaeolithic world and the practical demands of the landscape, not a demonstrated Irish social system.

The principal development was environmental: a changing edge-land of open vegetation, freshwater pockets, large mammals, carnivores and increasingly formidable ice. Derryvree records life in a cold wetland temporarily preserved between glacial advances. Castlepook records a longer and more complex history of animals reaching southern Ireland, dying or being carried into caves, and leaving remains later re-examined by scientists. Together they make 30,926 BCE meaningful without pretending that it was a year Ireland's archaeological record can isolate.

## Chapter 076 of 100

### 30925 BCE

#### BIRM-166's Tundra Waters<sup>[76]</sup>



**“30,925 BCE” is a modern chronological label, not a date that can be matched to an Irish event, ruler, settlement or season. There were no written records, calendars or named communities in Ireland from which such precision could be recovered. The most responsible approach is to place this notional year within the later part of Marine Isotope Stage 3, a long and climatically unstable phase of the last Ice Age. The strongest local evidence comes not from an excavated camp but from sediments, plant remains and animal bones. Together they reveal an Ireland in transition: cold, largely treeless and inhabited by mobile animals, with advancing ice increasingly reshaping what land could sustain life.**

### **A Date Within a Range**

The closest well-studied environmental archive is Derryvree, near Maguiresbridge in County Fermanagh. Roadworks there exposed freshwater silts and fine sands trapped between two thick layers of glacial till in a drumlin. The organic sediments produced radiocarbon determination Birm-166, conventionally dated to 30,500 radiocarbon years before present, with a substantial uncertainty. Radiocarbon years are not calendar years: once calibrated, the published range lies broadly around 36,900–31,700 calibrated years before present, approximately 34,950–29,750 BCE. The label 30,925 BCE therefore falls within the broad chronological window illuminated by the deposit, but it cannot be assigned to a particular layer, pool, plant or animal.

This distinction matters. Derryvree records an interval during which freshwater and organic sediment accumulated at one location before later ice buried and incorporated it into a drumlin. It is evidence for conditions in north-central Ireland over a span of time, not a diary entry for one year. Nor should a single

record be made to stand for every valley, coast and upland on the island. Its importance is that it gives rare, direct evidence that at least part of Ireland was ice-free during the later Middle Midlandian, before the British–Irish Ice Sheet reached its eventual maximum extent.

## Cold Wetlands Beneath Later Ice

The Derryvree plant and animal microfossils indicate open tundra and a periglacial climate. Rather than forests, the landscape supported low, cold-adapted vegetation and wet ground: sedges, mosses, dwarf shrubs and aquatic plants associated with shallow freshwater. Fossil finds including bogbean, water-milfoil, mountain avens, dwarf willow and clubmoss point to a mosaic of pools, marshy margins and sparsely vegetated ground. “Muskeg”, the term used in the original interpretation, conveys a waterlogged, peat-forming tundra environment rather than a modern Irish bog exactly reproduced in the deep past.

Such a setting would have changed sharply through the year. Winters were long and severe; freezing and thawing disturbed exposed soils; meltwater and shallow standing water could be important during warmer months. The evidence does not permit a local thermometer reading, but it does show that this was not an ice-free woodland landscape resembling later prehistoric Ireland. Trees had little or no place in the Derryvree assemblage. Open ground and wetland plants instead testify to a cold climate with a short growing season.

Crag Cave in County Kerry offers complementary, though differently dated, evidence for the wider climatic rhythm. Uranium-series dates from broken cave formations show that calcite growth occurred episodically during warmer interstadials of the last glacial period, when liquid water could move through the shallow karst system. These episodes align broadly with Greenland interstadials, abrupt northern climatic ameliorations visible in ice-core records. Around the modern label 30,925 BCE, Ireland was thus part of a North Atlantic world prone to swift shifts between relatively milder intervals and renewed cold. Derryvree should be understood against that restless background, not as a stable age of unchanging tundra.

## Animals on an Open Island

Southern Irish caves provide the principal evidence for the larger animals that reached Ireland in this part of the Pleistocene. Castlepook Cave near Doneraile, County Cork, is especially significant. Its antiquarian excavations recovered a mixed and complicated accumulation of bones from different episodes, later disturbed by water, carnivores and excavation itself. Modern radiocarbon reassessment has nevertheless shown that some of its fauna belongs to Marine Isotope Stage 3, much earlier than older dating programmes suggested.

The fauna demonstrates that Ireland could support, or at least receive, an imposing range of cold-stage mammals. Reindeer, woolly mammoth, giant deer, brown bear, wolf, Arctic fox, mountain hare, lemmings and spotted hyaena are among the animals recorded from Castlepook’s Pleistocene assemblage. They should not be imagined as a single herd or a perfectly simultaneous community. Cave deposits often combine material accumulated across centuries or millennia. Yet their presence establishes an ecological reality: open habitats, prey animals and predators existed in Ireland before the Last Glacial Maximum.

Reindeer are particularly useful for visualising this world. Herds could exploit patchy tundra vegetation and ranged across very large territories. Mammoths and giant deer, where present, would likewise have required extensive feeding grounds, while hyaenas, wolves and bears indicate competing scavengers and predators. Caves were not necessarily homes for every species represented in them. A cave

could be a carnivore den, a trap, a shelter used intermittently, or a place where water and sediment concentrated remains. The Castlepook bones reveal animal movement and survival more securely than they reveal a settled landscape.

## **The Castlepook Human Question**

The most tantalising possible evidence for people is a reindeer femur from Castlepook. It has been directly dated to roughly 33,000 radiocarbon years before present and bears a deep mark interpreted by palaeozoologist Ruth Carden as a fresh-bone cut or chop made with a sharp stone tool during carcass processing. If that interpretation is confirmed, it would indicate that a human or humans handled reindeer in Ireland during the Upper Palaeolithic, far earlier than the once accepted record of post-glacial settlement.

It would be wrong, however, to turn one marked bone into a population, a tribe or a village. The specimen derives from an old cave collection rather than a newly excavated, sealed occupation surface. Ireland has not yet produced a securely associated stone-tool assemblage, hearth, dwelling floor, burial, human bone or concentrated butchered food waste of comparable age. The mark is important proposed evidence of human action; it is not proof of permanent settlement or continuous occupation.

If people did visit Ireland around this broad period, the most cautious inference is that they were highly mobile Upper Palaeolithic hunter-gatherers, perhaps following animal movements or making a short foray into a marginal landscape. Even that remains an interpretation, not a demonstrated itinerary. The routes available to animals and people are uncertain. Lower sea levels exposed much more of the continental shelf than exists today, but the precise configuration of land, water, ice and passable corridors between Ireland, Britain and continental Europe remains debated. Movement need not imply a simple, continuous “land bridge”.

## **No Politics, but Real Constraints**

There is no evidence from which to reconstruct political affairs, diplomacy, warfare, social rank, language, formal religion or named groups for Ireland in 30,925 BCE. There were no states, kingdoms, farms, monuments or trading settlements. Claims about chiefs, rituals, alliances or conflicts would be invention. The available record is environmental and zooarchaeological, with one possible trace of butchery.

Nevertheless, the evidence speaks to the basic conditions from which social life, if present, had to proceed. Food would have depended on knowledge of seasonal animal behaviour, weather, shelter and terrain. A small hunting party would have faced exposure, uncertain prey and dangerous carnivores; it may have used portable stone tools, hides and fire, but none of these has yet been securely recovered from Ireland for this horizon. Exchange and diplomacy cannot be demonstrated. Nor can any permanent settlement pattern. What can be said is that access to game and safe movement across wet, frost-affected ground would have mattered more than boundaries or institutions.

## **Ice-Sheet Build-Up**

The greater historical development was geological. The British–Irish Ice Sheet was building after about 35,000–32,000 years ago, although its growth was neither simple nor synchronous across Ireland and Britain. Later it would cover all or almost all of Ireland’s low ground, scour older landscapes and


leave drumlins, tills, meltwater channels and offshore landforms that still define much of the island's physical geography. At the date represented here, Derryvree's freshwater deposits preserve a valuable pre-maximum window: not a timeless wilderness, but a vulnerable episode before advancing ice sealed its wetland archive below glacial sediment.

For Ireland, then, 30,925 BCE is best remembered not as the year of an identifiable human event but as part of the Derryvree interval. Freshwater lay among tundra plants in Fermanagh; large mammals moved through open country in places such as north Cork; and the climatic system was heading towards more extensive glaciation. The silence of the human record is itself historically important. It sets a firm boundary between evidence and wishful storytelling, while leaving open the possibility that future excavation, dating and microscopic analysis may clarify whether people briefly entered this demanding Ice-Age Ireland.

## Chapter 077 of 100

30924 BCE

### The Derryvree Drumlin Window<sup>[77]</sup>



30,924 BCE is not a recoverable Irish historical year. Nobody in Ireland left a written date, a named ruler, a settlement plan or an event record that can be assigned to it. The number is a modern point on a calendar, roughly 32,874 years before AD 1950, used here to orient a much broader Late Pleistocene story. At this depth in time, radiocarbon measurements must be calibrated and normally produce ranges rather than exact calendar years. The most responsible account is therefore of Ireland *around* this point: during Marine Isotope Stage 3, in the later Middle Midlandian cold stage, when climate, ice, plants and animal movements shaped a landscape that would later be profoundly remade by glaciation.

## Calendar Date, Geological Timescale

The closest important Irish chronological anchor is Derryvree, near Maguiresbridge in County Fermanagh. Roadworks in 1969 cut through a drumlin and exposed organic freshwater silts and fine sands sealed between two separate layers of glacial till. The order of those deposits is more secure than any attempt to narrate a particular year: glacier ice had deposited the lower till; an interval without ice at that spot permitted fresh water, sediment and organic matter to accumulate; later ice advanced and laid down the upper till.

Material from the organic bed returned a conventional radiocarbon age of 30,500  $\pm$  1,170/–1,030 radiocarbon years BP. Published calibration has expressed this broadly as about 36,900–31,700 calibrated years BP, or approximately 34,950–29,750 BCE. The modern label 30,924 BCE falls within that wide range. It does not demonstrate that a particular Derryvree pool, plant colony or animal was present in that named year, nor that conditions were constant across the entire interval. It does, however, make Derryvree the best local environmental window for Ireland near this horizon.



## Fresh Water Between the Tills

Derryvree was not a familiar green Irish bogland and certainly not a wooded countryside. Fossil pollen, plant remains, mosses and insects indicate a cold, open, treeless landscape with a periglacial regime. Grasses, sedges, herbs and juniper were among the vegetation recorded, while the insect evidence points to wet, plant-rich ground, open pools and mossy margins: a tundra-like muskeg rather than dense forest. The important qualification is scale. These are the conditions shown by a buried freshwater deposit in Fermanagh, not a weather report for every shore and upland across the island.

Nevertheless, the Derryvree evidence overturns any simple image of an Ireland uniformly entombed beneath ice throughout the Ice Age. It records a locally ice-free freshwater environment at some stage between glacial episodes. Pools and saturated ground would have created small refuges for aquatic plants and insects; exposed mineral soils and low vegetation occupied surrounding ground. Such a mosaic was probably highly seasonal. Winter cold, frozen ground, strong winds and short growing seasons limited what could live there, while summer thaw and water movement altered the margins of ponds and channels.

## An Unstable Ice-Age Ireland

The wider setting was one of rapid and uneven change. The Last Glacial Maximum, the period of the greatest late-glacial expansion of the British–Irish Ice Sheet, still lay ahead, but its growth was becoming an increasingly important constraint on the region. Modern reconstructions show that ice expansion did not occur everywhere at once. Scottish ice had expanded markedly by about 31,000 years ago, and the British–Irish Ice Sheet later advanced to the continental shelf edge in some western sectors. The timing, thickness and reach of ice varied from one region to another.

This makes sweeping claims hazardous. The Derryvree sequence and related Fermanagh deposits demonstrate that northern Ireland had supported non-glacial environments before renewed ice cover. They cannot tell us whether all of Ireland was open at 30,924 BCE. Equally, later glacial erosion and deposition destroyed, buried or rearranged earlier surfaces, so the surviving record is inherently patchy. The physical map of the island was also unlike that of today: sea level was lower on the continental shelves, while ice, water depth and changing coastlines governed possible routes between Ireland, Britain and mainland Europe. A continuous land bridge should not simply be assumed.

## Animals of Open Country

Caves preserve another, different archive. Castlepook Cave near Doneraile in north County Cork is Ireland's richest known repository of vertebrate remains from the long period leading towards the Last Glacial Maximum. Its collections include woolly mammoth, giant deer, reindeer, brown bear, spotted hyaena, wolf, foxes, hares and lemmings. Together they show that Ireland supported a far broader cold-stage fauna than its modern fauna. Reindeer and lemmings suggest severe, open conditions; mammoth and giant deer indicate extensive grazing landscapes; hyaenas and wolves show that large predators also used the region.

Yet Castlepook is not a frozen tableau of one day or one generation. Bones accumulated over a long interval through carnivore activity, natural deaths, water movement and early excavations. Improved radiocarbon pretreatment has also shown that some older cave dates required substantial revision.

Castlepook can therefore illuminate the kinds of animals present in pre-maximum Ice Age Ireland, but it cannot prove that every listed species stood together in County Cork in 30,924 BCE.

A further directly dated clue comes from Waterford caves. Genetic work on bones formerly identified as red deer showed that some were actually reindeer, but confirmed red-deer specimens include a pre-Last Glacial Maximum date of about 32,930–31,280 calibrated years BP. This overlaps the modern calendar position used here. It is modest but valuable evidence that animal communities and habitats differed by region and changed through time. The animals were not simply passive occupants: their grazing, browsing, predation and seasonal movements were central ecological forces in a sparsely vegetated landscape.

## **People: A Possibility, Not a Population**

No securely dated camp, hearth, dwelling, burial, tool scatter or human bone demonstrates a resident human community in Ireland at this horizon. Consequently there is no responsible basis for describing tribes, chiefs, political authority, warfare, diplomacy, family arrangements, language, ritual practice or learning. There was no Irish state, and no evidence permits the projection backwards of later Gaelic identities, monuments or traditions.

There is, however, an important question. A reindeer femur from Castlepook has been publicly reported as about 33,000 years old and as bearing a deep mark interpreted as damage made by a stone tool during carcass processing. If that interpretation is confirmed through full scholarly publication and comparison, it would indicate a very early Upper Palaeolithic human visit to Ireland. It would not establish permanent settlement, a large population or continuous occupation. A marked animal bone can show possible handling of a carcass; it cannot reveal whether the people concerned hunted it, scavenged it, crossed from Britain, travelled by boat, remained for an afternoon or returned over generations.

The distinction matters particularly for everyday life and economy. In north-west Europe, people of the Upper Palaeolithic possessed sophisticated stone technologies and depended on flexible hunting, gathering and social networks. That continental context makes a short Irish foraging visit plausible, especially where large grazing animals ranged through open country. But there is no Irish assemblage of securely contemporary tools from which to identify a technology, no hearth from which to reconstruct food preparation, and no settlement debris from which to infer exchange, clothing, shelter or artistic practice. These remain possibilities, not evidence for Ireland.

## **What This Date Can Mean**

The best history of Ireland around 30,924 BCE is consequently environmental and archaeological rather than political. Derryvree records freshwater life and low vegetation enclosed between two phases of glaciation. Castlepook and other caves preserve evidence for mammals and predators adapted to open, cold habitats. Ice-sheet research explains why these traces are discontinuous: advancing ice repeatedly transformed the terrain and erased many surfaces on which people or animals might once have left clearer marks.


This was a world of shallow water, sedge-rich margins, mosses, low shrubs, exposed ground and mobile herds—not a world of farms, towns, monuments or kingdoms. Its most significant development was not an annual event but an ongoing regional transformation: the narrowing of ecological opportunities

as the last great ice-sheet expansion approached. The surviving Irish evidence is slight, local and sometimes contested. Properly read, that limitation is not a failure of history; it is the essential fact of Ireland's deep past.

# Chapter 078 of 100

## 30923 BCE

### Doneraile's Possible Palaeolithic<sup>[78]</sup>



**30,923 BCE is a modern chronological label, not a year that anyone in Ireland recorded or could have recognised. It falls roughly 32,872 years before AD 1950, the reference point conventionally used for “before present” dating, but that arithmetic must not be mistaken for archaeological precision. No event, ruler, settlement or season can responsibly be assigned to this particular year. The appropriate setting is the Late Pleistocene, within Marine Isotope Stage 3 (MIS 3), a climatically unstable part of the last Ice Age.**

Ireland at this remote point was not the familiar island of farms, forests, monuments and named peoples known from later prehistory. Its evidence survives in rare environmental deposits sealed beneath later glacial sediments, in cave bone assemblages, and in the landforms created or remodelled by ice. These materials provide a patchy view of landscapes and animals. They provide vastly less information about humans. The distinction is central: fossils and sediments are evidence; reconstructions of journeys, hunting and social life are carefully limited interpretations.

## **A Date Inside Broad Ranges**

The closest Irish environmental sequence relevant to this date lies at Derryvree, near Maguiresbridge in County Fermanagh. There, roadworks exposed organic-rich freshwater silts and sands caught between two layers of glacial till. The sequence demonstrates a clear local order of events: glacier ice deposited the lower till; an interval without overriding ice allowed water, plants and organic sediment to gather; and a later ice advance covered the deposits with another till. It is an unusually valuable glimpse of a cold, ice-free interval, preserved because later ice sealed it.

Organic material from the Derryvree deposits returned a conventional radiocarbon age of about  $30,500 \pm 1,200$  radiocarbon years before present. Calibration matters because radiocarbon years are not calendar years: atmospheric carbon-14 levels have varied through time. Modern calibration places the broad result at approximately 36,900–31,700 calibrated years BP, or about 34,950–29,750 BCE. The notional year 30,923 BCE lies within that wide interval, but cannot be pinned to a particular horizon in the silt, a particular generation of animals, or a particular episode of human activity.

Derryvree should not be treated as a weather station for the whole island. It shows that its part of Fermanagh was ice-free long enough for a freshwater wetland to develop. It does not establish that every region of Ireland was simultaneously free of ice, that conditions were identical in Cork, or that the ice margin stood still. MIS 3 climate changed abruptly and repeatedly across the North Atlantic world. The record instead offers a local window into environments that existed before the fullest development of the Last Glacial Maximum.

## **Wetland in a Treeless Country**

The Derryvree plant and insect evidence indicates a cold, open landscape rather than woodland. Mosses, sedges, bogbean, dwarf willow and mountain avens point towards wet ground and tundra-like or muskeg conditions, with shallow water, saturated soils and low vegetation. Such a setting could appear unexpectedly rich at close range: pools and marshy margins supported aquatic plants and invertebrates, while drier patches carried cold-tolerant herbs and shrubs. Yet it was not a gentle northern countryside. Long winters, frost action, exposed ground and strong seasonality shaped the possibilities for all living things.

Later Ireland's deep soils and extensive Atlantic woodland did not yet exist in their familiar form. Vegetation cover was sparse to low and varied with drainage, exposure and changing temperature. This does not mean an entirely barren landscape. The important lesson from Derryvree is diversity at a small scale: freshwater, sedge-rich ground, mossy wetland and open mineral terrain could occur near one another. Such mosaics created resources for grazing animals and predators, but they were also vulnerable to climatic deterioration and advancing ice.

The wider ice-sheet history adds urgency to this picture. Recent reconstructions show that the British–Irish Ice Sheet grew rapidly around this broad period, though its expansion was regionally uneven rather than a single island-wide event. Ireland was entering an era in which ice, meltwater, sea level and drainage patterns would repeatedly alter access to habitats. Later glaciation would erode, bury or disperse many traces of the landscapes and any people that had preceded it. Absence of sites is therefore significant, but it is not simple proof that people never visited.

## **Castlepook and the Reindeer Femur**

The most consequential possible human evidence comes from Castlepook Cave, also known as Mammoth Cave, near Doneraile in north County Cork. Cave excavations and old museum collections there produced a rich but complicated Late Pleistocene faunal record. Reindeer, mammoth, giant deer, brown bear, wolf and spotted hyaena are among the animals represented. They did not necessarily occupy the cave or surrounding country at the same time. Cave assemblages may accumulate over long periods through natural deaths, carnivore activity, water movement and earlier excavation practices; they are not a snapshot of one landscape.

One reindeer femur from the Castlepook collection is particularly important. It has been radiocarbon dated to roughly 33,000 years ago and carries a deep surface incision interpreted by zooarchaeologist Ruth Carden as a mark made by a sharp stone tool while the bone was fresh. County Cork heritage material presents it as evidence of Palaeolithic butchery, approximately around 31,000 BCE. If that interpretation is upheld, it would show that at least one person handled a reindeer carcass in Ireland during MIS 3, pushing the possible human story of Ireland much further back than the formerly accepted post-glacial evidence.

That is a major possibility, but it remains a narrow claim. The date establishes when the animal died, not necessarily the exact moment at which the mark was made. Identifying a cut mark is a specialist taphonomic judgement, separate from radiocarbon measurement. Moreover, the femur was recovered from an old cave collection rather than a modernly excavated, sealed occupation floor. No securely associated hearth, stone-tool assemblage, shelter, burial, human remains or repeated food-waste deposit of comparable age has been recovered in Ireland. The bone cannot demonstrate a permanent settlement, a population size, a language or a named cultural group.

## **What Human Presence Could Mean**

If the Castlepook incision does record butchery, the most restrained inference is that one or more people possessed a sharp stone cutting edge and processed part of a reindeer carcass. They may have hunted the animal, encountered it after death, removed meat, hide, sinew or marrow, or worked elsewhere before the bone entered the cave deposit. Carnivores may also have carried remains into the cave. None of these alternatives can yet be distinguished with confidence.

It is reasonable to see any such visitors as highly mobile foragers operating in a demanding northern environment, but it would be irresponsible to turn that possibility into an imagined Irish tribe or village. No Irish evidence of this age identifies houses, family groups, campsites, seasonal territories, boats, exchange networks or regular routes between Ireland, Britain and continental Europe. The lower sea levels of the Ice Age altered coastlines, but archaeology has not supplied a mapped crossing route or evidence for trade. Nor do surviving materials show farming, herding, pottery, metalworking or monument building. These are all developments of much later millennia.

## **Politics, Belief and Learning Beyond the Evidence**

Political affairs, warfare and diplomacy leave no identifiable record for Ireland around this point. There are no chiefs, boundaries, alliances, fortifications or weapons that can be dated to 30,923 BCE. Even if people visited, their numbers and relationships are unknown. Competition between carnivores and human hunters for animal resources is conceivable in an ecological sense, but no Irish evidence documents an encounter or conflict. The language of kingdoms, nations and Irish identity has no place in this period.

The same restraint applies to religion, culture and learning. Humans capable of travelling through Ice Age Europe undoubtedly had social knowledge, practical skills and probably rich symbolic lives. However, no Irish artwork, burial practice, ritual place, musical object or teaching tradition can be attributed to this horizon. The possible use of a stone tool would attest technological competence, not a recoverable cultural system. Silence in the archaeological record does not mean that people lacked beliefs or stories; it means that Ireland presently offers no evidence from which to describe them.

Economically, the strongest evidence concerns wild resources rather than a human economy. Reindeer and other large herbivores formed part of a cold-stage food web, while carnivores used caves and open landscapes in ways that helped create the bone record. At Derryvree, wetland plants and insects reveal the ecological base of that world. A possible human carcass-processing trace at Castlepook would suggest opportunistic or planned use of animal resources, but not regular provisioning, trade or an established settlement system.

## **An Island Before Its Recorded Past**

The most important development illuminated by 30,923 BCE is therefore environmental, not political: Ireland was passing through an unstable late-Ice-Age phase before extensive later glaciation transformed much of the landscape. Derryvree preserves evidence of cold freshwater wetland in Fermanagh; Castlepook preserves a time-depth of animal life in Cork; the marked reindeer femur raises the possibility of a remarkably early human visit. Together they correct the old image of an Ireland that was either permanently empty or uniformly ice-covered.

They also impose discipline. The evidence does not permit an annual chronicle. Around the modern label 30,923 BCE, Ireland can be described as a changing, mostly treeless northern landscape inhabited by cold-adapted animals and threatened by expanding ice. It may also have been reached by people, perhaps briefly, as the Castlepook femur suggests. Whether that possibility represents a single visit or a wider but archaeologically elusive human presence remains one of the most important unanswered questions in Irish prehistory.

# Chapter 079 of 100

## 30922 BCE

### The Fermanagh Silt Clock<sup>[79]</sup>



**30,922 BCE is not a year that can be recovered from Irish prehistory in the ordinary historical sense. No community in Ireland recorded it, no ruler can be named, and no archaeological deposit can be assigned to a particular season or day within it. The number is a modern calendar label, approximately 32,871 years before AD 1950, the conventional reference point for “BP” dating. It falls in the Late Pleistocene, within Marine Isotope Stage 3, a climatically unstable part of the last Ice Age. The responsible approach is therefore to place it within dated ranges and to distinguish the physical evidence from the stories that may be built around it.**

## Between Two Glaciers

The most useful Irish evidence for this broad moment comes from Derryvree, near Maguiresbridge in County Fermanagh. Road works in 1969 cut through a drumlin and exposed a remarkable sequence: an older till laid down by ice, freshwater silts and fine sands containing organic material, then a second, later till. The order of these layers is secure. Ice had occupied the locality; afterwards, ice-free conditions allowed water, mineral silt, plants and animal remains to accumulate; later glacial activity sealed the deposit beneath fresh sediment.

The Derryvree organic bed, laboratory sample BIRM-166, produced a conventional radiocarbon determination of 30,500 +1,170/–1,030 radiocarbon years BP. Calibration has placed the deposit broadly at about 36,900–31,700 calibrated years BP. The modern date 30,922 BCE lies within that wide span, but it cannot be equated with a particular layer, organism or event in the bed. Calibration is necessary because atmospheric carbon-14 has varied over time, and uncertainty is considerable at this antiquity. Derryvree is consequently a window on an interval, not a diary entry for one numbered year.



## A Cold Wetland Landscape

The Derryvree flora and fauna indicate open tundra vegetation and a periglacial climate: ground affected by severe cold and seasonal freezing, but not then buried beneath glacier ice. This was not a forested Ireland. Mosses, sedges and small cold-adapted flowering plants grew where the short summer permitted them, around shallow pools, saturated ground and slow-moving freshwater. Fossil evidence includes bogbean, mountain-avens, dwarf willow and lesser clubmoss. Insects and plant remains point to a muskeg-like mosaic of wet ground rich in decaying vegetation, open water and mossy margins.

Such a landscape should not be imagined as uniform. Exposure, drainage, snow cover, altitude and the proximity of ice all created local differences. Fermanagh's drumlin country was a changing terrain of low ridges, basins and watercourses, while colder or drier patches may have supported more sparsely vegetated ground. The evidence supports a treeless, harsh setting with cold winters; it does not permit a precise reconstruction of annual temperatures, snow depth or the appearance of every valley. Nor does it show that all Ireland shared exactly the Derryvree conditions at once.

## Cork's Animal Archive

Castlepook Cave, near Doneraile in County Cork, supplies a different but complementary record. The limestone cave system, also called Mammoth Cave, has yielded more than 2,000 bones from deposits disturbed and accumulated over a long period. Geological Survey Ireland describes it as Ireland's richest site for vertebrate fauna in the period leading towards the Last Glacial Maximum. Its Ice-Age fauna includes woolly mammoth, giant deer, reindeer, brown bear and spotted hyena; later material includes Arctic fox, wolf and lemmings. The cave was a repository, not a simple snapshot of one living community. Water movement, carnivore activity, early excavations and the mixing of deposits all complicate the record.

Nevertheless, Castlepook shows that Ireland was connected to wider north-west European animal worlds during favourable phases of the Ice Age. Reindeer and mammoth indicate open country capable of supporting large grazing mammals; hyenas and wolves indicate predators and scavengers within that ecosystem. Hyenas may also explain why some bones entered the cave: dens and feeding places can accumulate carcass parts brought in from elsewhere. It is therefore wrong to treat every species represented in the cave as proof that it stood outside the entrance in 30,922 BCE. The assemblage establishes broad regional possibilities, not a census for a single year.

## The Human Question

One Castlepook reindeer femur makes this period especially important for Irish history. Ruth Carden's examination identified a deep linear mark interpreted as damage made by a sharp stone tool while the bone was fresh. The bone has been publicly presented as approximately 33,000 years old and, if the interpretation and chronological association hold, it may indicate that a person processed a reindeer in Ireland during the Upper Palaeolithic. That would greatly extend the island's human record beyond the terminal-Pleistocene evidence from Alice and Gwendoline Cave in County Clare.

The limits are as important as the possibility. A radiocarbon measurement dates the animal's death, not necessarily the instant at which a surface mark was made. The old Castlepook collection lacks a securely excavated, undisturbed context for this individual bone. No stone-tool assemblage, hearth, dwelling floor, burial, repeated butchery deposit or human remains of comparable age has been recovered

there. Recent work has also shown that some older Irish cave radiocarbon dates need reassessment under improved pretreatment methods. The femur is thus an intriguing possible trace of human action, not evidence for a known settlement or permanent population in Ireland in this particular year.

## **Society Without a Settlement**

There is no evidence from Ireland at this date for political institutions, chiefs, borders, diplomacy, organised warfare, farming, villages, monuments, formal religion or literacy. Nor is there evidence for trade networks operating within Ireland. If people did reach the island during this broader interval, they were likely highly mobile hunter-gatherers moving through a challenging north-west European landscape, perhaps following seasonal opportunities associated with large mammals and open habitats. That is an interpretation drawn from wider Upper Palaeolithic lifeways and the possible Castlepook butchery trace; it is not a demonstrated description of an Irish community.

Everyday life, if human visitors were present, would have depended on shelter, fire, clothing, stone tools and close knowledge of animal behaviour and seasonal terrain. Yet none of these has been securely found in Ireland for 30,922 BCE. It would be misleading to import cave art, ritual practices, named cultures or detailed hunting customs from France, Iberia or mainland Britain and present them as Irish facts. Ireland's evidence is too sparse. Its silence is historically meaningful: later ice advances and erosion removed, buried or disturbed many landscapes where ephemeral camps might once have stood.

## **Approaching the Ice Maximum**

This was also a time of major environmental change rather than stability. Derryvree's intertill deposit proves that north-central Ireland was locally ice-free during its formation. Other dated evidence has been used to argue that substantial parts of Ireland remained ice-free until at least about 34,000 years ago, before the principal build-up of the last Irish Ice Sheet. But the precise timing, extent and behaviour of earlier ice remain debated. Newer syntheses emphasise retreat–advance behaviour within Marine Isotope Stage 3 and caution against treating the later Last Glacial Maximum as a single, uncomplicated event.

The full Last Glacial Maximum came later, conventionally around 26,500–19,000 years ago, when the Irish Ice Sheet formed part of the much larger British–Irish Ice Sheet. Ice subsequently reshaped or concealed vast areas of the earlier landscape. That later destruction partly explains why the record for 30,922 BCE consists of a buried Fermanagh wetland, cave bones in Cork, speleothems, tills, landforms and laboratory dates rather than settlements. Crag Cave in County Kerry preserves episodic speleothem growth across parts of Marine Isotope Stage 3, independently underlining that climatic conditions fluctuated rather than declining in a simple straight line.

## **What Can Be Said Responsibly**


Ireland around 30,922 BCE was not a political landscape but an Ice-Age environment in transition. The strongest direct evidence is environmental: an ice-free, cold freshwater wetland at Derryvree, preserved between separate glacial deposits. Castlepook adds a geographically distant animal archive showing that reindeer, mammoth, giant deer, bears, hyenas and other mammals formed part of Ireland's wider Late Pleistocene story. A marked reindeer femur raises the prospect of a brief human encounter with that world, but cannot yet demonstrate a settlement, society or event in this exact year.

The Fermanagh silt clock therefore marks duration rather than an anniversary. It tells of water lying in a basin between glacial episodes; plants and insects surviving a severe climate; animals moving through changing habitats; and a landscape soon to be transformed again by expanding ice. That is enough to make this remote point in time part of Irish history, provided its uncertainties are kept visible.

## Chapter 080 of 100

30921 BCE

The Maguiresbridge Freshwater Archive<sup>[80]</sup>



Modern calendar-year precision is not available for Ireland in 30,921 BCE. No one on the island recorded a date, named a season, or left an archaeological sequence capable of identifying a particular year, event or individual. The number is a modern point on a retrospective calendar: it is roughly 32,870 calendar years before AD 1950, the conventional starting point for “before present” dating. The responsible approach is therefore to ask what dated environmental evidence can illuminate Ireland within a broad interval around that point, rather than to invent an episode for the year itself.

That evidence places Ireland in the Late Pleistocene, within Marine Isotope Stage 3 (MIS 3), the long and climatically volatile phase before the Last Glacial Maximum. The most useful Irish archive is not a settlement or a monument but a buried freshwater deposit at Derryvree, near Maguiresbridge in County Fermanagh. Its silts and fine sands were exposed during road works in 1969 within a drumlin: a hill shaped by glacier ice. They lay between two separate sheets of till, the unsorted sediment deposited directly by ice. The sequence is important because it records a period in which freshwater and vegetation existed locally after one glacial advance and before another buried the evidence.

### A Date Within a Range

Organic material from the Derryvree freshwater series produced a conventional radiocarbon age of 30,500 +1,170/-1,030 radiocarbon years BP. Radiocarbon years are not calendar years. The proportion of radioactive carbon in the atmosphere has varied through time, so a measurement must be calibrated against independent records. Modern calibration places the Derryvree material broadly between about

36,900 and 31,700 calibrated years BP, approximately 34,950–29,750 BCE. The modern label 30,921 BCE lies within that wide range, but cannot be fixed to a particular layer, month, generation or environmental episode.

The distinction matters. Derryvree does not provide a snapshot of all Ireland on a single day. Nor does it prove that every part of the island was ice-free at once. It establishes something more limited but substantial: during part of this broad late-MIS-3 interval, ground in south Fermanagh supported a freshwater environment in a cold, periglacial landscape. The lower till shows that ice had previously affected the area; the upper till shows that ice returned later. Between them lies a rare survival of a landscape usually erased by later glaciation.

## **Wet Ground in a Cold Country**

The fossil evidence from Derryvree indicates open tundra rather than forest. Pollen was poorly preserved, but it was chiefly from herbaceous plants. Plant macrofossils included mosses and species associated with cold, wet or exposed ground, among them bogbean, dwarf willow, mountain avens and lesser clubmoss. Insect evidence pointed to a muskeg-like setting: waterlogged ground rich in plant matter, with open pools and mossy margins. This was not a featureless white wilderness. It was a patchwork of sedges, shallow water, low vegetation, bare mineral ground and seasonally frozen surfaces.

Yet it should not be romanticised as a stable northern marsh. The environmental reconstruction suggests harsh winters and a short productive season. Estimates derived from the fossil assemblage envisage July temperatures perhaps around 11–13°C, while January temperatures could have been far below freezing. Such figures are reconstructions for the wider deposit, not a thermometer reading for 30,921 BCE. They nevertheless convey the central fact of life in this period: survival for plants and animals depended on making use of brief summers in an unstable climate.

Crag Cave in County Kerry provides a second, independent indication of this instability. Uranium-thorium dating of broken and reworked cave formations shows that stalagmites formed intermittently during MIS 3. As such deposits require liquid water, their growth signals episodes when local annual temperatures were sufficiently mild for water to percolate through the shallow cave system. The pattern broadly tracks warmer Greenland interstadials and demonstrates that south-west Ireland responded sharply to North Atlantic climatic swings. Derryvree's wetland should therefore be understood as part of a changing Ice Age world, not as evidence for a permanently benign interval.

## **Animals and the Cave Record**

The animal record is strongest in limestone caves, especially Castlepook Cave near Doneraile in north County Cork. Cave deposits there have yielded reindeer, woolly mammoth, brown bear, hare, wolf and spotted hyaena, alongside other remains accumulated over a long and complicated history. The assemblage confirms that, before the later maximum spread of ice, Ireland could support elements of the north-west European cold-stage fauna. Reindeer were adapted to open country; mammoths grazed broad expanses; hyaenas and wolves were formidable scavengers and predators. Their presence is powerful evidence that Ireland was not biologically empty.

But cave bones require caution. Castlepook was excavated largely in the early twentieth century, before modern recovery standards, and many deposits were disturbed. A bone found in a cave is not necessarily evidence that the animal died there. Carnivores could drag prey or carrion into chambers; water and later digging could move remains; specimens from different millennia might become mixed.

Researchers of the Irish Quaternary Fauna Project consequently treated the chronology and formation of cave assemblages as questions to be tested through direct radiocarbon dating rather than assumed from association.

One Castlepook reindeer femur has attracted special attention because it bears a deep linear mark interpreted by Ruth Carden as damage made by a sharp stone tool during butchery. If that interpretation is sustained, it would indicate that a person handled a reindeer in Ireland during the Upper Palaeolithic, vastly earlier than the well-established post-glacial settlement record. It is a significant possibility, but it is not proof of a resident population in 30,921 BCE. There is no securely excavated camp of that age in Ireland, no hearth, stone-tool assemblage, dwelling floor, human burial or repeated processing site associated with the bone. A single modified specimen cannot demonstrate continuous occupation.

## **People: Possibility, Not a Polity**

The available evidence therefore permits only a restrained account of human affairs. There are no Irish political institutions, leaders, territories, wars, treaties or diplomatic encounters visible at this depth of time. There is no evidence for farming, herding, pottery, metalworking, writing, monuments, formal religious sites or long-distance trade networks based in Ireland. Nor can language, kinship rules or named communities be recovered. To fill these silences with prehistoric chiefs or tribal conflicts would be fiction rather than history.

If people did reach Ireland during a milder late-MIS-3 episode, the most reasonable comparison is with highly mobile Upper Palaeolithic hunter-gatherers elsewhere in north-west Europe. Their immediate concerns would have been shelter, fuel, safe movement, knowledge of animals and weather, and access to food in a landscape of extreme seasonality. Reindeer could have supplied meat, fat, hide, sinew and bone, but this is an inference from the animal and from comparable human societies, not direct evidence of a particular Irish hunting party. The Castlepook mark, even if anthropogenic, may record a brief visit rather than a settled community.

## **Ice, Land and Regional Change**

The wider trajectory was towards greater glaciation. Recent British–Irish Ice Sheet reconstructions begin their detailed mapping at 31,000 years ago because evidence before then is fragmentary. They indicate that ice was building over Ireland and Britain from about that point, ultimately expanding to its Last Glacial Maximum extent around 25,000–23,000 years ago. At 30,921 BCE, ice conditions across Ireland were neither simple nor uniform: Derryvree preserves local non-glacial ground within a dated range, while broader evidence indicates ice centres, advances and retreats elsewhere in the region.

This regional unevenness is the key to the year. Ireland was not yet the familiar green, wooded island of later millennia, nor was it a single continuous ice sheet at every moment. It contained transient habitats at the edge of changing ice: wetlands beneath Fermanagh drumlins, open grazing land capable of supporting large mammals, cave refuges and carnivore dens in Cork, and uplands where cold conditions imposed severe limits. The sea, coastlines and routes across the surrounding region also differed from those of today because global ice locked away water, though the evidence does not allow a precise route to be assigned to any possible human visitors.


## What Can Be Said Responsibly

For 30,921 BCE, the principal Irish development is environmental, not political. Derryvree's freshwater sediments show that an open, cold wetland existed in County Fermanagh during a calibrated interval embracing this modern date. Castlepook's fauna shows that large mammals and carnivores occupied at least parts of Ireland during the wider Late Pleistocene. The marked reindeer femur raises the important but still limited possibility of human activity. Together these records replace an older image of an entirely lifeless Ice Age Ireland with a more complex one: a land repeatedly transformed by climate, supporting hardy plants and animals, and perhaps visited by people whose trace is presently no more than a contested mark on bone.

# Chapter 081 of 100

## 30920 BCE

### Awbeg Valley Faunal Threshold <sup>[81]</sup>



## A Date Measured in Millennia

**“30,920 BCE” is a modern calendar label, not a year that can be recovered from Ireland’s archaeological record. No Irish community recorded seasons, rulers or events at this depth in time, and there is no excavated settlement whose occupation can responsibly be assigned to that precise year. In conventional archaeological terms, the label falls roughly 32,900 years before 1950, within Marine Isotope Stage 3 (MIS 3), a long, climatically variable phase of the Late Pleistocene. Radiocarbon results from this era are reported as probabilities and must be calibrated against changing atmospheric carbon levels. They provide ranges, not an annalistic date.**

The best responsible account of Ireland at this point is therefore one of landscapes, animal remains, sediments and ice-sheet history. Around the time indicated, parts of the island supported a cold, open environment and substantial mammals, while the wider British–Irish Ice Sheet was beginning an expansion that would soon transform Ireland. The evidence is uneven. North-western Fermanagh preserves an organic sediment sequence that offers a rare glimpse of vegetation and water; Castlepook Cave near Doneraile in north County Cork preserves an exceptional but complicated animal-bone archive. Neither site is a complete portrait of the entire island, and neither permits a story of named people or events.



## Wetland Evidence at Derryvree

At Derryvree, near Maguiresbridge in County Fermanagh, organic-rich freshwater deposits lie between glacial tills. This stratigraphic position is crucial: the sediments accumulated during an interval when local ground was not overridden by ice, then were buried as ice returned. Pollen, plant macrofossils and other biological remains indicate a treeless, cold-stage landscape with wet ground and shallow freshwater. Sedges, mosses and small hardy plants were central components of this environment; aquatic and wetland taxa demonstrate that the deposits record real standing or slowly moving water, rather than merely wind-blown dust on frozen ground.

A radiocarbon determination from the Derryvree organic silts,  $30.5 \pm 1.2$  thousand radiocarbon years BP, has been calibrated to approximately 36.9–31.7 thousand calendar years BP. The modern date-label 30,920 BCE falls within that broad calibrated range. That does *not* mean the Derryvree pool can be dated to this particular notional year, nor that all Ireland shared its precise vegetation. It does mean that this Fermanagh evidence is directly relevant to the broad period: before the island's later, more extensive ice cover, some places contained cold freshwater habitats capable of supporting a sparse tundra-wetland flora.

Such evidence changes the usual image of an Ice Age Ireland as simply a white wilderness. Conditions were severe and highly seasonal, but there were mosaics of water, sedge-rich ground, exposed mineral soils and low vegetation. The term “mammoth-steppe” is useful only with caution here. It describes a broad Eurasian assemblage of open, productive cold-environment habitats, not a uniform Irish biome. Derryvree records one local wetland, while the composition of vegetation varied with drainage, altitude, latitude and proximity to ice.

## An Island Approaching Glaciation

Ireland was moving towards a major environmental threshold. Recent reconstructions of the British-Irish Ice Sheet place substantial expansion over Ireland around 29,000 years BP, with much of the island covered by about 28,000 BP; the ice sheet reached its greatest overall volume later, around 23,000 BP. These reconstructions are necessarily regional: advance was not a single wall of ice arriving everywhere on one date. Nevertheless, they make clear that the relatively habitable conditions represented by MIS 3 deposits would not last. Ice, permafrost processes, meltwater, changing sea levels and the disruption of plant and animal ranges remade the landscape.

For 30,920 BCE, the important point is transition rather than culmination. The Last Glacial Maximum had not yet reached its full extent, but Ireland was already part of a north-west European world of marked climatic instability. The island's later glaciation also explains why the evidence is so fragmentary. Advancing ice eroded, redeposited or buried older surfaces; rivers and cave processes mixed deposits; coastlines that might once have held evidence are now drowned or altered. Absence of a site is not proof that animals, or people, were absent.

## Castlepook and the Animal Record

Castlepook Cave, also called Mammoth Cave or Doneraile Cave, lies in the limestone country of the Awbeg Valley below the Ballyhoura Hills. It is Ireland's richest known cave archive for vertebrate life before the Last Glacial Maximum. Excavations, chiefly undertaken in the early twentieth century,

recovered many thousands of bone fragments, although only a portion of the original collection survives. Modern reassessment, radiocarbon dating and renewed excavation have made the site more informative, while also exposing the limitations of its antiquarian recovery.

The cave's fauna includes woolly mammoth, giant deer, reindeer, brown bear and spotted hyaena, with wolf, Arctic fox, mountain hare and lemmings also represented. These species did not necessarily all live side by side at the same moment, nor do their bones all describe one landscape. Castlepook accumulated material across a long period, and water movement, carnivore activity and later disturbance complicate associations between finds. Yet the assemblage securely establishes that animals adapted to cold, open country used, crossed or were brought into Ireland during the wider MIS 3 interval.

Spotted hyaenas are particularly revealing. Castlepook appears to have functioned, at least in part, as a carnivore den or feeding place. Hyaenas could carry prey and bones into underground chambers, gnaw them, and leave dung and skeletal debris behind. A cave bone is therefore not automatically proof that an animal died at the entrance, much less proof of human hunting. The mammoth and reindeer remains evoke a landscape with large herbivores, but their presence at Castlepook is evidence of animal ecology and cave taphonomy before it is evidence of any human economy.

## **The Uncertain Human Trace**

A reindeer femur from Castlepook has been reported as bearing a deep modification interpreted as a cut or chop made by a sharp stone tool, and the bone has been presented as dating to roughly 33,000 years ago. If microscopic study and contextual research ultimately confirm that interpretation, it would be a remarkable indication that one or more Upper Palaeolithic people processed a reindeer in Ireland during the wider pre-maximum glacial period. It would not, however, establish a village, a permanent population or a continuous Irish settlement.

That distinction is essential. The bone dates the death of an animal within a scientific range; it does not on its own date the mark to an exact moment. Nor is the bone from a securely excavated, single-event living floor with an associated hearth, stone-tool assemblage, shelter, burial or repeated food-processing area. Castlepook's old collections were made before modern standards of stratigraphic recording, and the cave's deposits have experienced natural disturbance. The suggested modification is important evidence under investigation, not a licence to invent hunters' names, social groups or journeys.

## **Society Beyond the Evidence**

There is no basis for describing political affairs, diplomacy, warfare, leadership, law, religion or learning in Ireland at this time. No houses, graves, ornaments, art, inscriptions, hearths or toolkits can presently be tied securely to 30,920 BCE. There is likewise no direct evidence for exchange networks, seafaring, trade goods, livestock, cultivation or a settled economy. Even if the Castlepook mark proves human-made, the most it would demonstrate is a moment of carcass processing by a small mobile party, not the structure of that party's society.

Interpretation can go only a little further. Across Upper Palaeolithic Europe, people used stone tools, moved through seasonal landscapes and drew heavily on animal resources. Ireland lay at the far north-western edge of that wider world. It is reasonable to regard a possible Castlepook intervention as compatible with short-lived mobility through an open, cold landscape. It is not reasonable to transfer the rich artistic, ritual or settlement evidence of continental sites directly to Ireland. Those would remain analogies, not Irish evidence.

## A Precarious Ecological World

Everyday life, if people were present at all, would have been constrained by weather, animal movements and the availability of sheltered places, fuel and workable stone. But the firmer story belongs to the non-human inhabitants. Reindeer could exploit open ground and seasonal forage; lemmings and Arctic fox point towards cold conditions; mammoth, giant deer, wolf, bear and hyaena show that Ireland's Pleistocene fauna was once far more varied than its later historic fauna. Their ranges probably expanded and contracted as climates shifted, rather than forming an unchanging resident community.

The coming ice-sheet growth was the decisive regional change. It reduced and rearranged habitats, broke ecological connections and erased much of the physical record that might have survived. Ireland around this date should therefore be understood not as an early chapter of later Gaelic, medieval or modern society, but as a fragile environmental interval: cold wetlands in Fermanagh, large mammals in the Awbeg Valley, and a possible yet unproven human action at the edge of the European Upper Palaeolithic world.

# Chapter 082 of 100

## 30919 BCE

### Derryvree's Tundra Drumlin<sup>[82]</sup>



Modern calendar-year precision is not available for Ireland in 30,919 BCE. The label is a convenient point on a modern chronological scale, roughly 32,868 years before AD 1950, rather than a recoverable Irish year in which archaeology can identify a particular season, event or generation. No written record, settlement sequence or securely dated human occupation allows historians to say what happened on the island at that exact moment. The responsible approach is to place it within the Late Pleistocene, broadly Marine Isotope Stage 3 (MIS 3), and to use the fragmentary evidence of caves, sediments, fossils and radiocarbon measurements to describe conditions across a much wider span.

## A Cold Interval, Not a Historical Year

Ireland at this depth in time was part of a climatically unstable north-west European world. MIS 3, conventionally dated to about 57,000–29,000 years ago, was marked by sharp shifts between severe cold phases and relatively milder interstadials. Ice masses, sea level, vegetation and animal ranges changed repeatedly over millennia. Conditions in one Irish region could differ greatly from another: uplands and northern districts were especially vulnerable to expanding ice, while southern lowlands and sheltered karst caves could preserve evidence of animals during intervals when suitable habitat existed.

The numbered date should therefore not be imagined as an entry in a prehistoric annal. It falls before the maximum expansion of the last British–Irish Ice Sheet, whose major shelf-edge advances occurred later, especially around 27,000–24,000 calibrated years before present. Yet it was part of the long approach to that glacial maximum. Research on the ice sheet indicates that ice growth was complex and

regionally uneven; it was not a single smooth advance that instantly buried Ireland. Around the horizon represented by 30,919 BCE, some landscapes could still contain open ground, water and animal life, while other areas were affected by cold-based ice, permafrost or advancing glaciers.

## **Derryvree Between the Tills**

The clearest Irish environmental window broadly relevant to this date lies at Derryvree, near Maguiresbridge in County Fermanagh. Roadworks in 1969 cut through a drumlin and exposed freshwater silts and fine sands trapped between two substantial layers of glacial till. The sequence is important because it records order rather than a story: glacier ice deposited the lower till; an ice-free interval then permitted freshwater and organic sediments to accumulate; later ice overrode the locality and sealed the deposit beneath another till sheet.

Organic material in the Derryvree freshwater series produced the radiocarbon determination Birm-166, 30,500 radiocarbon years before present, with a substantial uncertainty of +1,170 and –1,030 years. A radiocarbon age is not identical to a calendar age. Atmospheric carbon-14 levels varied in the past, and calibration at such antiquity carries broad ranges rather than year-level accuracy. Modern calibration work can place comparable results within wide calibrated intervals, but cannot make 30,919 BCE a precise date for the Derryvree wetland. The site is relevant because it demonstrates that part of Fermanagh supported a freshwater environment during the later middle of the last glacial period, not because it records a day or year in the life of a community.

The Derryvree flora and fauna indicated open tundra vegetation and a periglacial regime. This was no familiar Irish countryside of woodland, hedges and pasture. Short growing seasons, frozen ground and wet, shallow-water habitats favoured hardy plants. Pollen, plant remains and invertebrate evidence offer direct testimony to organisms present in or near the water. Their wider interpretation is of a largely treeless mosaic of wet ground, pools, sedges, mosses and sparse cold-adapted vegetation. Such places could be locally productive, especially in summer, but they were not evidence for farming, permanent villages or a settled political landscape.

## **Cork's Cave Fauna**

Far south of Derryvree, Castlepook Cave near Doneraile in north County Cork provides the richest Irish assemblage of vertebrate remains from before and around the onset of the Last Glacial Maximum. Also known as Mammoth Cave, it is a limestone maze cave whose excavations, particularly those directed by Richard J. Ussher and reported by the Royal Irish Academy in 1918, recovered a remarkable range of bones. Later study and redating have made the site central to any account of Ireland's MIS 3 fauna.

Its deposits contain evidence for woolly mammoth, reindeer, giant deer, brown bear and spotted hyaena, alongside wolf, Arctic fox, mountain hare and lemmings. This is not a list of animals that can safely be pictured standing together at Castlepook in 30,919 BCE. Cave accumulations formed over long periods and were altered by carnivore activity, water movement, sediment disturbance and early excavation. Individual bones have different ages. Revised radiocarbon work has also shown that some older dates obtained in the 1990s require reconsideration because improved pretreatment techniques can produce markedly older and more reliable results.

Nevertheless, the fauna establishes a vital point: during parts of MIS 3, Ireland had ecological connections with the wider cold-stage landscapes of north-western Europe. Reindeer imply open country capable of supporting grazing herds; mammoths point to expansive herb-rich habitat at least

intermittently; lemmings and Arctic fox indicate severe climatic conditions; and spotted hyaenas demonstrate the presence of formidable scavenging and predatory animals. Caves may have been dens, traps, shelters or places where bones were washed and reworked. They were not necessarily human homes.

For everyday life on the island, the animal evidence is stronger than the human evidence. We can responsibly envisage a difficult seasonal environment in which animals moved through open, cold terrain and competed for food and shelter. We cannot infer a named people, language, kin group, technology or territory from the fossil record. Nor can the faunal list establish a continuous population of any species across the whole island. It instead records changing opportunities for particular animals in particular regions.

## **The Human Question**

Castlepook has acquired special significance because a reindeer femur from the old collection has been reported as carrying a deep mark consistent with cutting or chopping by a sharp stone tool while the bone was fresh. If that interpretation is upheld, it would indicate human handling of a reindeer about 33,000 years ago and would push possible human activity in Ireland far earlier than the well-established post-glacial record. It is an important claim, but it must be kept in proportion.

The bone itself is evidence for a reindeer. Its direct age dates the animal, not an excavated camp. The proposed tool mark is an interpretation based on the form and placement of damage to bone. Castlepook's antiquarian excavations removed and mixed much sediment, and the femur was not recovered with a securely stratified hearth, stone-tool collection, dwelling surface or human remains. There is no confirmed Upper Palaeolithic settlement in Ireland of this age, no securely associated tool-making area and no basis for assuming permanent occupation.

The most cautious conclusion is therefore that a brief visit by people remains possible, perhaps involving the processing of an animal, but is not yet a demonstrated population history. A visitor could have arrived over a wider, lower-sea-level north-west European landscape by routes that are now submerged or obscured; equally, the surviving evidence cannot identify the route, duration or frequency of any visit. Lower sea levels did not automatically provide a simple land bridge, and neither boats nor crossings can be demonstrated for Ireland at this date.

## **No Politics, No Diplomacy**

Political affairs, diplomacy and organised warfare cannot be reconstructed for Ireland around 30,919 BCE. There are no monuments, burials, boundaries, weapons assemblages or settlement hierarchies from which authority or conflict can be inferred. It would be misleading to project later tribal societies, kingdoms, Gaelic identities or modern regional divisions into this period. If humans did enter Ireland, they left no evidence capable of revealing how they organised themselves socially.

The same restraint applies to religion, culture and learning. No art, ornament, musical instrument, grave or ritual deposit from Ireland can be securely assigned to this horizon. People elsewhere in Upper Palaeolithic Europe made sophisticated tools and symbolic objects, but that wider fact cannot fill Ireland's evidential silence. There is likewise no evidence for local trade. Animal movement and ecological connectivity across the region are real archaeological questions; commerce, exchange networks and maritime transport in Ireland at this date are not demonstrated.

## What Can Be Said


The most important development relevant to 30,919 BCE was environmental rather than political: Ireland was entering a more intensely glacial phase while retaining, at least intermittently and regionally, cold open habitats capable of supporting a distinctive Ice Age fauna. Derryvree preserves the environmental signature of an ice-free freshwater interval in Fermanagh. Castlepook preserves a long, complicated archive of animals in Cork, including species now absent from Ireland and, potentially, one trace of human butchery.

These sites also show why prehistoric precision matters. Derryvree's intertill sediments are direct evidence for past water, vegetation and climate; Castlepook's dated bones are direct evidence for individual animals. From them, scholars infer wider tundra-like environments, changing ice margins and intermittent faunal colonisation. Claims of resident human communities, hunting territories, trade, political conflict or belief belong to a further level of inference for which the Irish evidence around this date is presently insufficient. The silence is not emptiness: it is the proper boundary of what the archaeology can bear.

# Chapter 083 of 100

## 30918 BCE

### Derryvree's Mossy Fen<sup>[83]</sup>



The label 30,918 BCE is a modern point on a retrospective timeline, not a year that can be recovered from Ireland's Ice Age record. No calendar, ruler, settlement sequence or dated event permits year-by-year history at this depth of time. In the conventional archaeological system that counts back from AD 1950, it lies roughly 32,867 calendar years before present. The responsible approach is therefore to place it within a much broader archaeological and environmental interval: the Late Pleistocene, during Marine Isotope Stage 3 (MIS 3), when climates around the North Atlantic changed sharply and repeatedly.

The strongest Irish evidence relevant to this notional year comes not from an excavated camp but from sediments, fossils and cave bones. These sources can show that particular landscapes existed, that plants and animals occupied them, and that ice advanced or retreated. They cannot identify an Irish community in 30,918 BCE, still less its leaders, beliefs or political affairs. This is a history of a changing land and its living inhabitants, with only a tentative possibility of human contact.

## A Date Within a Range

The key local archive is at Derryvree, near Maguiresbridge in County Fermanagh. Road works in 1969 cut through a drumlin and exposed organic freshwater silts and fine sands enclosed between two substantial layers of till, the unsorted material deposited by glacier ice. The sequence is unusually informative. A lower till records an earlier glacial occupation; above it came an interval in which water, sediment, plants and small animals accumulated in an ice-free basin; an upper till shows that glacier ice later returned and sealed the deposits.



Organic material from this freshwater series produced the radiocarbon determination Birm-166: 30,500 radiocarbon years before present, with an uncertainty of  $\pm 1,170$ – $\pm 1,030$  years. A radiocarbon result is not itself a calendar date, since atmospheric carbon-14 levels have varied over time. Published calibration of this old determination has expressed the deposit broadly as about 36,900–31,700 calibrated years before present. The modern label 30,918 BCE falls within that wide span. It does not date a particular season at Derryvree, nor prove that every fossil in the deposit lived simultaneously. What it securely indicates is an ice-free, biologically active Fermanagh environment during part of this cold-stage interval.

This distinction matters because the evidence is exceptionally vulnerable to over-reading. The Derryvree bed tells a relative story of glacier ice, freshwater conditions and renewed glaciation. It does not provide an annual climate diary. Nor can one site in south Fermanagh stand for every district of the landmass that would become Ireland. Yet its preservation beneath a drumlin makes it one of the most valuable windows into an Irish landscape otherwise heavily reworked by later ice.

## Water, Mosses and Open Ground

Derryvree was not the wooded island familiar from later prehistory. Its pollen, plant macrofossils and small-fauna evidence point instead to open tundra vegetation and a periglacial regime: severe cold, frequent freezing and thawing, and ground likely affected by seasonal frost. The old descriptive term *muskeg* is useful if treated carefully. It evokes a wet, moss-rich mosaic of shallow water, saturated sediment, sedges, herbs and low-growing plants rather than an uninterrupted blanket of snow or a later peat bog.

Among the surviving botanical clues are bogbean, dwarf willow, mountain avens, lesser clubmoss and aquatic water-milfoil, together with mosses and pollen dominated by herbaceous plants. These remains demonstrate that a cold landscape could nonetheless contain freshwater pools and short but productive growing seasons. Plant communities occupied different niches: water plants in pools and channels, mosses and sedges in wet ground, and hardy tundra herbs or low shrubs on better-drained patches. A few pollen grains of trees are not evidence for nearby forest; they may have travelled far or been reworked from older sediments. The defensible picture is treeless or almost treeless open country.

Such terrain would have changed rapidly over small distances. Meltwater, frost cracking, shallow ponds, exposed mineral ground and snow patches could coexist, while the growing season imposed strict limits on plant growth. For animals, the most valuable places may have been wetland margins and the richer summer vegetation around them. For any people who entered the region, water, fuel, shelter and prey would have been unevenly distributed and strongly seasonal. That last point is an ecological inference, not evidence for a documented human occupation at Derryvree.

## An Island Approaching Reorganisation

At this time Ireland was within the long last glacial cycle but had not yet reached the later Last Glacial Maximum, when ice expanded much more extensively across the island and adjoining shelf. Research on the British–Irish Ice Sheet increasingly portrays the earlier cold stage as dynamic rather than simple: ice masses could grow, retreat and readvance, while different sectors responded differently to climate and topography. The Derryvree sequence gives this larger picture a tangible Irish form. It records an interval without local glacier cover, bracketed by episodes of ice deposition.

Coastlines were also unlike those of the present. Global sea level was lower than today, but the precise pattern of exposed shelf, sea, sea ice, glaciers and possible crossings cannot be reconstructed for one numbered year. Later ice erosion and marine inundation have removed many potential land surfaces. Consequently, the absence of settlements or stone artefacts is not proof that people never reached Ireland during MIS 3; it is also a consequence of a difficult archaeological record. Equally, missing evidence cannot be filled with confident stories of migration routes or permanent communities.

## **Castlepook's Animal Archive**

County Cork provides a different kind of evidence. Castlepook Cave, near Doneraile, has produced Ireland's most important pre-Last Glacial Maximum animal assemblage. Its deposits and older excavations yielded bones of reindeer, giant deer, woolly mammoth, brown bear, wolf, Arctic fox, lemmings and spotted hyaena. Revised accelerator radiocarbon dating has shown that several specimens are considerably older than earlier results suggested, placing part of the fauna firmly within MIS 3. The cave confirms that Ireland was repeatedly accessible to, and capable of supporting, a rich cold-stage fauna between roughly 45,000 and 20,000 radiocarbon years ago.

That does not mean all of these animals shared one landscape at one time. Cave deposits can accumulate through carnivore activity, natural deaths, water movement and disturbance over many millennia. Castlepook was in part a carnivore den, not a neatly sealed hunting camp. Its fauna is therefore best read as a long archive of changing ecological opportunities rather than a single photograph of Ice Age Cork. Reindeer and other grazers indicate open habitats; predators demonstrate a food web in which carcasses could be contested, scavenged and transported into caves. Mammoth or hyaena remains are evidence of animals in Ireland, not evidence that a mammoth hunt occurred there.

## **The Reindeer Femur Question**

One Castlepook reindeer femur gives this era special importance for Irish human history. The bone bears a deep linear mark interpreted by the palaeozoologist Ruth Carden as damage made by a sharp stone implement during butchery. County Cork heritage interpretation has presented it as a Palaeolithic object of about 31,000 BC. If that diagnosis is confirmed through further contextual and microscopic work, it would be striking evidence that a person processed a reindeer in Ireland far earlier than the well-established terminal Pleistocene traces of human activity.

For 30,918 BCE, however, caution is essential. The bone's radiocarbon age dates the death of the animal, not necessarily the instant when the mark was made. Its reported age must be calibrated rather than treated as an exact BCE equivalent. Nor does one modified bone establish where the carcass was killed, whether butchery occurred in the cave, how many people were involved, or whether they lived on the island. No securely associated hearth, lithic assemblage, dwelling floor, human remains or repeated occupation deposit of comparable age has yet been recovered. The strongest formulation is that Castlepook preserves a significant proposed trace of human action, not proof of a settled Irish population in this particular year.

## No Politics, but a Living Landscape


There is no evidence here for political institutions, diplomacy, warfare, trade networks, formal religion, art or learning in Ireland. There are no named groups and no recoverable social hierarchy. If mobile Upper Palaeolithic hunters did occasionally reach the island, comparison with better documented north-west European contexts suggests small, flexible groups exploiting seasonal resources. That is a plausible model, not an Irish fact established by a camp or burial.

The principal development around this broad horizon was environmental. Derryvree records fresh water and resilient tundra vegetation between glacial advances; Castlepook documents a wider world of herbivores and formidable carnivores in the south. Together they show that Ice Age Ireland was neither a timeless wilderness nor a uniformly ice-covered void. It was a fragmented, cold and changing landscape. Its fragile sediments and bones define both what can be said about 30,918 BCE and the firm limits beyond which responsible history must not go.

# Chapter 084 of 100

## 30917 BCE

### Castlepook's Marked Hindleg<sup>[84]</sup>



30,917 BCE is not a date at which Ireland can be described year by year. No written record, annual chronology or securely dated event survives from this part of the Late Pleistocene. The label is best treated as a modern point within a much broader archaeological and environmental timespan. It falls roughly 32,866 years before AD 1950, the conventional 'present' used in scientific dating, but that arithmetic is not the same as a precise archaeological date. Radiocarbon ages must be calibrated, and beyond about 14,000 years ago calibration is built from several kinds of natural archive rather than an annual tree-ring sequence. The responsible picture is therefore of Ireland during the later part of Marine Isotope Stage 3, a climatically unstable interval before the fullest expansion of the last British–Irish Ice Sheet.

The evidence closest in spirit to this date comes from a small number of cave-bone assemblages, buried wetland sediments and glacial landforms. They document environments and animal movements over centuries or millennia. They do not permit the assignment of a named occurrence to 30,917 BCE, nor do they reveal a continuous human population. Indeed, the apparently simple question of whether people were in Ireland at this time remains dependent on exceptionally slight and debated evidence.

## A Cold Country Before Maximum Ice

Ireland was not yet the familiar green island of later millennia. It lay within the Midlandian cold stage, the Irish expression of the last glacial cycle. Climate swung sharply between colder and relatively milder phases, while expanding ice masses, altered sea levels and changing vegetation repeatedly transformed routes across north-west Europe. The Last Glacial Maximum is generally placed later,

broadly after 26,500 calibrated years before present, although the British–Irish Ice Sheet did not reach its greatest extent everywhere at one moment. Large-scale reconstructions show advances and retreats between roughly 31,000 and 15,000 years ago, with different sectors behaving differently.

For the particular horizon represented by 30,917 BCE, it is safer to speak of a cold, open and changeable Irish landscape than of an island wholly entombed beneath ice. Geological sequences in County Fermanagh preserve organic sediments trapped between tills: deposits made when water and vegetation existed in places later overridden or enclosed by glacial activity. At Derryvree, near Maguiresbridge, fossil mosses, sedges, aquatic plants and insects point to cold freshwater wetlands and a treeless tundra or muskeg mosaic. These deposits have been associated with a later Middle Midlandian cold phase, with an old radiocarbon determination of about 30,500 BP; its uncertainty and the subsequent development of dating methods mean that it cannot be made to coincide with one numbered BCE year.

Nevertheless, Derryvree offers an essential corrective to any image of unbroken ice. Low hollows could hold pools, sedge beds and organic mud during ice-free or marginal intervals. Open ground supported plants able to cope with short growing seasons, frozen subsoil and strong winds. Dwarf shrubs, grasses, sedges, herbs and mosses supplied a thin but meaningful ecological base. In summer, meltwater and shallow wetlands would have broken up the stony terrain; in winter, snow, frost and exposed ground dominated. Such evidence describes habitat, not a settled landscape.

## The Castlepook Question

The most arresting object relevant to this distant period is a reindeer femur fragment from Castlepook Cave, also called Mammoth Cave, near Doneraile in north County Cork. Castlepook is Ireland's richest known cave locality for Pleistocene vertebrate remains. Its collections include evidence for animals associated with cold open country and cave use, among them reindeer, woolly mammoth, brown bear, fox, hare, lemmings and spotted hyaena. Crucially, however, cave assemblages are not snapshots. Carnivores, water, gravity, scavenging and nineteenth- and early twentieth-century excavation all affected how bones entered the cave, where they were found and what contextual information survived.

The femur has been publicised as approximately 33,000 years old and bears a deep linear modification interpreted by zoologist Ruth Carden as a cut or chopping mark made with a sharp stone implement while the bone was fresh. If that interpretation is upheld, it is Ireland's earliest currently proposed evidence of human activity: a brief Upper Palaeolithic encounter involving the processing of a reindeer carcass. County Cork heritage material has reasonably presented the find as broadly around 31,000 BCE. That broad public label explains its relevance here, but it must not be converted into a claim that the mark was made in 30,917 BCE specifically.

The limits are as important as the possibility. There is no securely associated hearth, stone-tool assemblage, dwelling surface, burial, artwork or human bone of this age from Ireland. A modified animal bone, even if genuinely cut by people, cannot establish a village, a permanent population, a named culture, a migration route or descent from later Irish communities. It does not tell us whether hunters killed the animal, found carrion, visited for hours, travelled seasonally or returned. Nor can it settle whether other bones in the cave represent the same episode. This is evidence for a possible human action, not proof of an Irish society in the ordinary historical sense.

## **Animals, Food and Movement**

The animal evidence does establish something substantial: Ireland could support a much richer Ice Age fauna than the modern island. Reindeer are especially suggestive of open grazing landscapes and may have moved over broad seasonal ranges. Mammoth remains point to the existence, at least in suitable phases, of extensive plant resources for very large herbivores. Giant deer, bears, foxes, hares, lemmings and hyaenas belong to a varied northern fauna whose composition changed with climate and access. Hyaena remains also warn against easy conclusions: a cave may have been a carnivore den or a place where bones accumulated naturally, rather than a human camp.

If people did reach Ireland, their economy would have been entirely mobile and opportunistic. The only defensible inference from the marked femur is possible meat and marrow processing. Reindeer could provide food, hide, sinew, bone and antler, but none of those wider uses is demonstrated at Castlepook. There is no basis for estimating population, defining territories or reconstructing a seasonal round. Equally, there is no evidence for farming, pottery, metalworking, built monuments, stored grain or domestic animals. The familiar categories of later prehistory simply do not apply.

Sea level was substantially lower during the glacial period than it is today, exposing areas now beneath the Irish Sea and Atlantic shelf. Ireland's connections to Britain and the European mainland changed as sea level and ice margins changed. This makes animal and possible human movement more plausible than it would be across the modern sea, but it does not mean that a simple, dry 'land bridge' stood open continuously. Routes could have involved coastal plains, river valleys, ice margins, changing channels and hazardous terrain. The geographical setting enabled episodes of dispersal; it does not demonstrate regular travel or exchange.

## **No Kingdoms, No Diplomacy**

There is no evidence from this period for political institutions, leaders, warfare, diplomacy, law or collective identities recognisable as nations or tribes. Nor is there evidence for religion in the archaeological sense: no burial rite, shrine, image, engraved symbol or ceremonial deposit can be assigned to Ireland around this point. Silence on these subjects is not an omission to be filled with imaginative narrative. It is a real property of the surviving record.

That silence also applies to language, learning and culture. Any visitors, if the Castlepook modification is anthropogenic, would have carried knowledge of cold-country travel, animal behaviour, carcass processing and stone technology. Yet no stone tool has been recovered in direct association with the bone, so even the technological tradition cannot responsibly be named. Their speech, kinship, beliefs, clothing and social organisation are unknown. Comparisons with Upper Palaeolithic groups elsewhere in Europe may suggest possibilities, but they are interpretation, not Irish evidence.

## **Landscape as the Main Archive**


The strongest history for this date is environmental. Sediments at Derryvree, faunal remains from Castlepook and reconstructions of the growing British-Irish Ice Sheet reveal a landscape repeatedly remade by cold. Wetland plants and insects record local conditions; mammal bones show that larger animals reached and lived in parts of Ireland; tills, erratics and glacially scoured rock demonstrate later ice expansion. Each archive has a different timescale and its own problems of preservation. Together they show neither a blank nor a settled homeland, but a sparsely evidenced northern landscape in transition.

By the time later ice expansion reached its maximum, many such habitats had been buried, eroded or drastically altered. That destruction helps explain why the record for 30,917 BCE is so thin. Ireland's deep past survives as scattered traces rather than a continuous story: a wetland sealed between glacial deposits, a cave bone curated from old excavation, a fossil insect or a landform dated long after its formation. The marked hindleg at Castlepook is important not because it answers every question, but because it makes the question of early human presence unavoidable. For this year, as for much of Ice Age Ireland, the most honest conclusion is both compelling and limited: there was a cold, ecologically active country here, and perhaps a fleeting human encounter within it.

# Chapter 085 of 100

## 30916 BCE

### The Castlepook Bone Debate<sup>[85]</sup>



**The label 30,916 BCE cannot be treated as a date in the modern historical sense. Nobody in Ireland recorded a year, a season, a ruler or an event at this depth in time, and no archaeological sequence can distinguish one calendar year from the next. The number is a modern chronological convention, approximately 32,865 years before the radiocarbon reference year of AD 1950. The responsible frame is a broad one: Ireland in the later part of the Last Glacial Period, within Marine Isotope Stage 3 (MIS 3), before the fullest expansion of the last British–Irish Ice Sheet. Radiocarbon dates must be calibrated rather than read as calendar years, and their uncertainty at this antiquity is substantial.**

The evidence nearest this point is not a settlement, grave, monument or tool-making floor. It is a scattered archive of cave bones, freshwater muds, fossil plants, insects, glacial deposits and landforms. Together these sources indicate a harsh, open and ecologically variable Ireland. They can illuminate animals, vegetation, water and changing ice margins; they cannot responsibly supply a named people, a political system, a religious practice or a particular annual occurrence.

## **A Date Within Wide Ranges**

The most useful northern record comes from Derryvree, near Maguiresbridge in County Fermanagh. Road works in 1969 exposed a drumlin cut through by a sequence of two separate tills—unsorted material left by glacier ice—with freshwater silts and fine sands between them. The stratigraphy establishes an important order of events: ice deposited the lower till; an interval of open water and vegetation followed; then a later ice advance laid down the upper till and sealed the deposit.



Organic material from the intervening freshwater beds, known as Birm-166, returned a conventional radiocarbon age of about 30,500 radiocarbon years before present, with an uncertainty of more than a thousand years. Published calibration places the deposit broadly at about 36,900–31,700 calibrated years before present, approximately 34,950–29,750 BCE. Thus 30,916 BCE lies inside a very wide possible span, but cannot be pinpointed within it. Derryvree documents a cold-stage landscape over a long interval, not conditions in one recoverable year.

This distinction matters. Ireland was not simply either “covered by ice” or “ice-free”. Glaciers advanced and retreated in different sectors at different times, while local basins could preserve water, vegetation and animal life between phases of ice activity. The later Last Glacial Maximum was still to come. Recent reconstruction of the British–Irish Ice Sheet stresses both rapid growth and major regional variation between about 31,000 and 15,000 years ago; a single island-wide ice edge cannot be assigned to this date.

## **Wet Ground in Fermanagh**

Derryvree offers Ireland’s clearest local environmental picture for the wider period. Its fossils include plants associated with treeless or very sparsely wooded cold environments: sedges, grasses, mosses, bogbean, dwarf willow, mountain avens and other herbs. Aquatic and wetland remains show that this was not an unbroken desert of snow and bare ground. There were pools, shallow water, marshy margins and sediment-rich freshwater habitats, supplied by meltwater or local drainage.

The wider setting was nevertheless severe. Low temperatures, short growing seasons, frost disturbance and exposed ground would have limited tree growth and made the landscape resemble tundra or mammoth-steppe mosaics elsewhere in north-west Europe. Such terms are interpretative shorthand, not photographs of a uniform countryside. A wet basin could stand beside stony, wind-scoured slopes, braided streams and patches of herb-rich grassland. The key evidence is local, and it should not be stretched into a detailed map of every Irish region.

Environmental change was probably a central fact of life for every animal that crossed this terrain. Watercourses shifted, shallow wetlands appeared and filled, vegetation responded quickly to temperature and moisture, and growing ice altered both drainage and access. These processes help explain why the Irish record is so fragmented: later ice frequently eroded, mixed or buried older deposits. The survival of Derryvree’s organic bed beneath a drumlin is exceptional rather than routine.

## **Castlepook’s Animal Archive**

In the south, Castlepook Cave, also called Mammoth Cave, near Doneraile in County Cork, is the most important Irish archive of mammals from the last cold stage. Excavated principally in the early twentieth century, it produced remains attributed to reindeer, giant deer, red deer, brown bear, wolf, Arctic fox, hare, lemming, woolly mammoth and spotted hyaena. The National Museum of Ireland describes it as Ireland’s most important site for mammal remains of the last cold stage, while modern re-dating has confirmed that some Castlepook fauna belongs to MIS 3.

The assemblage does not mean that all these animals lived together in precisely 30,916 BCE, or that each occupied every part of Ireland simultaneously. Cave collections accumulated over long periods and through several processes. Carnivores dragged in prey and scavenged carcasses; animals could die in or

near caves; water could move bones; early excavators did not record deposits to modern standards. Reindeer and hyaena are especially useful indicators of the cold, open and connected north-west European world in which Ireland participated, but individual bones require careful dating and taphonomic study.

Spotted hyaena is particularly revealing. It was not an Irish curiosity but a formidable social carnivore whose denning and scavenging activities could collect bones in a cave. Its presence, alongside large herbivores, indicates a food web with sufficient prey and usable terrain during at least some ice-age intervals. Mammoth and giant deer similarly demonstrate that Ireland could, at times, sustain very different large-animal communities from those of the present island. Yet a faunal list is evidence of changing ecological opportunity, not proof of a stable “Ice Age fauna” enduring unchanged for millennia.

## **The Reindeer Femur Question**

One Castlepook specimen has transformed discussion of Ireland’s deepest human past: a fragment of reindeer femur reported to carry a deep incision interpreted by zooarchaeologist Ruth Carden as a cut made by a sharp stone tool on fresh bone. County Cork’s heritage publication presents it as evidence that Palaeolithic hunters processed a reindeer around 31,000 BCE. If that interpretation is upheld, it would be a remarkable indication that a person, or a very small group, handled animal tissue in Ireland during MIS 3.

Its importance must be matched by caution. The bone derives from an old cave collection, not from a freshly excavated occupation layer containing a hearth, stone tools, butchered bones and shelter evidence in secure association. A cut mark can indicate carcass processing; it cannot tell us whether people killed the animal, scavenged it, stripped hide or sinew, removed meat or marrow, or whether the bone was subsequently carried to the cave by carnivores. Nor can one marked specimen establish a permanent population, a camp, a migration route or a named archaeological culture.

There is also a wider methodological warning. Improved radiocarbon pretreatment has shown that several earlier Irish cave-bone dates were too young, in some cases by thousands of years. The Castlepook debate is therefore a useful example of science revising its own evidence: new measurements can strengthen the case for early fauna while also making old chronologies less secure. The careful conclusion for this date is not that Ireland certainly possessed settled Palaeolithic communities, but that the possibility of episodic human presence deserves serious investigation.

## **People, Power and Belief: What Cannot Be Known**

There is no evidence from Ireland around this time for political authority, warfare, diplomacy, territorial lordship, formal institutions or identifiable ethnic groups. Such categories belong to much later archaeological and written worlds. If people entered Ireland, they would have done so in a landscape where survival depended on knowledge of animals, weather, fuel, water and safe movement, rather than on states or kingdoms. But this is a general inference from Upper Palaeolithic lifeways elsewhere in Europe, not direct evidence for an Irish society.

The same restraint applies to everyday life. No securely dated dwelling, hearth, clothing, ornament, stone-tool assemblage or burial is known from Ireland for 30,916 BCE. It is possible that mobile foragers elsewhere in north-west Europe pursued reindeer and other seasonal resources, using hides, bone, antler and stone; it is not legitimate to turn that possibility into an Irish household, hunting party or campsite. A single possible butchery mark is evidence of an action, if correctly identified, rather than a complete social world.

Nothing can be said directly about religion, ritual, language, learning, art or oral tradition in Ireland at this date. Cave bones and wetland sediments have not preserved symbols, images or structures that would support such claims. Nor is there evidence for trade in the later prehistoric sense. Animal and perhaps human movement shows that Ireland was not ecologically isolated at all times, especially when lower sea levels and changing ice affected surrounding seas and coasts. It does not demonstrate regular exchange networks.

## **An Island on the Edge of Change**

Ireland around 30,916 BCE was therefore a place of environmental transition rather than a country with a recoverable annual history. In Fermanagh, freshwater sediments preserve a rare glimpse of cold wetlands and tundra-like vegetation between glacial advances. In Cork, Castlepook preserves a time-averaged animal archive of reindeer, hyaenas and other large mammals, plus a disputed but consequential sign of possible human butchery. These traces show a landscape capable of supporting life, but vulnerable to rapid climatic and glacial change.

The most important historical development is not a named event. It is the narrowing of ecological possibilities as the last ice sheet built towards its later maximum. Ireland's land, waters and animal corridors were being repeatedly remade. Whether or not the Castlepook incision ultimately proves an early human visit, it directs attention to a profound truth: the island's human story may have roots far deeper than its once sparse archaeological record appeared to allow, but the evidence must remain proportionate to what bones and sediments can actually bear.

# Chapter 086 of 100

## 30915 BCE

### Bogbean Between Fermanagh Tills<sup>[86]</sup>



**Modern calendar-year precision is not available for Ireland in 30,915 BCE. No inhabitants left a written calendar, and no excavated settlement, ruler, battle or ceremony can be assigned to this numbered year. The label is a modern convenience: it lies roughly 32,864 years before AD 1950, the conventional reference point for radiocarbon dating. The responsible subject is therefore a broad environmental horizon in the later Pleistocene, within Marine Isotope Stage 3 (MIS 3), rather than an annual chronicle.**

The evidence nearest to this point is revealing but uneven. It consists principally of freshwater sediments sealed beneath a drumlin at Derryvree near Maguiresbridge in County Fermanagh, and of animal bones accumulated over long periods in Castlepook Cave, near Doneraile in County Cork. These records establish that parts of Ireland supported cold-stage plants and animals before the Last Glacial Maximum. They do not establish an island-wide landscape at a single moment, still less a named human community.

## A Date Within a Range

Derryvree offers the clearest local guide. Roadworks in 1969 cut through a drumlin and exposed two thick, distinct beds of till: unsorted sediment laid down directly by glacier ice. Between them lay fine sands, freshwater silts and organic material. The sequence is unusually valuable because its order is secure. Ice had first crossed this part of Fermanagh and laid down the lower till. Afterwards, at least locally, open water and wet ground existed long enough for sediment, plants and insects to accumulate. A later ice advance buried the deposit beneath a second till sheet.

Organic material from this freshwater series gave the radiocarbon determination BIRM-166, 30,500 radiocarbon years BP, with a substantial uncertainty of  $+1,170/-1,030$  years. A radiocarbon age is not a calendar age. Atmospheric carbon-14 has varied through time, and the result must be calibrated against independently dated records; at this depth in time the calibration curve gives a broad rather than pinpointed answer. Published discussion places the Derryvree horizon broadly within about 36,900–31,700 calibrated years BP. The modern year 30,915 BCE falls within that wide window, but it cannot be equated with the formation of a particular pool, the growth of one plant or an event in a human life.

This caution matters because Ireland's Late Pleistocene record is patchy. Later glaciers scraped, redeposited or covered large tracts of the island. A deposit found beneath till is an exceptional survival, not a complete national archive. Other Fermanagh sites, including Hollymount near Maguiresbridge and Greenagho near Belcoo, also preserve evidence for cold, non-glacial intervals. Together they show that the island's ice history involved advances, retreats and ice-free pockets rather than one unbroken frozen state.

## Fresh Water in Open Country

At Derryvree, plant remains, pollen and insects provide direct evidence for a treeless, periglacial wetland landscape. Freshwater mosses, sedges, grasses and low herbs were present. Fossils of bogbean (*Menyanthes trifoliata*) and mountain avens (*Dryas octopetala*) are especially evocative: both are plants associated with cold or Arctic-alpine conditions today. Juniper and dwarf woody vegetation may have occurred in sheltered places, but the evidence does not support a woodland scene. This was open country with short growing seasons, severe winters and low vegetation exposed to wind.

The phrase “tundra” is useful only if handled carefully. It describes the broad ecological character suggested by the fossils—open, cold-adapted ground—not a uniform blanket of vegetation across all Ireland. The Derryvree deposit records a freshwater hollow with mossy margins, decaying plant matter and shallow pools. Conditions at a dry ridge, limestone cave entrance or distant coast could have been different. The insect assemblage indicates habitats around wet, plant-rich ground, showing that even a rigorous climate supported a functioning local food web.

Everyday life at this date can therefore be described confidently for plants and animals, but not for people. There were no fields, livestock, houses, roads, pottery, monuments or metalworking. Nothing supports farming, trade networks, political authority, diplomacy, formal religion or a learned tradition in Ireland at this point. Such absences should not be filled with invented Ice Age clans. They reflect both the likely conditions of a cold Pleistocene landscape and the severe limits imposed by the surviving evidence.

## Castlepook's Animal World

Far to the south-west, Castlepook Cave—also called Mammoth Cave—preserves Ireland's richest known assemblage of mammals from before and during the last cold stage. Excavations undertaken in the early twentieth century recovered more than 2,000 bones. Subsequent research and redating have identified a varied fauna that includes woolly mammoth, reindeer, giant deer, brown bear, wolf, fox, Arctic fox, mountain hare, lemmings and spotted hyena. The cave is consequently vital evidence that animals repeatedly reached and lived in, or at least moved through, Ireland during parts of the Late Pleistocene.

Its limitations are as important as its riches. Castlepook was not excavated to modern standards, and the remains came from cave sediments affected by water movement, carnivore activity and old digging. Bones from different episodes can be mixed together. A cave bone proves that an animal was present in the wider landscape or was carried into the cave; it does not automatically prove where it grazed, died or was hunted. Nor should the entire animal list be compressed into one imagined season around 30,915 BCE.

Nevertheless, the fauna indicates a landscape far removed from modern Ireland. Reindeer and lemmings point to cold open environments; mammoth and giant deer indicate that substantial herbivores could find enough forage during favourable phases; wolves and spotted hyenas occupied the upper levels of the food chain. Hyenas may have used caves as dens or scavenging sites, helping to explain why carcass remains accumulated there. The National Museum of Ireland's Castlepook collections are therefore evidence both of animal dispersal and of natural bone-accumulation processes.

## **The Reindeer Femur Question**

A reindeer femur from Castlepook has made this period especially important for Irish archaeology. Palaeozoologist Ruth Carden identified a deep linear modification on the bone as consistent with cutting or chopping by a sharp stone tool during butchery. The bone has been presented as dating to roughly 33,000 years ago, close in broad terms to the date considered here. If that interpretation is sustained, it would be evidence that a person or people processed reindeer in Ireland during the Upper Palaeolithic, much earlier than the long-accepted record of post-glacial occupation.

That is a significant possibility, not proof of a settled population. The find is one modified bone from an old cave collection, not a sealed camp floor. No securely associated stone tools, hearth, dwelling, burial, human remains or dense scatter of butchered remains of comparable age has been recovered. The radiocarbon result dates the animal bone; interpreting a mark as humanly made is a separate taphonomic judgement. Neither point can tell us whether people killed the reindeer, encountered an already dead animal, remained for a day or returned repeatedly.

Accordingly, there is no secure basis for describing a political community, kin group, territory, language, ritual practice or trade route in Ireland in 30,915 BCE. If humans did visit, they would have moved through a demanding north-west European world shaped by lowered sea levels, changing coastlines and climatic fluctuations. Their presence would have been fleeting in the evidence now available. The archaeological silence is meaningful, but it is not absolute proof that nobody ever came.

## **Ice, Access and Change**

The larger trend was towards major environmental reorganisation. The British–Irish Ice Sheet did not simply appear at one date: recent reconstruction shows sustained growth between about 31,000 and 26,000 years ago, followed by its maximum volume around 23,000 years ago. This chronology concerns a changing ice-sheet system across Britain, Ireland and adjacent shelves, not a guarantee that every Irish district was simultaneously ice-covered. Yet it explains why habitat, drainage, coast and possible movement routes became progressively less stable.

For the Derryvree wetland, renewed glaciation eventually brought burial beneath till. For animals, advancing ice and colder conditions would have fragmented forage and altered corridors of movement. For any human visitors, the practical challenges would have been formidable: finding game, fuel, shelter


and safe passage through a landscape where conditions could change across short distances and longer climatic oscillations. None of this demonstrates conflict or diplomacy. It shows instead why continuity of settlement would have been difficult to establish and harder still to preserve archaeologically.

The most accurate picture of Ireland around 30,915 BCE is therefore neither an empty white ice sheet nor a populated prehistoric homeland. It is a fragmentary, dynamic late-Ice-Age landscape. At Derryvree, cold-adapted plants and insects occupied freshwater ground during an ice-free interval. At Castlepook, a diverse fauna—including formidable predators and large herbivores—left a time-averaged record in limestone passages. A single reindeer bone raises the possibility of human butchery. Beyond those hard-won traces, the history remains deliberately—and instructively—unknown.

# Chapter 087 of 100

## 30914 BCE

### Maguirebridge's Three-Leaved Pool<sup>[87]</sup>



**30,914 BCE is a useful modern label, not a date at which Ireland's past can be read year by year. No written record, calendar, settlement sequence or archaeological layer can isolate a particular Irish day, season or generation so far back. In archaeological terms the point lies roughly 32,864 years before the conventional reference year of AD 1950, within the Late Pleistocene and Marine Isotope Stage 3, a long, climatically unstable part of the last Ice Age. The responsible account is therefore built from broad calibrated ranges, glacial sediments, fossil plants and cave fauna. It can illuminate conditions in and around Ireland; it cannot furnish an event for this numbered year.**

## **A Date Inside a Range**

The closest Irish environmental anchor is at Derryvree, near Maguiresbridge in County Fermanagh. Road works in 1969 cut through a drumlin, exposing freshwater silts, fine sands and organic deposits sealed between two thick tills: unsorted sediment left by moving glacier ice. The sequence gives an unusually clear order of events. Ice first deposited the lower till; a period followed in which an ice-free freshwater environment accumulated mud and organic remains; later glacier ice overrode or buried the deposit beneath the upper till. That relative sequence is secure, even though the duration of each phase cannot be reduced to an annual timetable.

Organic material from the Derryvree freshwater bed, laboratory determination BIRM-166, produced a radiocarbon age of about 30,500 years before present, with a large uncertainty of +1,170 and -1,030 years. Radiocarbon years are not calendar years: atmospheric carbon-14 has varied through time, so measurements must be calibrated against independently dated records. Published calibration places the



Derryvree material broadly at about 36,900–31,700 calibrated years before present, approximately 34,950–29,750 BCE. Thus 30,914 BCE falls within the possible age range of this Irish archive, but it cannot be tied to a particular sediment layer, flower, animal or episode at the pool.

This distinction matters. A deposit formed over time is not a contemporary snapshot of the entire island. Derryvree demonstrates that, during a broad Middle Midlandian interval, its locality was ice-free long enough for freshwater sediments and organic material to gather between glacial advances. It does not prove that every region of Ireland was simultaneously free of ice, nor that the climate was constant. At this depth in time, even excellent chronological evidence has margins measured in centuries or millennia.

## Wetlands Between Glaciers

The Derryvree deposits nonetheless offer a vivid, carefully limited view of an Irish landscape compatible with this broad horizon. Plant macrofossils, mosses and pollen point towards a cold, open environment with freshwater and wet ground rather than a closed forest. Sedges, dwarf willow, clubmoss and bogbean or water clover (*Menyanthes trifoliata*) are among the remains used to reconstruct such conditions. The three-leaved bogbean, which gives this article its title, is evidence that plants associated with wet, shallow-water habitats grew there during the deposit's formation. It is not evidence that one can identify a particular bogbean plant in 30,914 BCE.

The best interpretation is of a varied periglacial wetland: shallow pools, muddy margins, sedge-rich ground and sparse low vegetation, within a wider treeless or very lightly wooded landscape. Periglacial does not mean an empty white wilderness. Cold-climate plants, invertebrates and small mammals could exploit sheltered, waterlogged niches, while frost action, seasonal meltwater and short growing seasons shaped the ground. The landscape would have changed quickly in ecological terms as temperature, snowfall, ice margins and drainage shifted. A marsh beside a pool may have been productive in summer yet exposed and severe in winter.

Irish evidence must also be placed in a North Atlantic setting. Greenland ice-core records show that the last glacial period was punctuated by abrupt shifts between relatively milder interstadials and colder stadials. The date in question falls close to a time of considerable climatic volatility rather than within a stable 'Ice Age climate'. Northern Atlantic conditions influenced Irish temperatures, precipitation, sea ice and glacier behaviour, but they did not make Derryvree a weather station for the whole island. Local relief, water and proximity to ice would have mattered greatly.

## Cave Fauna and Open Country

For animal life, the principal Irish evidence comes from cave collections, especially Castlepook Cave, also called Mammoth Cave, near Doneraile in north County Cork. Excavations conducted in the early twentieth century recovered a remarkable assemblage including remains attributed to reindeer, giant deer, brown bear, wolf, fox, hare, lemming, woolly mammoth and spotted hyaena. Castlepook is important because it establishes that a much richer cold-stage fauna reached Ireland during parts of Marine Isotope Stage 3 than survives on the island today.

It would be misleading, however, to arrange all those species together in a single scene set in 30,914 BCE. Cave deposits may mix material accumulated over long periods; carnivores can carry bones into dens; older excavations did not always preserve the stratigraphic information expected today; and recent radiocarbon reassessment has shown that some earlier dates were substantially too young. The assemblage

supports the existence of changing open-country food webs, but not a census for this year. Reindeer in particular fit the general image of cold, open habitats, while hyaena remains demonstrate that Ireland's Pleistocene fauna was neither uniform nor exclusively Arctic.

Sea level was lower than today, and the geography of the Irish Sea region differed substantially from the modern map. Mammals evidently reached Ireland at various points in the Late Pleistocene, perhaps through changing combinations of exposed coastal plains, shallow-water crossings, ice and land connections. Yet the route taken by any particular herd, predator or possible human visitor remains uncertain. The fossil record demonstrates arrival and survival at broad scales; it does not demonstrate a permanent corridor, a single migration route or an unbroken mainland connection at this precise moment.

## **The Castlepook Question**

Castlepook also raises the most intriguing, but still provisional, question about people in Ireland at this time. A reindeer femur in the National Museum of Ireland collection has been identified as bearing a deep mark interpreted by zooarchaeologist Ruth Carden as the work of a sharp stone tool during carcass processing. County Cork heritage material associates the bone with an age of about 31,000 BCE. If the mark is confirmed as humanly made, it would be potentially momentous evidence that Upper Palaeolithic hunters handled a reindeer in Ireland far earlier than the better-established evidence for post-glacial human activity.

The limits of the claim are as important as its promise. The bone's date concerns the animal, not a precisely timed act of butchery. A modified bone is not by itself a camp, a settled population or proof that hunters lived in the cave. No securely associated hearth, stone-tool assemblage, dwelling floor, burial, food store or repeated butchery area has yet been recovered at Castlepook for this age. The cave may have been used principally by carnivores, which could have transported scavenged carcass remains underground. Ongoing investigation is needed to test the mark, the bone's context and whether further in-situ evidence survives.

## **What Cannot Be Written**

Consequently, political affairs, diplomacy and warfare cannot responsibly be described for Ireland in 30,914 BCE. There are no known polities, named peoples, leaders, languages or territorial institutions. Nor is there evidence for religious observance, art, formal learning, exchange networks or a settled economy. If people were present, they may have belonged to highly mobile foraging groups familiar with the wider north-west European world; that is a reasonable comparative possibility, not a demonstrated Irish social history. Later Gaelic identities, Celtic languages and medieval traditions have no place in this reconstruction.

Everyday life is likewise recoverable only by inference. The ecology could have supported animals valuable for meat, hide, bone, antler and fuel, while wetlands supplied water and concentrated plant and animal resources. But no Irish site of this date securely records how people sheltered, cooked, organised kinship or moved through the landscape. The evidence speaks more confidently of sedimentation, vegetation, fauna and ice than of human institutions. Its silences are historical facts, not gaps to be filled with picturesque invention.

## Iceward Change


The larger trajectory was towards more extensive glaciation. The Last Glacial Maximum in Ireland came later, with major Irish Ice Sheet advances generally placed around 27,000–23,000 calibrated years ago. At roughly 32,864 years before present, Ireland was not yet at that maximum, but its environments were already subject to the cold oscillations and shifting ice limits that preceded it. Derryvree's organic bed, entombed between tills, embodies that unstable history: an interval of freshwater life was ultimately sealed by renewed glacial action.

For this reason, the most important Irish development around 30,914 BCE was environmental rather than political. Ireland contained, or had recently contained, local ice-free refuges and cold wetlands amid a changing glacial landscape. Open-country mammals moved through the wider region; cave deposits retained fragments of their histories; and a single marked reindeer bone poses an unresolved question about human presence. The record is fragmentary, but it is not empty. Beneath a Fermanagh drumlin and in a Cork cave lie the traces from which Ireland's deepest known past can cautiously be reconstructed.

# Chapter 088 of 100

## 30913 BCE

### Derryvree's Sealed Tundra<sup>[88]</sup>



The label 30,913 BCE cannot identify a known Irish event, ruler, journey or settlement. No calendar, written record or archaeological sequence can be resolved to a single year so far back. In archaeological terms this notional date lies about 32,862 calendar years before AD 1950, in the Late Pleistocene and broadly within Marine Isotope Stage 3 (MIS 3), an interval of abrupt climatic fluctuation during the last Ice Age. The responsible account is therefore one of dated ranges, sediments, animal remains and limits on what can be inferred.

The closest Irish evidence is not a settlement but an exceptional buried landscape at Derryvree, near Maguiresbridge in County Fermanagh. Its dated organic deposits overlap the requested point in time, but they are not an annual snapshot. Elsewhere, cave deposits in southern Ireland demonstrate that large mammals entered the island during the same broad climatic era. A controversial marked reindeer bone raises the possibility of an early human encounter. Taken together, these records illuminate a cold and changing country, while also showing how little can safely be said about people within it.

## A Date Within a Range

At Derryvree, roadworks in 1969 cut through a drumlin and exposed a striking sequence: one thick glacial till beneath freshwater silts and fine sands, followed by another till above. Till is the unsorted mixture of clay, stones and other debris laid down directly by glacier ice. The order of the layers is firm evidence for a local sequence of change. Ice occupied the site; an interval without overriding ice allowed standing or slow-moving freshwater, sediment and organisms to develop; then later ice advanced across the locality and sealed that evidence beneath fresh glacial debris.

Organic material from the intervening freshwater deposits produced the conventional radiocarbon determination Birm-166, 30,500 radiocarbon years BP, with a substantial published uncertainty of +1,170/–1,030 years. Radiocarbon years are not calendar years. Calibration against the modern IntCal20 curve gives a broad calendar range rather than a single answer: approximately 36,900–31,700 calibrated years BP, or roughly 34,950–29,750 BCE. The year 30,913 BCE falls within that wide span. Yet the range dates the organic deposit in general, not an individual day, season or phase of wetland life. It cannot prove that the Derryvree pool looked exactly the same in the nominal year used here.

This distinction matters. The Derryvree evidence establishes that this part of Fermanagh was ice-free long enough, at some point in the range, for freshwater sediment and a functioning cold-climate ecosystem to form. It does not establish that all Ireland was ice-free simultaneously, nor that every cave fauna or other environmental record belongs to one shared moment. Ireland's Ice Age geography was regionally varied and repeatedly transformed by glacier growth, frozen ground, water and changing sea level.

## **Wet Ground Between Glaciers**

The fossils within the Derryvree silts give the clearest picture of local everyday conditions available for this date. Plant pollen, seeds, mosses and insect remains indicate open, largely treeless ground under a periglacial climate. The word “periglacial” describes landscapes strongly affected by severe cold and freeze-thaw processes around ice margins; it does not mean that the site itself lay beneath a glacier. Sedges, grasses, herbs, mosses and aquatic or wet-margin plants point to shallow pools, wet hollows and saturated ground. The resulting landscape has often been described as tundra or muskeg-like wetland.

That language should not conjure an unbroken white desert. The Derryvree sediments imply liquid freshwater, plant growth and insects during at least part of the year. A short growing season could support mossy banks, sedge-rich margins and patches of herbaceous vegetation, while frost, seasonally frozen ground and cold winds constrained tree growth. Different microhabitats may have existed only a short distance apart: waterlogged hollows, exposed mineral soil, low vegetation on drier rises and perhaps snow lingering in sheltered places. The evidence supports a low, open mosaic, not a detailed map of every plant community.

It also warns against importing the later Irish landscape into the deep past. There were no hedged fields, peat-cuttings, oak woods, farms or familiar river valleys in their historic form. Drumlins now prominent in Fermanagh were shaped through glacial processes, and later ice profoundly altered the ground surface. The Derryvree freshwater bed survived precisely because it was buried. Much comparable evidence will have been eroded, overridden or carried away by succeeding ice advances.

## **Animals on a Changing Island**

Cave archives, especially Castlepook Cave near Doneraile in north County Cork, show that Ireland supported or was visited by a much richer Late Pleistocene fauna than survives today. The Irish Quaternary Fauna Project documented mammoth, reindeer, giant deer, brown bear, wolf, Arctic fox, mountain hare, lemmings and spotted hyaena among the remains from Castlepook and related collections. Such animals did not necessarily occupy the cave, or even southern Ireland, together. Cave assemblages accumulated over long periods through carnivore activity, natural deaths, water movement, collapse and nineteenth- and early twentieth-century excavation. They must not be turned into a single cinematic herd scene.

Nevertheless, the assemblage is decisive evidence that Ireland was not biologically empty during parts of the last glaciation. Reindeer and lemmings are especially compatible with open, cold environments; mammoth, giant deer, wolf and hyaena indicate broader food webs containing large herbivores and predators. Their presence also implies repeated routes into Ireland from wider north-western European populations. Lower sea levels changed the shape of the Irish Sea basin, but the animal record alone cannot tell us whether a continuous land connection existed at any particular moment, which route each species followed, or whether all movements occurred in the same climatic phase.

Crag Cave, County Kerry, provides another kind of climate evidence. Uranium-thorium dating of cave calcite shows episodic speleothem growth through the last glacial period, including the early part of MIS 2 immediately after the time considered here. In a shallow cave system, calcite growth requires liquid water and is taken to indicate episodes when average annual conditions were not persistently below freezing. This does not mean that south-west Ireland was mild by modern standards. Rather, it reinforces the central fact of the age: cold conditions were punctuated by rapid shifts, and ice-sheet margins could be more dynamic than a simple story of steadily advancing winter allows.

## The Human Question

No house, hearth, burial, durable stone-tool assemblage, camp floor or human skeleton has been securely dated in Ireland to around 30,913 BCE. Consequently there is no responsible basis for describing an Irish community's population, language, kinship, political authority, religious practice, art, trade or routine diet at this time. There were no demonstrable Irish polities, diplomatic relationships or wars. "Economy" can be used only in the ecological sense of food webs and seasonal resources, not as evidence for a human system of production or exchange.

The caution is particularly important because Castlepook has yielded a reindeer femur with an incision interpreted by some researchers and public reports as a possible fresh-bone cut mark made with a stone tool. Its reported age of roughly 33,000 years has prompted the suggestion that people may have handled a reindeer in Ireland during the broader period under discussion. If that interpretation is sustained, it would be an important indication of a brief Upper Palaeolithic human presence. But one marked bone is not a settlement. It cannot reveal whether people hunted the animal, scavenged it, removed meat, hide or sinew, or came from a group that stayed only briefly before moving on.

The evidential gap is substantial. No associated artefacts have been recovered with the specimen; no unquestioned hearth or butchery area accompanies it; and the cave's deposits are complex and time-mixed. The National Museum of Ireland has accordingly long emphasised the absence of clear Palaeolithic evidence for human occupation on the island. The later, securely dated Upper Palaeolithic cut-marked brown-bear patella from Alice and Gwendoline Cave in County Clare belongs around 12,800–12,600 calibrated years BP, far later than this article's horizon. It demonstrates that humans did reach Late Pleistocene Ireland, but cannot be projected backwards to establish continuous occupation thirty millennia ago.

## What Ireland Can and Cannot Tell Us

For 30,913 BCE, the most important Irish development is environmental rather than political: a landscape repeatedly opened, flooded, vegetated, frozen, buried and reshaped as climate fluctuated and ice expanded. Derryvree preserves a rare interval when cold wetland life existed between glacier advances. Castlepook preserves fragments of the animal communities that moved through the island in the wider


Middle Midlandian cold stage. Crag Cave records climatic oscillation in mineral form. These are separate archives with different dating methods, resolutions and weaknesses; their agreement lies in the broad picture of an unstable Ice Age Ireland.

Human history at this point remains a possibility rather than a narrative. The prudent conclusion is not that Ireland was certainly inhabited, nor that it was certainly empty, but that its archaeological record is too sparse to decide how often people reached it or what they did when they arrived. The island's later prehistoric institutions, identities and cultures were still unimaginably far in the future. What can be recovered for this deep time is more elemental: freshwater among frozen ground, low vegetation under a severe climate, large mammals crossing a changing north-west European world, and an Irish record repeatedly hidden beneath the work of ice.

## Chapter 089 of 100

30912 BCE

BIRM-166's Thawline<sup>[89]</sup>



**“30,912 BCE” is a modern label, not a year that can be recovered from the Irish evidence with calendar-like precision. No written record, settlement sequence or dated event identifies a particular season, person or action on the island at that point. In radiocarbon terms it lies roughly 32,900 calendar years before AD 1950, in the Late Pleistocene and broadly within Marine Isotope Stage 3 (MIS 3), a climatically unstable part of the last Ice Age. The responsible subject is therefore an interval, not an annual chronicle.**

The best evidence close to this horizon comes from environmental deposits, animal remains and the geological traces of ice, not from monuments or villages. They show a changing Ireland in which cold, exposed, locally ice-free landscapes existed before the fullest expansion of the last British–Irish Ice Sheet. They do not support a narrative of kingdoms, warfare, organised religion, trade networks or permanent communities. Around this notional date, the history of Ireland is principally the history of land, water, climate and animal life.

### A Date Inside a Range

The key archive is at Derryvree, near Maguiresbridge in County Fermanagh. Roadworks exposed a sequence within a drumlin: glacial till below, freshwater silts, sands and organic deposits in the middle, and a later till above. Till is the unsorted debris laid down directly by glacier ice. The order of these layers is powerful evidence. An earlier glacier had crossed the site; a subsequent ice-free interval allowed standing or slow-moving freshwater, sediments and organic material to accumulate; later ice advanced again and sealed the record.



Organic material from the Derryvree freshwater bed, laboratory code BIRM-166, produced a conventional radiocarbon determination of about 30,500 years before present, with a substantial uncertainty. Radiocarbon years are not identical to calendar years, because atmospheric carbon-14 levels have varied over time. When calibrated, the deposit has been placed broadly at about 36,900–31,700 calibrated years before present, approximately 34,950–29,750 BCE. The requested date falls within that wide span. It cannot be attached to a particular pool, plant, animal movement or human visit within it.

This limitation is not a weakness to be concealed; it is the central fact of deep-time history. A calibrated range expresses what the evidence can bear. Derryvree is an unusually valuable window onto an Irish environment between glacial episodes, but it is not a diary. Nor can one Fermanagh wetland stand for every region of the landmass now called Ireland.

## Waterlogged Open Country

The plants and small creatures preserved at Derryvree indicate cold, largely treeless ground rather than the familiar green, wooded Ireland of later millennia. Pollen, mosses, plant macrofossils and insect remains point to a periglacial wetland mosaic: shallow freshwater, sedge-rich margins, damp peaty ground and open terrain exposed to severe seasonal conditions. Finds associated with such deposits include hardy northern and alpine-tundra plants, such as dwarf willow, mountain avens, clubmosses and bogbean, alongside aquatic vegetation. Their combination suggests that water was locally abundant even in a cold climate.

“Tundra” is a useful shorthand, provided it is not imagined as a featureless plain. Derryvree’s record instead implies variation at a small scale: pools, wet hollows, mineral ground, mossy patches and sedge beds. Summer growth could be brief but productive in sheltered, wet places; winters would have been long and hard. Frost action, frozen ground and sparse vegetation would have made much of the surface unstable or difficult to travel across. This was an environment capable of sustaining specialised plant and animal communities, not an empty wasteland.

The broader setting was unstable. MIS 3 contained abrupt cold and relatively milder phases, while the ice sheet itself changed shape and extent over time. Recent reconstructions emphasise that the British–Irish Ice Sheet did not behave as one fixed white cover. Ice accumulated, advanced and retreated asynchronously in different sectors. Around this horizon, evidence is insufficient to map its margin in Ireland to a particular year, but Derryvree demonstrates that north-central Ireland was locally free of overriding ice for part of the wider interval. The much more extensive Last Glacial Maximum lay ahead, with its principal Irish phase broadly between 26,500 and 19,000 calibrated years before present.

## Caves and Cold-Stage Fauna

Southern cave deposits provide a second, more fragmentary record. Castlepook Cave near Doneraile in County Cork has yielded remains attributed to a Late Pleistocene fauna that includes reindeer, woolly mammoth, giant deer, brown bear, wolf, Arctic fox, mountain hare, lemmings and spotted hyaena. Taken together, these finds show that Ireland supported animals adapted to cold, open habitats during parts of MIS 3. Grazers and browsers were accompanied by predators and scavengers; caves may have served as dens, traps, sheltered resting places or places where bones accumulated through several processes.

That qualification matters. The bones do not demonstrate that every listed species stood together in one Cork valley, still less that they lived in the same year as the Derryvree wetland. Cave deposits are often mixed and were collected in part through early excavations that did not meet modern standards of

stratigraphic recording. Improved radiocarbon pretreatment has shown that some Castlepook specimens are thousands of years older than earlier dates suggested. Re-dating has nonetheless confirmed that important elements of the fauna belong to MIS 3, while also warning against compressing a long ecological history into a single scene.

Reindeer are especially evocative, because their presence is compatible with wide-ranging seasonal movement through open country. Mammoth, giant deer and hyaena point to a richer Late Pleistocene animal world than survives in Ireland today. Yet the fossil record is sparse, unevenly preserved and biased towards caves and bones robust enough to survive. Absence from the record does not prove absence from the landscape; presence at a site proves only that the animal, or part of it, reached that site within its dated range.

## **The Human Question**

A reindeer femur from Castlepook has attracted particular attention because one mark on it has been interpreted as damage made by a stone tool during carcass processing. If that interpretation is confirmed, it may indicate a human visit to Ireland around 33,000 years ago, far earlier than the well-established post-glacial settlement record. It is an important possibility, but it must remain proportionate to the evidence.

The marked bone is not a securely excavated camp. It is not accompanied by a hearth, a stone-tool assemblage, a dwelling floor, a burial or repeated occupation deposits of comparable age. Its radiocarbon date concerns the animal; the mark's diagnosis concerns bone modification; neither alone proves a resident population. The most defensible interpretation is that occasional Upper Palaeolithic contact or hunting activity is possible. Permanent settlement, population size, language, kinship and routes of arrival remain unknown.

This distinction also clarifies what cannot be written for Ireland at this date. There is no evidence for political authority, diplomacy, territorial boundaries, warfare or formal institutions. There is no evidence for farming, livestock, crop cultivation, pottery, metalworking, long-distance commerce or managed exchange. Nor are there monuments, graves or images from which religious practice can be responsibly reconstructed. If people did reach the island, their lives may have involved mobile foraging and the careful use of seasonal resources, but that is an inference from wider Upper Palaeolithic patterns, not a demonstrated Irish social history.

## **An Island Still in Formation**

Modern Ireland's coastlines should not be projected backwards unchanged. During glacial periods, much water was stored in continental ice sheets and sea level was lower than today, exposing parts of the surrounding continental shelves. At the same time, advancing ice, meltwater, shifting shorelines and difficult marine channels made access variable. Any route between Ireland, Britain and mainland Europe around 30,912 BCE is therefore uncertain and cannot be assumed to have been an easy land bridge.


The regional story is one of repeated transformation. Freshwater sediments at Derryvree were eventually buried by renewed glacier activity; later ice reshaped terrain on a far larger scale, producing many of the drumlins, tills and scoured surfaces visible in Ireland today. Those later processes also destroyed, reworked or concealed much earlier evidence. The scarcity of archaeological traces is thus partly a record of human uncertainty, but also a consequence of preservation.

For this deep prehistoric horizon, the most meaningful Irish development was not a human event but a fragile interval of life between ice advances. At Derryvree, wet ground supported cold-climate plants and insects; elsewhere, animals moved through open country and caves accumulated bones. The record is thin, local and difficult, yet it establishes an essential truth: Ireland's Ice Age past was dynamic. Long before farms, monuments and named peoples, its landscapes were already being remade by water, frost, fauna and ice.

# Chapter 090 of 100

## 30911 BCE

### BIRM-166's Marshland <sup>[90]</sup>



**30,911 BCE is a modern chronological label, not a year that anyone in Ireland could have named or recorded. It falls roughly 32,861 years before the conventional radiocarbon reference year of AD 1950, in the Late Pleistocene and Marine Isotope Stage 3 (MIS 3), a fluctuating phase of the last Ice Age. Modern calendar-year precision is not available at this depth of time. No Irish settlement, person, journey or event can responsibly be assigned to this particular year. The evidence instead consists of deposits, animal bones and landforms dated across broad ranges, many of them later disturbed, buried or eroded by ice.**

## **A Date Within a Wide Range**

The best Irish environmental evidence relevant to this point comes from Derryvree, near Maguiresbridge in County Fermanagh. Roadworks in 1969 cut through a drumlin and revealed a remarkable sequence: a lower glacial till, freshwater silts and fine sands rich in organic material, and then a second, upper till. Till is sediment deposited directly by glacier ice. The arrangement therefore establishes a relative sequence: ice had crossed the district; an interval followed in which fresh water, plants and animals occupied the locality; later ice covered and sealed it again.

Organic material from the intervening deposit produced radiocarbon determination BIRM-166, conventionally reported as 30,500 radiocarbon years BP, with a substantial uncertainty of +1,170 and -1,030 years. Radiocarbon years are not calendar years. Calibration is necessary because atmospheric carbon-14 has varied over time, and at this age the resulting calendar ranges are broad. Later discussion has placed the Derryvree material approximately within 36,900–31,700 calibrated years BP. Thus 30,911 BCE falls within a useful chronological horizon for the deposit, but it is not the date of a particular pool, leaf, animal death or human action.

This is more than a technical qualification. The numbered year must not create an illusion of a precise Irish annal. BIRM-166 describes sampled carbon from one buried wetland sequence. It does not date all of Ireland, and it cannot tell us what occurred in one season at a site dozens or hundreds of kilometres away. Its great value is that it preserves a local environment from a period otherwise badly obscured by later glaciation.

## **Wet Ground Between Glaciers**

Derryvree was not an image of a mild, wooded island. The flora and fauna recovered from its freshwater beds indicate open tundra vegetation and a periglacial climate: a landscape shaped by frost, seasonal thaw, wind exposure and a short growing season. Mosses, sedges and other herbaceous plants grew in wet ground and around shallow water. Fossil botanical remains, including cold-adapted species, demonstrate that this was not sterile terrain. Pools and marshy margins could sustain aquatic and semi-aquatic life even where nearby ground was sparsely vegetated and vulnerable to frost action.

The evidence supports a mosaic rather than an unbroken white wilderness. During warmer months, meltwater and standing freshwater could create productive patches of mossy ground, sedge beds and herb-rich margins. In winter, the same landscape would have offered far less food and shelter. Such seasonal contrast is an interpretation based on the sedimentary setting and cold-climate assemblage; it is not a direct record of temperatures, snowfall or the duration of any particular season.

Nor should one small Fermanagh basin stand for the whole island. Derryvree lay in north-central Ireland, with its own drainage, relief and exposure. Southern limestone country, Atlantic-facing coasts, uplands and areas now beneath the Irish Sea may have differed markedly. Other deposits at Hollymount and Greenagho in Fermanagh likewise indicate cold, non-glacial intervals, but their dates and records do not combine into a uniform national landscape. At this time Ireland's environments were changing on long timescales as the British–Irish Ice Sheet developed towards its later maximum.

## **Mammoths and Hyenas in Cork**

At the opposite end of the island, Castlepook Cave near Doneraile in County Cork provides the principal animal archive for Ireland before the Last Glacial Maximum. Also known as Mammoth Cave, it has yielded more than 2,000 bones from deposits accumulated over a long span, rather than from one occupation surface. Its fauna includes woolly mammoth, reindeer, giant deer, brown bear and spotted hyaena, while later cold-stage layers include Arctic fox, wolf and lemmings. Modern re-dating has also shown that some older cave radiocarbon results underestimated the age of MIS 3 animals.

These remains establish that, during suitable pre-maximum intervals, large herbivores and predators reached Ireland and formed parts of a wider north-west European ecological world. They do not show that all these animals lived together at one moment, or that they ranged across every part of the island. A cave is especially difficult evidence: carnivores may drag in prey, water can move bones, and nineteenth- and early twentieth-century excavations did not always recover or record deposits to modern standards. Castlepook nevertheless overturns any simple idea that Ice-Age Ireland was permanently empty of large mammals.

The animals also point to the practical conditions any human visitor would have faced. Herbivores represented potential food, hide, bone and sinew; carnivores represented danger and competition for carcasses and sheltered places. Yet this is a statement about possibilities, not proof of a settled hunting

economy in Ireland. No securely dated camp, hearth, tool assemblage or dwelling belongs specifically to 30,911 BCE.

## **The Human Question**

A reindeer bone from Castlepook has been reported as carrying a mark interpreted as a cut made with a sharp stone tool, and it has been publicised as possible evidence for very early human butchery in Ireland. It is an important lead, because a genuine cut mark on fresh bone would indicate a person handling an animal carcass. But one modified bone is not a settlement, and a cave assemblage accumulated through complex natural processes cannot by itself reveal the size, origin, language or duration of any human presence. The interpretation remains far less secure than evidence from a well-excavated site containing tools, hearths and stratified occupation debris.

The responsible conclusion is therefore limited. Ireland may have received brief Upper Palaeolithic visits during favourable intervals before the Last Glacial Maximum; the Castlepook evidence makes that possibility harder to dismiss. It does not demonstrate continuous occupation. Later glacial erosion may have removed many open-air sites, while rising post-glacial seas and difficult offshore preservation conditions may conceal or have damaged others. Absence of sites is not absolute proof of absence of people, but neither is it permission to fill the gap with an imagined population.

## **No Politics, No Proven Trade**

There is no evidence for political institutions, leaders, diplomacy, warfare between human groups, formal religion, monuments, art, agriculture, livestock, trade routes or permanent settlements in Ireland at this date. These are not merely missing details: the surviving record is unable to demonstrate that any human community was living on the island then. It would be misleading to describe a chiefdom, clan territory, exchange network or ritual landscape.

If people did enter Ireland, comparison with Upper Palaeolithic groups elsewhere suggests that mobility, careful knowledge of animal movements, stone resources, fuel and weather would have been crucial. That comparison can help frame questions, but it cannot substitute for Irish finds. The demonstrable Irish economy was ecological rather than social: wetland plants, insects, grazers, scavengers and predators occupying shifting habitats at the edge of expanding ice.

## **Approaching a Colder Future**


30,911 BCE belongs before the Last Glacial Maximum, not within it. The major expansion of the last British–Irish Ice Sheet came later, with maximum conditions broadly falling between about 26,500 and 19,000 years ago, though the timing and extent varied across regions and remain subjects of research. Derryvree’s position between tills is therefore a powerful reminder that the Ice Age was not one static freeze. Ice advanced and retreated; freshwater basins formed; vegetation returned locally; and later glacier ice buried much of the evidence.

The most faithful portrait of Ireland around this notional year is consequently neither a kingdom nor an empty void. It is a changing cold-stage island or near-island landscape, locally ice-free in places such as the Derryvree wetland, inhabited by hardy plant and animal communities, and connected intermittently to wider environmental systems beyond its shores. Its history survives not in names or dates but in silt, pollen, moss, bone and the difficult science required to read them.

# Chapter 091 of 100

## 30910 BCE

### Maguirebridge's Reedbed <sup>[91]</sup>



**“30,910 BCE” is a modern chronological label, not a date that anyone in Palaeolithic Ireland could have recognised or recorded. It corresponds roughly to 32,860 calendar years before AD 1950, but archaeology cannot identify an event, a community or even a season in Ireland at that degree of calendar precision. The responsible subject is therefore Ireland during the later part of Marine Isotope Stage 3, a fluctuating cold phase before the Last Glacial Maximum. Evidence comes in broad radiocarbon and calibrated ranges, from fossils, cave deposits, pollen, plant remains and sediments rather than from written history. It illuminates a landscape inhabited by animals and perhaps occasionally visited by people, but not a year-by-year human society.**

## **A Cold Interval, Not a Frozen Island**

Ireland lay on Europe’s far north-western edge during a period of sharp climatic instability. The great Last Glacial Maximum, when the Irish Ice Sheet expanded across much of the island and onto the continental shelf, belongs mainly to the later interval of about 26,500–19,000 calibrated years BP. Around the notional date used here, its growth lay ahead rather than behind. That does not mean a mild or uniform Ireland. Conditions could be severe, with long winters, short growing seasons, frost-shattered ground and a vegetation cover unlike the modern green island.

Neither should Ireland be imagined as a single, unchanging expanse of ice. Ice margins advanced and retreated over long timescales, while local conditions varied with altitude, latitude, drainage and proximity to ice. Geological research in western and southern Ireland shows that reconstructing the dimensions and timing of the last ice sheet remains technically difficult. Later glacial erosion also

destroyed or buried much of the evidence needed to describe the preceding landscape. At this depth of time, a surviving wetland lens or cave bone can be more informative than many square kilometres of terrain remodelled by ice.

## **Derryvree's Waterlogged Record**

The closest Irish environmental evidence for this broad phase comes from Derryvree, near Maguiresbridge in County Fermanagh. Road cutting through a drumlin exposed freshwater silts and fine sands sealed between two tills: deposits left by glacier ice. The intervening organic bed proves that, for a time, this particular locality was not buried beneath an active ice sheet. It contained a conventional radiocarbon age of  $30,500 \pm 1,170/1,030$  radiocarbon years BP. That measurement is not an exact equivalent of 30,910 BCE. Modern calibration converts radiocarbon measurements into probability ranges rather than single historical dates, and the uncertainty of the original measurement is substantial. Yet it makes Derryvree a valuable approximate window on Ireland's middle Midlandian, or Devensian, cold-stage environment.

The deposit records a shallow freshwater setting, not an imagined lost village. Its pollen, mosses, plant macrofossils and insects indicate treeless, open tundra or muskeg-like ground under periglacial conditions. Sedges and other herbaceous plants, dwarf shrubs and cold-tolerant aquatic species could occupy wet hollows and the edges of pools. Fossils including bogbean, mountain avens, dwarf willow, water-milfoil and clubmoss are clues to particular microhabitats: shallow water, damp ground, open mineral soil and a brief but usable growing season. They show that liquid water, vegetation and invertebrate life persisted locally. They do not establish a pleasant climate, extensive woodland or a stable landscape across all Ireland.

Such evidence is especially important because it restores texture to a period often reduced to the phrase "Ice Age". Derryvree was probably a patchwork of sedge-fringed pools, wet mineral ground and sparse open vegetation, shaped by freezing and thawing. Ground may have been seasonally frozen, and wind exposure would have limited taller vegetation. The plants recorded are compatible with cold, continental and largely treeless settings seen across parts of glacial north-west Europe. They also indicate that the island contained biological refuges on a local scale, even as climate and ice conditions altered.

## **Animals on the Western Margin**

Southern Irish caves provide a second, very different archive. Castlepook Cave, near Doneraile in north County Cork, is Ireland's richest known pre-Last Glacial Maximum vertebrate site. Its historic excavations yielded more than 2,000 surviving bones, while subsequent dating and reassessment have shown that the assemblage accumulated over a very long interval, not during one moment. Individual finds span roughly 45,700 to 19,950 years BP in reported radiocarbon ages. They must not be compressed into a single scene for 30,910 BCE.

Nevertheless, the cave demonstrates that a striking range of large mammals reached Ireland during MIS 3: reindeer, giant deer, woolly mammoth, brown bear and spotted hyaena, as well as smaller cold-adapted animals in later parts of the sequence. This was no modern Irish fauna. Reindeer suggest open country capable of supporting grazing herds; mammoth and giant deer belong to wider Late Pleistocene ecosystems; hyaenas and bears reveal large carnivores competing for carcasses and shelter. The cave itself



was a repository, affected by carnivore activity, water movement, natural deaths, earlier excavation and disturbance. A bone in Castlepook proves an animal's presence in the regional landscape more securely than it proves exactly how, when or why it entered the cave.

Recent redating has altered the picture significantly. Improved bone-pre-treatment methods produced Castlepook dates thousands of radiocarbon years older than some results obtained in the 1990s. The revision is a warning against treating old dates as permanent facts, especially with cave collections whose original contexts were disturbed or imperfectly recorded. It also strengthens the case that parts of Ireland supported a diverse cold-stage fauna well before the climatic maximum. Some species, notably giant deer and spotted hyaena, may have disappeared locally before about 40,000 calibrated years BP, though the cave record is still too discontinuous to map a precise sequence of extinction and return.

## **The Human Question**

Political affairs, diplomacy, warfare, named leaders and institutions cannot be recovered for Ireland at this time. No settlement, hearth, tool-making floor, burial, house, artwork, language or social group of approximately 30,910 BCE has been securely identified on the island. There is therefore no defensible basis for describing a Palaeolithic Irish people, their religion, their kinship arrangements or their relations with neighbouring groups.

The most intriguing possible human clue is a reindeer femur from Castlepook. It has been interpreted as bearing a deep mark made by a sharp stone tool during butchery, and the bone has been presented as approximately 33,000 years old. If that interpretation is sustained by further taphonomic study, it indicates that a person or small party handled a reindeer in Ireland during the Upper Palaeolithic. It would be a major discovery, extending possible human activity on the island far earlier than the formerly accepted post-glacial record. But its limits matter. A single modified bone does not demonstrate a resident population, a camp at Castlepook, a continuous occupation or a named archaeological culture. Nor can it be assigned confidently to the exact year in this article's heading.

The wider European context makes brief mobility conceivable rather than proven. During glacial low sea levels, the outlines of Britain and Ireland differed greatly from today, and animal movement into Ireland was possible by routes that are now submerged or obscured. Human visitors, if present, may have followed seasonal animal movements, sought meat, marrow, hide, sinew or antler, and left little trace in a harsh, mobile landscape. Those are reasonable interpretations of hunter-gatherer economies elsewhere in Upper Palaeolithic Europe; they are not direct observations from Ireland. There is no evidence for trade networks, formal diplomacy or territorial polities here.

## **Life Without Monuments**

The evidence permits only a modest account of everyday life. The confirmed story is ecological: freshwater pools supported plants and insects at Derryvree; grazing animals and predators moved through parts of the Irish landscape; cave systems captured and preserved fragments of that world. If humans reached Ireland, their material footprint has either not survived, remains undiscovered, or has been removed by later glaciation and geological disturbance. Organic materials such as wood, fibre and hide would have been especially unlikely to endure in exposed settings.

Religion, art and learning are similarly beyond recovery. No Irish cave art, engraved object, ritual deposit or burial of this age is known. The later prehistoric Ireland of tombs, farming communities, metalwork, kingship and written tradition lay tens of millennia in the future. Applying those familiar

categories backwards would obscure the real historical importance of this interval: it reveals that Ireland was neither outside Pleistocene ecological change nor necessarily beyond the reach of mobile humans.


## **An Archive of Probabilities**

For this date, the most honest historical conclusion is one of qualified possibility. Around the broad calibrated span in which 30,910 BCE falls, Ireland contained cold, open and locally waterlogged environments rather than a settled agricultural landscape. At Derryvree, tundra vegetation grew beside freshwater; at Castlepook, an extraordinary animal archive records the passage of mammals through a changing region. Ice would later expand and erase much of the evidence. What survives is fragmentary, but it is meaningful: a reedbed beneath a drumlin, bones in a Cork cave, and a careful scientific debate over one possible human cut mark. They are not a calendar-year chronicle. They are the beginnings of Ireland's recoverable deep past.

## Chapter 092 of 100

30909 BCE

Derryvree Mosses, Castlepook Hyenas<sup>[92]</sup>



**Modern calendar-year precision is not available for Ireland in 30,909 BCE. No people on the island kept a calendar that can be tied to this date, and neither archaeology nor Quaternary science can identify an event, season or individual year so far back. The date is best treated as a modern reference point within the Late Pleistocene, broadly within Marine Isotope Stage 3 and the later part of the Midlandian cold stage in Irish terminology. The responsible evidence is therefore environmental and faunal: deposits, pollen, mosses, insects, bones and glacial sediments rather than chronicles, settlements or named communities.**

What can be said is significant. Ireland was entering a period of major ice-sheet growth, but it was not simply a uniform, featureless expanse of ice. The best surviving evidence indicates that, during part of this broad interval, some localities supported open, cold, biologically active landscapes. At Derryvree near Maguiresbridge in County Fermanagh, freshwater sediments buried within a drumlin preserve one of the rare Irish windows onto such a world. At Castlepook Cave near Doneraile in County Cork, bones record a striking community of large mammals and carnivores that belonged to wider north-west European Ice-Age ecosystems.

### A Date Without an Annual Record

The expression “30,909 BCE” should not suggest the kind of dating possible for a medieval battle or an eighteenth-century election. Scientific ages are normally reported in radiocarbon years before present, with “present” conventionally fixed at 1950, then calibrated against independently dated records. Calibration matters because atmospheric carbon levels have varied substantially through time. IntCal20, the principal Northern Hemisphere calibration curve, extends to 55,000 calibrated years before present, but its use does not turn a deposit into an annual diary.

The Derryvree material produced a radiocarbon determination of 30,500  $\pm$  1,170/–1,030 radiocarbon years BP. Published discussions place the deposit broadly within a calibrated later-MIS-3 range, often expressed as approximately 36,900–31,700 cal BP. That wide span encompasses the modern chronological label used here, but it cannot prove that every layer, creature or process at Derryvree belongs to this particular numbered year. More securely, the sequence records three ordered stages: glacial till was laid down; freshwater and organic sediments accumulated during a locally ice-free interval; and a later ice advance sealed the deposit beneath another till.

## **Fresh Water Beneath a Drumlin**

Derryvree is important precisely because so much Ice-Age evidence in Ireland was later eroded, buried or rearranged by advancing glaciers. Roadworks in 1969 cut through the drumlin and exposed silts and fine sands containing organic material between thick tills. The deposit was not a village site, and it provides no tools, structures, graves or hearths. It does, however, preserve direct evidence for the living landscape around freshwater.

Its pollen, plant macrofossils, mosses and insects indicate open, treeless terrain under periglacial conditions. Periglacial does not mean that a glacier necessarily stood beside the pool at every moment. It means that severe cold, frozen ground and frost-driven processes strongly shaped the land. Sedges, grasses, herbs, dwarf willow, juniper and cold-adapted mosses formed a sparse but varied vegetation. Bogbean and aquatic plants point to wet margins and pools. Insect evidence supports a cold, northern environment. The resulting scene is often described as tundra or muskeg-like wetland: mossy, sedgy, intermittently waterlogged ground, with shallow open water set within a wider exposed landscape.

This was no forested Ireland. There is no evidence for the oak, hazel and elm woods of much later prehistory, nor for fields, stock animals or cultivated crops. Vegetation was constrained by cold, short growing seasons and unstable ground. Yet the Derryvree record also rejects the image of a completely sterile frozen waste. Fresh water, wetland plants and summer growth created habitats for insects and, potentially, grazing and browsing animals. The distinction matters: a harsh landscape could still be ecologically productive in particular places and seasons.

## **Ice Growth and Changing Coasts**

The wider regional setting was changing rapidly. Reconstructions of the British–Irish Ice Sheet indicate sustained growth from about 31,000 to 26,000 years ago, followed by its greatest overall extent and volume later in the Last Glacial Maximum. Around the date in question, Ireland lay in an unstable transition towards much more extensive glaciation, not at a securely demonstrable island-wide maximum. Conditions differed by region, elevation and proximity to ice masses. Derryvree shows that one inland Fermanagh locality had experienced an interval without overriding ice; it cannot be used as a complete map of the whole island.

Lower global sea levels transformed the geography of north-west Europe, exposing areas now submerged beneath surrounding seas. This helps explain how animals could intermittently move between Ireland, Britain and the continental mainland. It does not licence a simple claim that there was a permanent, dry land bridge to Ireland in 30,909 BCE. Shorelines, isostatic movements, sea level, ice margins and shallow marine basins changed through time. The strongest conclusion is ecological connection at intervals: animal populations reached Ireland from the wider European world, but the exact routes and their availability at this precise date remain uncertain.

## Castlepook's Faunal World

Castlepook Cave, also called Mammoth Cave, lies in the Awbeg Valley below the Ballyhoura Hills of north County Cork. Excavations in the early twentieth century recovered a large and complex bone assemblage. Modern reassessment and renewed fieldwork have made the cave central to the study of Ireland before the Last Glacial Maximum. Its deposits include remains of woolly mammoth, giant deer, reindeer, brown bear, wolf, Arctic fox, lemmings and spotted hyena.

These species should not be imagined as one neatly contemporaneous herd gathered outside the cave in 30,909 BCE. Castlepook was a repository accumulating material over a long period. Individual bones have returned dates ranging broadly from about 45,700 to 19,950 BP, and the cave deposits were affected by water movement, carnivore activity and early excavation. A bone proves that its animal, or material from it, entered the cave system; it does not automatically prove where it lived, died or was killed. The cave's great value is its record of repeated faunal presence, not a single frozen moment.

Even with that caution, the assemblage is powerful evidence. Mammoth and reindeer indicate open country capable of supporting large herbivores. Spotted hyena, represented by skulls, teeth, bones and other evidence, was an active carnivore in this wider animal community. The cave may itself have been used by hyenas, whose scavenging, carrying and gnawing could help explain how some bones arrived there. Brown bears and wolves add to a picture of a much richer Pleistocene mammal fauna than historic Ireland possessed. These animals demonstrate that Ireland was connected, at least episodically, to continental-scale ecological networks before later glaciation and eventual insularity reduced its fauna.

## People: Possibility, Not a Proven Settlement

Human history is the most difficult subject at this date. A reindeer femur from Castlepook has been interpreted as bearing a mark made during butchery with a stone tool, and the bone's antiquity has encouraged the possibility that Upper Palaeolithic hunters reached Ireland around 33,000 years ago. If that interpretation is correct, it would indicate a brief human encounter with a reindeer carcass, not the existence of a settled population, a camp, a route regularly used by hunters or a named culture across the island.

The limitations are substantial. The evidence is isolated, the old cave assemblage is time-mixed and there are no securely associated stone tools, hearths, human remains or living surfaces from this period in Ireland. Improved collagen pretreatment has also shown that some older radiocarbon results from Irish caves were unreliable, making direct re-dating and stratified excavation especially important. It is therefore better to describe human presence around this broad period as possible or contested, rather than confirmed settlement. The clearest current evidence for people in Ireland belongs much later, near the end of the Pleistocene and in the Early Holocene.

## No Politics, No Trade Networks

There is no evidence from Ireland in this period for political institutions, warfare, diplomacy, chiefs, territorial boundaries, organised religion, monuments, literacy or formal learning. Nor is there evidence for farming, craft production or trade in the later prehistoric sense. To supply each of those subjects with an invented answer would turn an environmental archive into fiction.

If people did enter the island, their economy would most plausibly have resembled the highly mobile hunting and gathering practised by Upper Palaeolithic groups elsewhere in north-west Europe: flexible seasonal movement, close attention to animal behaviour and the use of stone, hide, bone and fire. That is an informed comparative interpretation, not direct evidence from an excavated Irish camp. No Irish object from 30,909 BCE allows us to reconstruct language, kinship, beliefs, ritual or social rank.

The principal development around this point in Ireland's deep past was environmental rather than political. Local freshwater wetlands and open tundra-like ground survived or formed during a cold phase; mammal communities moved through a changing regional landscape; and expanding ice increasingly threatened to erase their traces. Derryvree's mosses and Castlepook's hyenas preserve fragments of that lost Ireland. Their survival is extraordinary, but their message is necessarily modest: this was a changing Ice-Age landscape, rich enough for life, too ancient for annual history, and still only partly recovered from beneath the deposits left by later ice.

# Chapter 093 of 100

## 30908 BCE

### Derryvree's Periglacial Census<sup>[93]</sup>



Modern calendar-year precision is not available for Ireland in 30,908 BCE. No people on the island recorded a year, and neither radiocarbon dating nor glacial stratigraphy can identify an event to a particular season, let alone a day. The label is a modern chronological convenience, placing this article roughly 32,900 years before AD 1950, within the Late Pleistocene and Marine Isotope Stage 3 (MIS 3). Ireland's history at this depth of time is therefore not an annal of rulers, battles or settlements. It is a reconstruction assembled from sediments, plant remains, animal bones and the marks left by moving ice.

## A Date Within a Broad Range

The most informative Irish evidence close to this notional date comes from Derryvree, near Maguiresbridge in County Fermanagh. Road works in 1969 cut through a drumlin and exposed an exceptional sequence: a bed of freshwater silts, sands and organic material enclosed between two thick layers of till, the unsorted debris deposited by glacier ice. The order of those deposits is crucial. An earlier glacier had affected the locality; an intervening period then allowed water, plants and small animals to leave a record; later ice advanced and buried it beneath another till.

Organic material from the freshwater beds produced the radiocarbon measurement BIRM-166, conventionally reported as 30,500 radiocarbon years BP, with an uncertainty of more than a thousand years either way. A radiocarbon age is not a calendar age. Atmospheric carbon-14 has fluctuated through time, and calibration produces wide probability ranges at this antiquity. Published discussion places the Derryvree deposit broadly within a range of approximately 36,900–31,700 calibrated years BP. That range overlaps the chronological neighbourhood of 30,908 BCE, but it does not date a single pool, animal, journey or human action to that year.

## Fresh Water Beneath a Drumlin

Derryvree provides unusually detailed evidence for an Ireland that was cold but biologically active. Pollen was poorly preserved, so it cannot furnish a complete vegetation map. Plant macrofossils, mosses and insect remains are more informative. They indicate open tundra vegetation and a periglacial regime: ground strongly affected by frost, freezing and thawing, but not necessarily lying beneath glacier ice. The site is evidence for a particular local environment during a broad interval, not a photograph of the whole island at one moment.

The landscape around the freshwater deposit was probably a mosaic. Shallow pools and wet margins supported sedges, mosses and aquatic plants. Finds associated with bogbean, water-milfoil, mountain avens, dwarf willow and lesser clubmoss point to wet ground and open, cold-tolerant vegetation. Exposed patches may have held sparse herbs and grasses on thin, frost-disturbed soils. A few grains attributed to trees such as pine or hazel do not prove a nearby woodland: wind can transport pollen over long distances, while older material can be redeposited. The firmer conclusion is that south Fermanagh was largely treeless or nearly treeless country, with short growing seasons and seasonally waterlogged hollows.

Such conditions had practical consequences for every living thing. Winter frost, wind and prolonged snow cover would have constrained plant growth. Summer, however brief, could bring standing water, insect activity and new grazing. The Derryvree evidence has been compared with muskeg-like ground: wet, organic-rich terrain with low vegetation and shallow pools. It was not the blanket of permanent snow often imagined as an Ice Age landscape, nor was it the wooded island familiar from much later Irish prehistory.

## Ice, Coasts and Regional Change

Ireland lay in an unstable North Atlantic climatic world. The great maximum of the last British–Irish Ice Sheet was still to come, but ice was expanding and reorganising over long timescales. Modern reconstructions show that advance, maximum extent and retreat were not synchronous across every Irish region. At Derryvree, the sediments demonstrate that the site was ice-free while the freshwater deposits accumulated; the tills above and below demonstrate glacial occupation before and after. They cannot establish that every part of Ireland was simultaneously ice-free.

Later glaciation destroyed, mixed or concealed much earlier evidence. This is one reason why the archaeological record of Ireland around 30,908 BCE is so thin. It also cautions against neat maps showing a fixed ice margin or a uniform national climate. Coasts, drainage, local relief and distance from ice all changed. Lower global sea levels altered the extent of shelves and shorelines, but the exact routes by which animals or people could have reached Ireland remain difficult to reconstruct. The evidence does not support assuming an easy, permanent land connection with Britain or continental Europe at this particular time.

## Animals in a Cold Landscape

Cave deposits in southern Ireland nevertheless show that substantial mammals reached the island during MIS 3. Castlepook Cave, also called Mammoth Cave, near Doneraile in north County Cork is the best-known site. Collections made during early twentieth-century excavations included remains attributed



to mammoth, reindeer, giant deer, wolf, fox, Arctic fox, bear and spotted hyena, alongside smaller animals. A spotted-hyena skull from the cave is preserved by the National Museum of Ireland. Together, these finds overturn any idea that Ice Age Ireland was simply empty ice.

They must, however, be handled with care. Castlepook was used as a natural bone trap, den or shelter by animals over long periods, and its early excavations disturbed or removed much of the original sediment. Direct dates on different specimens span many millennia. The cave assemblage therefore demonstrates that these species occurred in Ireland during broad Pleistocene intervals; it does not prove that every listed animal met at Castlepook in 30,908 BCE. Nor can the animal list be projected without qualification across the entire island.

The fauna is still revealing. Reindeer fit open, cold grazing country; mammoth and giant deer imply that parts of the wider landscape could sustain large herbivores; wolves and hyenas indicate predators and scavengers within those food webs. Their presence suggests intermittent ecological connections with north-western Europe, whether by shifting coastal routes, crossings available under particular sea-level conditions, or movements across landscapes since erased by ice and sea. Precisely how and when each population arrived remains a matter for evidence rather than assumption.

## **The Human Question**

There is no securely identified Irish house, hearth, grave, tool assemblage or settlement surface dating to around 30,908 BCE. Consequently there is no responsible basis for describing clans, leaders, territorial politics, warfare, diplomacy, religious institutions, trading networks, agriculture or established communities in Ireland at this date. There is likewise no evidence for a local artistic or learned tradition that can be assigned to this horizon. Silence in these categories is not proof that no individual ever entered the island, but it is decisive against writing a conventional social history for the year.

A reindeer femur from Castlepook has made this restraint especially important. One deep mark on the bone has been interpreted as a cut or chop made with a sharp implement during carcass processing, and the specimen has been presented as possible evidence of very early human activity in Ireland. It is an important claim, because a confirmed human modification would greatly extend the island's known human story. Yet a single modified bone from a complicated cave context cannot establish a settlement, a population, a date-specific hunt or a continuing occupation. Its interpretation and chronological implications require further scrutiny.

If people did reach Ireland during the wider MIS 3 interval, they would most plausibly have been small, mobile foraging groups, as elsewhere in Upper Palaeolithic north-west Europe. That is a regional comparison, not demonstrated Irish evidence. No Irish site currently permits a reconstruction of their camps, food-sharing, belief or relations with other groups. The disciplined conclusion is narrower: animal remains make a human encounter with this landscape conceivable, but archaeology has not yet converted that possibility into a documented society.

## **What This Year Can Mean**

The importance of 30,908 BCE lies in the survival of rare environmental archives rather than an event. Derryvree preserves a cold freshwater wetland briefly protected between advances of ice. Castlepook preserves a partial, time-mixed record of mammals that inhabited or reached Ireland during

the long lead-up to the Last Glacial Maximum. Both records are incomplete, and both have been transformed by natural processes and early excavation. Yet together they show an Ireland of sedgy pools, frost-worked ground, open vegetation and large cold-stage animals: harsh, changing and far from lifeless.

That is the appropriate historical perspective for this deep prehistoric date. The island had no known polity or calendar, but it had environments, ecological thresholds and geological changes that shaped every later possibility of habitation. The evidence is fragmentary, but its lesson is substantial: before the great ice-sheet maximum remade much of the landscape, parts of Ireland were briefly available to freshwater life, tundra plants and a remarkable Pleistocene fauna.

# Chapter 094 of 100

## 30907 BCE

### Maguirebridge and Doneraile<sup>[94]</sup>



**Modern calendar-year precision is not available for Ireland in 30,907 BCE. The label is a useful point on a modern timeline, but it does not identify a recorded year, season, ruler, migration or battle. Counted back from the archaeological convention of AD 1950, it lies about 32,856 calendar years before present, during the Late Pleistocene and Marine Isotope Stage 3 (MIS 3). At this depth of time, evidence comes from dated deposits, animal bones, cave sediments and glacial landforms, all of which describe intervals rather than a single year.**

The responsible history of Ireland at this point is therefore one of changing environments and limited traces of animal and possibly human movement. Ireland was not yet a political or cultural community in any historical sense. It was a north-western extension of a larger Ice Age world, repeatedly reshaped by ice, frost, rivers, changing coastlines and shifts in sea level. The best Irish evidence relevant to this broad horizon comes from a freshwater deposit beneath a drumlin at Derryvree near Maguiresbridge, County Fermanagh, and from the remarkable bone assemblage of Castlepook Cave, near Doneraile in north County Cork.

## **A Date, Not a Dateline**

Radiocarbon dates must not be read as direct calendar dates. They measure the decay of carbon-14 and require calibration against independently dated records of past atmospheric change. The current IntCal20 calibration curve extends to 55,000 calibrated years before present, but its output at this antiquity is a probability range, not a date that can be narrowed to a named year. A modern BCE label is even less exact: it is imposed retrospectively on a landscape whose inhabitants, if people were present, left neither writing nor a calendar.

Derryvree provides the closest securely dated environmental archive. Organic silts and fine sands were exposed during roadworks in 1969 within a Fermanagh drumlin. They lay between two layers of glacial till: unsorted material left by ice. The arrangement matters. An earlier ice advance deposited the lower till; afterwards, a hollow held freshwater sediments and organic remains; a subsequent advance covered the deposit with the upper till. One conventional radiocarbon determination from the organic sequence was 30,500 radiocarbon years BP, with a large published error margin of +1,170 and –1,030 years. Calibration places such a result broadly in the mid-to-late 30,000s calendar years BP, not at a precise point equivalent to 30,907 BCE.

The numbered year should thus be treated as falling within a broad late-MIS-3 setting, not as the moment when the Derryvree pool formed or vanished. Equally, the target date cannot be made to coincide mechanically with a radiocarbon result from Cork. These archives are separated by hundreds of kilometres and accumulated over long, differently dated spans. Their value lies in what they establish together: parts of Ireland supported functioning cold-climate ecosystems before the later maximum expansion of the British–Irish Ice Sheet.

## **Wet Ground Beneath a Drumlin**

Derryvree overturns the simplest image of Ice Age Ireland as a featureless white expanse. Its fossils indicate a largely open, treeless and periglacial landscape: one shaped by severe cold, repeated freezing and thawing, sparse cover and poorly developed soils, but not necessarily buried beneath glacier ice at the time the sediments formed. The site has been described as a muskeg-like environment, with saturated ground, pools, mosses and sedges.

Plant remains include grasses, sedges, herbs and cold-tolerant species. Mountain-avens, dwarf willow, lesser clubmoss and bogbean are especially revealing, while water-milfoil indicates shallow or slow-moving freshwater. Mosses and insect remains support the interpretation of wet, exposed ground under harsh climatic conditions. These are local signals, not a complete map of Ireland. They show what grew around one basin and its catchment; they do not prove that every Irish valley or upland had the same vegetation, nor that trees were absent everywhere. Pollen can travel far and can be redeposited, whereas the macrofossils from the wetland provide firmer evidence for its immediate surroundings.

For living creatures, this was not an empty world. During the short growing season, water and marsh-edge plants could support insects and other small animals, while herbs, grasses and low shrubs created patches of forage across more freely drained ground. Winter would have sharply altered the balance: deep frost, snow, frozen soil, exposure to wind and a restricted food supply. The essential environmental rhythm was seasonal uncertainty rather than settled agricultural plenty. There were no fields, livestock, cleared woodland or permanent farmsteads known from Ireland at this time.

## **Ice Building Across the Islands**

30,907 BCE predates the Last Glacial Maximum, the phase when the last British–Irish Ice Sheet reached its greatest overall volume and extent. Recent ice-sheet reconstruction places substantial growth between about 31,000 and 26,000 years ago, with maximum volume around 23,000 years ago; different sectors advanced, peaked and retreated at different times. Ireland was therefore entering a major glacial reorganisation, not experiencing one simultaneous island-wide event.

That distinction prevents two errors. First, the later maximum ice map cannot simply be projected backwards onto every earlier millennium. Second, an ice-free wetland at Derryvree does not mean that all Ireland was hospitable, connected or uniform. Glaciers and local ice caps occupied some regions, while exposed lowlands, valleys and coastal plains could differ greatly over relatively short distances. Much of the evidence has also been destroyed, buried or reworked by later ice. The archaeological silence of many areas is consequently not proof that nothing ever lived or travelled there.

Lower sea levels changed the physical setting too. Ireland's modern shorelines did not exist in their present form, and the surrounding shelves exposed or submerged at different stages. Yet a simple claim of a permanent land bridge to Britain or continental Europe would be unsafe. Access routes depended on the geometry of ice, water, sea level and terrain at particular times. The animal record shows that movements occurred during the Pleistocene; it does not reveal a single route, season or uninterrupted corridor.

## Castlepook's Mixed Fauna

At Castlepook Cave, a Carboniferous limestone cave system near Doneraile, excavators recovered more than 2,000 bones from deposits investigated mainly in the early twentieth century. The cave is Ireland's richest known site for vertebrate fauna in the period leading towards the Last Glacial Maximum. Its assemblage includes woolly mammoth, reindeer, giant deer, brown bear, wolf, fox, Arctic fox, stoat, mountain hare, collared lemming, Norwegian lemming and spotted hyena. The hyena is particularly significant: Castlepook is the only Irish locality known to have yielded it.

This list should not be mistaken for a census of animals seen together in 30,907 BCE. Cave deposits may accumulate over many generations or millennia. Carnivores may drag prey or scavenged material inside; animals can die in traps; water, burrowing and later excavation disturb layers. Some Castlepook material was collected before modern excavation standards, and later research has warned that older radiocarbon determinations need reassessment because methods of collagen preparation have improved. Individual dates from the cave span a wide range, approximately 45,700 to 19,950 radiocarbon years BP.

Even so, the fauna makes a robust larger point. Southern Ireland was intermittently part of a north-west European cold-stage ecological zone able to sustain large herbivores, small Arctic-adapted mammals and major predators. Reindeer and mammoth suggest open forage-rich habitats rather than closed forest. Hyenas and wolves indicate carnivore activity within that broader food web. Giant deer belonged to the same long Pleistocene story, though their precise local timing and habitat relationships cannot be reduced to one scene or one date.

## A Possible Human Trace

The most consequential but most limited evidence for people is a reindeer femur from Castlepook reported to bear a deep mark consistent with fresh-bone butchery by a sharp stone tool. The animal has been publicised as roughly 33,000 years old, making the find relevant to the general time horizon of this article. If the interpretation of the modification is sustained, it suggests that one or more Upper Palaeolithic people processed a reindeer in Ireland long before the well-established post-glacial settlement record.

But the evidence does not establish a resident population, a camp, a journey from any particular homeland or a date in 30,907 BCE. The bone comes from an old and complex cave collection rather than a sealed occupation floor. No securely associated hearth, stone-tool assemblage, dwelling surface, burial,

repeated food-processing area or settlement has been published for this horizon. The cautious conclusion is that the femur may preserve a fleeting human action; it cannot support a narrative of an Irish tribe, household or colony.

## What Cannot Be Recovered

Political affairs, diplomacy and organised warfare cannot responsibly be described for Ireland at this date. There are no named communities, leaders, territories, monuments, languages or institutions. Nor is there evidence for religion in the archaeological sense: no demonstrable shrine, burial rite, figurative art or ceremonial object belongs securely to this Irish horizon. People, if present, certainly had social lives, knowledge and beliefs, but archaeology cannot specify them from one possibly worked bone and environmental deposits.


There is likewise no evidence for trade in the later historical meaning of regular exchange between settled communities. The faunal record demonstrates movement across a wider region, not commerce. The most defensible account of everyday life is ecological: mobile animals seeking forage and shelter; predators using caves and landscapes of pursuit; perhaps transient human visitors taking meat, marrow, hide or sinew from a carcass. Those possibilities remain interpretation, not recovered fact.

The principal development around this notional year was environmental rather than political. Ireland stood within a cold, dynamic Late Pleistocene world as ice grew, wetlands persisted in sheltered places and animal communities shifted through a fragmented landscape. Derryvree and Castlepook preserve rare windows onto that world. Their very incompleteness is part of the history: later ice repeatedly erased the ground on which any camps, tracks, shorelines and seasonal encounters might once have stood.

## Chapter 095 of 100

30906 BCE

### Fermanagh's Buried Freshwater<sup>[95]</sup>



**30,906 BCE is a modern chronological label, not a date that anyone in Ireland could have known or recorded. There was no writing, named polity, calendar or recoverable annual sequence from which to identify an event in that particular year. Expressed against the radiocarbon convention of “before present”, where present is AD 1950, it lies roughly 32,850 years ago. That conversion should not imply false precision. At this depth of time, deposits are dated in ranges, often with substantial uncertainty, and the evidence speaks most securely about long environmental intervals rather than a single winter, journey or generation.**

Ireland then belonged to the Late Pleistocene, conventionally placed within Marine Isotope Stage 3 and the regional Midlandian cold stage. It was part of a north-west European world marked by abrupt climatic swings, changing ice margins and lower seas. The island was not yet simply the uniformly ice-covered landscape often imagined for the later Last Glacial Maximum. Nor can its condition at one named year be mapped with confidence. The appropriate history is therefore a history of sediments, plants, animals, ice and uncertainty.

## Dating a Calendarless Landscape

The most illuminating evidence comes from Derryvree, near Maguiresbridge in County Fermanagh. Road works in 1969 cut through a drumlin and exposed an extraordinary sequence: organic freshwater silts and fine sands lay trapped between two thick layers of till, the unsorted sediment deposited by glacier ice. The stratigraphic order is robust. Ice had formed the lower till; subsequently, at least at this locality, a freshwater environment accumulated mineral and organic sediment; later ice crossed the district and sealed the deposit below an upper till.

Organic material from the Derryvree series returned a conventional radiocarbon result of 30,500 years BP, with an uncertainty of  $\pm 1,170$ – $1,030$  years. Such a result is not itself a calendar date. Radiocarbon ages must be calibrated because atmospheric carbon-14 levels changed through time, and calibration at more than thirty millennia ago necessarily yields broad ranges. The Derryvree evidence is thus relevant to the climatic world around this article's notional year, but it cannot be made to prove that a particular pond, plant or insect existed in 30,906 BCE. The distinction between an age estimate and an annual historical date is essential.

## **The Derryvree Wetland**

What the buried freshwater layers do preserve is unusually direct local evidence for a cold, treeless landscape in northern Ireland. Their pollen, plant macrofossils, mosses and insect remains point to open tundra or tundra-steppe conditions and a periglacial climate: ground subject to severe cold and freeze-thaw processes, although not necessarily covered by glacier ice at Derryvree while the organic layers formed. Sedges, mossy wet ground and shallow water mattered more here than woodland. Even the limited pollen evidence suggests that any dry-land vegetation was sparse.

This was not a timeless, featureless white wilderness. Fresh water, silts and organic remains imply pools, saturated ground and seasonally changing margins in a sheltered lowland setting. Cold-adapted plants could occupy damp hollows, while exposed ground beyond them supported a thin, open cover rather than closed forest. But the evidence does not justify a painted panorama in which every species was contemporaneous or every part of Ireland looked alike. Derryvree was a local archive, preserved by exceptional burial beneath the drumlin; it provides a window, not a census of the whole island.

## **Ice Before the Maximum**

The enclosing tills make one larger fact unmistakable: glaciation in Ireland was episodic and regionally varied. The wetland formed between glacial episodes, and renewed ice later erased or buried much of the terrain that had existed around it. Other inter-till deposits in Fermanagh, including sites near Hollymount and Greenagho, reinforce the conclusion that cold, non-glacial conditions occurred in parts of the north between advances. These deposits are not identical in date or environmental detail, but together they caution against treating the Irish Ice Age as one unchanging freeze.

Recent reconstructions of the last British–Irish Ice Sheet model substantial ice-sheet growth from about 31,000 years ago, with the greatest expansion later, broadly during the interval from c. 26,000 to 20,000 years ago. At the chronological scale relevant here, Ireland was entering a phase of major climatic and glacial reorganisation, not yet living through a single island-wide maximum frozen state. Precise ice limits at roughly 32,850 years ago remain modelled estimates constrained by uneven evidence. It is safer to say that ice, periglacial ground and ice-free refuges could coexist across a changing region than to draw a firm shoreline or glacier front for one calendar year.

## **Animals in an Open Country**

Southern Irish caves provide a complementary, though more difficult, record. Castlepook Cave near Doneraile in County Cork has yielded remains attributed to animals including reindeer, woolly mammoth, giant deer, brown bear, wolf, Arctic fox, mountain hare, lemmings and spotted hyaena. Re-dating has demonstrated that some older cave chronologies were too young, while confirming the importance of



Castlepook and related sites for Ireland's Marine Isotope Stage 3 fauna. Reindeer and lemmings particularly fit a cold, open environment; mammoth and hyaena indicate ecological connections far removed from modern Ireland.

Yet a cave bone assemblage is not a photograph of a living herd. Carnivores may carry prey into caves, scavenging may redistribute bones, and early excavations did not always preserve the contextual information expected today. Different bones can also represent occupations separated by thousands of years. The responsible conclusion is that Late Pleistocene Ireland supported, at various times, a richer and colder-adapted mammalian fauna than today. It is not that mammoths, hyaenas, reindeer and people can all be placed together beside one Cork cave entrance in 30,906 BCE.

## **The Human Question**

Human history at this date is especially uncertain. No securely excavated settlement, hearth, lithic assemblage, dwelling, grave, artwork or ritual monument is known in Ireland from around 30,906 BCE. Consequently, there is no evidence for an Irish people, language, chieftdom, conflict, diplomacy, trade network or religious practice that can responsibly be described for this year. There is equally no basis for reconstructing clothing, cooking, family organisation or seasonal movement on the island itself.

A reindeer femur from Castlepook Cave has been reported as carrying a mark interpreted as a possible stone-tool butchery trace and as dating to roughly 33,000 years ago. If that interpretation is eventually confirmed through further analysis and secure contextual work, it would indicate a very early, probably fleeting, human visit to Ireland during the Ice Age. It would not demonstrate permanent settlement. The claim remains much narrower than later popular retellings: one modified bone, from a cave with complex deposits, cannot establish a population, a hunting camp or a continuous occupation. The first well-published evidence of human activity presently accepted with much firmer contextual support comes far later, from a butchered brown-bear patella at Alice and Gwendoline Cave in County Clare, dated to the terminal Pleistocene.

## **Society, Economy and Belief: Evidential Limits**

For a conventional year-by-year history, politics, war, diplomacy, religion, culture and learning are often central. Here, silence is the finding. No Irish evidence supports named leaders or communities; no weaponry can be linked to conflict; no imported objects demonstrate exchange; and no ceremonial structure, image or burial illuminates belief. The absence does not prove that no human being ever set foot on the land during this long climatic phase. It means that the archaeological record presently cannot convert that possibility into social history.

Likewise, an economy cannot be inferred merely because animals and edible plants existed. Reindeer, hare or mammoth remains show animal presence, while wetland plants reveal habitats; they do not prove hunting, trapping, hide-working or trade by people in Ireland. Should people have visited, the open landscapes and animal resources may have been attractive, but that is interpretation rather than evidence. The line must remain visible.

## Island, Region and Legacy


Lower global sea levels changed the outlines of the seas around Ireland, exposing areas of continental shelf now submerged. This did not automatically create a simple, continuously usable land bridge, nor does the presence of mammals reveal exactly how they reached the island. Ice, changing coastlines, channels and cold seas all affected movement. Ireland's relationship with Britain and the wider European landmass therefore changed through time, but the routes available at this precise point remain unresolved.

The enduring importance of 30,906 BCE lies not in an invented event but in the evidence's scale. Derryvree's buried freshwater bed, Fermanagh's other inter-till deposits and the cave faunas of Cork show an Ireland repeatedly reshaped by climatic instability. Wet ground could sustain tundra vegetation between glacial advances; animals adapted to open northern environments crossed or recolonised changing landscapes; and later ice could entomb the traces. Around this point in deep time, environment is not merely the setting for history. It is the surviving history.

# Chapter 096 of 100

## 30905 BCE

### Fermanagh's Buried Muskeg<sup>[96]</sup>



The label 30,905 BCE gives a useful point of reference, but it cannot identify an Irish event in the way a later historical year can. No written record, settlement sequence or calendar-based chronology exists for this depth of time. Indeed, modern calendar-year precision is unavailable. The responsible frame is a broad part of the Late Pleistocene, within Marine Isotope Stage 3 (MIS 3) and Ireland's Middle Midlandian cold-stage record. The closest illuminating evidence comes from Derryvree near Maguiresbridge, County Fermanagh, where a rare organic deposit preserves a glimpse of an ice-age landscape. It is evidence for an interval, not for the particular day, season or year denoted by 30,905 BCE.

## A Date With Wide Margins

In 1969, road works cut through a drumlin at Derryvree and exposed an exceptional sequence: thick glacial till below, freshwater silts and fine sands in the middle, and another thick till above. Tills are debris laid down directly by glacier ice. The intervening sediments therefore show that, between episodes of glaciation, this locality was not continuously buried beneath an ice sheet. Organic material in the freshwater bed produced the radiocarbon determination Birm-166: 30,500 radiocarbon years before present, with a substantial uncertainty of +1,170 and -1,030 years.

Radiocarbon years are not calendar years. They must be calibrated because atmospheric carbon levels have altered through time, and at such antiquity the resulting calendar ranges are broad. Scholarship has placed the Derryvree result approximately within 36,900–31,700 calibrated years before present, or roughly 34,950–29,750 BCE. Thus 30,905 BCE lies within a reasonable broad chronological horizon for the deposit, but cannot be singled out from it. The sediment may have accumulated over time; neither its

plants nor its insects can be assigned to this numbered year. The important conclusion is more modest and more secure: at some point during this range, an ice-free freshwater wetland existed in what is now eastern Fermanagh.

## Water Between the Tills

Derryvree is valuable precisely because most landscapes from this period have been transformed or erased by later ice. Its plant remains, pollen, mosses and insect evidence point to open, treeless vegetation and a severe periglacial regime. “Periglacial” does not mean beside a glacier alone: it describes terrain shaped by intense freezing and thawing, seasonal waterlogging, sparse plant cover and cold ground conditions. The published interpretation is a muskeg-like environment, a waterlogged mosaic of peat-rich ground, shallow pools and sedge-rich margins rather than a continuous lake or forest.

The fossil flora includes grasses, sedges, herbs, mosses and cold-tolerant plants. Bogbean, mountain avens, dwarf willow, juniper and lesser clubmoss are among the kinds of plants represented in the assemblage. Their presence does not permit a picturesque reconstruction of every hillside. Pollen can travel, and a fossil found in a wet hollow does not map an entire region. Yet the combined evidence strongly supports a largely open landscape in which low vegetation survived around standing water and damp soil. There is no basis for imagining modern Irish woodland, farmland, hedges or bogland. This was an ice-age environment, though not necessarily a featureless snow desert.

The insect assemblage gives the reconstruction further texture. Beetles associated with cold, wet ground, plant litter and shallow pools reinforce the interpretation of local freshwater and mossy, organic-rich margins. Such evidence records ecological conditions more directly than later folklore or historical analogy ever could. It suggests seasonal variation: summer thaw produced water and plant growth, while long cold winters and repeated frost action constrained soils, drainage and vegetation. The Derryvree wetland was therefore a small but living refuge within a difficult wider landscape.

## Ice, Land and an Uncertain Coast

Thirty millennia ago Ireland was not the island landscape known today, but its precise outline remains difficult to reconstruct. Global sea level was lower than now because vast volumes of water were locked in continental ice sheets. The configuration of the Irish Sea, land bridges, channels and ice margins changed as sea level and ice loading changed. It is tempting to turn lower sea level into a simple claim that Ireland was joined to Britain. The evidence does not allow that certainty for this precise interval. Connections may have existed at some times and routes may have been blocked at others by water, ice, difficult terrain or all three.

The broader glaciological picture is also changing as new modelling and dating refine the history of the British–Irish Ice Sheet. The great Last Glacial Maximum ice cover came later, with Ireland and its continental shelf extensively glaciated around 27,000–23,000 calibrated years before present. Around the Derryvree interval, however, researchers increasingly envisage a dynamic world of growing regional ice masses, local ice-free ground and rapidly shifting margins rather than one simple all-Ireland condition. The drumlin sequence itself proves alternating ice advance and ice-free sedimentation at one Fermanagh locality; it does not establish exactly how much of every province was ice-covered in 30,905 BCE.

That distinction matters for regional history. Derryvree documents an inland wetland in the north-western part of the landmass. Castlepook Cave near Doneraile in north County Cork, far to the south, has yielded a different archive: mammoth, reindeer, spotted hyaena and other Pleistocene animal remains.

Some Castlepook specimens have returned pre-Last Glacial Maximum ages, demonstrating that Ireland could support, or at least receive, a much richer cold-stage fauna than later millennia did. Cave deposits, however, collect remains by carnivores, water movement, natural death and excavation disturbance over long periods. They must not be treated as a census of animals living together in one year.

## **Animals and a Human Question**

The Castlepook evidence makes an important environmental point. Reindeer and mammoth are consistent with open, cold-country habitats; spotted hyaena indicates a predator and scavenger capable of moving through those landscapes. Their presence in the Irish fossil record shows that animal populations reached the region during parts of the Pleistocene. It does not show that humans established a community, camped at Derryvree, or hunted there in 30,905 BCE. The ecological world was connected to north-west Europe at least intermittently enough for large mammals to appear, but the exact routes and timings remain unresolved.

A reindeer femur from Castlepook has attracted particular attention because a deep mark has been interpreted as a fresh-bone cut or chop made by a stone implement. If that assessment is upheld and the mark is contemporary with the animal's death, it would be significant evidence for human handling of a carcass in pre-Last Glacial Maximum Ireland. But the qualification is essential. A radiocarbon date measures the age of the bone's organic carbon, not automatically the instant when a surface mark was made; identifying human modification also requires careful taphonomic comparison with damage caused by carnivores, excavation, weathering and other processes.

No securely associated hearth, stone-tool assemblage, floor surface, dwelling, burial or repeatedly butchered bone concentration has been demonstrated for Ireland at this age. The first widely accepted evidence of a human incursion into Ireland remains much later: cut-marked brown-bear bone from Alice and Gwendoline Cave, County Clare, dated to the terminal Pleistocene, around 12,810–12,590 calibrated years before present. Therefore, the fair account for 30,905 BCE is not one of known inhabitants, leaders or tribes. It is a period in which a possible, still limited human signal has been proposed against an overwhelmingly environmental and palaeontological record.

## **No Polity, No Proven Trade**

Political affairs, diplomacy and warfare cannot be recovered here. There are no named peoples, territories, institutions, monuments or material assemblages from which social rank or collective identity might responsibly be inferred. Nor is there evidence for farming, animal husbandry, pottery, metalwork, permanent villages, literacy, formal religion or trade networks in Ireland at this date. To supply them would confuse general knowledge of Upper Palaeolithic Europe with evidence from Ireland itself.

If people did enter Ireland during this broader cold-stage horizon, they would have been highly mobile hunter-gatherers, relying on practical knowledge of animals, seasons, stone and shelter. That is an inference from comparable Upper Palaeolithic societies elsewhere, not a documented description of an Irish group. The proposed Castlepook cut mark may suggest carcass processing, but one marked bone cannot establish diet, population size, migration pattern, language, ritual practice or exchange. Likewise, Derryvree's wetland gives no evidence of a settlement beside its pools. It tells us what habitats were available, not who used them.

## The Record's Greatest Lesson


For Ireland around 30,905 BCE, the central historical development was environmental instability. Freshwater silts accumulated in a cold open wetland; later glacier ice overrode or sealed that world beneath till. The survival of this fragile inter-till archive is exceptional. It illuminates a country of tundra-like vegetation, shallow water, frost and mobile animal life, at the threshold of much more extensive glaciation. It also explains why the human story is so hard to write: later ice destroyed landscapes, while rising seas and subsequent erosion altered potential coastal routes and campsites.

The evidence therefore demands both imagination and restraint. Derryvree supports a vivid account of wet ground beneath cold skies, where sedges, mosses and hardy flowering plants occupied a brief ice-free interval. Castlepook supports the presence of large mammals in the wider Irish Pleistocene, and a debated possibility of human action. Neither archive yields an event that happened in 30,905 BCE. Their real significance lies in preserving the deep background from which Ireland's far later, securely attested human history eventually emerged.

# Chapter 097 of 100

## 30904 BCE

### BIRM-166's Tundra Flora<sup>[97]</sup>



Modern calendar-year precision is not available for Ireland in 30,904 BCE. The label is a point on a retrospective modern timeline, not a date for which archaeology can identify an Irish event, ruler, community or season. In simple chronological terms it falls about 32,853 years before AD 1950, within Marine Isotope Stage 3 (MIS 3), a fluctuating part of the last Ice Age. The closest evidence is dated in broad scientific ranges. Most importantly, an organic deposit at Derryvree near Maguiresbridge, County Fermanagh, has a conventional radiocarbon determination of 30,500 +1,170/-1,030 radiocarbon years BP; published calibration places it broadly around 36,900–31,700 calibrated years BP. That range encompasses the approximate period represented by 30,904 BCE, but it cannot identify conditions in one exact year.

## Freshwater Between Ice Advances

Derryvree is the key Irish environmental archive for this moment. Roadworks in 1969 cut through a drumlin and revealed freshwater silts and fine sands sealed between two substantial sheets of glacial till. The sequence establishes a valuable relative history: glacier ice had deposited the lower till; the site later supported freshwater and waterlogged ground; and renewed ice eventually overran or buried that landscape beneath the upper till. It does not demonstrate that all Ireland was ice-free at once, nor that the whole organic bed accumulated in a single generation. Yet it securely shows that a part of the Fermanagh interior experienced an ice-free interval during the wider Middle Midlandian cold stage.

The Derryvree deposit was not a lost forest or a temperate lakeside. Its pollen, plant macrofossils, mosses and insect remains indicate a cold, open, largely treeless environment often described as tundra or muskeg. Such language should be understood as an ecological shorthand rather than a modern landscape label. Saturated ground, shallow pools, sedge-rich margins and patches of low vegetation lay within a

periglacial regime shaped by prolonged winter cold and frost. Fossil evidence includes aquatic and wetland plants alongside hardy arctic-alpine species. These remains make the landscape more intelligible: water persisted locally despite severe conditions, while vegetation was sufficient to support insects and small ecological communities. They do not, however, provide a complete map of Fermanagh or a thermometer reading for 30,904 BCE.

## **An Unstable Ice-Age Island**

Ireland was in the later Pleistocene, long before the familiar wooded landscapes, farms, monuments and named territories of later prehistory. Climate in MIS 3 was not uniformly frozen. North Atlantic conditions changed sharply between colder stadials and relatively milder interstadials, and the growth of the British-Irish Ice Sheet was neither instantaneous nor identical in every region. The Derryvree beds are especially important because they preserve a landscape before the later, more extensive glaciation erased or reworked much of the island's older surface record. Research on the ice sheet indicates major expansion towards the continental shelf in the following millennia, with outer-margin advance commonly placed around 29,000–27,000 calibrated years BP. Therefore this date belongs not to a timeless white wilderness, but to a changing interval in which ice-free habitats could be lost as ice expanded.

Sea level was lower than today because great quantities of water were held in continental ice sheets. Coastlines and shallow seas around Ireland consequently differed greatly from modern ones. That fact does not licence an easy story of a permanent land bridge or unrestricted migration. The exact form, timing and passability of routes between Ireland, Britain and continental Europe varied with sea level, ice margins, currents and terrain. For animal populations, and perhaps for occasional people, Ireland was part of a north-west European environmental zone whose connections repeatedly narrowed or altered. The evidence is stronger for changing access and habitat than for any particular route used in this specific period.

## **Castlepook's Animal Evidence**

More than 300 kilometres south-west of Derryvree, Castlepook Cave near Doneraile in County Cork preserves the other major body of evidence relevant to this broad era. Antiquarian excavations there produced an exceptional but complicated collection of animal remains. Mammoth, reindeer, giant deer, brown bear, wolf, Arctic fox, mountain hare, lemmings and spotted hyaena are among species recorded from the cave system. Re-dating has shown that several earlier determinations underestimated the age of some bones, placing important parts of the fauna in MIS 3. The assemblage demonstrates that Ireland could support, or be reached by, a strikingly varied cold-stage fauna before the Last Glacial Maximum.

It would be misleading, though, to arrange every Castlepook species into one simultaneous scene. Cave deposits accumulate through many processes: carnivores drag in prey; animals die in cavities; water and sediment move bones; deposits collapse or are disturbed; and early excavators often removed material before modern stratigraphic recording existed. Individual dated bones can be highly informative, but the cave's collection spans episodes rather than a single day or century. The reasonable picture is of open-country habitats capable of sustaining grazing animals and predators at different points in the middle of the last glacial cycle. It is not proof that mammoth, hyaena, reindeer and every other recorded animal stood together in north Cork in 30,904 BCE.



## **A Human Trace, Not a Settlement**

One Castlepook reindeer femur has particular historical importance. It has been reported as bearing a mark interpreted as a cut made by a sharp stone tool, and the animal bone has been presented as approximately 33,000 radiocarbon years old. If the mark is correctly identified as butchery damage, it would be evidence that a person handled a reindeer in Ireland far earlier than the island's better-established terminal-Pleistocene human evidence. But the distinction between a promising trace and a demonstrated settlement is crucial. The specimen derives from an old cave collection, not an intact excavated camp floor, and no securely associated hearth, stone-tool assemblage, dwelling, human remains or repeatedly used processing area of comparable age has yet been established at Castlepook.

Accordingly, there is no responsible basis for describing an Irish tribe, leader, language, ritual practice or political order in this year. There are no known states, alliances, warfare, diplomacy, trade networks or institutions to narrate. Nor is there evidence for agriculture, livestock keeping, pottery, metalworking, permanent villages or monuments. If people did reach Ireland during this part of MIS 3, they were more likely small, highly mobile hunter-gatherer groups operating at the extreme north-western edge of Upper Palaeolithic Europe. That is an inference from wider human ecology and the possible cut-marked bone, not a fact directly demonstrated by an Irish settlement.

## **What Everyday Life Cannot Yet Reveal**

The environmental evidence does permit a restrained account of the practical demands of life. Animals and any human visitors would have faced exposed terrain, intense seasonality, limited tree cover and an environment in which shelter, food and movement were strongly conditioned by cold, wet ground and changing ice margins. Reindeer were well suited to open, cold landscapes; predators such as wolf and spotted hyaena indicate food webs with substantial prey, though their precise local relationships remain unknown. Freshwater pools and wetland plants at Derryvree show that even harsh landscapes possessed productive microhabitats. Beyond this, claims about clothing, family organisation, belief, artistic expression or exchange would be speculation.

The lasting significance of 30,904 BCE in Irish history is therefore geological and evidential rather than eventful. Derryvree's organic silts preserve a rare glimpse of ice-free tundra wetland between glacial advances. Castlepook's bones reveal that large mammals, carnivores and perhaps people reached an Ireland whose later ice cover would destroy much of the evidence. The records are fragmentary, locally specific and often difficult to date, but they replace the old image of an empty, uniformly frozen island with a more compelling one: a shifting cold-world frontier, intermittently habitable, in which water, mosses, sedges, herbivores and predators briefly left traces beneath the ice.

## Chapter 098 of 100

30903 BCE

BIRM-166 and the Fermanagh Pool<sup>[98]</sup>



**“30,903 BCE” is a useful modern label, not a recoverable Irish date. Nobody in Ice Age Ireland used a calendar from which an individual year could be recorded, and no archaeological deposit can be assigned responsibly to that precise point. In calendar terms the label falls roughly 32,850 years before AD 1950, within Marine Isotope Stage 3 (MIS 3), a long and climatically unstable part of the Late Pleistocene. The best evidence relevant to this moment is therefore regional, dated in ranges, and environmental rather than historical in the conventional sense. It illuminates cold landscapes, animals, water, vegetation and perhaps a fleeting human encounter; it cannot supply a named community, ruler, battle, treaty or settlement.**

The key Irish archive is Derryvree, near Maguiresbridge in County Fermanagh. Road works in 1969 cut through a drumlin and exposed organic freshwater silts and fine sands lying between tills. The sequence contained plant and insect remains and yielded the radiocarbon determination BIRM-166:  $30,500 \pm 1,100$  radiocarbon years BP. A modern calibration converts such a measurement into a broad span rather than a single year; published modelling places the relevant Derryvree interval broadly within about 36,900–31,700 calibrated years BP. Thus the modern label 30,903 BCE lies near the late edge of a possible dating range, not at a pinpointed event horizon.

### A Wetland Between Ice Advances

Derryvree is important because its organic layer proves that, at some point during this range, ground in south Fermanagh was not buried beneath glacier ice. Water collected in a shallow freshwater setting amid a cold, periglacial landscape. Later ice advances sealed that modest wetland beneath glacial deposits.

This is an unusually fortunate survival: most landscapes available to us now were repeatedly reshaped by ice, meltwater, frost and erosion. The road cutting exposed a brief geological archive of conditions that would otherwise have remained hidden inside the drumlin.

The evidence points to open, treeless or nearly treeless country, not to woodland. Pollen was poorly preserved, but plant macrofossils, mosses and insect remains indicate tundra-like vegetation and wet ground. Sedges, aquatic plants and bogbean (*Menyanthes trifoliata*) belonged to the local freshwater margin, while mountain-avens, dwarf willow, clubmosses and cold-tolerant mosses are consistent with sparse vegetation beyond it. Such finds do not permit a painted, metre-by-metre reconstruction of Fermanagh in one year. They do show that a small pool or marsh could support specialised plants despite severe cold, while the wider land had limited tree cover and a short growing season.

That distinction matters. The surviving Derryvree material records a locality and a span of deposition, not the whole island at once. Ireland's topography, coasts, rainfall and ice margins would have varied markedly from region to region. At this stage, changing ice and low sea level made the island's physical geography very different from that of today. Yet scholars remain cautious about exactly where ice lay across every Irish district at any particular moment before the Last Glacial Maximum. Firmer chronological evidence shows major expansion of the British–Irish Ice Sheet after this broad interval, with extensive Irish glaciation associated especially with the period after about 26,000 calibrated years BP.

## Cold Country, Living Animals

The Derryvree wetland has to be read beside Ireland's cave faunas, particularly those from Castlepook Cave near Doneraile in north Cork. The cave collections demonstrate that during parts of MIS 3 Ireland supported a richer large-mammal community than the island has known in recent millennia. Reindeer, woolly mammoth, giant deer, brown bear, wolf, Arctic fox, hare, lemmings and spotted hyaena are represented in Irish Pleistocene material. They should not, however, be turned into a single contemporary herd gathered at Castlepook or anywhere else. Cave deposits may combine bones accumulated over long periods through carnivore activity, natural death, water movement, disturbance and early excavation.

Even with that caution, the fauna gives the Fermanagh wetland a wider ecological setting. Reindeer and lemmings are strong indicators of cold, open habitats. Large grazers and browsers required seasonally available forage; wolves and hyaenas reveal a food web with substantial predators and scavengers. Mammoth remains evoke the broader north-west European mammoth-steppe world, but they do not prove that mammoths stood beside the Derryvree pool in the modern calendar year used here. The responsible conclusion is less dramatic but more secure: suitable phases of Late Pleistocene Ireland had connected ecological opportunities for cold-adapted mammals, whose ranges expanded and contracted with climate, ice and access to neighbouring lands.

These animals were not “Irish” in any modern national sense. Their populations moved through a changing north-west European landscape, and the sea crossings and land configurations that governed access were unlike those of the present. A lower global sea level enlarged continental shelves, but it does not justify an uncomplicated claim of a permanent land bridge, a fixed migration corridor or easy travel from Britain. Routes depended on local topography, ice, rivers, marine channels and season. Inferences about movement are therefore plausible ecological interpretations, not direct observations.

## The Human Question at Castlepook

The most arresting possibility for this period comes from Castlepook: a reindeer femur, from an older cave collection, reported as bearing a deep mark interpreted by zoologist Ruth Carden as stone-tool damage made during butchery. County Cork heritage material has presented the specimen as dating to around 31,000 BC. If the mark is confirmed as anthropogenic and contemporary with the animal's death, it would be evidence that one or more Upper Palaeolithic people handled a reindeer in Ireland tens of millennia earlier than the long-established evidence for post-glacial settlement.

Its importance is precisely why restraint is necessary. The dated bone is not an excavated village floor. It does not come with a securely associated hearth, stone-tool assemblage, shelter, burial, repeated butchered bone concentration or occupation sequence. A date on bone establishes an age range for the animal, not a calendar date for the incision. Nor can one modified object demonstrate a resident population, an annual migration route, family structure or continuous human presence. Recent reassessment has also shown that improved collagen treatment and ultrafiltration can substantially alter dates obtained from old Irish cave specimens, reinforcing the need to test claims rather than repeat them as settled fact.

If people did reach Ireland during an MIS 3 interval relevant to 30,903 BCE, they were most likely highly mobile hunter-gatherers rather than settlers in any later agricultural sense. A party capable of processing a large carcass would have needed cutting tools, practical knowledge of animal anatomy, co-operation and protection from cold. Those are reasonable inferences from Upper Palaeolithic lifeways elsewhere in Europe, but they remain inferences. Ireland has not yielded securely dated evidence here for houses, camps, clothing, ornament, art, ritual structures, graves, exchange networks or a sustained lithic industry. It would be wrong to populate the Fermanagh and Cork evidence with imagined clans, chiefs or ceremonies.

## No Politics, No Diplomacy

Accordingly, there is no political history for Ireland at this point. Archaeology provides no basis for discussing kingship, territories, formal diplomacy, warfare, law or institutions. Conflict may have existed among animals competing for prey and shelter, and any visiting humans would have faced dangerous predators and environmental risk, but that is not evidence for human warfare. Likewise, there is no evidence for religion or formal learning. The absence is meaningful: it identifies the boundary between what the archaeological record supports and what later historical habits tempt us to invent.

Everyday life is equally elusive. Derryvree documents a wetland ecosystem, not a household. Castlepook offers an important but presently isolated indication of possible carcass processing, not a menu, seasonal round or social biography. There is no direct evidence for cultivation, animal husbandry, pottery, metallurgy, built settlement or trade in Ireland. "Economy" can only be used in the minimal ecological sense: animals obtained food from a patchy cold landscape, while any people present may have relied on opportunistic hunting, scavenging or butchery. Exchange and long-distance social ties, well documented among some contemporary Upper Palaeolithic societies elsewhere, cannot yet be demonstrated on the island.

## What This Date Can Mean


The most historically valuable development around this projected year is therefore not a human event but an evidential window. Beneath a Fermanagh drumlin, BIRM-166 preserves the record of freshwater, mosses, sedges, insects and open cold-country vegetation during a pre-maximum glacial interval. In Cork, cave bones show that Ireland could sustain a varied Ice Age fauna, while one marked reindeer bone raises—without finally resolving—the prospect of a very early human visit. Together they overturn the older caricature of a uniformly empty, perpetually ice-covered Ireland before the final glacial retreat.

They do not reveal an inhabited country in the later historical sense. Around the modern label 30,903 BCE, Ireland's recoverable story is one of climatic volatility, local ice-free refuges or intervals, wetland persistence, mobile animals and profound uncertainty. Future excavation of undisturbed cave deposits, direct dating with modern methods, microscopic study of bone surfaces and further palaeoenvironmental cores may refine that picture. For now, the Fermanagh pool remains the clearest guide: a small, cold freshwater world, preserved between tills, whose evidence is more compelling because it tells us exactly how much we do—and do not—know.

# **Chapter 099 of 100**

## **30902 BCE**

### **Derryvree Before the Advance<sup>[99]</sup>**



**30,902 BCE is a modern calendar label imposed on a stretch of the Late Pleistocene for which Ireland has no annals, rulers, settlements, named peoples or dateable events. It must not be treated as a year in the historical sense. The closest responsible evidence comes from radiocarbon determinations, fossils and layered sediments, each representing intervals rather than a single season or day. In particular, the date falls within a calibrated range associated with a buried freshwater deposit at Derryvree, near Maguiresbridge in County Fermanagh. It is therefore possible to describe an Irish Ice Age landscape relevant to this point in time; it is not possible to recount what happened in Ireland in that numbered year.**

## **A Date Within a Range**

The archaeological setting is Marine Isotope Stage 3, a long and climatically unstable portion of the last Ice Age. Radiocarbon years are conventionally counted backwards from AD 1950, and they are not identical to calendar years because the proportion of carbon-14 in the atmosphere has varied through time. Modern calibration curves turn a radiocarbon measurement into one or more probability ranges, not an exact historical date. This distinction is especially important at an age of more than 30,000 years.

At Derryvree, roadworks in 1969 cut through a drumlin and exposed organic freshwater silts and fine sands lying between two thick tills: unsorted material deposited by glacial ice. The organic bed produced radiocarbon determination Birm-166, 30,500 radiocarbon years before present, with a substantial uncertainty. Later discussion has placed it broadly at about 36,900–31,700 calibrated years before present, approximately 34,950–29,750 BCE. Thus 30,902 BCE lies inside that broad calibrated span, but it cannot

be assigned to a particular layer, living creature or human action. The sequence instead establishes an order of events: glacial deposition, an ice-free freshwater interval at this locality, and renewed glacial deposition.

## **The Derryvree Wetland**

Derryvree is one of the most revealing Irish records for this period because it preserves life as well as ice. Plant remains and insects from the freshwater sediments indicate open tundra vegetation and a periglacial regime: ground and water affected by intense cold, repeated freezing and thawing, and long winters. The deposit has been interpreted as a muskeg-like wetland with pools, plant-rich water and surrounding mosses. Such a place should not be imagined as a pleasant modern bog. It was a cold, exposed, seasonally changing environment, with shallow water and wet ground surviving amid a generally treeless landscape.

The evidence supports local environmental reconstruction, not a complete map of Ireland. Yet it is important precisely because it shows that the island was not simply entombed beneath continuous ice throughout the period. At least in north-central Ireland, there was an interval in which freshwater organisms, wetland plants and insects could inhabit an ice-free terrain. Summer thaw, flowing or standing water, and short growing seasons made small ecological refuges possible. The upper till shows how precarious that opening was: ice later returned across the site and sealed the record beneath glacial sediment.

Open tundra does not mean lifelessness. Low vegetation would have included herbs, sedges, mosses and scattered dwarf shrubs suited to cold ground and short summers. There is no basis for depicting forest, farming or permanent village life. Wood would have been scarce locally, while exposure to wind and frost would have been severe. The rhythm of the year was likely governed by snow cover, meltwater, wet ground, the availability of graze and the movements of animals rather than by any calendar recognised by people.

## **An Island Approaching Greater Glaciation**

The Derryvree sequence also matters for the history of the Irish Ice Sheet. It demonstrates ice-free conditions in Fermanagh before the major build-up of the last British–Irish Ice Sheet. Syntheses of dating evidence suggest that much of Ireland’s later ice cover expanded from relatively limited conditions after about 34,000 years ago, ultimately reaching a far more extensive state during the Last Glacial Maximum, around 26,000–20,000 years ago. At 30,902 BCE, therefore, Ireland was not yet the uniformly ice-covered island often imagined in popular accounts of the Ice Age; nor was it secure from advancing ice.

This was regional change on a vast scale. Glacier ice, frozen ground, meltwater and shifting coastlines remodelled terrain, while later ice erosion destroyed or buried many older surfaces and archaeological traces. That destructive history is a major reason why the evidence for very early human activity in Ireland is so sparse. Drumlins, tills, striations and sediment-filled basins are not merely geological scenery: they are the damaged archive through which this period must be reconstructed.

## Castlepook's Animal Archive

The strongest faunal evidence relevant to this age comes from Castlepook Cave, also called Mammoth Cave, near Doneraile in north County Cork. Excavated in the early twentieth century, it yielded a remarkable assemblage including woolly mammoth, reindeer, giant deer, brown bear, wolf, Arctic fox, lemmings and spotted hyena. The National Museum of Ireland describes Castlepook as the country's most important site for mammal remains of the last cold stage. Radiocarbon work indicates that hyenas and other mammals reached Ireland from Britain during an interval broadly around 45,000–30,000 years ago.

That list should not be turned into a single frozen scene. Cave deposits accumulated over long periods, and bones may have entered through carnivore transport, natural death, water movement and excavation practices that did not meet modern recording standards. A mammoth bone and a lemming remain may be broadly comparable in age without proving that the animals met at the cave entrance. Nonetheless, the assemblage securely demonstrates that Ireland intermittently supported a cold-adapted, open-country fauna very different from the later wooded island.

Spotted hyenas are particularly revealing. Their presence implies not an imagined African climate but the existence of the Eurasian spotted hyena, a powerful carnivore able to use caves as dens and bone accumulators. Reindeer, mammoth and giant deer point to grazing landscapes; wolves and foxes to predators and scavengers moving through the same food webs. Caves could preserve the remains of this world, but they were not necessarily places where people lived. A bone assemblage is an ecological record first, and only sometimes an archaeological one.

## The Reindeer Femur Question

Castlepook has acquired special importance because a reindeer femur bears a deep linear mark interpreted by palaeozoologist Ruth Carden as damage made by a sharp stone tool while the bone was fresh. County Cork heritage material presents the object as Palaeolithic and about 31,000 BC. If the mark is confirmed as human butchery, it would be evidence that a person processed a reindeer in Ireland far earlier than the better-established terminal-Pleistocene human evidence from Alice and Gwendoline Cave in County Clare.

That conclusion remains appropriately cautious. The date of a bone establishes when the animal died within a range; it does not itself date the incision, identify its maker, demonstrate a hunt, or show that butchery happened inside Castlepook Cave. No associated stone tools, hearth, dwelling, human remains or repeated occupation surface has yet been identified for this early claim. Carnivores may have taken discarded bone into the cave after people handled a carcass elsewhere. The femur is consequently best treated as possible evidence of a brief human encounter with Ireland, not proof of a settled Palaeolithic population.

## Society Beyond the Evidence

There is no evidence for political affairs, diplomacy, organised warfare, religious practice, trade routes, language, artistic traditions or systems of learning in Ireland at this date. Nor can social rank, family structure, seasonal camps or beliefs be recovered from Derryvree's silts or Castlepook's bones. It would be misleading to supply them by analogy with later Irish communities or with better-known Upper Palaeolithic societies elsewhere in Europe.



If people did visit, the practical demands would have been stark: obtaining food from unpredictable animal resources, finding shelter and fuel, making and maintaining stone tools, and travelling through a landscape in which weather and ice margins could change quickly. These are reasonable ecological inferences, not direct observations of Irish daily life. A visitor may have been part of a highly mobile group operating across north-west Europe; equally, the present evidence cannot establish the route, number, duration or frequency of visits.

## **No Historical Ireland Yet**

The most meaningful story for 30,902 BCE is therefore neither one of kingdoms nor of an empty, featureless wilderness. Ireland was an environmentally varied, cold-stage landscape caught between episodes of glaciation. Derrynvree records freshwater life and treeless tundra in Fermanagh; Castlepook preserves the bones of animals that crossed or recolonised parts of the island during favourable intervals; and one marked reindeer femur raises, without finally resolving, the possibility of human activity. The evidence is fragmentary, but it is powerful enough to show an Ireland with water, vegetation, grazers, predators and perhaps transient people—an island on the threshold of a much greater advance of ice.

# Chapter 100 of 100

## 30901 BCE

### Hyenahall's Faunal Frontier<sup>[100]</sup>



**There is no recoverable event for Ireland in 30,901 BCE, no contemporary Irish calendar and no evidence that can identify a particular season, person or action in that numbered year. The label is a modern conversion, roughly 32,850 years before AD 1950, rather than a date known to anyone then living. The responsible view is therefore framed by radiocarbon determinations, calibrated ranges and geological sequences. Around this point lies the later part of Marine Isotope Stage 3, a fluctuating cold interval before the fullest expansion of the last British–Irish Ice Sheet.**

Ireland at this time was neither simply an ice-covered blank nor a familiar green island. It was a changing northern landscape in which glaciers, exposed ground, wetland basins, rivers, limestone caves and an altered coastline existed at different places and times. Later ice growth, erosion and rising seas have removed or buried much of its evidence. What survives is especially valuable, but it cannot support a conventional annual history of rulers, battles or settled communities.

## **A Date Within Broad Ranges**

Calendar precision is not available at this depth of time. Radiocarbon dates measure the decay of carbon-14, not BCE years directly, and must be calibrated against independently dated records of past atmospheric carbon. At ages above 30,000 years, the resulting calendar ranges can be wide. The date 30,901 BCE should consequently be treated as a point inside a broad chronological horizon, not as a moment that can be isolated archaeologically.

The closest important Irish environmental sequence is at Derryvree, near Maguiresbridge in County Fermanagh. Road works exposed freshwater and organic deposits sealed between two tills: unsorted sediments laid down by glacier ice. The lower till records glacial conditions, the organic silts and sands indicate an intervening ice-free local environment, and the upper till shows that ice later returned across

the site. A radiocarbon determination from the organic material has been placed by later calibration in a broad range of approximately 36,900–31,700 calibrated years before present. That range overlaps the world represented by 30,901 BCE, but does not date every layer, plant or animal at Derryvree to this exact year.

This distinction is fundamental. Derryvree is a stratified record of environmental change over a substantial interval, not a weather report for all Ireland and certainly not a diary. Its importance lies in demonstrating that, before the Last Glacial Maximum, at least one part of Fermanagh could support freshwater conditions between episodes of glaciation.

## **Derryvree's Cold Wetland**

The plant remains from the Derryvree sediments portray open, treeless and cold-adapted country. Mosses, sedges, dwarf willow, mountain avens, lesser clubmoss, bogbean and aquatic plants indicate shallow water, wet ground and tundra-like vegetation rather than woodland. The term 'muskeg' has often been used for this kind of mossy, waterlogged terrain. Such a place may have held pools, sedge margins and poorly drained ground amid frost-shattered mineral soils.

This was not necessarily a lifeless wilderness. Wetlands can be productive in cold landscapes, offering water, vegetation and sheltering topography. Yet the evidence allows only an environmental reconstruction. It cannot tell us how extensive the wetland was in a particular decade, whether it was frozen for much of each year, or how far similar plant communities reached beyond the basin. Pollen, plant macrofossils and insects preserve ecological traces, not a complete map.

For the wider island, glacial history remains regionally complex. Modern reconstructions show that the British–Irish Ice Sheet grew asynchronously: different sectors advanced, thickened and later retreated at different rates. Around 31,000 years before present, the ice sheet was building towards a maximum volume reached much later, around 23,000 years ago. It would be wrong to project the later maximum over every part of Ireland in 30,901 BCE. Equally, an ice-free wetland in Fermanagh cannot prove that all districts were accessible, vegetated or hospitable.

## **Castlepook's Bone Archive**

County Cork provides the other major line of evidence. Castlepook Cave, near Doneraile, is a limestone maze cave whose chambers received animal remains over a very long period. Excavations begun by Richard J. Ussher and colleagues in the early twentieth century recovered more than 2,000 bones. Geological Survey Ireland describes it as the country's richest known vertebrate archive for the period leading towards the Last Glacial Maximum.

The fauna is striking: woolly mammoth, reindeer, giant deer, brown bear and spotted hyaena are among the animals represented. Their presence establishes that Ireland, during portions of the Middle and Late Pleistocene, was connected ecologically to the cold-stage animal worlds of north-west Europe. Large herbivores could exploit open vegetation, while predators and scavengers formed part of the food web. Spotted hyaenas matter particularly because caves can be dens and feeding places: carnivores may carry bones inside, gnaw them, fragment them and mix the remains of animals killed or found elsewhere.

But Castlepook must not be imagined as one simultaneous scene. Individual specimens have yielded dates spanning many thousands of years, while water disturbance, animal activity and antiquarian excavation complicated the original contexts. A mammoth bone and a reindeer bone from the same cave

may not represent the same generation, season or even climatic phase. The cave provides a long archive of repeated deposition, rather than a securely excavated settlement floor dating to 30,901 BCE.

Re-dating has transformed the significance of this archive. Improved bone preparation and accelerator radiocarbon methods showed that several earlier determinations were too young, placing elements of Castlepook's fauna more firmly within Marine Isotope Stage 3. The revisions indicate that some cold-stage species were present in southern Ireland well before the Last Glacial Maximum and that populations such as spotted hyaena and giant deer may have disappeared locally before its height. This is a powerful reminder that scientific chronology is provisional: old collections can yield new history when methods improve.

## **A Possible Human Trace**

A reindeer femur from Castlepook has been interpreted as bearing marks made during carcass processing with a stone tool and has been publicised as evidence of human activity in Ireland around 33,000 years ago. If that interpretation remains secure, it pushes the island's known human story far earlier than the later Mesolithic settlement record. It is directly relevant to the broad period surrounding 30,901 BCE.

It does not, however, prove a resident Irish population in that numbered year. The bone is not a house, hearth, campsite, tool-kit or burial. Nor does it demonstrate continuous occupation, a named cultural group, or a route followed by a particular hunting party. Its cave context was disturbed, and a single modified bone can represent a brief encounter rather than a durable settlement. The most cautious conclusion is that one or more Upper Palaeolithic people may have reached Ireland during this wider cold-stage interval and processed a reindeer carcass there.

That possibility is historically important but socially limited. There is no sound basis for describing clans, chiefs, territorial polities, diplomacy or warfare in Ireland at this date. There is likewise no evidence for agriculture, domestic animals, permanent villages, long-distance Irish trade, writing or formal institutions. If people were present, they would have depended on mobile foraging, knowledge of seasonal animals and flexible movement through a hazardous landscape. Such statements are informed comparison with Upper Palaeolithic lifeways elsewhere, not direct proof of a Castlepook community.

## **Coasts, Routes and Risk**

Sea level was lower than today because vast quantities of water were stored in continental ice sheets. Ireland's coastline was therefore different, with areas of the present continental shelf exposed or transformed. Yet lower sea level should not be turned into a simple land-bridge story. The Irish Sea basin, local ice margins, rivers, lakes and changing coastlines created obstacles as well as possible routes. Whether people or animals crossed by exposed land, ice, short sea passages or combinations of these depended on changing conditions that cannot be reconstructed year by year.

For animals, movement into Ireland need not mean permanent abundance. Populations could arrive during favourable episodes and vanish as vegetation, predation, snow cover or ice barriers changed. The Castlepook evidence is best read as proof of intermittent ecological connectivity. It shows that Ireland was not wholly isolated from the Pleistocene fauna of Britain and continental Europe, while also revealing how fragile that connection could be.

## Silence on Belief and Learning

No securely dated Irish cave art, portable art, ritual structure or symbolic object belongs to this horizon. Religion, stories, languages, kinship rules and learning cannot responsibly be reconstructed from plant beds and cave bones. It is tempting to infer a rich spiritual life from the dramatic animals of the Ice Age, but the Irish evidence does not permit it. Nor can the later names given to Castlepook's chambers, such as Hyenahall and Elephant Hall, be projected backwards: they are products of modern exploration.

The great development represented by 30,901 BCE is thus environmental and evidential. Ireland was entering a period of intensifying glacial pressure, while parts of its landscape still contained wet ground, open vegetation and large mammals. Derryvree preserves the ecological setting; Castlepook preserves the animal record and a possible human action. Together they replace the false certainty of a year-by-year narrative with a more compelling picture: a difficult, mutable island at the edge of Ice Age worlds, whose earliest human traces remain rare, contested and scientifically alive.





## About the Author

Gerard J. Hannan is an Irish author, historian, journalist and broadcaster with a lifelong interest in the people, places and events that have shaped Ireland's past. Based in Limerick, he spent more than twenty-five years working in journalism and broadcasting, developing a particular interest in local history, social change and the preservation of historical memory.

He is the founder and curator of Emerald Archives, an expanding digital historical collection dedicated to preserving, restoring and sharing material connected with Ireland's social, cultural and political history. Through the archive and its associated publishing projects, he aims to make historical information accessible to both general readers and serious researchers.

Hannan holds a BA in History and Media, a Master of Business Studies in International Entrepreneurship Management, and an MA in Teaching English to Speakers of Other Languages. His academic background complements decades of practical experience in writing, research, broadcasting and historical documentation.

He is also the author of several books and long-form historical projects exploring Irish life, identity and memory. As creator of Emerald Gazette, Hannan continues to develop a growing chronological collection designed to bring Ireland's extraordinary historical record to a broad international readership.

## Endnotes

1. Chapter 001 — Castlepook's Uncertain Cut (31000 BCE). Sources: References 15, 38, 83, 94, 115, 129, 141, 152, 204, 213, 216–217, 226, 240, 254, 328, 346, 358, 364, 396.
2. Chapter 002 — Derryvree's Sedgewater Interval (30999 BCE). Sources: References 2, 36, 39, 83–84, 114, 116, 118, 129, 141, 213–214, 226, 233, 237, 240, 254, 270, 359, 380, 396.
3. Chapter 003 — Derryvree's Frostwater Basin (30998 BCE). Sources: References 16, 33, 38, 77, 98, 118, 129, 141, 159, 162, 164, 226, 229, 240, 245, 263, 316, 359, 365, 373–374, 380.
4. Chapter 004 — Derryvree's Buried Bogbean (30997 BCE). Sources: References 15, 38, 83, 95, 129, 141, 165, 189, 213, 227, 244, 250, 255, 325, 328, 345–346, 360, 380, 388.
5. Chapter 005 — Derryvree's Water-Milfoil (30996 BCE). Sources: References 17, 39, 52, 77, 89, 130, 141, 165, 176, 213, 215, 221, 229, 233, 240, 308, 310, 346, 361, 380, 397.
6. Chapter 006 — Mosses Beneath Fermanagh (30995 BCE). Sources: References 17, 36, 40, 59–60, 83, 86, 130–131, 156, 182, 213, 217, 229, 240, 256, 308, 311, 314, 347, 380, 384.
7. Chapter 007 — Derryvree's Cold Fen (30994 BCE). Sources: References 2, 38, 51, 89, 91, 108, 115, 118, 132, 141, 156, 183, 221, 226, 229, 240, 288, 315, 358, 374, 380, 397.
8. Chapter 008 — Castlepook's Mammoth-Steppe Archive (30993 BCE). Sources: References 2, 15, 39, 57, 59, 62, 69, 85, 101, 117, 141, 169, 199, 213, 226, 232, 252, 304, 310, 342, 361, 374–375, 380, 391.
9. Chapter 009 — BIRM-166 and the Fermanagh Thaw (30992 BCE). Sources: References 15, 38, 90–92, 102, 127, 129, 141, 155, 159, 184, 226, 239–240, 275–276, 331, 346, 354, 380, 396.
10. Chapter 010 — Cork's MIS 3 Fauna (30991 BCE). Sources: References 20, 22, 38, 44, 77, 114, 122, 141, 173, 184, 188, 197, 226, 234, 237, 246, 278, 280, 336, 339, 346, 358, 374, 392.
11. Chapter 011 — Doneraile's Reindeer and Reedbeds (30990 BCE). Sources: References 2, 60, 62, 77, 87–88, 108, 114, 119, 133, 141, 165, 205, 226, 229, 240, 311, 314, 342, 358, 361, 380, 397.
12. Chapter 012 — Awbeg Valley Reindeer Country (30989 BCE). Sources: References 2, 17, 36, 39, 61, 115, 129, 141, 169, 226, 230, 240, 252, 297, 325, 333, 358, 369, 384, 397.
13. Chapter 013 — Hyaena Hall and Derryvree (30988 BCE). Sources: References 2, 17, 40, 60, 134, 141, 147, 199, 229, 240, 250, 252, 264, 271, 308, 311, 345, 358, 384, 397.
14. Chapter 014 — Castlepook's Mammoth Bones (30987 BCE). Sources: References 2, 36, 83, 132, 169, 199, 205, 213, 226, 229, 233, 240, 259, 297, 301, 309, 329, 358, 374, 380, 384, 392, 397.
15. Chapter 015 — Ireland's MIS Three Tundra (30986 BCE). Sources: References 15, 38, 52, 73, 116, 141, 152, 169, 185, 221, 226, 231, 257, 272, 293, 346, 358, 362, 376, 380, 396, 398.
16. Chapter 016 — Ussher's Reindeer Femur (30985 BCE). Sources: References 3, 36, 39, 78, 109, 116, 120, 141, 177, 184, 203, 222, 226, 234, 240, 277, 346, 361, 380, 403.
17. Chapter 017 — Maguirebridge's Tundra Reedbed (30984 BCE). Sources: References 15, 38, 75, 78, 102, 120, 129, 194, 206, 226, 234, 249, 278, 286, 328, 361, 380, 386, 393, 396.
18. Chapter 018 — The Doneraile Femur Debate (30983 BCE). Sources: References 17, 38, 60, 114, 117, 129–130, 160, 169, 213, 226, 237, 252, 263, 304, 325, 361, 380, 384, 399.
19. Chapter 019 — Fermanagh's Glacial Reedlands (30982 BCE). Sources: References 2, 15, 17, 28, 36, 38, 60, 114, 120, 129, 135, 141, 229, 237, 261, 314, 325, 342, 359, 380.
20. Chapter 020 — Ballyhoura's Mammoth-Steppe Passage (30981 BCE). Sources: References 2, 15, 38, 129, 141, 144, 156, 161, 166, 177, 208, 226, 286, 314, 359, 362, 374, 376, 386, 396.



- 21.** Chapter 021 — The Maguiresbridge Drumlin Archive (30980 BCE). Sources: References 2, 15, 38, 77, 83, 92, 98, 129, 141, 213, 226, 232, 234, 245, 250, 252, 286, 328, 346, 361, 366, 380, 393, 396.
- 22.** Chapter 022 — Castlepook Reindeer Mark (30979 BCE). Sources: References 2, 9, 13, 26, 36, 39, 79, 86, 121, 130, 141, 143, 183–184, 226, 245, 257, 287, 357, 359, 374, 385, 397.
- 23.** Chapter 023 — Derryvree’s Sedge Pools (30978 BCE). Sources: References 2, 13, 39, 52, 89, 134, 169, 183, 205, 215, 226, 252, 263, 305, 308, 314, 347, 361, 371, 380, 394.
- 24.** Chapter 024 — Dwarf Willow Below Maguiresbridge (30977 BCE). Sources: References 39, 52, 59, 63, 112, 123, 133, 143, 152, 162, 169, 175, 205, 213, 226, 230, 247, 256, 263, 309, 314, 358, 367, 374, 380.
- 25.** Chapter 025 — Derryvree’s Muskeg Witness (30976 BCE). Sources: References 2, 11, 15, 37–38, 52, 60, 80, 96, 129, 141, 161, 184, 191, 206, 226, 259, 272, 289, 305, 308, 314, 346, 359, 380.
- 26.** Chapter 026 — Lesser Clubmoss at Derryvree (30975 BCE). Sources: References 2, 15, 36, 38, 60–61, 81, 108, 113, 118, 141, 177, 226, 230, 240, 305, 324–325, 346, 359, 383, 396.
- 27.** Chapter 027 — Derryvree’s Sealed Waterline (30974 BCE). Sources: References 13, 15, 38, 59, 83, 120, 129, 141, 165, 213, 215, 217, 226, 234, 240, 314, 346, 358, 364, 374, 386, 396.
- 28.** Chapter 028 — Hyenahall’s Reindeer Femur (30973 BCE). Sources: References 2, 15, 39, 59–60, 83, 101, 120, 141, 169, 205, 213, 217, 226, 230, 240, 250, 308, 347, 361, 384, 397.
- 29.** Chapter 029 — Derryvree’s Buried Tundra Pool (30972 BCE). Sources: References 15, 60, 76–77, 89, 96, 129, 168, 174, 176, 215, 219, 233, 240, 247, 309, 344–345, 348, 380, 392, 396.
- 30.** Chapter 030 — Castlepook’s Contested Reindeer (30971 BCE). Sources: References 2, 29, 36, 39, 63, 77, 99, 141, 147, 161, 229, 240, 252, 285, 309, 314, 347, 358, 380, 385, 397, 404.
- 31.** Chapter 031 — Derryvree’s Trifoliate Wetland (30970 BCE). Sources: References 2, 17, 77, 117, 129, 163, 166, 199, 209, 226, 230, 240, 247, 252, 257, 293, 332, 346, 361, 380, 384, 392.
- 32.** Chapter 032 — BIRM-166 Between Glaciers (30969 BCE). Sources: References 2, 38, 66, 129, 141, 146, 157, 159, 184, 226, 235, 287, 346, 359, 363, 366, 376, 380, 386, 392.
- 33.** Chapter 033 — The Derryvree Freshwater Bed (30968 BCE). Sources: References 15, 38, 59–60, 70, 83, 113, 129, 199, 202, 213, 217, 226, 229–230, 240, 272, 287, 346, 359, 377, 396.
- 34.** Chapter 034 — Mammoth Cave’s Cold Fauna (30967 BCE). Sources: References 2, 17, 29, 39, 60, 97, 114, 128, 141, 152, 161, 205, 226, 230, 240, 264, 333, 338, 349, 358, 374, 380, 385, 395.
- 35.** Chapter 035 — Maguirebridge’s Frost Garden (30966 BCE). Sources: References 2, 39, 61, 64, 70, 83, 91, 116, 129, 141, 199, 206, 213, 226, 230, 240, 325, 346, 359, 364, 374, 396.
- 36.** Chapter 036 — BIRM-166’s Bogbean Seed (30965 BCE). Sources: References 2, 15, 38, 81, 89, 92, 113, 141, 169, 215, 226, 230, 240, 252, 287, 328, 346, 361, 380, 396.
- 37.** Chapter 037 — Castlepook’s Fossil Corridor (30964 BCE). Sources: References 2, 17, 60–61, 73, 100, 141, 152, 165, 193, 199, 226, 251–252, 259, 309, 314, 325, 350, 358, 378, 380.
- 38.** Chapter 038 — The Castlepook Cut Mark (30963 BCE). Sources: References 32, 52, 77, 115, 117, 129, 136, 141, 182, 226, 233, 237, 240, 250, 291, 314, 346, 358, 361, 374, 380, 397.
- 39.** Chapter 039 — Derryvree’s Moss Assemblage (30962 BCE). Sources: References 2, 17, 36, 60, 76, 93, 95, 97, 141, 149, 199, 213, 217, 228, 230, 240, 252, 268, 288, 306, 308, 311, 314, 330, 351, 358, 380.
- 40.** Chapter 040 — Maguirebridge’s Frostwater Basin (30961 BCE). Sources: References 2, 11, 39, 57, 63, 90, 116, 120, 133–134, 141, 152, 161, 173, 175, 185, 226, 257, 280, 310, 314, 347, 361, 397.
- 41.** Chapter 041 — Dryas Beneath the Drumlin (30960 BCE). Sources: References 2, 15, 38, 59, 79, 83, 90, 116, 120, 129, 141, 213, 217, 226, 240, 243, 250, 346, 359, 374.

- 42.** Chapter 042 — Maguirebridge Fresh-Water Series (30959 BCE). Sources: References 82–83, 89, 129, 134, 141, 154–155, 161, 165, 169, 178, 199, 213, 226, 298, 323, 346, 359, 362, 376, 380, 396.
- 43.** Chapter 043 — BIRM-166's Arctic Marsh (30958 BCE). Sources: References 17, 39, 70, 81, 83, 88–89, 91, 141, 152, 213, 226, 240, 291, 307, 347, 361, 372, 380, 392.
- 44.** Chapter 044 — BIRM-166's Tundra Horizon (30957 BCE). Sources: References 15, 38, 59–60, 115–116, 134, 141, 150, 152, 155, 226, 240, 247, 308, 320, 345–346, 359, 376, 380, 386, 396.
- 45.** Chapter 045 — Derryvree's Frozen Ledger (30956 BCE). Sources: References 2, 17, 38, 42, 52, 90, 120, 129, 215, 226, 230, 311, 333, 342, 346, 359, 363, 376, 380, 386.
- 46.** Chapter 046 — Castlepook's Two Thousand Bones (30955 BCE). Sources: References 40, 60, 78, 85, 126, 141, 172, 199, 206, 220, 223, 226, 240, 279, 287, 311, 359, 374, 383–384.
- 47.** Chapter 047 — The Derryvree Fossil Flora (30954 BCE). Sources: References 2, 13, 15, 36, 38, 67, 83, 89, 129, 141, 169, 213, 226, 229, 240, 265, 295, 314, 328, 346, 359, 365, 380, 396.
- 48.** Chapter 048 — Greenland Stadial Five (30953 BCE). Sources: References 2, 17, 36, 39, 43, 99, 133, 146, 169, 195, 226, 253, 272, 294, 310, 314, 358, 363, 378, 380.
- 49.** Chapter 049 — Derryvree's Silted Basin (30952 BCE). Sources: References 2, 17, 39, 92, 114, 116, 118, 136, 141, 155, 165, 175, 215, 221, 226, 229–230, 247, 291, 297, 356, 361, 380, 382.
- 50.** Chapter 050 — Birm-166 Freshwater Find (30951 BCE). Sources: References 2, 15, 36–38, 74, 86, 129, 152, 157, 159, 206, 226, 240, 247, 312, 346, 359, 362, 376, 386.
- 51.** Chapter 051 — Derryvree's Coldwater Silt (30950 BCE). Sources: References 2, 6, 17, 38, 90, 116, 118, 120, 140–141, 184, 194, 226, 240, 250, 338, 341, 346, 359, 364, 380, 386.
- 52.** Chapter 052 — Mosses, Tills and Reindeer (30949 BCE). Sources: References 7, 15, 38, 52, 78, 102, 129, 141, 161, 169, 206, 215, 226, 240, 247, 256, 292, 359, 386, 396.
- 53.** Chapter 053 — Castlepook Reindeer Horizon (30948 BCE). Sources: References 38, 42, 49, 60, 65, 111, 165, 207, 226, 230, 240, 252, 259, 282, 313–314, 346, 359, 383, 386.
- 54.** Chapter 054 — Maguiresbridge Under Permafrost (30947 BCE). Sources: References 2, 15, 38, 59, 73, 81, 83, 103, 113, 116, 129, 141, 199, 213, 226, 240, 259, 314, 359, 378, 380.
- 55.** Chapter 055 — Maguirebridge's Fossil Bogbean (30946 BCE). Sources: References 15, 38, 117, 129, 155, 169, 199, 226, 230, 240, 247, 249, 293, 302, 308, 361, 380, 386, 392, 396.
- 56.** Chapter 056 — Fermanagh Pools, Cork Hyenas (30945 BCE). Sources: References 2, 15, 36, 90, 120, 129, 161, 165, 169, 199, 205, 229, 247, 286, 309, 346, 358, 380, 386, 396.
- 57.** Chapter 057 — Castlepook's Deep Bone Archive (30944 BCE). Sources: References 2, 17, 36, 39, 48, 60, 117, 129, 165, 169, 226, 240, 272, 308, 314, 326, 347, 361, 380, 397.
- 58.** Chapter 058 — Derryvree's Ice-Free Interval (30943 BCE). Sources: References 15, 38, 58, 77, 89, 169, 180, 206, 221, 226, 236, 240, 247, 262, 286, 314, 328, 335, 359, 368, 374, 386.
- 59.** Chapter 059 — Derryvree's Permafrost Wetland (30942 BCE). Sources: References 2, 15, 62, 92, 129, 141, 152, 176, 226, 229, 240, 252, 288, 306, 323, 328, 345–346, 358, 380.
- 60.** Chapter 060 — BIRM-166's Sedgewater (30941 BCE). Sources: References 15, 38, 54, 92, 129, 141, 152, 154, 165, 169, 186, 201, 213, 226, 234, 237, 262, 303, 314, 321, 328, 346, 374, 380, 386.
- 61.** Chapter 061 — BIRM-166's Cold-Stage Silts (30940 BCE). Sources: References 2, 15, 63, 91, 107, 129, 165, 170, 190, 217, 264, 272, 284, 304, 306, 346, 356, 358, 361, 380, 384, 396.
- 62.** Chapter 062 — Derryvree's Intertill Wetland (30939 BCE). Sources: References 2, 7, 18, 59, 78, 89, 116, 120, 130, 141, 170, 177, 187, 217, 229, 234, 240, 309, 314, 330, 346, 359, 386, 392.

- 63.** Chapter 063 — Derryvree's Menyanthes Bed (30938 BCE). Sources: References 15, 31, 38, 62, 78, 91–92, 141, 152, 161, 175, 226, 238, 257, 273, 276, 286, 308, 330, 332, 346, 359, 396.
- 64.** Chapter 064 — The Derryvree Bogbean Seed (30937 BCE). Sources: References 2, 17, 83, 86, 104, 130, 141, 169, 213, 220, 240, 258–259, 314, 317, 326, 343, 346, 361, 380.
- 65.** Chapter 065 — BIRM-166's Periglacial Ledger (30936 BCE). Sources: References 2, 17, 91, 105, 115, 132, 141, 165, 169, 226, 240, 247, 306, 314, 347, 361, 363, 374, 378, 380, 384, 389.
- 66.** Chapter 066 — The Incised Castlepook Femur (30935 BCE). Sources: References 15, 38, 83, 102, 117, 129, 141, 152, 165, 169, 200, 206, 213, 221, 226, 253, 257, 309, 314, 325, 358, 380, 392, 396.
- 67.** Chapter 067 — Castlepook's Unfound Hearth (30934 BCE). Sources: References 15, 36, 39, 55, 116, 129, 141, 158, 165, 184, 206, 226, 230, 240–241, 314, 334, 361, 374, 384, 392, 396.
- 68.** Chapter 068 — Derryvree's Winter Pond (30933 BCE). Sources: References 2, 4, 15, 39, 47, 63, 77, 83, 91, 141, 185, 213, 221, 229, 233, 240, 346, 371, 375, 397.
- 69.** Chapter 069 — Cave Earth at Castlepook (30932 BCE). Sources: References 25, 39, 53, 119–120, 133, 141, 152, 165, 169, 221, 226, 240, 314, 348, 361, 374, 387, 397, 401.
- 70.** Chapter 070 — Maguirebridge's Winter Waters (30931 BCE). Sources: References 2, 39, 83, 89, 115, 131, 141, 169, 213, 226, 240, 299, 304, 351–352, 361, 383–384, 392, 397.
- 71.** Chapter 071 — Castlepook Hyaena Toothmarks (30930 BCE). Sources: References 7, 11, 30, 36, 40, 115, 141, 152, 221, 226, 240, 266, 318, 345, 348, 358, 369, 375, 380, 402.
- 72.** Chapter 072 — Derryvree's Silted Fen (30929 BCE). Sources: References 15, 34, 38, 45, 75, 113, 129, 141, 152, 165, 185, 221, 248, 346, 358, 374, 380, 386, 396, 400.
- 73.** Chapter 073 — Doneraile's Reindeer Record (30928 BCE). Sources: References 2, 15, 36, 38, 42, 78, 102, 141–142, 169, 226, 250, 304, 309, 332, 361, 363, 376, 380, 396.
- 74.** Chapter 074 — Derryvree's Drumlin Wetland (30927 BCE). Sources: References 6, 15, 21, 23, 38, 78, 89, 122, 129, 148, 184, 198, 240, 245, 337, 340, 346, 359, 364, 380.
- 75.** Chapter 075 — Derryvree's Drumlin Waters (30926 BCE). Sources: References 15, 38, 59–60, 71, 85, 103, 113, 116, 169, 184, 188, 213, 224, 226, 247, 264, 290, 333, 346, 359, 396.
- 76.** Chapter 076 — BIRM-166's Tundra Waters (30925 BCE). Sources: References 8, 15, 38, 73, 92, 108, 113, 129, 141, 221, 226, 230, 234, 245, 252, 260, 333, 359, 378, 380, 386, 392.
- 77.** Chapter 077 — The Derryvree Drumlin Window (30924 BCE). Sources: References 2, 15, 38, 60, 83, 116, 120, 129, 141, 161, 169, 226, 240–241, 314, 346, 361, 375–376, 380, 386, 398.
- 78.** Chapter 078 — Doneraile's Possible Palaeolithic (30923 BCE). Sources: References 2, 38, 43, 62, 83, 129, 141, 176, 206, 226, 240, 248, 250, 288, 305, 314, 346, 359, 364, 374, 380, 386.
- 79.** Chapter 079 — The Fermanagh Silt Clock (30922 BCE). Sources: References 2, 15, 17, 60, 92, 95, 102, 141, 193, 226, 262, 265, 288, 309, 335, 346, 359, 380, 386, 396.
- 80.** Chapter 080 — The Maguiresbridge Freshwater Archive (30921 BCE). Sources: References 2, 15, 60, 63, 68, 91–92, 129, 141, 165, 226, 229, 240, 311, 314, 326, 346, 359, 380, 386, 396.
- 81.** Chapter 081 — Awbeg Valley Faunal Threshold (30920 BCE). Sources: References 1–2, 17, 24, 40, 60–61, 114, 129, 137, 141, 165, 183, 210, 226, 229, 237, 272, 314, 361, 371, 380, 384, 394, 397.
- 82.** Chapter 082 — Derryvree's Tundra Drumlin (30919 BCE). Sources: References 9, 12, 15, 38, 60, 102, 130, 153, 167, 215, 226, 240, 242, 272, 296, 314, 338, 346, 359, 380, 386, 392.
- 83.** Chapter 083 — Derryvree's Mossy Fen (30918 BCE). Sources: References 2, 15, 36, 38, 59, 83, 95, 141, 213, 217, 226, 233, 240, 272, 304, 314, 346, 359, 380, 386.

- 84.** Chapter 084 — Castlepook's Marked Hindleg (30917 BCE). Sources: References 14, 60, 77, 89, 113, 130–131, 141, 183, 196, 225–226, 234, 237, 346, 359, 362, 392, 396, 406.
- 85.** Chapter 085 — The Castlepook Bone Debate (30916 BCE). Sources: References 15, 38, 60, 110, 120, 129, 141, 151, 153, 170, 194, 196, 221, 226–227, 257, 272, 308, 346, 361, 374, 380, 396.
- 86.** Chapter 086 — Bogbean Between Fermanagh Tills (30915 BCE). Sources: References 15, 38, 60, 83, 89, 129, 141, 151, 171, 213, 226, 241, 247, 250, 276, 308, 319, 346, 361, 396.
- 87.** Chapter 087 — Maguirebridge's Three-Leaved Pool (30914 BCE). Sources: References 2, 5, 15, 35, 39, 114, 141, 165, 226, 240, 283, 290–291, 308, 344, 352, 359, 380, 397, 400.
- 88.** Chapter 088 — Derryvree's Sealed Tundra (30913 BCE). Sources: References 2, 10, 19, 38, 92, 116, 138, 147, 199, 211, 226, 230, 257, 269, 276, 306, 314, 350, 353, 359, 374, 380.
- 89.** Chapter 089 — BIRM-166's Thawline (30912 BCE). Sources: References 38, 51–52, 114, 116, 118, 123, 129, 172, 218, 229, 234, 254, 281, 355, 375, 380, 386, 390, 396.
- 90.** Chapter 090 — BIRM-166's Marshland (30911 BCE). Sources: References 15, 38, 60, 90, 116, 129, 141, 147, 159–160, 179, 199, 226, 240, 250, 272, 293, 314, 346, 359, 370, 396.
- 91.** Chapter 091 — Maguirebridge's Reedbed (30910 BCE). Sources: References 2, 36, 38, 60, 78, 86, 139, 141, 152, 181, 212, 226, 240, 285, 330, 346, 359, 379–380, 396.
- 92.** Chapter 092 — Derryvree Mosses, Castlepook Hyenas (30909 BCE). Sources: References 2, 17, 60–63, 89, 133, 141, 165, 169, 226, 240, 309, 314, 325, 347, 358, 365, 378, 380, 397.
- 93.** Chapter 093 — Derryvree's Periglacial Census (30908 BCE). Sources: References 2, 15, 38, 61, 73, 86, 129, 161, 199, 226, 230, 240, 247, 276, 308, 333, 346, 359, 376, 380, 386, 396.
- 94.** Chapter 094 — Maguirebridge and Doneraile (30907 BCE). Sources: References 2, 40, 60, 83, 95, 130, 133, 152, 199, 213, 226, 230, 257, 259, 264, 272, 308, 314, 347, 361, 380.
- 95.** Chapter 095 — Fermanagh's Buried Freshwater (30906 BCE). Sources: References 15, 27, 38, 43, 53, 89, 114, 116, 120, 129, 161, 194, 215, 226, 240, 312, 342, 346, 359, 381, 386, 396.
- 96.** Chapter 096 — Fermanagh's Buried Muskeg (30905 BCE). Sources: References 15, 46, 108, 116, 133, 141, 161, 169, 205, 229, 240, 304, 310, 328, 346, 369, 374, 380, 384, 397.
- 97.** Chapter 097 — BIRM-166's Tundra Flora (30904 BCE). Sources: References 2, 15, 38, 78, 86, 141, 161, 184, 199, 206, 226, 230, 240, 300, 305, 325, 359, 380, 393, 405.
- 98.** Chapter 098 — BIRM-166 and the Fermanagh Pool (30903 BCE). Sources: References 17, 41, 63, 77, 87, 106, 141, 145, 165, 176, 185, 205, 229, 240, 286, 310, 314, 358, 374, 380.
- 99.** Chapter 099 — Derryvree Before the Advance (30902 BCE). Sources: References 15, 56, 72, 117, 123, 125, 141, 162, 226, 264, 267, 274, 278, 309, 322, 325, 346, 358, 374, 399.
- 100.** Chapter 100 — Hyenahall's Faunal Frontier (30901 BCE). Sources: References 2, 17, 38, 50, 60, 124, 136, 156, 160, 180, 184, 192, 226, 240, 247, 259, 327, 346, 358, 380, 396.

## References

1. **2014:526 - Castlepook South, Cork**  
<https://excavations.ie/report/2014/Cork/0026356/>
2. **2022:564 – Castlepook Cave, Castlepook South, Cork**  
<https://excavations.ie/report/2022/Cork/0032564/>
3. **A 10Be-Dated Record of Glacial Retreat in Connemara, Ireland, Following the Last Glacial Maximum and Implications for Regional Climate**  
<https://doi.org/10.1016/j.palaeo.2022.110901>
4. **A 10Be-Dated Record of Glacial Retreat in Connemara, Ireland, Following the Last Glacial Maximum and Implications for Regional Climate**  
<https://www.sciencedirect.com/science/article/pii/S0031018222000712>
5. **A 60 000 year Greenland stratigraphic ice core chronology**  
<https://www.bas.ac.uk/data/our-data/publication/a-60-000-year-greenland-stratigraphic-ice-core-chronology/>
6. **A 60,000 Year Greenland Stratigraphic Ice Core Chronology**  
<https://doi.org/10.5194/cp-4-47-2008>
7. **A Critical Review and Re-Investigation of the Pleistocene Deposits Between Cranfield Point and Kilkeel, Northern Ireland**  
<https://nora.nerc.ac.uk/id/eprint/521184/>
8. **A Critical Review and Re-Investigation of the Pleistocene Deposits Between Cranfield Point and Kilkeel, Northern Ireland**  
<https://www.sciencedirect.com/science/article/abs/pii/S0016787818300415>
9. **Advance and Retreat of the Marine-Terminating Irish Sea Ice Stream into the Celtic Sea During the Last Glacial**  
<https://doi.org/10.1016/j.margeo.2019.03.003>
10. **Advance and Retreat of the Marine-Terminating Irish Sea Ice Stream into the Celtic Sea During the Last Glacial: Timing and Maximum Extent**  
<https://www.sciencedirect.com/science/article/pii/S0025322718303372>
11. **Advances in Irish Quaternary Studies**  
<https://link.springer.com/book/10.2991/978-94-6239-219-9>
12. **Advice to the Public: Caves and Archaeology**  
<https://www.archaeology.ie/sites/default/files/media/publications/NMS%20Caves%20Leaflet%20lo-res.pdf>
13. **Aghnadarragh**  
<https://www.habitas.org.uk/escr/site.asp?item=1>
14. **Aghnadarragh: Earth Science Conservation Review Site Summary**  
<https://www2.habitas.org.uk/escr/summary.php?item=1>
15. **A Middle Midlandian Freshwater Series at Derryvree, Maguiresbridge, County Fermanagh, Northern Ireland**  
<https://doi.org/10.1098/rspb.1972.0018>
16. **A Middle Midlandian Freshwater Series at Derryvree, Maguiresbridge, County Fermanagh, Northern Ireland**  
<https://www.tara.tcd.ie/tara8/server/api/core/bitstreams/969fd7c8-36ef-4262-a961-336fe7285015/content>
17. **A Middle Midlandian Freshwater Series at Derryvree, Maguiresbridge, County Fermanagh, Northern Ireland**  
[https://www.researchgate.net/publication/252327954\\_A\\_Middle\\_Midlandian\\_Freshwater\\_Series\\_at\\_Derryvree\\_Maguiresbridge\\_County\\_Fermanagh\\_Northern\\_Ireland](https://www.researchgate.net/publication/252327954_A_Middle_Midlandian_Freshwater_Series_at_Derryvree_Maguiresbridge_County_Fermanagh_Northern_Ireland)
18. **A Middle Midlandian Freshwater Series at Derryvree, Maguiresbridge, County Fermanagh, Northern Ireland**  
<https://doi.org/10.1098/rspb.1972.0017>
19. **A Middle Midlandian Freshwater Series at Derryvree, Maguiresbridge, County Fermanagh, Northern Ireland**  
<https://royalsocietypublishing.org/doi/10.1098/rspb.1972.0018>
20. **AMS Radiocarbon Dating of Ancient Bone Using Ultrafiltration**  
<https://doi.org/10.1017/S0033822200038731>
21. **AMS Radiocarbon Dating of Ancient Bone Using Ultrafiltration**  
<https://doi.org/10.1017/S0033822200035788>

22. **AMS Radiocarbon Dating of Middle and Upper Palaeolithic Bone in the British Isles: Improved Reliability Using Ultrafiltration**  
<https://doi.org/10.1002/jqs.946>
23. **AMS Radiocarbon Dating of Middle and Upper Palaeolithic Bone in the British Isles: Improved Reliability Using Ultrafiltration**  
<https://doi.org/10.1002/jqs.1112>
24. **Ancient Hybridization and an Irish Origin for the Modern Polar Bear Matriline**  
<https://doi.org/10.1016/j.cub.2011.05.058>
25. **A New Chronology for the Last Glacial Maximum in the Irish Sea Basin**  
[https://mural.maynoothuniversity.ie/8868/1/SMcC\\_ice%20sheet%202015.pdf](https://mural.maynoothuniversity.ie/8868/1/SMcC_ice%20sheet%202015.pdf)
26. **An Inter-Till Freshwater Deposit at Hollymount, Maguiresbridge, Co. Fermanagh**  
<https://www.bugscep.com/downloads/qbib.pdf>
27. **An Inter-Till Freshwater Deposit at Hollymount, Maguiresbridge, Co. Fermanagh**  
<https://www.habitas.org.uk/escr/site.asp?Item=486>
28. **A North-Western Habitat: the Paleoethology and Colonisation of a European Peninsula**  
<https://intarch.ac.uk/journal/issue61/1/6.html>
29. **Anthropogenic changes to the Holocene nitrogen cycle in Ireland**  
<https://pmc.ncbi.nlm.nih.gov/articles/PMC6007156/>
30. **A Palaeo-Glaciological Reconstruction of the British-Irish Ice Sheet**  
[https://etheses.whiterose.ac.uk/id/eprint/14933/1/489647\\_vol1.pdf](https://etheses.whiterose.ac.uk/id/eprint/14933/1/489647_vol1.pdf)
31. **A Palaeo-Glaciological Reconstruction of the Last Irish Ice Sheet**  
[https://etheses.whiterose.ac.uk/id/eprint/14933/2/489647\\_vol2.pdf](https://etheses.whiterose.ac.uk/id/eprint/14933/2/489647_vol2.pdf)
32. **Archaeological Excavations at Killuragh Cave, Co. Limerick**  
<https://researchrepository.ucd.ie/rest/bitstreams/47195/retrieve>
33. **Archaeological Excavations at Killuragh Cave, Co. Limerick: A Persistent Place in the Landscape from the Early Mesolithic to the Late Bronze Age**  
<https://researchrepository.ucd.ie/server/api/core/bitstreams/0fa70d1c-1476-4f2f-b49a-7a47c83c23bc/content>
34. **Archaeological excavations at Killuragh Cave, Co. Limerick: a persistent place in the landscape from the Early Mesolithic to the Late Bronze Age**  
<https://researchrepository.ucd.ie/entities/publication/69b1e443-b6c0-4d49-8443-bb819a38eacd>
35. **Archaeological Survey**  
<https://www.archaeology.ie/about-us/what-we-do/archaeological-survey/>
36. **Archaeology Research Excavation Grant 2022: Castlepook Cave Final Report**  
[https://www.ria.ie/assets/uploads/2024/05/areg\\_2022\\_jennings\\_final\\_report\\_web\\_ready.pdf](https://www.ria.ie/assets/uploads/2024/05/areg_2022_jennings_final_report_web_ready.pdf)
37. **Archaeology Research Excavation Grant Report: Castlepook Cave Geophysical Survey**  
<https://www.ria.ie/assets/uploads/2024/10/AREG-2023-Richard-Jennings.pdf>
38. **A reconsideration of the radiocarbon dating of the Marine Isotope Stage 3 fauna from southern Ireland**  
<https://doi.org/10.1111/bor.12451>
39. **A Reconsideration of the Radiocarbon Dating of the Marine Isotope Stage 3 Fauna from Southern Ireland**  
<https://onlinelibrary.wiley.com/doi/10.1111/bor.12451>
40. **A Reconsideration of the Radiocarbon Dating of the Marine Isotope Stage 3 Fauna from Southern Ireland**  
<https://onlinelibrary.wiley.com/doi/abs/10.1111/bor.12451>
41. **A Reconsideration of the Radiocarbon Dating of the Marine Isotope Stage 3 Fauna from Southern Ireland**  
<https://scispace.com/papers/a-reconsideration-of-the-radiocarbon-dating-of-the-marine-1tem0gn0b1>
42. **A Stratigraphic Framework for Abrupt Climatic Changes During the Last Glacial Period Based on Three Synchronized Greenland Ice-Core Records**  
<https://doi.org/10.1016/j.quascirev.2014.09.007>
43. **A Stratigraphic Framework for Abrupt Climatic Changes During the Last Glacial Period Based on Three Synchronized Greenland Ice-Core Records: Refining and Extending the INTIMATE Event Stratigraphy**  
[https://pure.aber.ac.uk/ws/portalfiles/portal/5708372/A\\_stratigraphic\\_framework\\_for\\_abrupt\\_climatic\\_changes\\_during\\_the\\_Last\\_Glacial\\_period\\_based\\_on\\_three\\_synchronized\\_Greenland\\_ice\\_core\\_records\\_refining\\_and\\_extending\\_the\\_INTIMATE\\_event\\_stratigraphy.pdf](https://pure.aber.ac.uk/ws/portalfiles/portal/5708372/A_stratigraphic_framework_for_abrupt_climatic_changes_during_the_Last_Glacial_period_based_on_three_synchronized_Greenland_ice_core_records_refining_and_extending_the_INTIMATE_event_stratigraphy.pdf)

**44. Bayesian Analysis of Radiocarbon Dates**

<https://doi.org/10.1017/S0033822200033865>

**45. Behavioural tendencies of the last British–Irish Ice Sheet revealed by data–model comparison**

<https://doi.org/10.1002/jqs.3628>

**46. Behavioural Tendencies of the Last British–Irish Ice Sheet Revealed by Data–Model Comparison**

<https://onlinelibrary.wiley.com/doi/10.1002/jqs.3628>

**47. Britain and Ireland: Glacial Landforms from the Last Glacial Maximum**

<https://www.sciencedirect.com/science/article/pii/B9780128234983000339>

**48. BRITICE-CHRONO**

<https://britice-chrono.sites.sheffield.ac.uk/>

**49. BRITICE-CHRONO: Constraining Rates and Style of Later British–Irish Ice Sheet Deglaciation**

<https://doi.org/10.1016/j.quascirev.2022.107444>

**50. BRITICE-CHRONO: Constraining the Retreat of the Last British-Irish Ice Sheet**

[https://www.aber.ac.uk/en/dges/research/quaternary/luminescence-research-laboratory/recent-research-projects/britice\\_chrono/](https://www.aber.ac.uk/en/dges/research/quaternary/luminescence-research-laboratory/recent-research-projects/britice_chrono/)

**51. BRITICE-CHRONO: Introduction**

<https://britice-chrono.sites.sheffield.ac.uk/project/introduction>

**52. BRITICE-CHRONO Maps and GIS Data of the Last British-Irish Ice Sheet 31 to 15 ka**

<https://doi.pangaea.de/10.1594/PANGAEA.945729>

**53. BRITICE-CHRONO Maps and GIS Data of the Last British-Irish Ice Sheet 31 to 15 ka**

<https://doi.org/10.1594/PANGAEA.945729>

**54. BRITICE Glacial Map, version 2: a map and GIS database of glacial landforms of the last British–Irish Ice Sheet**

<https://doi.org/10.1111/bor.12273>

**55. BRITICE Glacial Map, Version 2: A Map and GIS Database of Glacial Landforms of the Last British–Irish Ice Sheet**

<https://onlinelibrary.wiley.com/doi/full/10.1111/bor.12273>

**56. BRITICE Glacial Map, Version 2: A Map and GIS Database of Glacial Landforms of the Last British–Irish Ice Sheet**

<https://onlinelibrary.wiley.com/doi/10.1111/bor.12273>

**57. British–Irish Ice Sheet and Polar Front History of the Goban Spur, Offshore Southwest Ireland Over the Last 250,000 Years**

<https://onlinelibrary.wiley.com/doi/10.1111/bor.12631>

**58. British–Irish Ice Sheet and Polar Front History of the Goban Spur, Offshore Southwest Ireland Over the Last 250,000 Years**

<https://doi.org/10.1111/bor.12631>

**59. BSBI: Salix herbacea**

<https://fermanagh.bsbi.org/salix-herbacea-l>

**60. Castlepook Cave: County Geological Site Report**

[https://gsi.geodata.gov.ie/downloads/Geoheritage/Reports/CK032\\_Cork\\_CGS\\_Castlepook\\_Cave.pdf](https://gsi.geodata.gov.ie/downloads/Geoheritage/Reports/CK032_Cork_CGS_Castlepook_Cave.pdf)

**61. Castlepook Caves**

[https://www.npws.ie/sites/default/files/publications/pdf/Goodwillie\\_1986\\_ASI\\_Cork.pdf](https://www.npws.ie/sites/default/files/publications/pdf/Goodwillie_1986_ASI_Cork.pdf)

**62. Cenozoic: Tertiary and Quaternary**

<https://files.core.ac.uk/download/pdf/297011667.pdf>

**63. Character of advance and retreat of the southwest sector of the British-Irish Ice Sheet during the last glaciation**

<https://www.sciencedirect.com/science/article/pii/S0277379122002864>

**64. Character of Advance and Retreat of the Southwest Sector of the British-Irish Ice Sheet During the Last Glaciation**

<https://doi.org/10.1016/j.quascirev.2022.107271>

**65. Character of Advance and Retreat of the Southwest Sector of the British-Irish Ice Sheet During the Last Glaciation**

<https://doi.org/10.1016/j.quascirev.2022.107079>

**66. Comprehensive Uncertainty Estimation of the Timing of Greenland Warmings in the Greenland Ice Core Records**

<https://cp.copernicus.org/articles/18/1275/2022/>

**67. Conserving Quaternary Geoheritage in Northern Ireland**

<https://www.sciencedirect.com/science/article/abs/pii/S0016787822000670>

**68. Continuity of Brown Bear Maternal Lineages in Northern England Through the Last-Glacial Period**

[https://www.researchgate.net/profile/Ross-Barnett/publication/258277804\\_Continuity\\_of\\_brown\\_bear\\_maternal\\_lineages\\_in\\_northern\\_England\\_through\\_the\\_Last-glacial\\_period/links/5bc87dd1299bf17a1c5b8fe2/Continuity-of-brown-bear-maternal-lineages-in-northern-England-through-the-Last-glacial-period.pdf](https://www.researchgate.net/profile/Ross-Barnett/publication/258277804_Continuity_of_brown_bear_maternal_lineages_in_northern_England_through_the_Last-glacial_period/links/5bc87dd1299bf17a1c5b8fe2/Continuity-of-brown-bear-maternal-lineages-in-northern-England-through-the-Last-glacial-period.pdf)

**69. Could Brown Bears Have Survived in Ireland During the Last Glacial Maximum?**

<https://pubmed.ncbi.nlm.nih.gov/23676655/>

**70. Dansgaard-Oeschger Events in Climate Models: Review and Baseline Marine Isotope Stage 3 Protocol**

<https://cp.copernicus.org/articles/19/915/2023/>

**71. Dating Constraints on the Last British-Irish Ice Sheet: A Map and Database**

<https://doi.org/10.4113/jom.2011.1145>

**72. Deglacial Rates and Controls for the Western Margin of the British-Irish Ice Sheet**

<https://pureadmin.uhi.ac.uk/ws/portalfiles/portal/15996924/jqs.3315.pdf>

**73. Deglaciation, Earth Crustal Behaviour and Sea-Level Changes in the Determination of Insularity: A Perspective From Ireland**

<https://research.ucc.ie/en/publications/deglaciation-earth-crustal-behaviour-and-sea-level-changes-in-the-2/>

**74. Deglaciation, Earth Crustal Behaviour and Sea-Level Changes in the Determination of Insularity: A Perspective from Ireland**

<https://doi.org/10.1144/GSL.SP.1995.096.01.14>

**75. Deglaciation Chronology of the Donegal Ice Centre, North-West Ireland**

<https://doi.org/10.1002/jqs.3077>

**76. Deglaciation Chronology of the Donegal Ice Centre, North-West Ireland**

<https://onlinelibrary.wiley.com/doi/full/10.1002/jqs.3077>

**77. Dimensions and Chronology of the Last Ice Sheet in Western Ireland**

<https://www.sciencedirect.com/science/article/abs/pii/S0277379107003022>

**78. Dimensions and Chronology of the Last Ice Sheet in Western Ireland**

<https://doi.org/10.1016/j.quascirev.2007.10.019>

**79. Dimensions and Chronology of the Last Ice Sheet in Western Ireland**

<https://doi.org/10.1016/j.quascirev.2007.12.023>

**80. Dimensions and Chronology of the Last Ice Sheet in Western Ireland**

<https://doi.org/10.1016/j.quascirev.2007.12.010>

**81. Dimensions and Chronology of the Last Ice Sheet in Western Ireland**

<https://research-portal.st-andrews.ac.uk/en/publications/dimensions-and-chronology-of-the-last-ice-sheet-in-western-ireland/>

**82. Dimensions and Chronology of the Last Ice Sheet in Western Ireland**

<https://doi.org/10.1016/j.quascirev.2007.09.015>

**83. Dryas octopetala**

<https://fermanagh.bsbi.org/dryas-octopetala-l>

**84. Dublin Radiocarbon Dates II**

<https://journals.uair.arizona.edu/index.php/radiocarbon/article/viewFile/381/386>

**85. Early Deglaciation of the British-Irish Ice Sheet on the Atlantic Shelf: Dating the Glenulra and Owenduff Moraines, County Mayo, Ireland**

<https://eprints.whiterose.ac.uk/140069/8/1-s2.0-S0277379117306157-main.pdf>

**86. Early Deglaciation of the British-Irish Ice Sheet on the Atlantic Shelf Northwest of Ireland Driven by Glacioisostatic Depression and High Relative Sea Level**

<https://livrepository.liverpool.ac.uk/3033771/>

**87. Early Deglaciation of the British-Irish Ice Sheet on the Atlantic Shelf Northwest of Ireland Driven by Glacioisostatic Depression and High Relative Sea Level**

<https://www.sciencedirect.com/science/article/pii/S0277379117306157>



- 88. Early Deglaciation of Western Ireland and Ice-Sheet Extent on the Atlantic Shelf Northwest of Ireland**  
<https://livrepository.liverpool.ac.uk/3033771/1/OCofaighetal2019Early%20deglaciation%20of%20western%20Ireland.pdf>
- 89. Early Midlandian–Middle Midlandian, Pleistocene, Northern Ireland**  
[https://earthwise.bgs.ac.uk/index.php/Early\\_Midlandian%E2%80%93Middle\\_Midlandian%2C\\_Pleistocene%2C\\_Northern\\_Ireland](https://earthwise.bgs.ac.uk/index.php/Early_Midlandian%E2%80%93Middle_Midlandian%2C_Pleistocene%2C_Northern_Ireland)
- 90. Early Midlandian–Middle Midlandian, Pleistocene, Northern Ireland**  
[https://earthwise.bgs.ac.uk/index.php/Early\\_Midlandian%E2%80%93Middle\\_Midlandian,\\_Pleistocene,\\_Northern\\_Ireland](https://earthwise.bgs.ac.uk/index.php/Early_Midlandian%E2%80%93Middle_Midlandian,_Pleistocene,_Northern_Ireland)
- 91. Episodic Speleothem Deposition Tracks the Terrestrial Impact of Millennial-Scale Last Glacial Climate Variability in SW Ireland**  
<https://edoc.unibas.ch/entities/publication/f1d27768-63f4-4316-9171-9e17fda96451>
- 92. Episodic speleothem deposition tracks the terrestrial impact of millennial-scale last glacial climate variability in SW Ireland**  
<https://doi.org/10.1016/j.quascirev.2016.09.019>
- 93. Episodic Speleothem Deposition Tracks the Terrestrial Impact of Millennial-Scale Last Glacial Climate Variability in SW Ireland**  
<https://www.sciencedirect.com/science/article/abs/pii/S0277379116303699>
- 94. Equilibrium simulations of Marine Isotope Stage 3 climate**  
<https://cp.copernicus.org/articles/15/1133/2019/>
- 95. ESCR Site Summary**  
<https://www2.habitas.org.uk/escr/summary.php?item=101>
- 96. Exhibition Galleries: National Museum of Ireland – Natural History**  
[https://www.museum.ie/getmedia/548be922-4e00-4c0a-8721-1f34cf1c2e51/NMI\\_NHFP\\_Eng.pdf](https://www.museum.ie/getmedia/548be922-4e00-4c0a-8721-1f34cf1c2e51/NMI_NHFP_Eng.pdf)
- 97. Exploring Controls of the Early and Stepped Deglaciation of the Western Margin of the British-Irish Ice Sheet**  
[https://researchportal.plymouth.ac.uk/files/39237921/JQS-20-0108.R1\\_Benetti\\_Mar21.pdf](https://researchportal.plymouth.ac.uk/files/39237921/JQS-20-0108.R1_Benetti_Mar21.pdf)
- 98. Exploring Controls of the Early and Stepped Deglaciation on the Western Margin of the British-Irish Ice Sheet**  
<https://pure.ulster.ac.uk/files/91186146/jqs.3315.pdf>
- 99. Exploring controls of the early and stepped deglaciation on the western margin of the British-Irish Ice Sheet**  
<https://onlinelibrary.wiley.com/doi/10.1002/jqs.3315>
- 100. Exploring Controls of the Early and Stepped Deglaciation on the Western Margin of the British-Irish Ice Sheet**  
[https://pure.bangor.ac.uk/ws/portalfiles/portal/37340552/JQS\\_20\\_0108.R1\\_Accepted.pdf](https://pure.bangor.ac.uk/ws/portalfiles/portal/37340552/JQS_20_0108.R1_Accepted.pdf)
- 101. Exploring Controls of the Early and Stepped Deglaciation on the Western Margin of the British Irish Ice Sheet**  
<https://onlinelibrary.wiley.com/doi/full/10.1002/jqs.3315>
- 102. Exploring controls of the early and stepped deglaciation on the western margin of the British Irish Ice Sheet**  
<https://doi.org/10.1002/jqs.3315>
- 103. Exploring Controls of the Early and Stepped Deglaciation on the Western Margin of the British Irish Ice Sheet**  
<https://eprints.gla.ac.uk/247061/1/247061.pdf>
- 104. Exploring Controls of the Early and Stepped Deglaciation on the Western Margin of the British Irish Ice Sheet**  
<https://livrepository.liverpool.ac.uk/3124996/1/jqs.3315.pdf>
- 105. Exploring Controls of the Early and Stepped Deglaciation on the Western Margin of the British Irish Ice Sheet**  
<https://eprints.gla.ac.uk/247061/>
- 106. Exploring Controls of the Early and Stepped Deglaciation on the Western Margin of the British Irish Ice Sheet**  
[https://research-repository.st-andrews.ac.uk/bitstream/handle/10023/23305/Benetti\\_2021\\_JQS\\_Exploring\\_CC.pdf?sequence=1](https://research-repository.st-andrews.ac.uk/bitstream/handle/10023/23305/Benetti_2021_JQS_Exploring_CC.pdf?sequence=1)
- 107. Exploring Controls of the Early and Stepped Deglaciation on the Western Margin of the British–Irish Ice Sheet**  
<https://pure.uhi.ac.uk/files/15996924/jqs.3315.pdf>
- 108. Exploring Controls on the Last British–Irish Ice Sheet's Deglaciation**  
[https://research-repository.st-andrews.ac.uk/bitstream/10023/23305/1/Benetti\\_2021\\_JQS\\_Exploring\\_CC.pdf](https://research-repository.st-andrews.ac.uk/bitstream/10023/23305/1/Benetti_2021_JQS_Exploring_CC.pdf)
- 109. Exposure-Age Constraints on the Extent, Timing and Rate of Retreat of the Last Irish Sea Ice Stream**  
<https://doi.org/10.1016/j.quascirev.2010.07.016>
- 110. Exposure-Age Constraints on the Extent, Timing and Rate of Retreat of the Last Irish Sea Ice Stream**  
<https://www.sciencedirect.com/science/article/abs/pii/S0277379110000983>

111. **Extending and Globally Tuning the Greenland Ice-core Chronology (GICC05) Back to 120 ka**  
<https://doi.org/10.1002/2013PA002577>
112. **Extent and timing of the Last Glacial Maximum (LGM) in Britain and Ireland: a review**  
<https://onlinelibrary.wiley.com/doi/10.1002/jqs.1404>
113. **Extent and Timing of the Last Glacial Maximum in Britain and Ireland: A Review**  
<https://doi.org/10.1002/jqs.1404>
114. **Field Guides**  
<https://iqua.ie/publications/field-guides/>
115. **First evidence of a Late Upper Palaeolithic human presence in Ireland**  
<https://mariondowd.com/wp-content/uploads/2025/04/2016-qsr-palaeolithic-ireland.pdf>
116. **First Evidence of a Late Upper Palaeolithic Human Presence in Ireland**  
<https://doi.org/10.1016/j.quascirev.2016.02.029>
117. **First Evidence of a Late Upper Palaeolithic Human Presence in Ireland**  
<https://www.sciencedirect.com/science/article/pii/S0277379116300610>
118. **First Evidence of a Late Upper Palaeolithic Human Presence in Ireland – Atlantic Technological University Record**  
<https://pure.atu.ie/en/publications/first-evidence-of-a-late-upper-palaeolithic-human-presence-in-ire-3/>
119. **Freshwater Organic Deposits and Stratified Sediments Between Early and Late Midlandian (Devensian) Till Sheets, at Aghnadarragh, County Antrim, Northern Ireland**  
<https://eurekamag.com/research/018/968/018968909.php>
120. **Freshwater Organic Deposits and Stratified Sediments Between Early and Late Midlandian (Devensian) Till Sheets, at Aghnadarragh, County Antrim, Northern Ireland**  
<https://doi.org/10.1002/jqs.3390020104>
121. **Freshwater Organic Deposits and Stratified Sediments Between Early and Late Midlandian (Devensian) Till Sheets, at Aghnadarragh, County Antrim, Northern Ireland**  
<https://iqua.ie/wp-content/uploads/2021/09/IQUA-Guide-13-unlocked.pdf>
122. **Freshwater Organic Deposits and Stratified Sediments Between Early and Late Midlandian (Devensian) Till Sheets at Aghnadarragh, County Antrim, Northern Ireland**  
<https://doi.org/10.1002/jqs.3390020103>
123. **Geology of Ireland**  
<https://www.gsi.ie/geoscience-topics/geology/geology-of-ireland/>
124. **Glacial Geomorphology in the Wicklow Mountains, Ireland**  
<https://doi.org/10.1080/17445647.2022.2132885>
125. **Glaciers and Ice Sheets**  
[https://nora.nerc.ac.uk/id/eprint/540572/1/uknc\\_glaciers\\_and\\_ice\\_sheets\\_report\\_digital-aw.pdf](https://nora.nerc.ac.uk/id/eprint/540572/1/uknc_glaciers_and_ice_sheets_report_digital-aw.pdf)
126. **Growth, dynamics and deglaciation of the last British-Irish ice sheet: the deep-sea ice-rafted detritus record**  
<https://nora.nerc.ac.uk/id/eprint/11204/>
127. **Growth and Retreat of the Last British-Irish Ice Sheet, 31,000 to 15,000 Years Ago: the BRITICE-CHRONO Reconstruction**  
<https://pure.ulster.ac.uk/files/104683424/bor.12594.pdf>
128. **Growth and Retreat of the Last British-Irish Ice Sheet, 31,000 to 15,000 Years Ago: The BRITICE-CHRONO Reconstruction**  
<https://pure.ulster.ac.uk/ws/portalfiles/portal/104683424/bor.12594.pdf>
129. **Growth and retreat of the last British-Irish Ice Sheet, 31,000 to 15,000 years ago: the BRITICE-CHRONO reconstruction**  
<https://doi.org/10.1111/bor.12594>
130. **Growth and Retreat of the Last British-Irish Ice Sheet, 31,000 to 15,000 Years Ago: the BRITICE-CHRONO Reconstruction**  
<https://www.bas.ac.uk/data/our-data/publication/growth-and-retreat-of-the-last-british-irish-ice-sheet-31-000-to-15-000-years-ago-the-britice%E2%80%90reconstruction/>

**131. Growth and Retreat of the Last British–Irish Ice Sheet, 31,000 to 15,000 Years Ago: The BRITICE-CHRONO Reconstruction**

<https://eprints.gla.ac.uk/278917/2/278917.pdf>

**132. Growth and Retreat of the Last British–Irish Ice Sheet, 31,000 to 15,000 Years Ago: the BRITICE-CHRONO Reconstruction**

<https://eprints.whiterose.ac.uk/id/eprint/194087/>

**133. Growth and Retreat of the Last British–Irish Ice Sheet, 31,000 to 15,000 Years Ago: the BRITICE-CHRONO Reconstruction**

<https://onlinelibrary.wiley.com/doi/10.1111/bor.12594>

**134. Growth and Retreat of the Last British–Irish Ice Sheet, 31,000 to 15,000 Years Ago: The BRITICE-CHRONO Reconstruction**

<https://eprints.ncl.ac.uk/286460>

**135. Growth and Retreat of the Last British–Irish Ice Sheet, 31,000 to 15,000 Years Ago: the BRITICE-CHRONO Reconstruction**

<https://eprints.whiterose.ac.uk/id/eprint/190923/>

**136. Growth and Retreat of the Last British–Irish Ice Sheet, 31,000 to 15,000 Years Ago: The BRITICE-CHRONO Reconstruction**

<https://nora.nerc.ac.uk/id/eprint/533160/>

**137. Growth and retreat of the last British–Irish Ice Sheet, 31,000 to 15,000 years ago: the BRITICE-CHRONO reconstruction**

<https://nora.nerc.ac.uk/id/eprint/533160/1/Boreas%20-%202022%20-%20Clark%20-%20Growth%20and%20retreat%20of%20the%20last%20British%20Irish%20Ice%20Sheet%2031%20000%20to%2015%20000%20years%20ago%20the.pdf>

**138. Growth and Retreat of the Last British–Irish Ice Sheet, 31,000 to 15,000 Years Ago: The BRITICE-CHRONO Reconstruction**

<https://research-repository.st-andrews.ac.uk/handle/10023/26038>

**139. Growth and Retreat of the Last British–Irish Ice Sheet, 31,000 to 15,000 Years Ago: The Role of the Marine Ice Sheet Instability**

<https://storre.stir.ac.uk/retrieve/8d577b73-20ca-48c5-b3d1-cfa5525e9b65/Boreas-2022-Clark.pdf>

**140. Growth Dynamics and Deglaciation of the Last British-Irish Ice Sheet: the Deep-Sea Ice-Rafted Detritus Record**

<https://doi.org/10.1016/j.quascirev.2009.08.009>

**141. Heritage Artefacts of County Cork**

<https://www.corkcoco.ie/sites/default/files/2023-06/heritage-artefacts-of-county-cork-2021.pdf>

**142. Ice-Core Data Used for the Construction of the Greenland Ice-Core Chronology 2005 and 2021 (GICC05 and GICC21)**

<https://doi.org/10.5194/essd-15-3351-2023>

**143. Ice Age Ireland: Cool Fossils!**

[https://www.museum.ie/getmedia/acab45bf-2252-4f25-9cf0-c0268f0c7f0d/Ice\\_Age\\_Activity\\_Overview.pdf](https://www.museum.ie/getmedia/acab45bf-2252-4f25-9cf0-c0268f0c7f0d/Ice_Age_Activity_Overview.pdf)

**144. Ice Sheet Extension to the Celtic Sea Shelf Edge at the Last Glacial Maximum**

<https://nora.nerc.ac.uk/id/eprint/511244/>

**145. Ice Sheet Extension to the Celtic Sea Shelf Edge at the Last Glacial Maximum**

<https://www.sciencedirect.com/science/article/abs/pii/S0277379114004934>

**146. Independent Tephrochronological Evidence for Rapid and Synchronous Oceanic and Atmospheric Temperature Rises Over the Greenland Stadial–Interstadial Transitions Between ca. 32 and 40 ka b2k**

<https://doi.org/10.1016/j.quascirev.2020.106277>

**147. IntCal**

<https://www.intcal.org/>

**148. IntCal13 and Marine13 Radiocarbon Age Calibration Curves 0–50,000 Years cal BP**

[https://doi.org/10.2458/azu\\_js\\_rc.55.16947](https://doi.org/10.2458/azu_js_rc.55.16947)

**149. IntCal20 Issue**

<https://www.cambridge.org/core/journals/radiocarbon/calibrations/intcal-20>

**150. IntCal Data**

<https://www.intcal.org/data.html>

**151. IntCal History**

<https://intcal.org/history.html>

**152. IntCal Publications**

<https://www.intcal.org/publications.html>

**153. IntCal Publications**

<https://intcal.org/publications.html>

**154. Introduction to the Glacial Sand and Gravel Landscapes of Northern Ireland**

<https://www.habitas.org.uk/escr/site.asp?Item=439>

**155. Introduction to the Late Quaternary and Holocene of Northern Ireland**

<https://www.habitas.org.uk/escr/site.asp?Item=101>

**156. Investigating Seasonal Mobility in Irish Giant Deer (*Megaloceros giganteus* Blumenbach)**

[https://research-portal.uu.nl/files/139756950/J\\_Quaternary\\_Science\\_2022\\_Douw\\_Investigating\\_seasonal\\_mobility\\_in\\_Irish\\_giant\\_deer\\_Megaloceros\\_giganteus\\_Blumenbach\\_.pdf](https://research-portal.uu.nl/files/139756950/J_Quaternary_Science_2022_Douw_Investigating_seasonal_mobility_in_Irish_giant_deer_Megaloceros_giganteus_Blumenbach_.pdf)

**157. Investigating Seasonal Mobility in Irish Giant Deer *Megaloceros giganteus* Through Strontium Isotope Analysis**

<https://doi.org/10.1002/jqs.3447>

**158. IQUA Newsletter No. 58**

<https://iqua.ie/wp-content/uploads/2018/09/IQUA-NEWSLETTER-58.pdf>

**159. Ireland: Submerged Prehistoric Sites and Landscapes**

[https://doi.org/10.1007/978-3-030-37367-2\\_11](https://doi.org/10.1007/978-3-030-37367-2_11)

**160. Ireland: Submerged Prehistoric Sites and Landscapes**

[https://pure.ulster.ac.uk/ws/portalfiles/portal/78797612/IrelandSubmergedPrehistoricSit\\_chapter.pdf](https://pure.ulster.ac.uk/ws/portalfiles/portal/78797612/IrelandSubmergedPrehistoricSit_chapter.pdf)

**161. Ireland: Submerged Prehistoric Sites and Landscapes**

[https://link.springer.com/chapter/10.1007/978-3-030-37367-2\\_11](https://link.springer.com/chapter/10.1007/978-3-030-37367-2_11)

**162. Ireland Through Geological Time**

<https://gsi.ie/education/the-geology-of-ireland/ireland-through-geological-time/>

**163. Ireland's Earliest Settlers: Evidence for an Irish Palaeolithic**

[https://pureadmin.qub.ac.uk/ws/portalfiles/portal/373000291/JSmall\\_thesis\\_final\\_2.pdf](https://pureadmin.qub.ac.uk/ws/portalfiles/portal/373000291/JSmall_thesis_final_2.pdf)

**164. Ireland's First Settlers: Time and the Mesolithic**

<https://www.oxbowbooks.com/9781789256888/irelands-first-settlers/>

**165. Ireland's Palaeolithic Archaeology – Fleeting Footprints in a Frozen Land**

<https://irisharchaeology.org/before-the-ice-melted-irelands-palaeolithic-fleeting-footprints-in-a-frozen-land/>

**166. Irish Cave Exploration**

<https://www.nature.com/articles/012212b0>

**167. Irish Cave Exploration**

<https://doi.org/10.1038/012212b0>

**168. Irish Fauna: Ground Floor**

[https://www.museum.ie/getmedia/cd11862c-a1a7-4691-a39f-d8f77f2268ea/nhm\\_guide\\_web\\_en.pdf](https://www.museum.ie/getmedia/cd11862c-a1a7-4691-a39f-d8f77f2268ea/nhm_guide_web_en.pdf)

**169. Irish Pleistocene Biostratigraphy**

[https://www.researchgate.net/publication/290822499\\_Irish\\_Pleistocene\\_biostratigraphy](https://www.researchgate.net/publication/290822499_Irish_Pleistocene_biostratigraphy)

**170. Irish Pleistocene Biostratigraphy**

<https://www.jstor.org/stable/30002348>

**171. Irish Pleistocene Biostratigraphy**

<https://doi.org/10.3318/irisjeartscie.2019.02>

**172. Irish Quaternary Association**

<https://iqua.ie/>

**173. Irish Quaternary Vertebrates**

[https://doi.org/10.2991/978-94-6239-219-9\\_9](https://doi.org/10.2991/978-94-6239-219-9_9)

**174. Karst of Ireland**

[https://gsi.geodata.gov.ie/downloads/Groundwater/Other/GSI\\_Karst\\_of\\_Ireland\\_David\\_Drew\\_2018.pdf](https://gsi.geodata.gov.ie/downloads/Groundwater/Other/GSI_Karst_of_Ireland_David_Drew_2018.pdf)

**175. Landscapes and environments of the last glacial-interglacial transition: a time of amazingly rapid change in Ireland**

[https://www.researchgate.net/publication/299975247\\_Landscapes\\_and\\_environments\\_of\\_the\\_last\\_glacial-interglacial\\_transition\\_a\\_time\\_of\\_amazingly\\_rapid\\_change\\_in\\_Ireland](https://www.researchgate.net/publication/299975247_Landscapes_and_environments_of_the_last_glacial-interglacial_transition_a_time_of_amazingly_rapid_change_in_Ireland)

**176. Last Glacial Maximum Cirque Glaciation in Ireland and Implications for Reconstructions of the Irish Ice Sheet**

<https://www.sciencedirect.com/science/article/abs/pii/S0277379116301172>

**177. Last Glacial Maximum Cirque Glaciation in Ireland and Implications for Reconstructions of the Irish Ice Sheet**

<https://doi.org/10.1016/j.quascirev.2016.04.006>

**178. Last Glacial Maximum Cirque Glaciation in Ireland and Implications for Reconstructions of the Irish Ice Sheet**

<https://doi.org/10.1016/j.quascirev.2016.06.002>

**179. Last Glacial Maximum Cirque Glaciation in Ireland and Implications for Reconstructions of the Irish Ice Sheet**

<https://doi.org/10.1016/j.quascirev.2016.07.022>

**180. Last Glacial Maximum Cirque Glaciation in Ireland and Implications for the Spatial Extent of the Last Irish Ice Sheet**

[https://aaronmbarth.weebly.com/uploads/3/7/9/8/37989143/barth\\_et\\_al\\_\\_2016\\_\\_qsr.pdf](https://aaronmbarth.weebly.com/uploads/3/7/9/8/37989143/barth_et_al__2016__qsr.pdf)

**181. Late Pleistocene Chrono-stratigraphy and Ice Sheet Limits, Southern Ireland**

<https://doi.org/10.1016/j.quascirev.2012.02.010>

**182. Late Pleistocene Chronostratigraphy and Ice Sheet Limits, Southern Ireland**

<https://intelligent-earth.ox.ac.uk/node/4030041>

**183. Late Pleistocene Chronostratigraphy and Ice Sheet Limits, Southern Ireland**

<https://durham-repository.worktribe.com/output/1486214>

**184. Late Pleistocene chronostratigraphy and ice sheet limits, southern Ireland**

<https://doi.org/10.1016/j.quascirev.2010.01.011>

**185. Late Pleistocene Chronostratigraphy and Ice Sheet Limits, Southern Ireland**

<https://www.sciencedirect.com/science/article/abs/pii/S0277379110000132>

**186. Late Pleistocene chronostratigraphy and ice sheet limits, southern Ireland**

<https://doi.org/10.1016/j.quascirev.2010.02.010>

**187. Late Pleistocene Chronostratigraphy and Ice Sheet Limits, Southern Ireland**

<https://doi.org/10.1016/j.quascirev.2010.01.005>

**188. Late Pleistocene Glaciation of the Mourne Mountains, Northern Ireland**

<https://pure.ulster.ac.uk/en/publications/last-glacial-maximum-cirque-glaciation-in-ireland-and-implication/>

**189. Late Pleistocene Sediments, Landforms and Events in Scotland: A Review of the Terrestrial Stratigraphic Record**

<https://www.cambridge.org/core/journals/earth-and-environmental-science-transactions-of-royal-society-of-edinburgh/article/abs/late-pleistocene-sediments-landforms-and-events-in-scotland-a-review-of-the-terrestrial-stratigraphic-record/04361148265AA29138A2843CEBA1108B>

**190. Late Pleistocene Sediments, Landforms and Events in Scotland: a Review of the Terrestrial Stratigraphic Record**

<https://www.cambridge.org/core/journals/earth-and-environmental-science-transactions-of-the-royal-society-of-edinburgh/article/abs/late-pleistocene-sediments-landforms-and-events-in-scotland-a-review-of-the-terrestrial-stratigraphic-record/04361148265AA29138A2843CEBA1108B>

**191. Learn About: The Ice Age**

<https://cms.museum.ie/en-IE/Museums/Natural-History/Engage-And-Learn/Museum-at-Home/Activity-Sheet-Ice-Age-Ireland-Cool-Fossils>

**192. Local Pleistocene Glaciation and the Level of the Snow Line of Croaghaun Mountain in Achill Island, Co. Mayo, Ireland**

<https://www.cambridge.org/core/journals/journal-of-glaciology/article/local-pleistocene-glaciation-and-the-level-of-the-snow-line-of-croaghaun-mountain-in-achill-island-co-mayo-ireland/C4E33D17F60E71CC23346E19FD6D5E8B>

**193. Mammals: National Museum of Ireland Natural History Collections**

<https://cms.museum.ie/en-IE/Collections-Research/Natural-History-Collections/Collections-List/Mammals>

**194. Mammoth and Musk Ox ESR-Dated to the Early Midlandian at Aghnadarragh, County Antrim, Northern Ireland, and the Age of the Fermanagh Stadial**

<https://doi.org/10.1002/gj.2668>

**195. Mammoth and Musk Ox ESR-Dated to the Early Midlandian at Aghnadarragh, County Antrim, Northern Ireland, and the Age of the Fermanagh Stadial**

<http://hdl.handle.net/1885/67296>

**196. Mammoth and Musk Ox ESR-Dated to the Early Midlandian at Aghnadarragh, County Antrim, Northern Ireland, and the Age of the Fermanagh Stadial**

<https://openresearch-repository.anu.edu.au/items/769ddf57-2327-4a9e-ad68-ea606103dc4c>

**197. Mammoth and Musk Ox ESR Dated to the Early Midlandian at Aghnadarragh County Antrim, Northern Ireland and the Age of the Fermanagh Stadial**

<https://doi.org/10.1002/gj.2576>

**198. Mammoth and Musk Ox ESR Dated to the Early Midlandian at Aghnadarragh County Antrim, Northern Ireland and the Age of the Fermanagh Stadial**

<https://doi.org/10.1002/gj.2649>

**199. Mammoth Cave**

<https://irishcaves.ubss.org.uk/gazetteer/cork/mammoth-cave/>

**200. Marine Archaeology Technical Report**

<https://www.pleanala.ie/publicaccess/EIAR-NIS/319799/Oriel%20Wind%20Farm%20Project%20-%20Planning%20Application/EIAR/Volume%20B%20EIAR%20Chapters%207-16%20and%20associated%20technical%20appendices/15-01%20Marine%20Archaeology%20Technical%20Report.pdf>

**201. Marine geophysical evidence for Late Pleistocene ice sheet extent and recession off northwest Ireland**

<https://pure.ulster.ac.uk/en/publications/marine-geophysical-evidence-for-late-pleistocene-ice-sheet-extent-3/>

**202. Marine Isotope Stage 3 Sea Level Fluctuations: Data Synthesis and New Outlook**

<https://doi.org/10.1029/2007RG000226>

**203. Maximum Extent and Dynamic Behaviour of the Last British-Irish Ice Sheet West of Ireland**

<https://doi.org/10.1016/j.quascirev.2015.10.006>

**204. Maximum extent and dynamic behaviour of the last British–Irish Ice Sheet west of Ireland**

<https://doi.org/10.1016/j.quascirev.2015.12.001>

**205. Maximum Extent and Dynamic Behaviour of the Last British–Irish Ice Sheet West of Ireland**

<https://www.sciencedirect.com/science/article/pii/S027737911530113X>

**206. Maximum Extent and Dynamic Behaviour of the Last British–Irish Ice Sheet West of Ireland**

<https://doi.org/10.1016/j.quascirev.2015.09.015>

**207. Maximum Extent and Dynamic Behaviour of the Last British–Irish Ice Sheet West of Ireland**

<https://doi.org/10.1016/j.quascirev.2015.11.005>

**208. Maximum Extent and Readvance Dynamics of the Irish Sea Ice Stream and Irish Sea Glacier Since the Last Glacial Maximum**

<https://doi.org/10.1002/jqs.3313>

**209. Maximum Extent and Readvance Dynamics of the Irish Sea Ice Stream and Irish Sea Glacier Since the Last Glacial Maximum**

<https://onlinelibrary.wiley.com/doi/10.1002/jqs.3313>

**210. Maximum extent and readvance dynamics of the Irish Sea Ice Stream and Irish Sea Glacier since the Last Glacial Maximum**

<https://onlinelibrary.wiley.com/doi/abs/10.1002/jqs.3313>

**211. Maximum Extent and Readvance Dynamics of the Irish Sea Ice Stream and Irish Sea Glacier Since the Last Glacial Maximum**

<https://durham-repository.worktribe.com/output/1242517/maximum-extent-and-readvance-dynamics-of-the-irish-sea-ice-stream-and-irish-sea-glacier-since-the-last-glacial-maximum>

**212. Maximum Extent and Readvance Dynamics of the Irish Sea Ice Stream and Irish Sea Glacier Since the Last Glacial Maximum**

<https://eprints.whiterose.ac.uk/174565/1/jqs.3313.pdf>

**213. Menyanthes trifoliata**

<https://fermanagh.bsbi.org/menyanthes-trifoliata-l>

**214. Mesolithic – Iron Age**

<https://heritageireland.ie/articles/mesolithic-iron-age-8000bc-400ad/>

**215. Middle Midlandian Interstadial Deposits at Greenagho, Near Belcoo, County Fermanagh, Northern Ireland**

<https://www.jstor.org/stable/30002377>

**216. Modes of Global Climate Variability during Marine Isotope Stage 3 (60–26 ka)**

<https://journals.ametsoc.org/view/journals/clim/23/6/2009jcli3416.1.xml>

**217. *Myriophyllum alterniflorum***

<https://fermanagh.bsbi.org/myriophyllum-alterniflorum-dc>

**218. National Monuments Service**

<https://www.gov.ie/en/department-of-housing-local-government-and-heritage/organisation-information/national-monuments-service/>

**219. Natural History Division Acquisition Strategy**

<https://source.museum.ie/en-IE/About/Corporate-Information/Policies-Guidelines/Natural-History-Division-Acquisition-Strategy>

**220. New age constraints for the maximum extent of the last British-Irish Ice Sheet (NW sector)**

<https://nora.nerc.ac.uk/id/eprint/21216/>

**221. New Data for the Last Glacial Maximum in Great Britain and Ireland**

<https://www.sciencedirect.com/science/article/pii/S0277379101001020>

**222. New Data for the Last Glacial Maximum in Great Britain and Ireland**

[https://doi.org/10.1016/S0277-3791\(01\)00029-2](https://doi.org/10.1016/S0277-3791(01)00029-2)

**223. New data for the Last Glacial Maximum in Great Britain and Ireland**

<https://doi.org/10.1016/j.quascirev.2010.11.029>

**224. New Data for the Last Glacial Maximum in Great Britain and Ireland**

[https://doi.org/10.1016/S0277-3791\(01\)00080-3](https://doi.org/10.1016/S0277-3791(01)00080-3)

**225. New Data for the Last Glacial Maximum in Great Britain and Ireland**

[https://doi.org/10.1016/S0277-3791\(01\)00102-0](https://doi.org/10.1016/S0277-3791(01)00102-0)

**226. New insights on the fauna of Ireland's Younger Dryas and Early Holocene from Alice & Gwendoline Cave**

<https://doi.org/10.1016/j.quascirev.2024.108827>

**227. New Insights on the Fauna of Ireland's Younger Dryas and Early Holocene from Alice & Gwendoline Cave**

<https://mariondowd.com/wp-content/uploads/2025/04/2024-qsr-ag.pdf>

**228. New Insights on the Fauna of Ireland's Younger Dryas and Early Holocene from Alice & Gwendoline Cave**

<https://www.sciencedirect.com/science/article/pii/S0277379124003287>

**229. New Insights on the Fauna of Ireland's Younger Dryas and Early Holocene from Alice & Gwendoline Cave (open-access PDF)**

[https://clarecastleballiea.clareheritage.org/wp-content/uploads/sites/5/2025/03/New\\_insights\\_on\\_the\\_fauna\\_of\\_Irelands\\_Yo\\_compressed.pdf](https://clarecastleballiea.clareheritage.org/wp-content/uploads/sites/5/2025/03/New_insights_on_the_fauna_of_Irelands_Yo_compressed.pdf)

**230. Occurrence of mammalia relicts at site Castlepook Cave**

<https://doi.pangaea.de/10.1594/PANGAEA.63585>

**231. On the Cave of Castlepook, Near Doneraile, Co. Cork**

<https://doi.org/10.1017/S0016756800122435>

**232. On the Discovery of *Hyaena*, Mammoth and Other Extinct Mammals in a Carboniferous Cavern in County Cork**

[https://sources.nli.ie/Record/PS\\_UR\\_095315](https://sources.nli.ie/Record/PS_UR_095315)

**233. Oscillating Retreat of the Last British-Irish Ice Sheet on the Continental Shelf Offshore Galway Bay, Western Ireland**

<https://www.sciencedirect.com/science/article/pii/S0025322719302245>

**234. Oscillating Retreat of the Last British-Irish Ice Sheet on the Continental Shelf Offshore Galway Bay, Western Ireland**

<https://doi.org/10.1016/j.margeo.2019.106087>

**235. Oscillating Retreat of the Last British-Irish Ice Sheet on the Continental Shelf Offshore Galway Bay, Western Ireland**

<https://doi.org/10.1016/j.marpetgeo.2019.104019>

**236. Our Ancient Landscapes: Hunter-Gatherers in Ireland**

<https://www.heritagecouncil.ie/ga/publications/oidhreacht-togtha/p3>

**237. Outreach and Education Resources**

<https://iqua.ie/outreach-and-education-resources/>

**238. OxCal**

<https://c14new.arch.ox.ac.uk/oxcal.html>

**239. OxCal: Radiocarbon Calibration and Analysis**

<https://c14.arch.ox.ac.uk/oxcal.html>

**240. Palaeoecology**

<https://iqua.ie/wp-content/uploads/2021/09/IQUA-Guide-16-600dpi.pdf>

**241. Palaeolithic Ireland – New Evidence Emerges from the Emerald Isle**

<https://www.ucl.ac.uk/human-evolution/news/2016/mar/palaeolithic-ireland-new-evidence-emerges-emerald-isle>

**242. Pattern, Style and Timing of British–Irish Ice Sheet Advance and Retreat Over the Last 45,000 Years**

<https://nora.nerc.ac.uk/id/eprint/530254/>

**243. Pattern, Style and Timing of British–Irish Ice Sheet Advance and Retreat Over the Last 45,000 Years: Evidence from NW Scotland and the Adjacent Continental Shelf**

<https://doi.org/10.1002/jqs.3296>

**244. Pattern, Style and Timing of British–Irish Ice Sheet Retreat: Shetland and Northern North Sea Sector**

<https://doi.org/10.1002/jqs.3163>

**245. Pattern and Timing of Retreat of the Last British-Irish Ice Sheet**

<https://doi.org/10.1016/j.quascirev.2010.07.019>

**246. Pattern and Timing of Retreat of the Last British-Irish Ice Sheet**

<https://eprints.whiterose.ac.uk/id/eprint/83510/8/Pattern%20and%20timing%20of%20retreat%20of%20the%20last%20British-Irish%20Ice%20Sheet%20-%20QSR.pdf>

**247. Pattern and timing of retreat of the last British-Irish Ice Sheet**

<https://nora.nerc.ac.uk/id/eprint/507486/>

**248. Pattern and timing of retreat of the last British-Irish Ice Sheet**

<https://www.sciencedirect.com/science/article/pii/S0277379110002817>

**249. Phylogeographic, Ancient DNA, Fossil and Morphometric Analyses Reveal Ancient and Modern Introductions of a Large Mammal: the Complex Case of Red Deer (*Cervus elaphus*) in Ireland**

<https://doi.org/10.1016/j.quascirev.2012.02.012>

**250. Phylogeography, Ancient DNA, and Morphometrics Support the Reintroduction of Red Deer (*Cervus elaphus*) into Ireland**

<https://www.npws.ie/sites/default/files/general/Quaternary%20Science%20Reviews%2042%20%282012%29%2074-84%20Carden%20et%20al.pdf>

**251. Pleistocene Rodents of the British Isles**

[https://www.rhinosourcecenter.com/pdf\\_files/137/1376158853.pdf](https://www.rhinosourcecenter.com/pdf_files/137/1376158853.pdf)

**252. Pleistocene Vertebrates in the British Isles**

[https://www.rhinosourcecenter.com/pdf\\_files/133/1336577813.pdf](https://www.rhinosourcecenter.com/pdf_files/133/1336577813.pdf)

**253. Pleistocene Vertebrates in the British Isles**

<https://rhinosourcecenter.com/wp-content/uploads/2012/04/1336577813.pdf>

**254. Prehistoric Details**

[https://source.museum.ie/en-IE/Collections-Research/Irish-Antiquities-Division-Collections/Collections-List-\(1\)/Stone-Age/Prehistoric-Details](https://source.museum.ie/en-IE/Collections-Research/Irish-Antiquities-Division-Collections/Collections-List-(1)/Stone-Age/Prehistoric-Details)

**255. Prehistoric Details**

[https://cms.museum.ie/en-IE/Collections-Research/Irish-Antiquities-Division-Collections/Collections-List-\(1\)/Stone-Age/Prehistoric-Details](https://cms.museum.ie/en-IE/Collections-Research/Irish-Antiquities-Division-Collections/Collections-List-(1)/Stone-Age/Prehistoric-Details)

**256. Prehistoric Details**

<https://cms.museum.ie/en-IE/Collections-Research/Irish-Antiquities-Division-Collections/Collections-List-%281%29/Stone-Age/Prehistoric-Details>

**257. Prehistoric Details**

<https://source.museum.ie/en-IE/Collections-Research/Irish-Antiquities-Division-Collections/Collections-List-%281%29/Stone-Age/Prehistoric-Details>

**258. Preliminary Assessment of the Archive of Faunal Remains from Excavated Irish Cave Sites**

[https://www.researchgate.net/publication/256886486\\_Preliminary\\_assessment\\_of\\_the\\_archive\\_of\\_faunal\\_remains\\_from\\_excavated\\_Irish\\_cave\\_sites](https://www.researchgate.net/publication/256886486_Preliminary_assessment_of_the_archive_of_faunal_remains_from_excavated_Irish_cave_sites)



**259. Proceedings of the Royal Irish Academy**

[https://upload.wikimedia.org/wikipedia/commons/d/da/Proceedings\\_of\\_the\\_Royal\\_Irish\\_Academy\\_%281A\\_proceedingsofro34roya%29.pdf](https://upload.wikimedia.org/wikipedia/commons/d/da/Proceedings_of_the_Royal_Irish_Academy_%281A_proceedingsofro34roya%29.pdf)

**260. Proceedings of the Royal Irish Academy, Volume 34**

<https://www.biodiversitylibrary.org/item/108026>

**261. Project Findings Provide Essential Insight into the Last British–Irish Ice Sheet**

<https://www.bgs.ac.uk/news/project-findings-provide-essential-insight-into-the-last-british-irish-ice-sheet/>

**262. Publications**

<https://iqua.ie/publications/>

**263. Quaternary**

<https://www.gsi.ie/data-and-maps/quaternary/>

**264. Quaternary**

<https://www.gsi.ie/ga-ie/data-and-maps/Pages/Quaternary.aspx>

**265. Quaternary**

<https://gsi.ie/en-ie/data-and-maps/Pages/Quaternary.aspx>

**266. Quaternary Deposits and Glacial Stratigraphy in Ireland**

<https://pure.ulster.ac.uk/en/publications/quaternary-deposits-and-glacial-stratigraphy-in-ireland-3/>

**267. Quaternary Geoheritage Activities: Themes**

<https://gsi.ie/programmes-projects/geoheritage/geoheritage-activities/county-geological-heritage-audits/themes/>

**268. Quaternary Geological Map of Ireland**

[https://inchheritage.org/dist/resources/Quaternary\\_500k\\_All\\_Ireland\\_Map.pdf](https://inchheritage.org/dist/resources/Quaternary_500k_All_Ireland_Map.pdf)

**269. Quaternary Geological Map of Ireland 1:500,000**

<https://gsi.ie/publications/publication/quaternary-geological-map-of-ireland-1500000/>

**270. Quaternary Geology of the Beara Peninsula**

<https://iqua.ie/wp-content/uploads/2021/09/IQUA-Guide-28-Corrected-after-print-version.pdf>

**271. Quaternary Geomorphology Map Service**

[https://gsi.geodata.gov.ie/server/rest/services/Quaternary/IE\\_GSI\\_Quaternary\\_Geomorphology\\_50K\\_IE26\\_ITM/MapServer](https://gsi.geodata.gov.ie/server/rest/services/Quaternary/IE_GSI_Quaternary_Geomorphology_50K_IE26_ITM/MapServer)

**272. Quaternary Site Descriptions**

<https://iqua.ie/wp-content/uploads/2020/10/Quaternary-sites-of-Ireland-map-INQUA-2019.pdf>

**273. Radiocarbon Calibration**

<https://www.oxcal.org/calibration.html>

**274. Radiocarbon Constraints on Readvances of the British–Irish Ice Sheet in the Northern Irish Sea Basin During the Last Deglaciation**

<https://www.sciencedirect.com/science/article/abs/pii/S0277379107000431>

**275. Radiocarbon constraints on the age of the maximum advance of the British–Irish Ice Sheet in the Celtic Sea**

<https://doi.org/10.1016/j.quascirev.2007.03.008>

**276. Radiocarbon Constraints on the Age of the Maximum Advance of the British–Irish Ice Sheet in the Celtic Sea**

<https://durham-repository.worktribe.com/output/1579471/radiocarbon-constraints-on-the-age-of-the-maximum-advance-of-the-british-irish-ice-sheet-in-the-celtic-sea>

**277. Radiocarbon Constraints on the Age of the Maximum Advance of the British–Irish Ice Sheet in the Celtic Sea**

<https://doi.org/10.1016/j.quascirev.2007.09.010>

**278. Radiocarbon Constraints on the Age of the Maximum Advance of the British–Irish Ice Sheet in the Celtic Sea**

<https://www.sciencedirect.com/science/article/abs/pii/S0277379107000844>

**279. Radiocarbon constraints on the age of the maximum advance of the British–Irish Ice Sheet in the Celtic Sea**

<https://doi.org/10.1016/j.quascirev.2007.02.010>

**280. Radiocarbon Constraints on the History of the Western Irish Ice Sheet Prior to the Last Glacial Maximum**

<https://pure.ulster.ac.uk/en/publications/radiocarbon-constraints-on-the-history-of-the-western-irish-ice-s-3/>

**281. Radiocarbon Dating**

<https://www.radiocarbon.org.uk/dating.html>

**282. Radiocarbon Dating and Chronological Modelling**

<https://historicengland.org.uk/images-books/publications/radiocarbon-dating-chronological-modelling/radiocarbon-dating/>

**283. Rapid global ocean-atmosphere response to Southern Ocean freshening during the last glacial**

<https://pmc.ncbi.nlm.nih.gov/articles/PMC5595922/>

**284. Rapid Response of Climatic Conditions During the Last Glacial: Evidence from U-Series Dated Irish Speleothems**

[https://www.researchgate.net/publication/258617696\\_Rapid\\_response\\_of\\_climatic\\_conditions\\_during\\_the\\_last\\_glacial\\_evidence\\_from\\_U-series\\_dated\\_Irish\\_speleothems](https://www.researchgate.net/publication/258617696_Rapid_response_of_climatic_conditions_during_the_last_glacial_evidence_from_U-series_dated_Irish_speleothems)

**285. Recent developments in calibration for archaeological and environmental samples**

<https://eprints.gla.ac.uk/210774/>

**286. Reconstructing the Last Irish Ice Sheet 2: a Geomorphologically-Driven Model of Ice Sheet Growth, Retreat and Dynamics**

<https://www.sciencedirect.com/science/article/pii/S0277379109003163>

**287. Reconstructing the Last Irish Ice Sheet 2: A Geomorphologically-Driven Model of Ice Sheet Growth, Retreat and Dynamics**

<https://doi.org/10.1016/j.quascirev.2009.09.014>

**288. Reindeer Bone Found in Cork Cave Shows Human Activity in Ireland 33,000 Years Ago**

<https://www.thejournal.ie/reindeer-bone-cork-cave-5413607-Apr2021/>

**289. Relative Sea-Level Change Around the Irish Coast**

[https://link.springer.com/chapter/10.2991/978-94-6239-219-9\\_7](https://link.springer.com/chapter/10.2991/978-94-6239-219-9_7)

**290. Research Groups and Publications**

<https://iqua.ie/outreach-and-education-resources/research-groups-and-publications/>

**291. Response of the Irish Ice Sheet to Abrupt Climate Change During the Last Deglaciation**

<https://www.sciencedirect.com/science/article/abs/pii/S0277379112000029>

**292. Response of the Irish Ice Sheet to Abrupt Climate Change During the Last Deglaciation**

<https://doi.org/10.1016/j.quascirev.2012.01.001>

**293. Revisiting Alice and Gwendoline Cave, Co. Clare: New Light on the 1902 Excavations**

<https://pure.atu.ie/en/publications/revisiting-alice-and-gwendoline-cave-co-clare-new-light-on-the-19-3/>

**294. Scientific Dating of Pleistocene Sites**

<https://historicengland.org.uk/images-books/publications/scientific-dating-pleistocene-sites/heag325-scientific-dating-pleistocene-sites/>

**295. Scientific Dating of Pleistocene Sites: Scientific Dating Methods**

<https://historicengland.org.uk/images-books/publications/scientific-dating-pleistocene-sites/scientific-dating-methods/>

**296. Sea-Level Change During the Last Glacial Cycle in Bantry Bay, Southwestern Ireland**

<https://nora.nerc.ac.uk/513300/1/Plots%20et%20a%202015%20Mar%20Geol.pdf>

**297. Sedimentary ancient DNA reveals Late Pleistocene faunal connectivity between Ireland and Eurasia**

<https://www.biorxiv.org/content/10.64898/2026.07.10.737191v1>

**298. Sedimentary Ancient DNA Reveals Late Pleistocene Faunal Connectivity Between Ireland and Eurasia**

<https://doi.org/10.64898/2026.07.10.737191>

**299. Sedimentary and Foraminiferal Records of Late Quaternary Environmental Change West of Ireland and Implications for the Last British-Irish Ice Sheet**

<https://onlinelibrary.wiley.com/doi/10.1002/jqs.3208>

**300. Sedimentary and Foraminiferal Records of Late Quaternary Environmental Change West of Ireland and Implications for the Last British-Irish Ice Sheet**

<https://doi.org/10.1002/jqs.3208>

**301. Sedimentology and Chronology of the Advance and Retreat of the Last British-Irish Ice Sheet on the Continental Shelf West of Ireland**

[https://eprints.whiterose.ac.uk/102848/7/Sedimentology\\_and\\_chronology\\_of\\_\\_the\\_last\\_British\\_Irish\\_Ice\\_Sheet\\_on\\_the\\_continental\\_shelf\\_west\\_of\\_Ireland\\_-\\_QSR\\_2016%20%281%29.pdf](https://eprints.whiterose.ac.uk/102848/7/Sedimentology_and_chronology_of__the_last_British_Irish_Ice_Sheet_on_the_continental_shelf_west_of_Ireland_-_QSR_2016%20%281%29.pdf)

**302. Sedimentology and Chronology of the Advance and Retreat of the Last British-Irish Ice Sheet on the Continental Shelf West of Ireland**

<https://eprints.gla.ac.uk/121683/>

**303. Sedimentology and chronology of the advance and retreat of the last British-Irish Ice Sheet on the continental shelf west of Ireland**

<https://doi.org/10.1016/j.quascirev.2016.03.012>

**304. *Selaginella selaginoides* (L.) P. Beauv.**

<https://fermanagh.bsbi.org/selaginella-selaginoides-p-beauv>

**305. Soils of County Waterford**

<https://www.teagasc.ie/media/website/publications/2011/Soils-of-Co-Waterford-WEB.pdf>

**306. Spatio-Temporal Dynamics of Speleothem Growth and Glaciation in the British Isles**

<https://cp.copernicus.org/articles/21/261/2025/>

**307. Spatio-Temporal Dynamics of Speleothem Growth and Glaciation in the British Isles**

<https://durham-repository.worktribe.com/preview/1340374/27125.pdf>

**308. Spotted Hyena Skull**

<https://cms.museum.ie/en-IE/Collections-Research/Collection/Documentation-Discoveries/Artefact/Spotted-Hyena-Skull/a8990d9b-84a9-4107-99b7-f3a8cc17a7d4>

**309. Spotted Hyena Skull**

<https://cms.museum.ie/ga-IE/Collections-Research/Collection/Documentation-Discoveries/Artefact/Spotted-Hyena-Skull/a8990d9b-84a9-4107-99b7-f3a8cc17a7d4>

**310. Stratigraphic and Palaeo-Geomorphological Evidence for the Glacial-Deglacial History of the Last British-Irish Ice Sheet in the North-Western Irish Sea**

<https://www.sciencedirect.com/science/article/pii/S0277379122005406>

**311. Stratigraphic and Palaeo-Geomorphological Evidence for the Glacial-Deglacial History of the Last British-Irish Ice Sheet in the North-Western Irish Sea**

<https://research.ucc.ie/en/publications/stratigraphic-and-palaeo-geomorphological-evidence-for-the-glacia/>

**312. Stratigraphic and Palaeo-Geomorphological Evidence for the Glacial-Deglacial History of the Last British-Irish Ice Sheet in the North-Western Irish Sea**

<https://doi.org/10.1016/j.quascirev.2022.107909>

**313. Stratigraphic and Palaeo-geomorphological Evidence for the Glacial-deglacial History of the Last British-Irish Ice Sheet in the North-western Irish Sea**

<https://doi.org/10.1016/j.quascirev.2022.107114>

**314. The Archaeological Heritage of County Cork**

<https://www.corkcoco.ie/sites/default/files/2023-06/archaeological-heritage-of-county-cork-2020.pdf>

**315. The Archaeological Survey of Ireland Collection**

<https://www.archaeology.ie/collections-and-publications/collections/access-and-deposit-of-collections/>

**316. The Archaeology of Caves in Ireland**

<https://www.jstor.org/stable/j.ctt16t8zkc>

**317. The Archaeology of Caves in Ireland**

<https://caves.org/journal-of-cave-and-karst-studies/jcks-articles/the-archaeology-of-caves-in-ireland-2/>

**318. The Archaeology of Caves in Ireland**

<https://www.worldcat.org/title/archaeology-of-caves-in-ireland/oclc/899141376>

**319. The Archaeology of Caves in Ireland**

<https://mariondowd.com/wp-content/uploads/2025/04/2015-the-archaeology-of-caves-in-ireland.pdf>

**320. The Archaeology of Ireland**

[https://ignca.gov.in/Asi\\_data/13687.pdf](https://ignca.gov.in/Asi_data/13687.pdf)

**321. The Bear from Clare: New Evidence for an Early Human Presence in Late Pleistocene Ireland**

<https://doi.org/10.1016/j.quaint.2016.02.018>

**322. The BRITICE Glacial Mapping Project**

<https://sheffield.ac.uk/geography-planning/research/geography/projects/britice>

**323. The Castlepook Cave Project**

<https://www.corkcoco.ie/sites/default/files/2023-05/county-cork-heritage-grant-scheme-2023-1.pdf>

**324. The Caves of Ireland: An Introduction to the Karst Landscape**

<https://www.iah-ireland.org/field-guides/2014.pdf>

**325. The Colonization of Ireland: A Human Ecology Perspective**

<https://doi.org/10.1016/j.quascirev.2020.106632>

**326. The Colonization of Ireland: A Human Ecology Perspective**

[https://hungarcolab.weebly.com/uploads/1/3/0/2/130279092/tune\\_2020\\_-\\_colonization\\_of\\_ireland.pdf](https://hungarcolab.weebly.com/uploads/1/3/0/2/130279092/tune_2020_-_colonization_of_ireland.pdf)

**327. The Colonization of Ireland: A Human Ecology Perspective**

<https://www.sciencedirect.com/science/article/pii/S0277379120305941>

**328. The deglaciation of the western sector of the Irish Ice Sheet from the inner continental shelf to its terrestrial margin**

<https://doi.org/10.1111/bor.12448>

**329. The Deglaciation of the Western Sector of the Irish Ice Sheet From the Inner Continental Shelf to its Terrestrial Margin**

<https://onlinelibrary.wiley.com/doi/full/10.1111/bor.12448>

**330. The Deglaciation of the Western Sector of the Irish Ice Sheet from the Inner Continental Shelf to its Terrestrial Margin**

<https://eprints.gla.ac.uk/213261/>

**331. The Dungarvan Valley Caves Project: First Interim Report**

<https://researchonline.ljmu.ac.uk/id/eprint/14938/>

**332. The Evolution of the Terrestrial-Terminating Irish Sea Glacier During the Last Glaciation**

[https://livrepository.liverpool.ac.uk/3093127/1/chiverrelletal\\_jqs2020\\_englishmidlands.pdf](https://livrepository.liverpool.ac.uk/3093127/1/chiverrelletal_jqs2020_englishmidlands.pdf)

**333. The exploration of Castlepook Cave, Co. Cork**

[https://sources.nli.ie/Record/PS\\_UR\\_073459](https://sources.nli.ie/Record/PS_UR_073459)

**334. The Exploration of Castlepook Cave, Co. Cork**

[https://sources.nli.ie/Search/Versions?](https://sources.nli.ie/Search/Versions?filter%5B%5D=geographic_facet%3A%22Fermoy+Barony%22&filter%5B%5D=topic_facet%3A%22Caves%22&lookfor=%2A&type=AllFields)

[filter%5B%5D=geographic\\_facet%3A%22Fermoy+Barony%22&filter%5B%5D=topic\\_facet%3A%22Caves%22&lookfor=%2A&type=AllFields](https://sources.nli.ie/Search/Versions?filter%5B%5D=geographic_facet%3A%22Fermoy+Barony%22&filter%5B%5D=topic_facet%3A%22Caves%22&lookfor=%2A&type=AllFields)

**335. The Exploration of Castlepook Cave, Co. Cork. With 3 Plates**

[https://sources.nli.ie/Record/PS\\_UR\\_073459/Details?lng=en&print=1&sid=111354](https://sources.nli.ie/Record/PS_UR_073459/Details?lng=en&print=1&sid=111354)

**336. The Exploration of Castlepook Cave, County Cork**

<https://www.jstor.org/stable/25504231>

**337. The Exploration of Castlepook Cave, County Cork**

<https://www.jstor.org/stable/20521549>

**338. The Exploration of Castlepook Cave, County Cork, Being the Third Report from the Committee Appointed to Explore Irish Caves**

<https://www.jstor.org/stable/i20490272>

**339. The Exploration of the Caves of County Clare**

<https://www.jstor.org/stable/25504179>

**340. The Explorations of Some Caves Near Castletownroche, Co. Cork**

<https://www.jstor.org/stable/20520887>

**341. The Geological Heritage of Clare**

[https://gsi.geodata.gov.ie/downloads/Geoheritage/Reports/Limerick\\_Audit.pdf](https://gsi.geodata.gov.ie/downloads/Geoheritage/Reports/Limerick_Audit.pdf)

**342. The Geological Heritage of County Leitrim**

[https://gsi.geodata.gov.ie/downloads/Geoheritage/Reports/Leitrim\\_Audit.pdf](https://gsi.geodata.gov.ie/downloads/Geoheritage/Reports/Leitrim_Audit.pdf)

**343. The Glacial Deposits of the Maguiresbridge Area, County Fermanagh, Northern Ireland**

<https://doczz.net/doc/7343058/the-glacial-deposits-of-the-maguires--bridge-area>

**344. The Greenland Ice Core Chronology 2005, 15–42 ka. Part 1: Constructing the Time Scale**

<https://www.sciencedirect.com/science/article/pii/S0277379106002587>

**345. The IntCal20 Approach to Radiocarbon Calibration Curve Construction: A New Methodology Using Bayesian Splines and Errors-in-Variables**

<https://eprints.gla.ac.uk/217180/>

**346. The IntCal20 Northern Hemisphere Radiocarbon Age Calibration Curve (0–55 cal kBP)**

<https://doi.org/10.1017/RDC.2020.41>

**347. The IntCal20 Northern Hemisphere Radiocarbon Age Calibration Curve (0–55 cal kBP)**

<https://www.cambridge.org/core/journals/radiocarbon/article/intcal20-northern-hemisphere-radiocarbon-age-calibration-curve-055-cal-kbp/83257B63DC3AF9CFA6243F59D7503EFF>

**348. The IntCal20 Northern Hemisphere Radiocarbon Age Calibration Curve (0–55 cal kBP)**

<https://www.cambridge.org/core/services/aop-cambridge-core/content/view/83257B63DC3AF9CFA6243F59D7503EFF/S0033822220000417a.pdf/the-intcal20-northern-hemisphere-radiocarbon-age-calibration-curve-0-55-cal-kbp.pdf>

**349. The IntCal20 Northern Hemisphere Radiocarbon Age Calibration Curve (0–55 cal kBP)**

[https://oceanrep.geomar.de/50508/1/intcal20\\_northern\\_hemisphere\\_radiocarbon\\_age\\_calibration\\_curve\\_055\\_cal\\_kbp.pdf](https://oceanrep.geomar.de/50508/1/intcal20_northern_hemisphere_radiocarbon_age_calibration_curve_055_cal_kbp.pdf)

**350. The IntCal20 Northern Hemisphere Radiocarbon Age Calibration Curve (0–55 cal kBP)**

<https://www.cambridge.org/core/services/aop-cambridge-core/content/view/83257B63DC3AF9CFA6243F59D7503EFF/S0033822220000417a.pdf/div-class-title-the-intcal20-northern-hemisphere-radiocarbon-age-calibration-curve-0-55-cal-kbp-div.pdf>

**351. The IntCal20 Northern Hemisphere Radiocarbon Age Calibration Curve (0–55 cal kBP)**

<https://epic.awi.de/id/eprint/53055/1/reimer2020r.pdf>

**352. The IntCal20 Northern Hemisphere Radiocarbon Age Calibration Curve (0–55 cal kBP)**

<https://www.cambridge.org/core/journals/radiocarbon/article/intcal20-northern-hemisphere-radiocarbon-age-calibration-curve-055-cal-kbp/83257B63DC3AF9CFA6243F59D7503EFF>

**353. The IntCal20 Northern Hemisphere Radiocarbon Age Calibration Curve (0–55 cal kBP)**

[https://research-repository.st-andrews.ac.uk/bitstream/handle/10023/20465/Reimer\\_2020\\_Radiocarbon\\_IntCal20\\_CC.pdf?sequence=1](https://research-repository.st-andrews.ac.uk/bitstream/handle/10023/20465/Reimer_2020_Radiocarbon_IntCal20_CC.pdf?sequence=1)

**354. The IntCal20 Northern Hemisphere radiocarbon age calibration curve (0–55 kcal BP)**

<https://eprints.gla.ac.uk/210753/>

**355. The IntCal20 Northern Hemisphere Radiocarbon Age Calibration Curve (0–55 kcal BP)**

<https://storre.stir.ac.uk/handle/1893/30981?mode=full>

**356. The Irish Biogeographical Society: Postglacial Colonisation Conference Proceedings**

<https://www.irishbiogeographicalsociety.com/pdf/OccPub1PostglacialConfIBS.pdf>

**357. The Irish Ice Sheet**

<https://www.antarcticglaciers.org/glacial-geology/british-irish-ice-sheet/the-irish-ice-sheet/>

**358. The Irish Quaternary Fauna Project**

[https://www.researchgate.net/publication/223448450\\_The\\_Irish\\_Quaternary\\_Fauna\\_Project](https://www.researchgate.net/publication/223448450_The_Irish_Quaternary_Fauna_Project)

**359. The Irish Quaternary Fauna Project**

[https://doi.org/10.1016/S0277-3791\(96\)00037-6](https://doi.org/10.1016/S0277-3791(96)00037-6)

**360. The Irish Quaternary Fauna Project**

[https://doi.org/10.1016/S0277-3791\(96\)00064-7](https://doi.org/10.1016/S0277-3791(96)00064-7)

**361. The Irish Quaternary Fauna Project**

<https://www.sciencedirect.com/science/article/pii/S0277379196000376>

**362. The Island of Ireland: Drowning the Myth of an Irish Land-Bridge?**

<https://www.tara.tcd.ie/tara8/server/api/core/bitstreams/496ba918-8adf-486f-a535-e9ede845c72f/content>

**363. The Island of Ireland: Drowning the Myth of an Irish Land-Bridge?**

<https://www.tara.tcd.ie/items/af898505-9836-458c-a5d6-78ce11d608ab>

**364. The last Eurasian ice sheets – a chronological database and time-slice reconstruction, DATED-1**

<https://doi.org/10.1111/bor.12142>

**365. The Last Glacial Maximum British–Irish Ice Sheet: a Reconstruction Using Digital Terrain Mapping**

<https://doi.org/10.1002/jqs.1143>

**366. The Last Irish Ice Sheet: Extent and Chronology**

[https://doi.org/10.2991/978-94-6239-219-9\\_5](https://doi.org/10.2991/978-94-6239-219-9_5)

**367. The Last Irish Ice Sheet: Extent and Chronology**

[https://www.researchgate.net/publication/309313799\\_The\\_Last\\_Irish\\_Ice\\_Sheet\\_Extent\\_and\\_Chronology](https://www.researchgate.net/publication/309313799_The_Last_Irish_Ice_Sheet_Extent_and_Chronology)

**368. The Last Scottish Ice Sheet**

<https://www.cambridge.org/core/journals/earth-and-environmental-science-transactions-of-royal-society-of-edinburgh/article/abs/last-scottish-ice-sheet/4730FF8269481713CCD4B3F58B7BBE0E>

**369. The Late Quaternary history of east-central Ireland**

<https://www.cambridge.org/core/journals/geological-magazine/article/abs/late-quaternary-history-of-eastcentral-ireland/0317E3C5FD4FBCDC0B2A8C2BB9EFD707>

**370. The Late Quaternary History of East-Central Ireland**

<https://doi.org/10.1017/S0016756805002749>

**371. The Mammoth Caves of Castlepook, Near Doneraile**

<https://corkhist.ie/wp-content/uploads/jfiles/1905/b1905-003.pdf>

**372. The Marine  $\delta^{18}\text{O}$  Record Overestimates Continental Ice Volume During Marine Isotope Stage 3**

<https://www.sciencedirect.com/science/article/pii/S0921818122000819>

**373. The Mesolithic in Ireland: Hunter-Gatherers in an Insular Environment**

<https://www.fulcrum.org/concern/monographs/12579t95q>

**374. The Mesolithic in Ireland: When Was It?**

<https://www.heritagecouncil.ie/content/files/Our-Ancient-Landscapes-Hunter-Gatherers-in-Ireland.pdf>

**375. The Origin and Status of the Red Deer in Ireland**

[https://www.npws.ie/sites/default/files/general/Quaternary%20Science%20Reviews%2042%20\(2012\)%2074-84%20Carden%20et%20al.pdf](https://www.npws.ie/sites/default/files/general/Quaternary%20Science%20Reviews%2042%20(2012)%2074-84%20Carden%20et%20al.pdf)

**376. The Problem of a Late Quaternary Landbridge Between Britain and Ireland**

[https://doi.org/10.1016/0277-3791\(85\)90028-9](https://doi.org/10.1016/0277-3791(85)90028-9)

**377. The Problem of a Late Quaternary Landbridge Between Britain and Ireland**

<https://doi.org/10.1002/jqs.3390050210>

**378. The Problem of a Late Quaternary Landbridge Between Britain and Ireland**

<https://www.sciencedirect.com/science/article/pii/0277379185900289>

**379. The Quaternary History of Ireland**

<https://catalogue.nli.ie/Record/vtls000090300>

**380. The Quaternary of the Mayo–Galway Region: Regional Pleistocene Geology**

<https://iqua.ie/wp-content/uploads/2021/09/IQUA-Guide-17-unlocked.pdf>

**381. The Quaternary of Western Ireland: INQUA Field Guide Pre:GL-2**

<https://doi.org/10.13025/19664>

**382. The Standard Stratigraphic Nomenclature of Offshore Ireland**

<https://researchrepository.ucd.ie/server/api/core/bitstreams/fcd9df1f-c0a8-4628-8ede-748459840990/content>

**383. The Stratigraphic Position and Age of the Gortian**

[https://www.burren geopark.ie/wp-content/uploads/2014/08/GSI-The\\_Stratigraphic\\_Position\\_and\\_Age\\_of\\_the\\_Gor.pdf](https://www.burren geopark.ie/wp-content/uploads/2014/08/GSI-The_Stratigraphic_Position_and_Age_of_the_Gor.pdf)

**384. The Timing and Magnitude of the British–Irish Ice Sheet Between Marine Isotope Stages 5d and 2**

<https://onlinelibrary.wiley.com/doi/full/10.1002/jqs.3611>

**385. The Timing and Magnitude of the British–Irish Ice Sheet Between Marine Isotope Stages 5d and 2**

<https://onlinelibrary.wiley.com/doi/10.1002/jqs.3611>

**386. The Timing and Magnitude of the British–Irish Ice Sheet Between Marine Isotope Stages 5d and 2: Implications for Glacio-Isostatic Adjustment, High Relative Sea Levels and ‘Giant Erratic’ Emplacement**

<https://doi.org/10.1002/jqs.3611>

**387. The Timing and Pattern of British–Irish Ice Sheet Growth and Decay: Constraints on the Last Glacial Cycle**

[https://etheses.dur.ac.uk/600/1/BradleySL\\_2011.pdf](https://etheses.dur.ac.uk/600/1/BradleySL_2011.pdf)

**388. The West Corrib Moraine System as Evidence for a Brief Glacial Readvance in Ireland During Overall Heinrich Stadial 1 Deglaciation**

<https://www.cambridge.org/core/journals/quaternary-research/article/west-corrib-moraine-system-as-evidence-for-a-brief-glacial-readvance-in-ireland-during-overall-heinrich-stadial-1-deglaciation/04FC292756F66D3AB3CC53FCC7F49F18>

**389. Timing, Pace and Controls on Ice Sheet Retreat: An Introduction to the BRITICE-CHRONO Transect Reconstructions of the British–Irish Ice Sheet**

<https://livrepository.liverpool.ac.uk/3124997/>

**390. Timing, Pace and Controls on Ice Sheet Retreat: An Introduction to the BRITICE-CHRONO Transect Reconstructions of the British–Irish Ice Sheet**

<https://doi.org/10.1002/jqs.3326>

**391. Timing and Pace of Ice-Sheet Withdrawal Across the Marine–Terrestrial Transition West of Ireland During the Last Glaciation**

<https://eprints.gla.ac.uk/234542/1/234542.pdf>

**392. Timing and Pace of Ice-Sheet Withdrawal Across the Marine–Terrestrial Transition West of Ireland During the Last Glaciation**

<https://mural.maynoothuniversity.ie/id/eprint/16633/1/OCofaighetal2021.pdf>

**393. Timing and Pace of Ice-Sheet Withdrawal Across the Marine–Terrestrial Transition West of Ireland During the Last Glaciation**

<https://doi.org/10.1002/jqs.3295>

**394. Timing and Pace of Ice-Sheet Withdrawal Across the Marine–Terrestrial Transition West of Ireland During the Last Glaciation**

<https://onlinelibrary.wiley.com/doi/full/10.1002/jqs.3295>

**395. Timing and Pace of Ice-Sheet Withdrawal Across the Marine–Terrestrial Transition West of Ireland During the Last Glaciation**

<https://onlinelibrary.wiley.com/doi/10.1002/jqs.3295>

**396. Trimlines, blockfields and the vertical extent of the last ice sheet in southern Ireland**

<https://doi.org/10.1111/bor.12109>

**397. Trimlines, Blockfields and the Vertical Extent of the Last Ice Sheet in Southern Ireland**

<https://onlinelibrary.wiley.com/doi/10.1111/bor.12109>

**398. Trimlines, Blockfields and the Vertical Extent of the Last Ice Sheet in Southern Ireland**

[https://www.researchgate.net/publication/271141377\\_Trimlines\\_blockfields\\_and\\_the\\_vertical\\_extent\\_of\\_the\\_last\\_ice\\_sheet\\_in\\_Southern\\_Ireland](https://www.researchgate.net/publication/271141377_Trimlines_blockfields_and_the_vertical_extent_of_the_last_ice_sheet_in_Southern_Ireland)

**399. Trimlines, Blockfields and the Vertical Extent of the Last Ice Sheet in Southern Ireland**

[https://research-repository.st-andrews.ac.uk/bitstream/10023/6021/1/ballantyne2015boreas\\_earlyview.pdf](https://research-repository.st-andrews.ac.uk/bitstream/10023/6021/1/ballantyne2015boreas_earlyview.pdf)

**400. UCD School of Archaeology Research Day 2022**

[https://www.ucd.ie/archaeology/t4media/UCD\\_Archaeology\\_Research\\_Day\\_2022.pdf](https://www.ucd.ie/archaeology/t4media/UCD_Archaeology_Research_Day_2022.pdf)

**401. Understanding Irish Landscape Evolution: Pollen Assemblages from Neogene and Pleistocene Palaeosurfaces in Western Ireland**

<https://www.tcd.ie/research/profiles/?profile=pcoxon>

**402. Upper Pleistocene Facies Sequences and Relative Sea-Level Trends Along the South Coast of Ireland**

<https://pure.ulster.ac.uk/en/publications/upper-pleistocene-facies-sequences-and-relative-sea-level-trends--3>

**403. Vertical Dimensions and Age of the Wicklow Mountains Ice Dome, Eastern Ireland, and Implications for the Extent of the Last Irish Ice Sheet**

<https://doi.org/10.1016/j.quascirev.2006.10.003>

**404. Vertical dimensions and age of the Wicklow Mountains ice dome, Eastern Ireland, and implications for the extent of the last Irish Ice Sheet**

<https://www.sciencedirect.com/science/article/pii/S0277379106000692>

**405. Vertical Dimensions and Age of the Wicklow Mountains Ice Dome, Eastern Ireland, and Implications for the Extent of the Last Irish Ice Sheet**

<https://doi.org/10.1016/j.quascirev.2006.09.003>

**406. What Was on the Menu in Prehistoric Ireland?**

<https://www.rte.ie/brainstorm/2025/0815/1475736-prehistoric-ireland-food-mesolithic-iron-age-bronze-age/>

# Index

**Agriculture**, 4291, 4304, 4314, 4342, 4370, 4400, 4416, 4485, 4503, 4512, 4595, 4606, 4622, 4633

**Antrim**, 4276, 4280, 4300, 4304, 4312, 4324, 4344, 4348, 4395, 4398, 4414, 4426, 4438, 4458, 4482, 4509, 4529, 4541, 4569, 4573, 4612

**Awbeg Valley**, 4284–4285, 4317, 4435, 4451, 4471, 4491, 4526, 4557–4558, 4560, 4602

**Ballyhoura**, 4285, 4316–4317, 4369, 4558, 4602

**Belfast**, 4581

**Birm-166**, 4248, 4253, 4272, 4274, 4280, 4289, 4300, 4313, 4320, 4353, 4361, 4364–4365, 4367–4368, 4376, 4380, 4382–4383, 4391, 4406, 4410, 4427, 4434, 4436, 4459, 4470, 4474, 4478, 4482, 4487, 4490, 4494–4495, 4497–4498, 4529, 4534, 4537, 4549, 4566, 4574, 4578, 4581, 4586, 4589–4590, 4593–4594, 4604, 4616, 4620, 4623, 4626–4627

**Bogbean**, 4241, 4245, 4249, 4252–4253, 4255, 4257–4258, 4261, 4269, 4273–4274, 4281, 4285, 4289, 4293, 4301, 4305, 4309, 4313, 4317, 4321, 4329, 4333, 4337, 4345, 4349, 4353, 4357, 4361, 4365, 4369, 4373, 4377, 4380–4382, 4384, 4392, 4396, 4399, 4403, 4407, 4423, 4435, 4439, 4447, 4451, 4454–4455, 4457, 4467, 4471, 4475, 4479, 4483, 4487, 4490–4491, 4493, 4495, 4499, 4502, 4506, 4510, 4514, 4518, 4526, 4530, 4534, 4538, 4546, 4550, 4554, 4566, 4574, 4577–4578, 4582, 4590, 4597, 4601, 4605, 4609, 4617, 4624, 4632

**Bronze Age**, 4326

**Castlepook**, 4240–4243, 4245–4247, 4249–4251, 4254–4255, 4257–4258, 4262, 4265–4271, 4273–4274, 4276–4279, 4281–4283, 4285–4288, 4290–4294, 4297–4298, 4301–4303, 4305–4307, 4309–4311, 4313–4314, 4317–4318, 4321–4326, 4329–4331, 4333–4334, 4337–4339, 4341–4342, 4345–4351, 4353–4354, 4356–4359, 4361–4362, 4365–4367, 4369–4370, 4372–4375, 4377–4378, 4381–4385, 4387–4389, 4392–4394, 4396–4397, 4399–4400, 4403–4405, 4407–4408, 4411–4413, 4415–4416, 4418–4425, 4427–4429, 4431–4433, 4435–4436, 4439–4441, 4443–4449, 4451–4456, 4459–4465, 4467–4469, 4471–4474, 4476–4481, 4484, 4488–4489, 4491–4493, 4495–4504, 4506–4509, 4511–4512, 4514–4515, 4517–4520, 4522, 4524, 4526–4528, 4530–4531, 4534–4536, 4538–4539, 4542–4543, 4546–4548, 4550–4551, 4554–4559, 4562–4564, 4567–4580, 4582–4583, 4586–4587, 4590–4591, 4594–4595, 4597–4600, 4602–4603, 4605–4606, 4608, 4610–4611, 4613–4614, 4617–4619, 4621–4622, 4624–4625, 4629–4630, 4632–4634

**Clare**, 4250, 4266, 4278, 4298, 4302, 4326, 4330, 4362, 4378, 4382, 4400, 4408, 4416, 4420, 4432, 4440, 4448, 4452, 4456, 4464, 4468, 4484, 4535, 4550, 4587, 4614, 4618, 4629

**Connacht**, 4325, 4452

**Derry**, 4240–4241, 4243–4245, 4247–4253, 4255–4258, 4260–4262, 4264–4265, 4267–4269, 4271–4274, 4277–4278, 4280–4281, 4283, 4285, 4287–4289, 4291–4293, 4296–4297, 4300–4301, 4303, 4305–4307, 4309, 4311, 4313–4314, 4316–4318, 4320–4325, 4328–4329, 4331, 4333–4334, 4336–4349, 4351–4354, 4357, 4359–4365, 4368–4373, 4375–4385, 4387–4388, 4391–4399, 4402–4403, 4405–4407, 4409–4411, 4413–4417, 4422–4423, 4425, 4427, 4429–4431, 4433–4436, 4438–4439, 4441–4447, 4449–4456, 4459–4467, 4469–4471, 4473–4479, 4481–4484, 4486–4487, 4489–4495, 4497–4502, 4505–4506, 4508, 4510, 4512–4515, 4517–4523, 4525–4526, 4528–4534, 4536–4538, 4540–4543, 4545–4546, 4548–4551, 4553–4556, 4558, 4561–4562, 4564–4566, 4568, 4570–4571, 4573–4574, 4577–4582, 4584–4587, 4589–4595, 4597–4601, 4603–4606, 4608–4613, 4615–4625, 4627–4632, 4634

**Derryvree**, 4240–4241, 4243–4245, 4247–4253, 4255–4258, 4260–4262, 4264–4265, 4267–4269, 4271–4274, 4277, 4280–4281, 4283, 4285, 4287–4289, 4291–4293, 4296–4297, 4300–4301, 4303, 4305–4307, 4309, 4311, 4313–4314, 4316–4318, 4320–4325, 4328–4329, 4331, 4333–4334, 4336–4349, 4351–4354, 4357, 4359–4365, 4368–4373, 4375–4385, 4387–4388, 4391–4399, 4402–4403, 4405–4407, 4409–4411, 4413–4417, 4422–4423, 4425, 4427, 4429–4431, 4433–4436, 4438–4439, 4441–4447, 4449–4456, 4459–4467, 4469–4471, 4473–4479, 4481–4484, 4486–4487, 4489–4495, 4497–4502, 4505–4506, 4508, 4510, 4512–4515, 4517–4523, 4525–4526, 4528–4534, 4536–4538, 4540–4543, 4545–4546, 4548–4551, 4553–4556, 4558, 4561–4562, 4564–4566, 4568, 4570–4571, 4573–4574, 4577–4582, 4584–4587, 4589–4595, 4597–4601, 4603–4606, 4608–4613, 4615–4625, 4627–4632, 4634

**Donegal**, 4388

**Doneraile**, 4240, 4245, 4249, 4254, 4257, 4262, 4265, 4269, 4273, 4276, 4280–4281, 4285, 4288, 4293, 4297, 4301, 4305, 4308–4309, 4311, 4313, 4317, 4321, 4325, 4329, 4333, 4341, 4345, 4348, 4353, 4357, 4361, 4365, 4369, 4372–4373, 4377, 4381, 4384, 4388, 4392, 4396, 4399, 4403, 4407, 4411, 4415, 4418, 4422–4423, 4427, 4431, 4435, 4439, 4443, 4446, 4451, 4454, 4459, 4463, 4467, 4471, 4474, 4478, 4484, 4491, 4495, 4499, 4502, 4506, 4511, 4514, 4517, 4522, 4525–4526, 4530, 4534, 4538, 4542, 4545–4546, 4550, 4554, 4557–4558, 4562, 4567, 4570, 4574, 4577, 4582, 4586, 4590, 4594, 4597, 4600, 4605, 4608, 4610, 4613, 4617, 4621, 4624, 4629, 4632

**Down**, 4248, 4264, 4268, 4272, 4296, 4320, 4353, 4391, 4406, 4423, 4442, 4455, 4466, 4474, 4482, 4490, 4505, 4518, 4541, 4549, 4573, 4577, 4585, 4589, 4601, 4616, 4631

**Education**, 4515



**Flora**, 4321, 4333, 4346, 4365, 4373, 4411, 4422, 4475, 4479, 4487, 4499, 4522, 4550, 4558, 4562, 4594, 4617, 4620

**Galway**, 4244, 4256, 4276, 4292, 4300, 4304, 4320, 4344, 4352, 4364, 4387, 4474, 4482, 4505, 4537, 4565, 4569, 4589

**Hyenahall**, 4348–4349, 4631, 4634

**Industry**, 4326, 4523, 4625

**Irish language**, 4503

**Iron Age**, 4326

**Kerry**, 4265, 4273, 4321, 4337, 4377–4378, 4392, 4406–4407, 4431, 4471, 4478, 4497, 4506, 4538, 4551, 4554, 4587

**Leitrim**, 4312, 4414, 4612

**Limerick**, 4248, 4387, 4521

**Maguirebridge**, 4304, 4376, 4395, 4402, 4454, 4513, 4581, 4596, 4608

**Maguiresbridge**, 4240–4241, 4244, 4248, 4253, 4256, 4260, 4264, 4268, 4272, 4278, 4280, 4285, 4288, 4292, 4296, 4300, 4305, 4309, 4313, 4316, 4320, 4323–4324, 4328, 4332–4333, 4336, 4340, 4344, 4348, 4352, 4357, 4360, 4364, 4368, 4372, 4376, 4380, 4383, 4387, 4391, 4395–4398, 4402, 4406, 4410, 4414, 4422, 4427, 4430, 4434, 4438, 4442–4443, 4446, 4450, 4454, 4459, 4462, 4466–4467, 4470, 4474, 4478, 4482–4483, 4487, 4490, 4494, 4498, 4501, 4505, 4510, 4513, 4517, 4521, 4525, 4529, 4534, 4537, 4541, 4545, 4549, 4553, 4558, 4562, 4565, 4570, 4573, 4577–4578, 4581, 4585, 4589, 4593, 4597, 4600, 4604, 4608, 4612, 4616, 4620, 4623, 4627, 4631

**Mayo**, 4244, 4268, 4631

**Mesolithic**, 4246, 4250, 4326, 4346, 4366, 4378, 4416, 4522, 4633

**Migration**, 4242, 4250, 4267, 4269, 4278, 4290, 4294, 4306, 4318, 4322, 4332, 4338, 4364, 4366, 4385, 4396, 4400, 4404, 4408, 4414, 4420, 4424, 4428, 4432, 4444, 4448, 4455, 4460, 4464, 4472, 4480, 4496, 4499, 4511, 4531, 4534, 4567, 4570, 4575, 4583, 4608, 4618, 4621, 4624–4625

**Munster**, 4325, 4403

**Music**, 4298, 4342, 4358, 4382, 4460, 4512, 4547, 4563

**Neolithic**, 4326, 4366, 4416

**Palaeoenvironment**, 4291, 4316, 4357, 4626

**Permafrost**, 4269, 4289, 4312, 4325, 4392, 4450, 4456, 4470, 4483, 4510, 4558, 4562

**Transport**, 4265, 4290, 4301–4302, 4305, 4317–4318, 4345, 4350, 4366, 4392, 4412, 4495, 4507–4508, 4515, 4519, 4563, 4567, 4583, 4605, 4629


**Ulster**, 4463

**Ussher**, 4281, 4300–4301, 4381, 4403, 4467, 4526, 4562, 4632

**Waterford**, 4265, 4305, 4400, 4543

**Wicklow**, 4300, 4356, 4620, 4631





# Discover Ireland Through the Pages of Emerald Gazette

Step into the remarkable world of Emerald Gazette, a publication series created for readers who want to experience Ireland's past through vivid storytelling, striking imagery and carefully researched historical features.

Every volume opens a window onto a particular era, revealing the individuals, communities, discoveries, struggles and achievements that helped shape the country we recognise today. From distant centuries to comparatively recent times, the series captures both celebrated landmarks of Irish history and lesser-known stories that deserve to be remembered.

Produced from the extensive resources of Emerald Archives, each edition is designed to be both informative and enjoyable, making it equally suitable for dedicated history enthusiasts, students, researchers, family historians and curious readers discovering Irish history for the first time.

Rather than being a publication to read once and set aside, Emerald Gazette is intended to become part of a growing historical library. Every new volume adds another piece to an extraordinary national record, creating a collection that can be explored, revisited and shared.

Whether your interest lies in ancient Ireland, medieval society, revolution, culture, local communities or the changing face of modern life, there is always another story waiting to be discovered.

**Open the book. Enter the period. Discover Ireland.**

Compiled & Edited by Gerard J. Hannan BA MBS MA